

Docket No. 50-336
B14033

Attachment 1

Millstone Nuclear Power Station, Unit No. 2

Proposed Change to Technical Specification
Containment Leakage

February 1992

9202180302 920207
PDR ADOCK 05000336
P PDR

CONTAINMENT SYSTEMS

CONTAINMENT LEAKAGE

LIMITING CONDITION FOR OPERATION

3.6.1.2 Containment leakage rates shall be limited to:

- a. An overall integrated leakage rate of $\leq L_a$, 0.50 percent by weight of the containment air per 24 hours^a at P_a , 54 psig.
- b. A combined leakage rate of $\leq 0.60 L_a$ for all penetrations and valves subject to Type B and C tests^a when pressurized to P_a .
- c. A combined leakage rate of $\leq 0.017 L_a$ for all penetrations identified in Table 3.6-1 as secondary containment bypass leakage paths when pressurized to P_a .

APPLICABILITY: MODES 1, 2, 3 and 4.

ACTION:

With either (a) the measured overall integrated containment leakage rate exceeding $0.75 L_a$, or (b) with the measured combined leakage rate for all penetrations and valves subject to Types B and C tests exceeding $0.60 L_a$, or (c) with the combined bypass leakage rate exceeding $0.017 L_a$, restore the leakage rate(s) to within the limit(s) prior to increasing the Reactor Coolant System temperature above 200°F.

SURVEILLANCE REQUIREMENTS

4.6.1.2 The containment leakage rates shall be demonstrated at the following test schedule and shall be determined in conformance with the criteria specified in Appendix J of 10 CFR 50.

- a. Three Type A tests (Overall Integrated Containment Leakage Rate) shall be conducted at 40 ± 10 month intervals* during shutdown at P_a (54 psig) during each 10-year service period. The third test of each set shall be conducted during the shutdown for the 10-year plant inservice inspection.

*The test interval for conducting a Type A test shall be extended to allow the second Type A test, within the second ten-year service period, to be conducted during Cycle 11 refueling outage. This extension expires upon completion of Cycle 11 refueling outage.

CONTAINMENT SYSTEMS

SURVEILLANCE REQUIREMENTS (Continued)

- g. All test leakage rates shall be calculated using observed data converted to absolute values. Error analyses shall be performed to select an acceptable integrated leakage measurement system.
- h. The provisions of Specification 4.0.2 are not applicable.