

SOUTH CAROLINA ELECTRIC & GAS COMPANY

POST OFFICE 764

COLUMBIA, SOUTH CAROLINA 29218

O. W. DIXON, JR.
VICE PRESIDENT
NUCLEAR OPERATIONS

July 24, 1984

Mr. Harold R. Denton, Director
Office of Nuclear Reactor Regulation
U.S. Nuclear Regulatory Commission
Washington, D.C. 20555

Subject: Virgil C. Summer Nuclear Station
Docket No. 50/395
Operating License No. NPF-12
Seismic Monitoring Instrumentation

Dear Mr. Denton:

South Carolina Electric and Gas Company (SCE&G) hereby requests a revision to the Virgil C. Summer Nuclear Station Technical Specification 3/4.3.3, Section 3.3.3.3, "Seismic Instrumentation." This amendment request involves moving one (1) Triaxial Peak Accelerograph from the pressurizer surge line to the accumulator safety injection line. This modification is necessary because the present instrument location causes the accelerometer to engrave the vibratory motion of the surge line on its record plates continuously. Therefore, the instrument is rendered inoperable for recording future earthquakes.

The accumulator safety injection line is Class 1 piping located inside the containment building. The instrument is to be located at a seismically analyzed point away from a restraint. This point produces relatively large accelerations under Operating Basis Earthquake (OBE) conditions.

SCE&G has determined that a finding of no significant hazards consideration is justified because this accelerograph is provided only to record the effects of a seismic event. The instrument is not required to provide any information to mitigate the consequences of an accident. This location has the capability of providing accurate and useful recorded information in the event of seismic activity.

This amendment has been reviewed and approved by both the Plant Safety Review Committee and the Nuclear Safety Review Committee. The statements and matters set forth herein are true and correct to the best of my knowledge, information and belief. As required by Title 10 of the Code of Federal Regulations, Part 170 (10CFR170), a check in the amount of one hundred fifty dollars (\$150.00) is enclosed to initiate the processing of this request.

8407310294 840724
PDR ADOCK 05000395
PDR


Rec'd w/check \$150.00

AD01
11

Mr. Harold R. Denton
Seismic Monitoring Instrumentation
July 24, 1984
Page #2

If you have any questions, please advise.

Very truly yours,



O. W. Dixon, Jr.

AMM/OWD/gj
Enclosure

cc: V. C. Summer	C. A. Price
T. C. Nichols, Jr./O. W. Dixon, Jr.	C. L. Ligon (NSRC)
E. H. Crews, Jr.	K. E. Nodland
E. C. Roberts	R. A. Stough
W. A. Williams, Jr.	G. Percival
D. A. Nauman	C. W. Hehl
J. P. O'Reilly	J. B. Knotts, Jr.
Group Managers	H. G. Shealy
O. S. Bradham	NPCF
	File