

CONTAINMENT SYSTEMS

SURVEILLANCE REQUIREMENTS

- b. If any periodic Type A test fails to meet $0.75 L_a$, the test schedule for subsequent Type A tests shall be reviewed and approved by the Commission. If two consecutive Type A tests fail to meet $0.75 L_a$, a Type A test shall be performed at least every 18 months until two consecutive Type A tests meet $0.75 L_a$ at which time the above test schedule may be resumed;
- c. The accuracy of each Type A test shall be verified by a supplemental test which:
 - 1) Confirms the accuracy of the test by verifying that the absolute value of the supplemental test result, L_c , minus the sum of the Type A and the superimposed leak, L_o , is equal to or less than $0.25 L_a$;
 - 2) Has a duration sufficient to establish accurately the change in leakage rate between the Type A test and the supplemental test; and
 - 3) Requires that the rate at which gas is injected into the containment or bled from the containment during the supplemental test is between $0.75 L_a$ and $1.25 L_a$.
- d. Type B and C tests shall be conducted with gas at a pressure not less than P_a , 37 psig, at intervals no greater than 24 months* except for tests involving:
 - 1) Air locks and
 - 2) Purge supply and exhaust isolation valves with resilient material seals.
- e. Air locks shall be tested and demonstrated OPERABLE by the requirements of Specification 4.6.1.3;
- f. Purge supply and exhaust isolation valves with resilient material seals shall be tested and demonstrated OPERABLE by the requirements of Specification 4.6.1.7.2;
- g. The provisions of Specification 4.0.2 are not applicable.

The Type B and C tests scheduled for refueling outage 1AG will be conducted in accordance with Option B of 10 CFR 50, Appendix J, using the guidance of Regulatory Guide 1.163, ~~June~~ September 1995.

**The Type C test interval for Unit 1 valves HV-1974 (and associated check valve 1-1217-U4-113), HV-1975, HV-1978, and HV-1979 may be extended to prior to entry into Mode 4 following the next scheduled refueling outage (or the next forced outage requiring entry into Mode 5), but no later than November 1, 1994.*