



**WOLF CREEK GENERATING STATION
CYCLE 8**

**CORE OPERATING LIMITS REPORT
Revision 1**

November 8, 1995

Prepared by:

Michael E. Howard
Michael E. Howard

Reviewed by:

Jeff T. Blair
Jeff T. Blair

Approved by:

R. D. Flannigan
R. D. Flannigan

2.0 OPERATING LIMITS

The cycle-specific parameter limits for the specifications listed in Section 1.0 are presented in the subsections below:

2.1 Moderator Temperature Coefficient (MTC) EOL Limit

(Tech Spec 3.1.1.3.b)

The EOL MTC shall be less negative than -50 pcm/deg F. |

(Tech Spec 4.1.1.3.b)

The 300 PPM MTC Surveillance Limit is -41 pcm/deg F (all rods withdrawn, Rated Thermal Power condition). |