

Document Transmittal #: 41813

Date: 3/2/96

To: NRC RES INSPECTOR

MAC: NSCC

Destination:

Description:

Document:	Revision:	Comment:	Copy #	Copy Totals		
				INFO	CNTL	MSTR
OP0404	98	EDITORIAL	8	1	0	0

Instructions to the Addressee:

Please verify the document(s) received agrees with the above information. Be sure to destroy document(s) or portions of document(s) superseded by the above.

The signature indicates acknowledgment of receipt of the above document(s). Return signed and dated transmittal to Document Control within 20 days at mail code:

070006

____ NA1C

____ Florida Power Corporation
Document Control, NA1C
Crystal River Energy Complex
15760 W. Power Line St.
Crystal River, FL 34428-6708

Signature of Addressee: _____ Date: _____

Independent Verification: _____ Date: _____


(Control Room documents only)

9603110439 960302
PDR ADOCK 05000302
P PDR

Adol
2/1

(E) Rev. 98

Effective Date 3/2/96



OPERATING PROCEDURE

OP-404

FLORIDA POWER CORPORATION

CRYSTAL RIVER UNIT 3

DECAY HEAT REMOVAL SYSTEM

THIS PROCEDURE ADDRESSES SAFETY RELATED COMPONENTS

APPROVED BY: Interpretation Contact

[Signature]
(SIGNATURE ON FILE)

DATE: 3-2-96

INTERPRETATION CONTACT: Manager, Nuclear Operations Support

TABLE OF CONTENTS

<u>SECTION</u>		<u>PAGE</u>
1.0	PURPOSE	1
2.0	REFERENCES	2
	2.1 <u>IMPLEMENTING REFERENCES</u>	2
	2.2 <u>DEVELOPMENTAL REFERENCES</u>	2
3.0	PERSONNEL INDOCTRINATION	5
	3.1 <u>SETPOINTS</u>	5
	3.2 <u>LIMITS AND PRECAUTIONS</u>	6
4.0	INSTRUCTIONS	14
	4.1 <u>INITIAL CONDITIONS</u>	14
	4.2 <u>INITIAL FILLING AND VENTING OF DECAY HEAT CCC</u> <u>SYSTEM</u>	15
	4.3 <u>FILLING AND VENTING DHP-1A/"A" DECAY HEAT TRAIN</u>	18
	4.4 <u>FILLING AND VENTING DHP-1B "B" DECAY HEAT TRAIN</u>	19
	4.5 <u>ESTABLISHING DECAY HEAT REMOVAL</u>	20
	4.5.1 <u>Initial Conditions</u>	20
	4.6 <u>ALTERNATING DECAY HEAT TRAINS</u>	33
	4.7 <u>RESTARTING DECAY HEAT REMOVAL AFTER PUMP TRIP</u>	45
	4.8 <u>PLACING DCHE-1A IN LAYUP</u>	52
	4.9 <u>PLACING DCHE-1B IN LAYUP</u>	54
	4.10 <u>DECAY HEAT SYSTEM PURIFICATION USING MAKEUP &</u> <u>PURIFICATION SYSTEM</u>	56
	4.11 <u>DECAY HEAT SYSTEM PURIFICATION USING SPENT FUEL</u> <u>SYSTEM</u>	58
	4.12 <u>DH OPERATION DURING A LOCA</u>	61
	4.13 <u>LONG-TERM POST-ACCIDENT COOLING</u>	75
	4.14 <u>ISOLATION AND RESTORATION OF INDIVIDUAL DECAY</u> <u>HEAT PUMPS AND HEAT EXCHANGERS</u>	81
	4.15 <u>DCHE ISOLATION/RESTORATION FOR MAINTENANCE</u>	88
	4.16 <u>DHCCC PUMP ISOLATION/RESTORATION FOR</u> <u>MAINTENANCE</u>	91
	4.17 <u>FILLING THE FUEL TRANSFER CANAL: "A" DH SYSTEM</u> <u>IN SERVICE, "B" DH SYSTEM RECIRC OF BWST</u>	94
	4.18 <u>FILLING THE FUEL TRANSFER CANAL: "B" DH SYSTEM</u> <u>IN SERVICE, "A" DH SYSTEM RECIRC OF BWST</u>	100
	4.19 <u>DRAINING FUEL TRANSFER CANAL VIA "A" DH SYSTEM</u>	106
	4.20 <u>DRAINING FUEL TRANSFER CANAL VIA "B" DH SYSTEM</u>	110
	4.21 <u>BWST RECIRCULATION WITH ALTERNATE SUCTION TO</u> <u>DECAY HEAT PUMPS</u>	114
	4.22 <u>CROSS TIE OF DECAY HEAT FLOW TO REACTOR VESSEL</u> <u>"A" DECAY HEAT PUMP IN SERVICE</u>	118
	4.23 <u>CROSS TIE OF DECAY HEAT FLOW TO REACTOR VESSEL</u> <u>"B" DECAY HEAT PUMP IN SERVICE</u>	119
	4.24 <u>RAISING LEVEL IN PARTIALLY DRAINED RCS</u>	120
	4.25 <u>LOWERING LEVEL IN PARTIALLY DRAINED RCS</u>	122
	4.26 <u>BWST RECIRCULATION WITH DHP-1A</u>	124
	4.27 <u>BWST RECIRCULATION WITH DHP-1B</u>	126

TABLE OF CONTENTS (Con't)

<u>SECTION</u>		<u>PAGE</u>
4.28	<u>FEED AND BLEED OF DC SYSTEM FOR CHEMISTRY CONTROL</u>	128
4.29	<u>COOLDOWN OF PRESSURIZER WITH AUXILIARY SPRAY (RCV-53)</u>	129
4.30	<u>SECURING DECAY HEAT REMOVAL</u>	131
4.31	<u>SETTING DHP LOW AMPS ALARM SETPOINT</u>	134
5.0	<u>FOLLOW-UP ACTIONS</u>	135
6.0	<u>RESTORATION INSTRUCTIONS</u>	136
<u>ENCLOSURES</u>		
1	Valve Check List I	137
2	Valve Check List II	139
3	Valve Check List III	148
4	Valve Check List IV	153
5	DH Removal Cooler Temperature Controls	154
6	Guidelines for Operating DCV-17, [DCV-18] and DCV-177, [DCV-178] Manually	155

1.0 PURPOSE

- 1.1 To provide procedures for filling, venting, and operating the Decay Heat (DH) Removal System and the Decay Heat Closed Cycle Cooling System.
- 1.2 To provide procedures for filling and draining the Fuel Transfer Canal using the Decay Heat Removal System(s).
- 1.3 To provide instructions for raising and lowering RCS level during partially drained conditions.

2.0 REFERENCES

2.1 IMPLEMENTING REFERENCES

- 2.1.1 CP-115, Nuclear Plant Tags & Tagging Orders
- 2.1.2 OP-402, Makeup and Purification System
- 2.1.3 OP-406, Spent Fuel Cooling System
- 2.1.4 EOP-08, LOCA Cooldown
- 2.1.5 OP-209, Plant Cooldown
- 2.1.6 SP-435, Valve Testing During Cold Shutdown
- 2.1.7 MP-125, Installation of Fuel Transfer Tube Covers and "Drain Line" Cover
- 2.1.8 FP-411, Seal Plate Inspection and Port Cover Installation
- 2.1.9 MP-122, Disassembly and Reassembly of Flanged Connections
- 2.1.10 OP-417, Containment Operating Procedure
- 2.1.11 CCNB, Control Center Notebook
- 2.1.12 OP-103B, Plant Operating Curves
- 2.1.13 SP-422, RC System Heatup and Cool Down Surveillance
- 2.1.14 SP-301, Shutdown Daily Surveillance Log
- 2.1.15 EOP-11, Loss of Decay Heat Removal
- 2.1.16 SP-195, Remote Reactor Vessel Level Instrumentation Calibration

2.2 DEVELOPMENTAL REFERENCES

- 2.2.1 EOP-08, LOCA Cooldown
- 2.2.2 EOP-07, Inadequate Core Cooling
- 2.2.3 OP-202, Plant Heatup
- 2.2.4 OP-209, Plant Cooldown
- 2.2.5 OP-301, Operation of the Reactor Coolant System

- 2.2.6 DELETED
- 2.2.7 OP-305, Operation of the Pressurizer
- 2.2.8 OP-401, Core Flooding System
- 2.2.9 OP-402, Makeup and Purification System
- 2.2.10 OP-403E, Chemical Addition System (Hydrazine System)
- 2.2.11 OP-405, Reactor Building Spray System
- 2.2.12 OP-406, Spent Fuel Cooling System
- 2.2.13 OP-409, Plant Ventilation Systems
- 2.2.14 SP-716, Reactivity Control System Chemistry Surveillance Program
- 2.2.15 MP-131A, Maintenance of Decay Heat Pumps
- 2.2.16 MP-131B, Maintenance of Building Spray Pumps
- 2.2.17 SP-301, Shutdown Daily Surveillance Log
- 2.2.18 SP-417, Refueling Interval Integrated Plant Response to Engineered Safeguards Actuation
- 2.2.19 SP-435, Valve Testing During Cold Shutdown
- 2.2.20 SP-456, Refueling Interval Equipment Response to an ESAS Test Signal
- 2.2.21 SP-457, Refueling Interval ECCS Response to a Safety Injection Test Signal
- 2.2.22 TBD, Technical Basis Document
- 2.2.23 SP-340A "A" Train ECCS - RWP-3A, DCP-1A, and System Valve Operability Test
- 2.2.24 SP-340B "A" Train ECCS - DHP-1A, BSP-1A, and System Valve Operability Test
- 2.2.25 SP-340D "B" Train ECCS - RWP-3B, DCP-1B, and System Valve Operability Test
- 2.2.26 SP-340E "B" Train ECCS - DHP-1B, BSP-1B, and System Valve Operability Test
- 2.2.27 Design Basis Document Section 6.2, 6.3, 6.6, 6.12
- 2.2.28 EQ 90-2492 "DHV-13 and DHV-24 Position"

- 2.2.29 SP-195, Remote Reactor Vessel Level Instrumentation Calibration
- 2.2.30 AI-500, Conduct of Operations
- 2.2.31 MAR 92-08-01-01, Installation of Permanent Seal Plate
- 2.2.32 E92-0223, Engineering Calculation
- 2.2.33 MAR 92-10-25-01, DHP Amps Alarms
- 2.2.34 MAR 92-10-19-01, RW & SW Pump Motor Cooler Vent Valves
- 2.2.35 MAR 86-09-22-01 FCN 9, Replacement of RM-L2, RM-L3, RM-L5, RM-L6, and RM-L7
- 2.2.36 TECH Manual #65
- 2.2.37 MAR 95-08-06-01, FCN 01, FCN 02, D.C. System Flow Margin Enhancement
- 2.2.38 PT-136B, D.C. System Flow Balance and EGDG KW Loading

3.0 PERSONNEL INDOCTRINATION

DESCRIPTION		VALUE
3.1 <u>SETPOINTS</u>		
3.1.1	Decay Heat Pump runout flow	4100 gpm
3.1.2	DH pump maximum recirculation flow	3700 gpm
3.1.3	High flow alarm	3750 gpm
3.1.4	Low flow alarm (with HPI signal)	2800 gpm
	Low flow alarm	1500 gpm
3.1.5	Flow controller setpoint	3000 gpm
3.1.6	Automatic Closure Interlock System (ACIS)	284 PSIG Nominal (without regard for instrument errors or calibration)
	DHV-3 Lowest Actuation	261 PSIG in RCS Loop A and increasing
	DHV-3 Lowest Reset	255 PSIG in RCS Loop A and decreasing
	DHV-4 Lowest Actuation	266 PSIG in RCS Loop B and increasing
	DHV-4 Lowest Reset	260 PSIG in RCS Loop B and decreasing
3.1.7	RC inventory low alarm	129 FT elevation
3.1.8	DH to PZR spray valve open alarm	DHV-91 not fully closed & RC press \geq 200 PSIG RCV-53 is open & RC press \geq 200 PSIG

3.2 LIMITS AND PRECAUTIONS

LIMIT	BASIS
3.2.1 Maximum DH pump flow is 4000 gpm	Prevents reaching D.H. Pump Runout
3.2.2 The DH pumps shall be tripped anytime their suction supply valves are not in the open position or evidence of cavitation (abnormal noise, fluctuating motor current or pump flow) exists	To minimize cavitation damage
3.2.3 <u>IF</u> Decay heat indicated flow is > 300 GPM and < 1400 GPM, <u>THEN</u> Total time of pump operation should be limited to 72 hrs for the life of pump. Total run time at this reduced flow shall be logged in the Control Center Notebook	Minimize wear of the DH rotating assembly Logged time may be reset to zero following replacement of the rotating assembly
3.2.4 Indicated Decay heat flow of < 300 GPM should be limited to < 2 hrs total accumulated life of the pump. Pump operation in this range shall be logged in the control Center Notebook	Prevents failure of DH Pump shaft and/or bearings. Logged time may be reset to zero following the replacement of the rotating assembly Notify Maintenance Superintendent when logged hrs exceeded 1.5 hrs

3.2 LIMITS AND PRECAUTIONS (Cont'd)

LIMIT	BASIS
<p>3.2.5 The following DH Pump Motor Start guidelines should be observed:</p> <p>No more than two consecutive starts from ambient conditions with the motor attaining full speed between starts</p> <p>If a motor trips, has experienced two consecutive starts (less than 15 minutes run time) or is shutdown prior to attaining full speed, wait 45 minutes prior to attempting a restart</p> <p>Following a restart, another restart may be performed if the motor has run \geq 15 minutes</p>	<p>Motor winding insulation damage may result from repeated starts</p>
<p>3.2.6 The following start guidelines should be observed for RWP-3A and RWP-3B:</p> <p>No more than four starts in succession with motor initially at ambient temp and coasting to rest between starts</p> <p>Two restarts may be performed following a trip/stop after operating at rated load</p> <p>Run for 20 minutes at full load before additional starts</p>	<p>Exceeding number of allowed starts may cause rotor and/or stator to overheat</p>

3.2 LIMITS AND PRECAUTIONS (Cont'd)

LIMIT	BASIS
<p>3.2.7 Maintain purification flow less than the most restrictive of the following;</p> <ul style="list-style-type: none">o One M.U. Demineralizer and One Pre/Post filter, 80 gpmo One M.U. Demineralizer and two Pre/Post filters, 125 gpmo Two M.U. Demineralizers and two Pre/Post filters, 140 gpm	<p>Prevent exceeding the maximum design of components</p>
<p>3.2.8 Maintain purification flow greater than 25 gpm</p>	<p>Prevents channeling of demin bed reducing effectiveness</p>
<p>3.2.9 Maintain D.H. cooler outlet temperature less than 135 degrees while on DH purification</p>	<p>Protects Anion resin from thermal degradation which prevents release of stored contaminants</p>
<p>3.2.10 MU purification system pressure shall be maintained < 100 PSIG during DH system operation and should be secured when RCS pressure is > 100 PSIG</p>	<p>Prevents lifting the M.U. system relief valves</p>

3.2 LIMITS AND PRECAUTIONS (Cont'd)

LIMIT	BASIS
3.2.11 When the DH system is in operation, do not close DHV-3, DHV-4, or DHV-41 unless the RC pumps and at least one OTSG are available to cool the core and DH pumps are stopped	To ensure decay heat removal from the Rx. Core at all times
3.2.12 The DH system shall be isolated from the RCS system if the RC pressure is greater than 284 PSIG and/or RC temperature is greater than 300°F	Prevents exceeding D.H. System components design limits
3.2.13 All personnel should be clear of the DH pits while starting a DH or Building Spray (BS) pump. A current Health Physics survey must be in effect prior to entering a pit	Personnel protection and ALARA considerations
3.2.14 Maximum ΔT across a DHCCC heat exchanger (seawater side) may not exceed 10°F	Prevents excessive flow restrictions in the DH RW system from fouled tubes
3.2.15 <u>WHEN</u> all HPI pumps are red tagged off and the RCS is vented to atmosphere, <u>THEN</u> A.C.I. may be bypassed at the SSOD's discretion	To prevent inadvertent shutdown of D.H. System and minimize possible pump cavitation damage

3.2 LIMITS AND PRECAUTIONS (Cont'd)

LIMIT	BASIS
3.2.16 During periods when the reactor vessel head is removed, the following valves shall be open and their breaker control handles shall be placed in the "Lock-Reset" position: *DHV-3 ES-MCC-3A1 (Unit 3C) DHV-4 ES-MCC-3B1 (Unit 11B) DHV-41 ES-MCC-3AB (Unit 4C) These valves and breakers shall be blue-tagged to the SSOD *DHV-3 must have breaker handle locked to eye bolt on breaker cubicle door	To prevent isolation of the DH System due to a spurious ACI signal
3.2.17 When the BWST is unavailable and a BAST is being used for emergency boration inventory, the following valves shall be closed and their breakers racked out: DHV-34 ES-MCC-3A1 (Unit 4C) DHV-35 ES-MCC-3B1 (Unit 6B) These valves and breakers shall be blue-tagged to the SSOD	To prevent damage to the LPI pumps due to inadvertent ES actuation

3.2 LIMITS AND PRECAUTIONS (Cont'd)

LIMIT	BASIS
<p>3.2.18 The following requirements shall be met prior to removing a DH train from service:</p> <p>No more than one DH train shall be removed from service at any one time</p> <p><u>AND</u></p> <p>The requirements for voluntarily entering a degraded mode of operation listed in CP-115, Nuclear Plant Tags and Tagging Orders, have been met</p> <p><u>AND</u></p> <p>The refueling transfer canal is flooded, or at least one OTSG is available for cooling by either forced flow or natural circulation</p>	<p>To assure that redundant or diverse DH removal methods are available during all modes of plant operation</p>
<p>3.2.19 Maximum PZR level is ≤ 220 inches whenever RCS temperature is $\leq 283^{\circ}\text{F}$ and the reactor vessel head is not completely detensioned</p>	<p>Low Temperature Overpressure Protection (LTOPS)</p>
<p>3.2.20 Maintain RCS level and DHP flow within the Acceptable region of OP-103B, curves 16 and 18</p>	<p>To ensure adequate suction capability and to prevent vortexing</p>
<p>3.2.21 <u>IF</u> RCS level indication becomes erratic or questionable, <u>THEN</u> stop draining RCS until resolved</p>	<p>To provide proper level indication</p>

3.2 LIMITS AND PRECAUTIONS (Cont'd)

LIMIT	BASIS
3.2.22 Whenever the RCS is partially drained, any evolutions that could disrupt the operation of the operating DH, DC, or RW systems should be avoided	To prevent loss of decay heat removal capability per NRC Generic Letter 88-17
3.2.23 Whenever the reactor vessel level is < 132 FT, one HPI pump should be available to supply flow through its associated flowpath to the RCS. "Available" means that the flowpath is intact and that the pump can be placed in service within a short enough time to meet the intended need	To provide alternate means of supplying RCS inventory per NRC Generic Letter 88-17
3.2.24 The equipment hatch should be installed within 2.5 hours of either: a) Loss of decay heat removal b) An inadvertent Reactor Vessel level reduction to < 129'6" Maintenance personnel should be available at all times to install the hatch whenever it is removed	Minimize the potential for an unmonitored airborne radioactive release per NRC Generic Letter 88-17
3.2.25 All containment penetrations to outside atmosphere should be capable of being closed within 2.5 hours upon a loss of decay heat removal	Minimize the potential for an unmonitored airborne radioactive release per NRC Generic Letter 88-17

3.2 LIMITS AND PRECAUTIONS (Cont'd)

LIMIT	BASIS
3.2.26 Simultaneous filling of RCS and BWST should be carefully monitored	Reduces the potential for underborated water into the core
3.2.27 When going on decay heat, high decay heat loads may be experienced during rapid cooldowns and SBLOCA's	The DH system may not be able to remove decay heat without a > 10°F temperature rise in incores under these conditions
3.2.28 For work located in Radiation Controlled Areas, due consideration must be given to the ALARA Program. This may result in a determination that special preparations and/or precautions are necessary	To ensure that all personnel doses are As Low As Reasonably Achievable

4.0 INSTRUCTIONS

ACTIONS

DETAILS

4.1 INITIAL CONDITIONS

- 4.1.1 Ensure BWST is within limits of Technical Specification 3.5.4

- o ☐ BWST level ≥ 44.9 ft and ≤ 47.1 ft.
- o ☐ BWST boron concentration 2270-3000 ppm
- o ☐ BWST temperature $\geq 40^{\circ}\text{F}$ and $\leq 100^{\circ}\text{F}$

Initial/Date

- 4.1.2 Ensure AHF-15A or AHF-15B, DC Pump Air Handling Unit, is operable

Initial/Date

- 4.1.3 Ensure necessary instrumentation and support systems are available

- o ☐ Flow instrumentation
- o ☐ Pressure instrumentation
- o ☐ Temperature instrumentation
- o ☐ Air supply to air operated DH valves
- o ☐ RML-5 operable
- o ☐ RML-6 operable

Initial/Date

- 4.1.4 Ensure penetration cooling is provided to penetrations 342, 343, and 344

- o Refer to OP-417, Containment Operating Procedure

Initial/Date

4.2 INITIAL FILLING AND VENTING OF DECAY HEAT CCC SYSTEM

ACTIONS	DETAILS
4.2.1 Complete Valve Check Lists I, and II for applicable Decay Heat CCC Train	<u> </u> / <u> </u> Initial/Date
4.2.2 Fill DC surge tanks (DCT-1A/1B)	<div data-bbox="868 620 1460 853">1. <u> </u> Open/Ensure Open the following valves: <u> </u> o DCV-59 (DCT 1A) <u> </u> o DCV-60 (DCT 1B) 2. <u> </u> Monitor DCV-10 and DCV-12 for proper control of tank levels (8 ft 6 in - 11 ft 4 in)</div> <div data-bbox="1257 886 1460 950"><u> </u>/<u> </u> Initial/Date</div>
4.2.3 Pressurize DC surge tanks with nitrogen (DCT-1A/1B)	<div data-bbox="868 1047 1460 1246">1. <u> </u> Open/Ensure Open the following valves: <u> </u> o DCV-186 (DCT 1A) <u> </u> o DCV-188 (DCT 1B) 2. <u> </u> Monitor tanks for proper pressure (5 - 10 PSIG)</div> <div data-bbox="1257 1278 1460 1343"><u> </u>/<u> </u> Initial/Date</div>

4.2 INITIAL FILLING AND VENTING OF DECAY HEAT CCC SYSTEM (Cont'd)

ACTIONS

DETAILS

NOTE: Maintain DC Surge tank level and pressure to ensure proper system venting.

4.2.4 Vent DC piping

Slowly open the following valves until no more air escapes, then close the valves

- ___ DCV-123, "A" Supply Vent
- ___ DCV-125, DHHE-1A Inlet Vent
- ___ DCV-129, DHHE-1A Outlet Vent
- ___ DCV-160, "A" Return Vent
- ___ DCV-124, "B" Supply Vent
- ___ DCV-126, DHHE-1B Inlet Vent
- ___ DCV-130, DHHE-1B Outlet Vent
- ___ DCV-159, "B" Return Vent
- ___ DCV-164, DCHE-1A Outlet Vent
- ___ DCV-179, DCHE-1A Vent
- ___ DCV-163, DCHE-1B Outlet Vent
- ___ DCV-180, DCHE-1B Vent
- ___ DCV-161, AHF-15A Outlet Vent
- ___ DCV-162, AHF-15B Outlet Vent
- ___ DCV-132, MUP-1A Supply Vent
- ___ DCV-134, MUP-1A Supply Vent
- ___ DCV-136, MUP-1A Supply Vent
- ___ DCV-141, MUP-1A Return Vent
- ___ DCV-143, MUP-1A Return Vent
- ___ DCV-145, MUP-1A Return Vent
- ___ DCV-147, MUP-1C Supply Vent
- ___ DCV-149, MUP-1C Supply Vent
- ___ DCV-151, MUP-1C Supply Vent
- ___ DCV-156, MUP-1C Return Vent
- ___ DCV-158, MUP-1C Return Vent

Initial/Date

4.2 INITIAL FILLING AND VENTING OF DECAY HEAT CCC SYSTEM (Cont'd)

ACTIONS

DETAILS

NOTE: RWP-3A/3B is not required to be started if DC temperature is expected to remain less than 105°F without RW heat removal.

NOTE: RWV-150 will not properly control SW system temperature if RWP-3B is running.

4.2.5 Start DC flow to aid in venting system

1. — IF required, START RWP-3A
AND RWP-3B
2. — START DCP-1A
AND DCP-1B
3. — WHEN DCP-1A and DCP-1B have
run for approximately 5 min,
THEN STOP DCP-1A/1B
AND RWP-3A/3B (if started)

Initial/Date

4.2.6 Repeat Step 4.2.4

Initial/Date

4.3 FILLING AND VENTING DHP-1A/"A" DECAY HEAT TRAIN

ACTIONS	DETAILS
4.3.1 Ensure Valve Check List III is complete	o Refer to Enclosure 3
	<u>Initial/Date</u>

NOTE: Opening DHV-10 may cause backflow from the BWST.

4.3.2 Align fill and vent flow	1. <u> </u> OPEN DHV-8, "A" DH Loop path Recirc Isolation
	2. <u> </u> OPEN DHV-10, DH Recirc Isolation Bypass
	<u>Initial/Date</u>

4.3.3 Fill and vent "A" DH train	1. <u> </u> Using the motor operator handwheel, OPEN DHV-34 slowly until BWST flow is audibly detected
	2. <u> </u> Slowly open the following valves until no more air escapes, then close the valves
	<u> </u> DHV-19, DHP-1A Vent and observe DH-50-FI while venting DHP-1A casing
	<u> </u> DHV-84, DHP-1A Suction Header Vent
	<u> </u> DHV-16, DHP-1A Discharge Vent
	3. <u> </u> <u>WHEN</u> venting is complete, <u>THEN</u> CLOSE the following:
	<u> </u> DHV-34
	<u> </u> DHV-8
	<u> </u> DHV-10
	<u>Initial/Date</u>

4.4 FILLING AND VENTING DHP-1B "B" DECAY HEAT TRAIN

ACTIONS	DETAILS
4.4.1 Ensure Valve Check List III is complete	o Refer to Enclosure 3
<div>Initial/Date</div>	

NOTE: Opening DHV-10 may cause backflow from the BWST.

4.4.2 Align fill and vent flow path	1. <input type="checkbox"/> OPEN DHV-7, "B" DH Loop Recirc Isolation
	2. <input type="checkbox"/> OPEN DHV-10, DH Recirc Isolation Bypass
<div>Initial/Date</div>	

4.4.3 Fill and vent "B" DH train	1. <input type="checkbox"/> Using the motor operator handwheel, OPEN DHV-35 slowly until BWST flow is audibly detected
	2. <input type="checkbox"/> Slowly open the following valves until no more air escapes, then close the valves
	<input type="checkbox"/> DHV-30, DHP-1B Vent and observe DH-51-FI while venting DHP-1B casing
	<input type="checkbox"/> DHV-83, DHP-1B Suction Header Vent
	<input type="checkbox"/> DHV-26, DHP-1B Discharge Vent
	3. <input type="checkbox"/> <u>WHEN</u> venting is complete, <u>THEN</u> CLOSE the following:
	<input type="checkbox"/> DHV-35
	<input type="checkbox"/> DHV-7
	<input type="checkbox"/> DHV-10
<div>Initial/Date</div>	

4.5 ESTABLISHING DECAY HEAT REMOVAL

ACTIONS	DETAILS
4.5.1 <u>Initial Conditions</u>	
4.5.1.1 Plant cooldown is in progress per OP-209, Plant Cooldown	<u> </u> Initial/Date
4.5.1.2 Conduct a Pre-job briefing with all personnel involved	<u> </u> SSOD /Date
4.5.1.3 Ensure plant conditions will allow DH removal operation	<ul style="list-style-type: none">o Ensure the following conditions exist:<ul style="list-style-type: none">— RC temperature < 280°F— RC pressure within limits of OP-103B, curve 5 or 6— Reactor vessel level Within the Acceptable region of OP-103B, curves 16 and 18 <u> </u> Initial/Date
4.5.1.4 Ensure that there is no maintenance or testing of the switchyard supplying power to the DH train that will be in service	<p>Stop maintenance, modifications or testing of Switchyard that will be supplying power to DH Train <u>OR</u> Consider alternate electrical lineup</p> <u> </u> Initial/Date
4.5.1.5 Repower DHV-3	<ul style="list-style-type: none">o — CLOSE/ensure Closed breaker for DHV-3, ES MCC 3A-1 # 3C <u> </u> Initial/Date

4.5 ESTABLISHING DECAY HEAT REMOVAL (Cont'd)

ACTIONS

DETAILS

NOTE: Steps 4.5.1.6 and 4.5.1.7 may be performed any time during the cooldown after reaching Mode 4 but prior to placing decay heat removal inservice.

NOTE: Clockwise rotation of DCV-177-MS simultaneously opens DCV-177 (increasing cooling flow) and closes DCV-17 (decreasing bypass flow). Counterclockwise rotation causes the opposite results. The purpose of this is to maintain DCP-1A flow within a minimum and maximum range to prevent pump runout and deadhead conditions.

4.5.1.6 Align DHHE-1A cooler temperature controls for DH system operation

1. ____ Ensure instrument air is aligned to remote control stations and valve operators (Refer to Enclosure 5)
2. ____ CLOSE DCV-195, IA Supply Vent from DCV-177-MS
3. ____ OPEN DCV-194, IA Supply Isolation from DCV-177-MS to temperature control valves
4. ____ Ensure DHHE-1A control switch in 4160V ES Switchgear Room "A" is selected to "Control Room"
5. ____ Start DCP-1A
6. ____ Cycle DHHE-1A temperature control valves from the Control Room to visually verify proper operation of DCV-17 and DCV-177.
7. ____ Position DCV-177-MS rheostat at "0" (Minimum Cooling)
8. ____ Stop DCP-1A at the SSOD's Discretion (you may want to leave this pump running if this is the train you are placing in service)

Initial/Date

4.5 ESTABLISHING DECAY HEAT REMOVAL (Cont'd)

ACTIONS	DETAILS
<p>NOTE: Clockwise rotation of DCV-178-MS simultaneously opens DCV-178 (increasing cooling flow) and closes DCV-18 (decreasing bypass flow). Counterclockwise rotation causes the opposite results. The purpose of this is to maintain DCP-1B flow within a minimum and maximum range to prevent pump runout and deadhead conditions.</p>	
4.5.1.7 Align DHHE-1B cooler temperature controls for DH system operation	<ol style="list-style-type: none"> 1. — Ensure instrument air is aligned to remote control stations and valve operators (Refer to Enclosure 5) 2. — CLOSE DCV-197, IA Supply Vent from DCV-178-MS 3. — OPEN DCV-196, IA Supply Isolation from DCV-178-MS to temperature control valves 4. — Ensure DHHE-1B control switch in 4160V ES Switchgear Room "B" is selected to "Control Room" 5. — Start DCP-1B 6. — Cycle DHHE-1B temperature control valves from the Control Room to visually verify proper operation of DCV-18 and DCV-178 7. — Position DCV-178-MS rheostat at "0" (Minimum cooling) 8. — Stop DCP-1B at the SSOD's Discretion (you may want to leave this pump running if this is the train you are placing in service)
	_____/_____ Initial/Date
4.5.1.8 Determine whether RWV-150 should remain in service	<ul style="list-style-type: none"> o Evaluate current/desired SW operating conditions o Evaluate STS requirements o Evaluate which DH train is to be placed in service o Refer to OP-408 to remove RWV-150 from service
	_____/_____ Initial/Date

4.5 ESTABLISHING DECAY HEAT REMOVAL (Cont'd)

ACTIONS	DETAILS
4.5.2 <u>IF</u> DHP-1A is to be used for DH removal, <u>THEN</u> continue with this step, <u>OTHERWISE</u> GO TO Step 4.5.3	1. — Ensure the following are CLOSED: — DHV-8, "A" DH BWST Recirc Isolation — DHV-11, MUP Crosstie — DHV-34, BWST Suction Isolation — DHV-42, RB Sump Suction Isolation — DHV-75, "A" DH Purification Return Isolation — DHV-76, "B" DH Purification Return Isolation — DHV-105, "A" DH Purification Supply Isolation — DHV-106, "B" DH Purification Supply Isolation

NOTE: TS 3.6.6 must be entered when disabling BS Train.

2. Isolate BSP-1A suction to prevent transfer of RCS to spray header.
 1. — Ensure BSV-16 is open with breaker in lock/reset.
 2. — Place BSP-1A Control Switch in Normal-after-Stop and red tag to the SSOD
 3. — Rack out BSP-1A Breaker and red tag to the SSOD
 4. — Unlock and close breaker for BSV-17
 5. — Close BSV-17
 6. — Open Breaker for BSV-17 and lock in Lock Reset
3. OPEN the following:
 1. — DHV-39, "A" DH Supply isolation
IF excessive differential pressure exists when opening,
THEN DHV-120 may be cycled to equalize pressure
 2. — DHV-5, "A" DH Outlet isolation

Initial/Date

4.5 ESTABLISHING DECAY HEAT REMOVAL (Cont'd)

ACTIONS	DETAILS
---------	---------

NOTE: Auxiliary spray is not available via this valve alignment.

4.5.3 IF DHP-1B is to be used for
DH removal,
THEN continue with this step,
OTHERWISE GO TO Step 4.5.4

1. ____ Ensure the following are
CLOSED:
 - ____ DHV-7, "B" DH BWST Recirc
Isolation
 - ____ DHV-12, MUP Crosstie
 - ____ DHV-35, BWST Suction
Isolation
 - ____ DHV-43, RB Sump Suction
Isolation
 - ____ DHV-75, "A" DH
Purification Return
Isolation
 - ____ DHV-76, "B" DH
Purification Return
Isolation
 - ____ DHV-105, "A" DH
Purification Supply
Isolation
 - ____ DHV-106, "B" DH
Purification Supply
Isolation

NOTE: TS 3.6.6 must be entered when disabling BS Train.

2. Isolate BSP-1B suction to
prevent transfer of RCS to
spray header
 1. ____ Ensure BSV-17 is open with
breaker in lock/reset
 2. ____ Place BSP-1B Control Switch
in Normal-after-Stop and
Red Tag to the SSOD
 3. ____ Rack out BSP-1B breaker and
Red Tag to the SSOD
 4. ____ Unlock and close breaker
for BSV-16
 5. ____ Close BSV-16
 6. ____ Open Breaker for BSV-16 and
lock in Lock Reset

(4.5.3 Continued on following page)

4.5 ESTABLISHING DECAY HEAT REMOVAL (Cont'd)

ACTIONS	DETAILS
4.5.3 (Cont'd)	3. OPEN the following: 1. — DHV-40, "B" DH Supply Isolation IF excessive differential pressure exists when opening, THEN DHV-121 may be cycled to equalize pressure 2. — DHV-6 "B" DH Outlet Isolation
	Initial/Date

4.5.4 IF Loop A RCPs are in operation, THEN reduce RCS PRESS below ACIS settings	1. — RC Loop A < 225 PSIG per SPDS Low Range RCS PRESS (RC-147-PT) on Alpha Page, or RC-147-PII on Remote Shutdown Panel Section AB 2. — RC Loop B < 275 PSIG per RC-132-PI located in ES channel test cabinet 3 3. — Within limits of OP-103B, curve 5 or 6 4. Bypass DHV-4 ACIS interlock; — Place ACI Bypass Key in BYPASS (Act Chan Cab # 3) — Verify "DH VALVE ACI SYSTEM TROUBLE" annunciator is actuated
	Initial/Date

4.5 ESTABLISHING DECAY HEAT REMOVAL (Cont'd)

ACTIONS	DETAILS
4.5.5 <u>IF</u> Loop B RCPs are in operation, <u>THEN</u> reduce RCS PRESS below ACIS settings	<ol style="list-style-type: none"> 1. — RC Loop A < 275 PSIG per SPDS Low Range RCS PRESS (RC-147-PT) on Alpha Page, or RC-147-PII on Remote Shutdown Panel Section AB 2. — RC Loop B PRESS < 225 PSIG per RC-132-PI located in ES channel test cabinet 3 3. — Within limits of OP-103B, curve 5 or 6 4. Bypass DHV-3 ACIS interlock; <ul style="list-style-type: none"> — Place ACI Bypass Key in BYPASS (Act Chan Cab # 1) — Verify "DH VALVE ACI SYSTEM TROUBLE" annunciator is actuated

Initial/Date

4.5.6 Perform valve stroke timing checks on DHV-3, DHV-4, DHV-5, and DHV-6. These checks are not required if the valves have been checked within the past three months	o Refer to SP-435, Valve Testing During Cold Shutdown
--	---

Initial/Date

4.5 ESTABLISHING DECAY HEAT REMOVAL (Cont'd)

ACTIONS	DETAILS	
4.5.7 Align DH dropline and auxiliary spray for operation	o OPEN the following: ___ DHV-3 ___ DHV-4 ___ DHV-41 ___ DHV-91	<u> </u> Initial/Date
4.5.8 <u>IF</u> DHP-1A is to be used for DH removal, <u>THEN</u> continue with this step, <u>OTHERWISE</u> Go to Step 4.5.12 Start DH flow	1. ___ START DCP-1A 2. ___ START RWP-3A 3. ___ START DHP-1A 4. ___ Adjust DHV-110 to obtain a flowrate of approximately 3000 gpm 5. ___ Adjust DHP-1A low amp alarm as desired per Section 4.31	<u> </u> Initial/Date
4.5.9 Ensure proper lubrication of DHP-1A	o ___ Observe proper operation of Slinger Rings o ___ Ensure proper oil levels	<u> </u> Initial/Date
4.5.10 Perform Cyclone Separator adjustment if required	1. ___ Throttle DHV-103 to obtain a reading on DH-32-PI of 80 to 110 PSIG less than indicated on DH-31-PI 2. ___ Throttle DHV-104 to obtain a reading on DH-33-PI of 80 to 110 PSIG less than indicated on DH-31-PI 3. ___ Ensure DHV-103 and DHV-104 are sealed in their throttled position	<u> </u> Initial/Date

4.5 ESTABLISHING DECAY HEAT REMOVAL (Cont'd)

ACTIONS	DETAILS
<p>NOTE: A maximum step change of 25°F is allowable when stopping all RCPs with DH system in operation. A step change is defined as RCS T-Cold prior to stopping all RCPs, minus operating DH Cooler Outlet temperature after stopping all RCPs.</p> <p>NOTE: Clockwise rotation of DCV-177-MS simultaneously opens DCV-177 (increasing cooling flow) and closes DCV-17 (decreasing bypass flow). Counterclockwise rotation causes the opposite results. The purpose of this is to maintain DCP-1A flow within a minimum and maximum range to prevent pump runout and deadhead conditions.</p> <p>NOTE: Suspected failures of DCV-17 and/or DCV-177 can be cross-checked against expected DHHE-1A outlet temperatures (DH-2-T11), DCP-1A discharge pressure, and DC 'A' system flow (DC-61-FI, local at DCPs).</p> <p>NOTE: When required, the details for adjusting/controlling, (DCV-177-MS) DHHE-1A outlet temperature can be achieved by manually throttling DCV-177 and DCV-17 to obtain the desired position and action of the detail. For local manual operation of DCV-17 and DCV-177, refer to Enclosure 6 for guidance.</p>	
4.5.11 <u>WHEN</u> DHHE-1A outlet temperature has equalized with RCS, <u>THEN</u> determine DH and DC systems are thermally coupled, <u>AND</u> establish RCS cooling using the DH system	<ol style="list-style-type: none"> 1. — <u>WHEN</u> DHHE-1A outlet temperature (DH-2-T11) rises to RCS temperature, <u>THEN</u> adjust DCV-177-MS (MCB, PSA panel) clockwise to obtain a small but noticeable delta-T across DHHE-1A (DHP-1A suction, DH-6-T11, minus DHHE-1A outlet, DH-2-T11). 2. — <u>WHEN</u> DHHE-1A delta-T indicates adequate thermal coupling between DH and DC, <u>THEN</u> shutdown operating RCPs in accordance with Section 4.2 of OP-209. 3. — Adjust DCV-177-MS as required for desired cooldown rate and continue to perform SP-422, RCS Heatup & Cooldown Surveillance <p>(4.5.11 Continued on following page)</p>

4.5 ESTABLISHING DECAY HEAT REMOVAL (Cont'd)

ACTIONS	DETAILS
4.5.11 (Cont'd)	<p>4. — Following DCV-177-MS adjustments, monitor DHHE-1A outlet temperature for expected temperature changes</p> <p>5. — Ensure DCHE-1A delta RW temperature (RW-13-TI & RW-33-TI) is maintained < 10°F</p> <p>6. — Monitor PZR level for decreasing trends which could be indicative of overcooling or leaks in the DH system</p> <p>7. — <u>WHEN</u> RCS is < 110°F, <u>THEN</u> establish the Programmable Computer Alarm at 115°F for an Incore Thermocouple (preferably R258)</p>
	_____ Initial/Date

NOTE: RWV-150 will not properly control SW system temperature if RWP-3B is running.

4.5.12 <u>IF</u> DHP-1B is to be used for DH removal, <u>THEN</u> continue with this step Start DH flow	<p>1. — START DCP-1B</p> <p>2. — START RWP-3B</p> <p>3. — START DHP-1B</p> <p>4. — Adjust DHV-111 to obtain a flowrate of approximately 3000 gpm</p> <p>5. — Adjust DHP-1B low amp alarm as desired per Section 4.31</p>
	_____ Initial/Date

4.5.13 Ensure proper lubrication of DHP-1B	<p>o — Observe proper operation of Slinger Rings</p> <p>o — Ensure proper oil levels</p>
	_____ Initial/Date

4.5 ESTABLISHING DECAY HEAT REMOVAL (Cont'd)

ACTIONS	DETAILS
4.5.14 Perform Cyclone Separator adjustments as required	<ol style="list-style-type: none">1. — Throttle DHV-100 to obtain a reading on DH-35-PI of 80 to 110 PSIG less than indicated on DH-34-PI2. — Throttle DHV-101 to obtain a reading on DH-36-PI of 80 to 110 PSIG less than indicated on DH-34-PI3. — Ensure DHV-100 and DHV-101 are sealed in their throttled position

Initial/Date

4.5 ESTABLISHING DECAY HEAT REMOVAL (Cont'd)

ACTIONS	DETAILS
<p>NOTE: A maximum step change of 25°F is allowable when stopping all RCPs with DH system in operation. A step change is defined as RCS T-Cold prior to stopping all RCPs, minus operating DH Cooler Outlet temperature after stopping all RCPs.</p>	
<p>NOTE: Clockwise rotation of DCV-178-MS simultaneously opens DCV-178 (increasing cooling flow) and closes DCV-18 (decreasing bypass flow). Counterclockwise rotation causes the opposite results. The purpose of this is to maintain DCP-1B flow within a minimum and maximum range to prevent pump runout and deadhead conditions.</p>	
<p>NOTE: Suspected failures of DCV-18 and/or DCV-178 can be cross-checked against expected DHHE-1B outlet temperatures (DH-2-TI2), DCP-1B discharge pressure, and DC 'B' system flow (DC-62-FI, local at DCPs).</p>	
<p>NOTE: When required, the details for adjusting/controlling, (DCV-178-MS) DHHE-1B outlet temperature can be achieved by manually throttling DCV-178 and DCV-18 to obtain the desired position and action of the detail. For local manual operation of DCV-18 and DCV-178, refer to Enclosure 6 for guidance.</p>	

4.5.15 WHEN DHHE-1B outlet temperature has equalized with RCS,
THEN determine DH and DC systems are thermally coupled,
AND establish RCS cooling using the DH system

1. WHEN DHHE-1B outlet temperature (DH-2-TI2) rises to RCS temperature,
THEN adjust DCV-178-MS (MCB, PSA panel) clockwise to obtain a small but noticeable delta-T across DHHE-1B (DHP-1B suction, DH-6-TI2, minus DHHE-1B outlet, DH-2-TI2)
2. WHEN DHHE-1B delta-T indicates adequate thermal coupling between DH and DC,
THEN shutdown operating RCPs in accordance with Section 4.2 of OP-209
3. Adjust DCV-178-MS as required for desired cooldown rate and continue to perform SP-422, RCS Heatup & Cooldown Surveillance

(4.5.15 Continued on following page)

4.5 ESTABLISHING DECAY HEAT REMOVAL (Cont'd)

ACTIONS	DETAILS
4.5.15 (Cont'd)	<ul style="list-style-type: none">4. — Following DCV-178-MS adjustments, monitor DHHE-1B outlet temperature for expected temperature changes5. — Ensure DCHE-1B delta RW temperature (RW-12-TI & RW-32-TI) is maintained < 10°F6. — Monitor PZR level for decreasing trends which could be indicative of overcooling or leaks in the DH system7. — <u>WHEN</u> RCS is < 110°F, <u>THEN</u> establish the Programmable Computer Alarm at 115°F for an Incore Thermocouple (preferably R258)

Initial/Date

4.6 ALTERNATING DECAY HEAT TRAINS

ACTIONS	DETAILS	
4.6.1 <u>IF</u> the RCS is partially filled, establish reactor vessel level watch prior to changing flowpaths or starting equipment in the alternate train, <u>OTHERWISE</u> "N/A" this step	<ul style="list-style-type: none">o Refer to Limits and Precautions involving Reduced inventory operationo <u>IF</u> tygon tube level indication is unavailable in the Control Room via a camera/monitor, <u>THEN</u> assign a level watch at the tygon level indicator and establish communications capability with the Control Room	<div>Initial/Date</div>
4.6.1.1 Ensure that there is no maintenance or testing of the switchyard supplying power to the DH train that will be placed in service	Stop maintenance, modifications, or testing of Switchyard that will be supplying power to DH Train <u>OR</u> Consider alternate electrical lineup	<div>Initial/Date</div>
4.6.1.2 Inform Health Physics and Chemistry of swapping DH Trains		<div>Initial/Date</div>

4.6 ALTERNATING DECAY HEAT TRAINS (Cont'd)

ACTIONS	DETAILS
4.6.2 <u>IF</u> the "A" DH train is in service, <u>THEN</u> continue with this step, <u>OTHERWISE</u> GO TO Step 4.6.12	<p>Ensure the following are CLOSED:</p> <ol style="list-style-type: none"> 1. <input type="checkbox"/> DHV-7, "B" DH BWST Recirc Isolation <input type="checkbox"/> DHV-12, MUP Crosstie <input type="checkbox"/> DHV-35, BWST Suction Isolation <input type="checkbox"/> DHV-43, RB Sump Suction Isolation 2. <input type="checkbox"/> DHV-105, "A" DH Purification Supply Isolation <input type="checkbox"/> DHV-106, "B" DH Purification Supply Isolation 3. <input type="checkbox"/> DHV-75, "A" DH Purification Return Isolation <input type="checkbox"/> DHV-76, "B" DH Purification Return Isolation
	_____ Initial/Date

NOTE: TS 3.6.6 must be entered when disabling BS Train.

4.6.2.1 <u>IF</u> in Mode IV, <u>THEN</u> isolate BSP-1B, <u>OTHERWISE</u> N/A this step	<ol style="list-style-type: none"> 1. <input type="checkbox"/> Ensure BSV-17 is open with breaker in lock/reset 2. <input type="checkbox"/> Ensure BSP-1A Breaker is racked in 3. <input type="checkbox"/> Place BSP-1B control switch in Normal-after-Stop and red tag to the SSOD 4. <input type="checkbox"/> Rack out BSP-1B Breaker and red tag to the SSOD 5. <input type="checkbox"/> Unlock and close breaker for BSV-16 6. <input type="checkbox"/> Close BSV-16 7. <input type="checkbox"/> Open breaker for BSV-16 and lock in Lock Reset to prevent inadvertent injection of RCS into BS Header
	_____ Initial/Date

4.6 ALTERNATING DECAY HEAT TRAINS (Cont'd)

ACTIONS	DETAILS	
4.6.2.2 Open DH Pump isolation valves	OPEN the following: — DHV-40, "B" DH Inlet Isolation — DHV-6, "B" DH Outlet Isolation	<u> </u> Initial/Date
4.6.3 Ensure proper operation of DHHE-1B temperature control valves by cycling DCV-178-MS and visually observing valve movement	o Observe DCV-178 and DCV-18 o When complete, leave the controller and the DC valves in the zero ("0"), <u>no</u> cooling position	<u> </u> Initial/Date
4.6.4 Record the "A" DH train outlet temperature	DHHE-1A outlet Temperature: <u> </u>	<u> </u> Initial/Date
4.6.5 Decrease "A" DH train flow in anticipation of dual DHP operation	o Adjust DHP-1A low amp alarm as desired per Section 4.31 o Using DHV-110, decrease DH flowrate to approximately 1500 gpm	<u> </u> Initial/Date

4.6 ALTERNATING DECAY HEAT TRAINS (Cont'd)

ACTIONS	DETAILS
<p>*****</p> <p>CAUTION: Starting an idle ambient DH train will cause a cooldown. The intent of the following steps is to expeditiously recover temperature and minimize the resultant effective cooldown</p> <p>*****</p>	
<p>NOTE: RWV-150 will not properly control SW temperature if RWP-3B is running.</p>	
4.6.6 Start "B" DH train flow	<ol style="list-style-type: none"> 1. <input type="checkbox"/> START DCP-1B 2. <input type="checkbox"/> START RWP-3B 3. <input type="checkbox"/> START DHP-1B 4. <input type="checkbox"/> THROTTLE DHV-111 to maintain approximately 1500 gpm in "B" DH train
Initial/Date	
4.6.7 Ensure proper lubrication of DHP-1B	<ol style="list-style-type: none"> <input type="checkbox"/> Observe proper operation of Slinger Rings <input type="checkbox"/> Ensure proper oil levels
Initial/Date	
4.6.8 Transfer cooling from DHHE-1A to DHHE-1B	<ol style="list-style-type: none"> 1. Adjust DCV-177-MS to the zero ("0"), <u>no</u> cooling position, while adjusting DCV-178-MS to recover temperature to the value recorded in step 4.6.4
Initial/Date	

4.6 ALTERNATING DECAY HEAT TRAINS (Cont'd)

ACTIONS	DETAILS
4.6.9 Secure "A" DH train	<ol style="list-style-type: none"> 1. <input type="checkbox"/> STOP DHP-1A 2. <input type="checkbox"/> STOP RWP-3A 3. <input type="checkbox"/> STOP DCP-1A 4. <input type="checkbox"/> CLOSE the following: <ul style="list-style-type: none"> <input type="checkbox"/> DHV-5 <input type="checkbox"/> DHV-39 5. <input type="checkbox"/> Adjust DHV-111 to approx. 3000 gpm 6. <input type="checkbox"/> Adjust DCV-178-MS to recover temperature, as close as possible, to the value recorded in step 4.6.4 7. <input type="checkbox"/> Adjust DHP-1B low amp alarm as desired per Section 4.31
	_____ Initial/Date

NOTE: The temperature recorded in this step should be the temperature that was obtained after the "B" DH train has stabilized.

4.6.10 Determine the effective cooldown	<ol style="list-style-type: none"> 1. <input type="checkbox"/> Record DHHE-1B outlet temperature: _____ 2. <input type="checkbox"/> Calculate the effective cooldown (temp recorded in step 4.6.4 - the temp recorded above = effective cooldown) 3. <input type="checkbox"/> <u>IF</u> the effective cooldown calculated above is $>10^{\circ}\text{F}$ in any one hour period <u>THEN</u> refer to SP-422
	_____ Initial/Date

Independent Verification _____

4.6 ALTERNATING DECAY HEAT TRAINS (Cont'd)

ACTIONS	DETAILS
<p>NOTE: Clockwise rotation of DCV-178-MS simultaneously opens DCV-178 (increasing cooling flow) and closes DCV-18 (decreasing bypass flow). Counterclockwise rotation causes the opposite results. The purpose of this is to maintain DCP-1B flow within a minimum and maximum range to prevent pump runout and deadhead conditions.</p>	
<p>NOTE: When required, the details for adjusting/controlling, (DCV-178-MS) DHHE-1B outlet temperature can be achieved by manually throttling DCV-178 and DCV-18 to obtain the desired position and action of the detail. For local manual operation of DCV-18 and DCV-178, refer to Enclosure 6 for guidance.</p>	

4.6.11 Control RCS cooling by DHR

- o — Adjust DCV-178-MS to provide desired cooling
- o — Monitor DHP-1B suction temperature (DH-6-TI2) to ensure RCS cooling is effective
- o — Monitor DHHE-1B Discharge temperature (DH-2-TI2) and continue SP-422, RC System Heatup and Cooldown Surveillance until cooldown is terminated
- o — Monitor RW-12-TI and RW-32-TI Maintain DCHE-1B ΔT less than 10 °F
- o — Monitor PZR level. Decrease in PZR level could be due to overcooling or leak in Decay Heat System
- o — WHEN the RCS is < 110 °F
THEN establish the Programmable Computer Alarm at 115 °F for an Incore Thermocouple (Preferably R258)
- o — GO TO Step 4.6.22

Initial/Date

4.6 ALTERNATING DECAY HEAT TRAINS (Cont'd)

ACTIONS	DETAILS
4.6.12 Align the "A" DH train for operation	<p>Ensure the following are CLOSED:</p> <ol style="list-style-type: none"> 1. — DHV-8, "A" DH BWST Recirc Isolation — DHV-11, MUP Crosstie — DHV-34, BWST Suction Isolation — DHV-42, RB Sump Suction Isolation 2. — DHV-105, "A" DH Purification Supply Isolation — DHV-106, "B" DH Purification Supply Isolation 3. — DHV-75, "A" DH Purification Return Isolation — DHV-76, "B" DH Purification Return Isolation
	_____ Initial/Date

NOTE: TS 3.6.6 must be entered when disabling BS Train.

4.6.12.1 IF in Mode IV, <u>THEN</u> isolate BSP-1A, <u>OTHERWISE</u> N/A this step	<ol style="list-style-type: none"> 1. — Ensure BSV-16 is open with breaker in lock/reset 2. — Ensure BSP-1B Breaker is racked in 3. — Place BSP-1A control switch in Normal-after-Stop and red tag to the SSOD 4. — Rack out BSP-1A breaker and red tag to the SSOD 5. — Unlock and close breaker for BSV-17 6. — Close BSV-17 7. — Open breakers for BSV-17 and lock in Lock Reset to prevent inadvertent injection of RCS into BS Header
	_____ Initial/Date

4.6.12.2 Open DH Pump Isolation valves	<p>OPEN the following:</p> <ul style="list-style-type: none"> — DHV-39, "A" DH Inlet Isolation — DHV-5, "A" DH Outlet Isolation
	_____ Initial/Date

4.6 ALTERNATING DECAY HEAT TRAINS (Cont'd)

ACTIONS	DETAILS
4.6.13 Ensure proper operation of DHHE-1A temperature control valves by cycling DCV-177-MS and visually observing valve movement	<ul style="list-style-type: none"> o Observe DCV-177 and DCV-17 o When complete, leave the controller and the DC valves in the zero ("0"), <u>no</u> cooling position
	_____ Initial/Date

4.6.14 Record the "B" DH train outlet temperature	DHHE-1B outlet Temperature: _____
	_____ Initial/Date

4.6.15 Decrease "B" DH train flow in anticipation of dual DHP operation	<ul style="list-style-type: none"> o Adjust DHP-1B low amp alarm as desired per Section 4.31 o Using DHV-111, decrease DH flowrate to approximately 1500 gpm
	_____ Initial/Date

CAUTION: Starting an idle ambient DH train will cause a cooldown. The intent of the following steps is to expeditiously recover temperature and minimize the resultant effective cooldown

4.6.16 Start "A" DH train flow	<ol style="list-style-type: none"> 1. ____ START DCP-1A 2. ____ START RWP-3A 3. ____ START DHP-1A 4. ____ THROTTLE DHV-110 to maintain approximately 1500 gpm in "A" DH train
	_____ Initial/Date

4.6 ALTERNATING DECAY HEAT TRAINS (Cont'd)

ACTIONS	DETAILS	
4.6.17 Ensure proper lubrication of DHP-1A	<ul style="list-style-type: none"> o <input type="checkbox"/> Observe proper operation of Slinger Rings o <input type="checkbox"/> Ensure proper oil levels 	<u>Initial/Date</u>
4.6.18 <u>Transfer cooling from DHHE-1B to DHHE-1A</u>	<ul style="list-style-type: none"> 1. Adjust DCV-178-MS to the zero ("0"), <u>no</u> cooling position, while adjusting DCV-177-MS to recover temperature to the value recorded in step 4.6.14 	<u>Initial/Date</u>
4.6.19 Secure "B" DH train	<ul style="list-style-type: none"> 1. <input type="checkbox"/> STOP DHP-1B 2. <input type="checkbox"/> STOP RWP-3B 3. <input type="checkbox"/> STOP DCP-1B 4. CLOSE the following: <ul style="list-style-type: none"> <input type="checkbox"/> DHV-6 <input type="checkbox"/> DHV-40 5. <input type="checkbox"/> Adjust DHV-110 to approx. 3000 gpm 6. <input type="checkbox"/> Adjust DCV-177-MS to recover temperature, as close as possible, to the value recorded in step 4.6.14 7. <input type="checkbox"/> Adjust DHP-1A low amp alarm as desired per Section 4.31 	<u>Initial/Date</u>

4.6 ALTERNATING DECAY HEAT TRAINS (Cont'd)

ACTIONS

DETAILS

NOTE: The temperature recorded in this step should be the temperature that was obtained after the "A" DH train has stabilized.

4.6.20 Determine the effective
cooldown

1. ____ Record DHHE-1A outlet
temperature: ____
2. ____ Calculate the effective
cooldown (temp recorded in
step 4.6.14 - the temp
recorded above = effective
cooldown)
____ - ____ = ____
3. ____ IF the effective cooldown
calculated above is $>10^{\circ}\text{F}$ in
any one hour period
THEN refer to SP-422

Initial/Date

Independent Verification _____

4.6 ALTERNATING DECAY HEAT TRAINS (Cont'd)

ACTIONS	DETAILS
<p>NOTE: Clockwise rotation of DCV-177-MS simultaneously opens DCV-177 (increasing cooling flow) and closes DCV-17 (decreasing bypass flow). Counterclockwise rotation causes the opposite results. The purpose of this is to maintain DCP-1A flow within a minimum and maximum range to prevent pump runout and deadhead conditions.</p>	
<p>NOTE: When required, the details for adjusting/controlling, (DCV-177-MS) DHHE-1A outlet temperature can be achieved by manually throttling DCV-177 and DCV-17 to obtain the desired position and action of the detail. For local manual operation of DCV-17 and DCV-177, refer to Enclosure 6 for guidance.</p>	

- 4.6.21 Control RCS cooling by DHR
- o — Adjust DCV-177-MS to provide desired cooling
 - o — Monitor DHP-1A suction temperature (DH-6-TI1) to ensure RCS cooling is effective
 - o — Monitor DHHE-1A Discharge temperature (DH-2-TI1) and continue SP-422, RC System Heatup and Cooldown Surveillance until cooldown is terminated
 - o — Monitor RW-13-TI and RW-33 TI Maintain DCHE-1A ΔT less than 10 °F
 - o — Monitor PZR level. Decrease in PZR level could be due to overcooling or leak in Decay Heat System
 - o — WHEN the RCS is < 110 °F
THEN establish the Programmable Computer Alarm at 115 °F for an Incore Thermocouple (Preferably R258)

Initial/Date

4.6 ALTERNATING DECAY HEAT TRAINS (Cont'd)

ACTIONS	DETAILS
4.6.22 If reactor vessel level is ≥ 132 feet, secure the reactor vessel level watch if stationed, otherwise, "N/A" this step	

Initial/Date

4.7 RESTARTING DECAY HEAT REMOVAL AFTER PUMP TRIP

ACTIONS	DETAILS
<p>NOTE: <u>IF</u> both Decay Heat Trains fail to operate, <u>THEN</u> immediately GO TO EOP-11, Loss of Decay Heat Removal.</p>	
<p>4.7.1 <u>IF</u> the RCS is partially filled, <u>OR</u> cause of DHP tripping is unknown, <u>THEN</u> ensure a system conditions for restarting a Decay Heat train have been reviewed</p>	<ul style="list-style-type: none"> o — Ensure RCS level Within the Acceptable region of OP-103B curves 16 and 18. o — Possible system air entrainment or gas binding has been considered. Refer to Sections 4.3 and 4.4 as required o — Other potential causes for DHP tripping have been considered
	Initial/Date

<p>4.7.2 Align the "A" DH train for operation if desired, <u>OTHERWISE</u> go to Step 4.7.6</p>	<p>Ensure the following are CLOSED:</p> <ul style="list-style-type: none"> — DHV-8, "A" DH BWST Recirc Isolation — DHV-11, MUP Crosstie — DHV-34, BWST Suction Isolation — DHV-42, RB Sump Suction Isolation — DHV-75, "A" DH Purification Return Isolation — DHV-76, "B" DH Purification Return Isolation — DHV-105, "A", DH Purification Supply Isolation — DHV-106, "B" DH Purification Supply Isolation — Position DCV-177-MS rheostat at "0" (Minimum cooling)
	Initial/Date

NOTE: TS 3.6.6 must be entered when disabling BS Train.

<p>4.7.2.1 <u>IF</u> in Mode IV, <u>THEN</u> isolate BSP-1A, <u>OTHERWISE</u> N/A this step.</p>	<ol style="list-style-type: none"> 1. — Ensure BSV-16 is open with breaker in lock/reset 2. — Ensure BSP-1B Breaker is racked in 3. — Place BSP-1A control switch in Normal-after-Stop and red tag to the SSOD
	(4.7.2.1 Continued on following page)

4.7 RESTARTING DECAY HEAT REMOVAL AFTER PUMP TRIP (Cont'd)

ACTIONS	DETAILS
4.7.2.1 (Cont'd)	4. <input type="checkbox"/> Rack out BSP-1A Breaker and red tag to the SSOD 5. <input type="checkbox"/> Unlock and close breaker for BSV-17 6. <input type="checkbox"/> Close BSV-17 7. <input type="checkbox"/> Open breaker for BSV-17 and lock in Lock Reset to prevent inadvertent injection of RCS into BS Header <div style="text-align: right;">_____ Initial/Date</div>
4.7.2.2 Open DH Pump isolation valves	OPEN the following: 1. <input type="checkbox"/> DHV-39, "A" DH Inlet Isolation <u>IF</u> excessive differential pressure exists when opening, <u>THEN</u> DHV-120 may be cycled to equalize pressure 2. <input type="checkbox"/> DHV-5, "A" DH Outlet Isolation <div style="text-align: right;">_____ Initial/Date</div>
4.7.3 Verify DH Drop line is properly aligned	o <input type="checkbox"/> OPEN/verify Open the following: <input type="checkbox"/> DHV-3 <input type="checkbox"/> DHV-4 <input type="checkbox"/> DHV-41 <div style="text-align: right;">_____ Initial/Date</div>
4.7.4 Start "A" DH train flow	1. <input type="checkbox"/> START DCP-1A 2. <input type="checkbox"/> START RWP-3A 3. <input type="checkbox"/> START DHP-1A 4. <input type="checkbox"/> THROTTLE DHV-110 to maintain approximately 3000 gpm in "A" DH train 5. <input type="checkbox"/> Adjust DHP-1A low amp alarm as desired per Section 4.31 <div style="text-align: right;">_____ Initial/Date</div>

4.7 RESTARTING DECAY HEAT REMOVAL AFTER PUMP TRIP (Cont'd)

ACTIONS	DETAILS
4.7.4.1 Ensure proper lubrication of DHP-1A	<ul style="list-style-type: none"> o — Observe proper operation of Slinger Rings o — Ensure proper oil levels
	_____ Initial/Date

NOTE: Clockwise rotation of DCV-177-MS simultaneously opens DCV-177 (increasing cooling flow) and closes DCV-17 (decreasing bypass flow). Counterclockwise rotation causes the opposite results. The purpose of this is to maintain DCP-1A flow within a minimum and maximum range to prevent pump runout and deadhead conditions.

NOTE: When required, the details for adjusting/controlling, (DCV-177-MS) DHHE-1A outlet temperature can be achieved by manually throttling DCV-177 and DCV-17 to obtain the desired position and action of the detail. For local manual operation of DCV-17 and DCV-177, refer to Enclosure 6 for guidance.

- | | |
|----------------------------------|--|
| 4.7.5 Control RCS cooling by DHR | <ul style="list-style-type: none"> o — Adjust DCV-177-MS to provide desired cooling o — Monitor DHP-1A suction temperature (DH-6-T11) to ensure RCS cooling is effective o — Monitor DHHE-1A Discharge temperature (DH-2-T11) and continue SP-422, RC System Heatup and Cooldown Surveillance until cooldown is terminated o — Monitor RW-13-TI and RW-33 TI Maintain DCHE-1A ΔT less than 10 °F o — Monitor PZR level. Decrease in PZR level could be due to overcooling or leak in Decay Heat System o — WHEN the RCS is < 110 °F
THEN establish the Programmable Computer Alarm at 115 °F for an Incore Thermocouple (Preferably R258) o — GO TO Step 4.7.10 |
|----------------------------------|--|

Initial/Date

4.7 RESTARTING DECAY HEAT REMOVAL AFTER PUMP TRIP (Cont'd)

ACTIONS	DETAILS
4.7.6 Align the "B" DH train for operation	<p>Ensure the following are CLOSED:</p> <ul style="list-style-type: none"> — DHV-7, "B" DH BWST Recirc Isolation — DHV-12, MUP Crosstie — DHV-35, BWST Suction Isolation — DHV-43, RB Sump Suction Isolation — DHV-75, "A" DH Purification Return Isolation — DHV-76, "B" DH Purification Return Isolation — DHV-105, "A" DH Purification Supply Isolation — DHV-106, "B" DH Purification Supply Isolation — Position DCV-178-MS rheostat at "0" (Minimum cooling)
	_____ Initial/Date

NOTE: TS 3.6.6 must be entered when disabling BS Train.

4.7.6.1 <u>IF</u> in Mode IV, <u>THEN</u> isolate BSP-1B, <u>OTHERWISE</u> , N/A this step	<ol style="list-style-type: none"> 1. — Ensure BSV-17 is open with breaker in lock/reset 2. — Ensure BSP-1A Breaker is Racked In 3. — Place BSP-1B control switch in Normal-after-Stop and red tag to the SSOD 4. — Rack out BSP-1B Breaker and red tag to the SSOD 5. — Unlock and close breaker for BSV-16 6. — Close BSV-16 7. — Open Breaker for BSV-16 and lock in Lock Reset to prevent inadvertent injection of RCS into BS Header
	_____ Initial/Date

4.7 RESTARTING DECAY HEAT REMOVAL AFTER PUMP TRIP (Cont'd)

ACTIONS	DETAILS
4.7.6.2 Open DH Pump isolation valves	OPEN the following: 1. <input type="checkbox"/> DHV-40, "B" DH Inlet Isolation IF excessive differential pressure exists when opening, THEN DHV-121 may be cycled to equalize pressure 2. <input type="checkbox"/> DHV-6, "B" DH Outlet Isolation <div>Initial/Date</div>
4.7.7 Verify DH Drop line is properly aligned	<input type="checkbox"/> OPEN/verify Open the following: <input type="checkbox"/> DHV-3 <input type="checkbox"/> DHV-4 <input type="checkbox"/> DHV-41 <div>Initial/Date</div>
NOTE: RWV-150 will not properly control SW temperature if RWP-3B is running.	
4.7.8 Start "B" DH train flow	1. <input type="checkbox"/> START DCP-1B 2. <input type="checkbox"/> START RWP-3B 3. <input type="checkbox"/> START DHP-1B 4. <input type="checkbox"/> THROTTLE DHV-111 to maintain approximately 3000 gpm in "B" DH train 5. <input type="checkbox"/> Adjust DHP-1B low amp alarm as desired per Section 4.31 <div>Initial/Date</div>
4.7.8.1 Ensure proper lubrication of DHP-1B	<input type="checkbox"/> Observe proper operation of Slinger Rings <input type="checkbox"/> Ensure proper oil levels <div>Initial/Date</div>

ACTIONS	DETAILS
<p>NOTE: Clockwise rotation of DCV-178-MS simultaneously opens DCV-178 (increasing cooling flow) and closes DCV-18 (decreasing bypass flow). Counterclockwise rotation causes the opposite results. The purpose of this is to maintain DCP-1B flow within a minimum and maximum range to prevent pump runout and deadhead conditions.</p> <p>NOTE: When required, the details for adjusting/controlling, (DCV-178-MS) DHHE-1B outlet temperature can be achieved by manually throttling DCV-178 and DCV-18 to obtain the desired position and action of the detail. For local manual operation of DCV-18 and DCV-178, refer to Enclosure 6 for guidance.</p>	

4.7.9 Control RCS cooling by DHR

- o — Adjust DCV-178-MS to provide desired cooling
- o — Monitor DHP-1B suction temperature (DH-6-TI2) to ensure RCS cooling is effective
- o — Monitor DHHE-1B Discharge temperature (DH-2-TI2) and continue SP-422, RC System Heatup and Cooldown Surveillance until cooldown is terminated
- o — Monitor RW-12-TI and RW-32-TI Maintain DCHE-1B ΔT less than 10 °F
- o — Monitor PZR level. Decrease in PZR level could be due to overcooling or leak in Decay Heat System
- o — WHEN the RCS is < 110 °F
THEN establish the Programmable Computer Alarm at 115 °F for an Incore Thermocouple (Preferably R258)

Initial/Date

4.7 RESTARTING DECAY HEAT REMOVAL AFTER PUMP TRIP (Cont'd)

ACTIONS	DETAILS
4.7.10 If reactor vessel level is \geq 132 feet, secure the reactor vessel watch if stationed, otherwise, "N/A" this step	<u> </u> Initial/Date
4.7.11 Re-establish DH purification as required	o Refer to Section 4.10 or 4.11 <u> </u> Initial/Date

4.8 PLACING DCHE-1A IN LAYUP

ACTIONS

DETAILS

CAUTION: Ensure cooling water is maintained to operating makeup pumps
prior to securing DCP-1A.

4.8.1 IF flow exists in "A" DC
train,
THEN secure flow,
OTHERWISE "N/A" this step

1. ☐ STOP RWP-3A train,
2. ☐ STOP DCP-1A

Initial/Date

4.8.2 Ensure all "B" side ES
equipment is operable

Initial/Date

4.8.3 Remove Control power for
RWP-3A

- ☐ Open DC knife switch on the
breaker for RWP-3A
- ☐ Refer to Technical
Specification actions

Initial/Date

4.8.4 Drain seawater side of
DCHE-1A

- ☐ OPEN RWV-77, DCHE-1A Drain
- ☐ OPEN RWV-73, DCHE-1A Vent
- ☐ OPEN RWV-75, DCHE-1A Drain

Initial/Date

4.8 PLACING DCHE-1A IN LAYUP (Cont'd)

ACTIONS	DETAILS
4.8.5 <u>WHEN</u> DCHE-1A is drained, <u>THEN</u> fill with demin water	1. <input type="checkbox"/> CLOSE RWV-77, Inlet Drain 2. <input type="checkbox"/> Connect a hose between DWV-336 and RWV-75 <u>AND</u> OPEN DWV-336 3. <input type="checkbox"/> <u>WHEN</u> demin water flows from RWV-73, <u>THEN</u> CLOSE DWV-336 4. <input type="checkbox"/> CLOSE the following valves: 1. <input type="checkbox"/> RWV-75, Outlet Drain 2. <input type="checkbox"/> RWV-73, Vent 5. <input type="checkbox"/> Remove and Store DW hose

Initial/Date

4.8.6 <u>WHEN</u> DCHE-1A fill is complete <u>THEN</u> restore RWP-3B to operable status	o <input type="checkbox"/> Close DC knife switch on the breaker for RWP-3A and verify power indications in control room o <input type="checkbox"/> Exit actions of Technical Specifications
---	--

Initial/Date

4.9 PLACING DCHE-1B IN LAYUP

ACTIONS	DETAILS	
***** CAUTION: Ensure cooling water is maintained to operating makeup pumps prior to securing DCP-1B. *****		
4.9.1 <u>IF</u> flow exists in "B" DC train, <u>THEN</u> secure flow, <u>OTHERWISE</u> "N/A" this step	1. <input type="checkbox"/> STOP RWP-3B train, 2. <input type="checkbox"/> STOP DCP-1B	<u> </u> Initial/Date
4.9.2 Ensure all "A" side ES equipment is operable		<u> </u> Initial/Date
4.9.3 Remove Control power for RWP-3B	<input type="checkbox"/> Open DC knife switch on the breaker for RWP-3B <input type="checkbox"/> Refer to Technical Specifications actions	<u> </u> Initial/Date
4.9.4 Drain seawater side of DCHE-1B	<input type="checkbox"/> OPEN RWV-78, DCHE-1B Drain <input type="checkbox"/> OPEN RWV-74, DCHE-1B Vent <input type="checkbox"/> OPEN RWV-76, DCHE-1B Drain	<u> </u> Initial/Date

4.9 PLACING DCHE-1B IN LAYUP (Cont'd)

ACTIONS	DETAILS
4.9.5 <u>WHEN</u> DCHE-1B is drained, <u>THEN</u> fill with demin water	<ol style="list-style-type: none"> 1. <input type="checkbox"/> CLOSE RWV-78, Inlet Drain 2. <input type="checkbox"/> Connect a hose between DWV-336 and RWV-76, Outlet drain 3. <input type="checkbox"/> OPEN DWV-336 4. <input type="checkbox"/> <u>WHEN</u> demin water flows from RWV-74, <u>THEN</u> CLOSE DWV-336 5. <input type="checkbox"/> CLOSE the following valves: <ol style="list-style-type: none"> 1. <input type="checkbox"/> RWV-76, Outlet drain 2. <input type="checkbox"/> RWV-74, Vent 6. <input type="checkbox"/> Remove and store DW hose

Initial/Date

4.9.6 <u>WHEN</u> DCHE-1B fill is complete <u>THEN</u> restore RWP-3B to operable status	<ol style="list-style-type: none"> o <input type="checkbox"/> Close DC knife switch on the breaker for RWP-3B and verify power indication in control room o <input type="checkbox"/> Exit actions of Technical Specifications
---	---

Initial/Date

4.10 DECAY HEAT SYSTEM PURIFICATION USING MAKEUP & PURIFICATION SYSTEM

ACTIONS		DETAILS
<p>*****</p> <p>CAUTION: This flow path shall not be used when RC pressure is ≥ 100 PSIG to prevent lifting MU System relief valves.</p> <p>*****</p>		
<p>*****</p> <p>CAUTION: Performance of this section could affect Decay Heat removal during drain down conditions.</p> <p>*****</p>		
4.10.1	Ensure flowpath is established between the MU&P pre-filter inlets and the MU&P letdown filter outlets	<p>o Refer to OP-402, Makeup and Purification System</p> <p>Initial/Date</p>
4.10.2	Ensure that the Decay Heat Removal System is in operation per Section 4.5 of this procedure	<p>Initial/Date</p>
4.10.3	Isolate makeup tank from purification flowpath	<p>o CLOSE MUV-357</p> <p>Initial/Date</p>
<p>*****</p> <p>CAUTION: Closing MUV-90 or MUV-91 may result in damage to letdown filter pressure instrumentation.</p> <p>*****</p>		
4.10.4	Align letdown filter outlets for DH purification	<p>o CLOSE MUV-182 MU-18-DPT Iso.</p> <p>o OPEN the following:</p> <p> ___ MUV-203, MUFL-1A Outlet</p> <p> ___ MUV-202, MUFL-1B Outlet</p> <p> ___ MUV-521, MU-18-DPT Isol.</p> <p>Initial/Date</p>

4.10 DECAY HEAT SYSTEM PURIFICATION USING MAKEUP & PURIFICATION SYSTEM
(Cont'd)

ACTIONS	DETAILS
4.10.5 Start DH purification	<ol style="list-style-type: none">1. <u> </u> OPEN DHV-75 ("A" DH train) <u> </u> OR DHV-76 ("B" DH train), Letdown Filter Supply to DH2. Monitor Make up Purification pressure at MU-105-PI near Prefilter Room and maintain less than 100 PSIG. <u> </u> Energize and throttle OPEN DHV-105 ("A" DH train) <u> </u> OR DHV-106 ("B" DH train), DH Supply to MU&P, until desired flowrate is obtained3. <u> </u> Adjust DHV-110 <u>OR</u> DHV-111 to limit DH flow \leq 3000 gpm <div style="text-align: right;">_____ Initial/Date</div>

4.10.6 <u>WHEN</u> DH purification is no longer desired, <u>THEN</u> secure purification lineup	<ol style="list-style-type: none">1. <u> </u> CLOSE and de-energize: <u> </u> DHV-105 <u> </u> DHV-1062. <u> </u> CLOSE the following: <u> </u> DHV-75 <u> </u> DHV-763. <u> </u> Adjust DHV-110 <u>OR</u> DHV-111 to maintain DH flowrate \leq 3000 gpm <div style="text-align: right;">_____ Initial/Date</div>
--	---

4.10.7 Restore MU&P lineup	<ol style="list-style-type: none">o <u> </u> RESTORE the following: <u> </u> CLOSE MUV-203 <u> </u> CLOSE MUV-202 <u> </u> OPEN MUV-357 <u> </u> CLOSE MUV-521 <u> </u> OPEN MUV-182 <div style="text-align: right;">_____ Initial/Date</div>
----------------------------	---

4.11 DECAY HEAT SYSTEM PURIFICATION USING SPENT FUEL SYSTEM

ACTIONS	DETAILS
***** CAUTION: Performance of this section could affect Decay Heat removal during drain down conditions. *****	
4.11.1 Notify Chemistry and Health Physics of impending lineup change	<u>Initial/Date</u>
4.11.2 <u>IF</u> Spent Fuel Cooling System is in operation, <u>THEN</u> ensure cooling is being accomplished by SFP-1A and SFHE-1A only	o Refer to OP-406, Spent Fuel Cooling System <u>Initial/Date</u>
4.11.3 Ensure Decay Heat System is in operation per Section 4.5 of this procedure	<u>Initial/Date</u>
4.11.4 Ensure borated water recirculation is stopped	<u>Initial/Date</u>
4.11.5 Ensure Spent Fuel System can support DH purification	o — Ensure the following are filled and vented: — SFDM-1 — SFFL-1A — SFFL-1B o — Ensure Spent Fuel System boron concentration is \geq RCS boron concentration SF boron _____ ppm RCS boron _____ ppm <u>Initial/Date</u>

4.11 DECAY HEAT SYSTEM PURIFICATION USING SPENT FUEL SYSTEM (Cont'd)

ACTIONS	DETAILS
4.11.6 Align Spent Fuel Cooling System for DH purification	<p>1. — CLOSE/ensure CLOSED the following:</p> <ul style="list-style-type: none">— SFV-50, SF Train Cross-tie— SFV-49, "B" Train Disch— SFV-46, BWST Isolation— SFV-38, BWST Recirc Iso— SFV-66, SF Filter Byp— SFV-68, SFFL-1B Inlet— SFV-69, SFFL Crosstie— SFV-77, SFFL Crosstie— SFV-76, SFFL-1B Disch— SFV-62, DW Isolation— SFV-91, DW Isolation— SFV-67, SF Filter Byp— SFV-54, SF Pool Iso— SFV-55, BWST Isolation <p>2. — OPEN/ensure OPEN the following:</p> <ul style="list-style-type: none">— SFV-71, SFFL-1A Inlet— SFV-75, SFFL-1A Outlet— SFV-100, SFDM-1 Inlet— SFV-65, SFDM-1 Outlet— SFV-70, SFFL-1B Inlet— SFV-78, SFFL-1B Disch— SFV-43, SF Filter Iso

Initial/Date

4.11 DECAY HEAT SYSTEM PURIFICATION USING SPENT FUEL SYSTEM (Cont'd)

ACTIONS	DETAILS
---------	---------

CAUTION: Ensure spent fuel purification pressure does not approach SF relief valve setting (125 PSIG) when initiating purification flow.

4.11.7 Start DH purification flow

1. ☐ Ensure CLOSED DHV-9 & 10, BWST Recirc Isolations
2. ☐ OPEN SFV-87, DH Supply Iso
3. ☐ OPEN SFV-85, DH Suction Iso
4. ☐ OPEN DHV-7 OR DHV-8, DH Recirc Isolation, as applicable
5. ☐ OPEN DHV-48, DH Outlet to Spent Fuel
6. ☐ Throttle DHV-5 OR DHV-6 to achieve approximately 150 gpm at SF-2-FI on 143 ft elevation. This may require readjustment of DHV-110/111 as applicable

Initial/Date

4.11.8 WHEN SF purification is no longer desired, THEN secure purification lineup

1. ☐ CLOSE the following:
☐ SFV-85
☐ SFV-87
☐ DHV-7 OR DHV-8
☐ DHV-48
2. ☐ OPEN DHV-5 OR DHV-6. This may require readjustment of DHV-110/111 as applicable
3. ☐ Restore Spent Fuel Cooling System as required per OP-406

Initial/Date

4.12 DH OPERATION DURING A LOCA

ACTIONS

DETAILS

CAUTION: This procedure section establishes DHR which may result in
elevated radiation levels in the Auxiliary Building.

NOTE: RCS pressure should be maintained above the RCP NPSH curve for
the existing RCP operating combination per Curve 19 of OP-103B
unless establishing DHR.

NOTE: This procedure section does not allow simultaneous DHR and RCP
operation.

NOTE: The performance of this section will result in one DHP
operating in LPI mode, with the other operating in the Decay
Heat Removal mode.

4.12.1 Initial Conditions

- o PZR level \geq 50"
- o RCS cooldown in progress
- o Adequate Subcooling Margin exists

Initial/Date

4.12.2 IF DHV-3 is not powered, THEN close breaker for DHV-3

- o ____ Unlock and Close breaker
- o ____ ES MCC 3A1 95' Aux Bld

Initial/Date

NOTE: Aligning DHP-1A for DH removal is preferred, to enable spray
and maintain LPI capabilities using DHP-1B.

4.12.3 IF two LPI pumps are running, THEN determine which LPI pump should be aligned for DH removal


- o ____ IF DHP-1A is to be aligned for
DH removal,
THEN GO TO Step 4.12.4
- o ____ IF DHP-1B is to be aligned for
DH removal,
THEN GO TO Step 4.12.19

Initial/Date

4.12 DH OPERATION DURING A LOCA (Cont'd)

ACTIONS

DETAILS



- 4.12.4 IF DHP-1B is providing suction to HPI pumps,
THEN ensure the MUP suction flow path is properly aligned

- ☐ OPEN/Ensure OPEN the following:
- ☐ DHV-12
- ☐ MUV-62
- ☐ MUV-69

Initial/Date

CAUTION: IF LPI is providing suction to MUP(s),
THEN MUP amps and flow should be carefully monitored while
securing a DH pump.

- 4.12.5 Stop DHP-1A

Initial/Date

- 4.12.6 Ensure DH cooler is properly aligned for Decay Heat Removal Operation

- ☐ Refer to Step 4.5.1.6

Initial/Date

4.12 DH OPERATION DURING A LOCA (Cont'd)

ACTIONS	DETAILS	
4.12.7 Establish DHP-1A for Decay Heat Removal Operation	1. ___ Ensure the following valves are closed: ___ DHV-8 ___ DHV-11 ___ DHV-34 ___ DHV-42 ___ DHV-75 ___ DHV-76 ___ DHV-105 ___ DHV-106 ___ DHV-40 2. ___ Open the following valves: <u>IF</u> DHV-39 binds when opening, <u>THEN</u> DHV-120 may be opened to equalize pressure ___ DHV-39 ___ DHV-5	<div>Initial/Date</div> <hr/>
4.12.8 Ensure DH/LPI train cooling water pumps are operating	o DCP-1A o RWP-3A	<div>Initial/Date</div> <hr/>
NOTE: Violation of the RCP NPSH curves may be necessary to establish DHR. Operation in this condition with RCP(s) running should be minimized in both magnitude and duration.		
4.12.9 Establish RCS conditions to enable placing DHR in service	o Ensure RCS temperature $\leq 280^{\circ}\text{F}$ o Ensure RCS pressure ≤ 200 PSIG	<div>Initial/Date</div> <hr/>

4.12 DH OPERATION DURING A LOCA (Cont'd)

ACTIONS	DETAILS
4.12.10 Trip all running RCPs	<ul style="list-style-type: none"> o RCP-1A o RCP-1B o RCP-1C o RCP-1D
	_____ Initial/Date

NOTE: Whenever the RB 4 PSIG Isolation ES feature actuates and the RCS pressure is sufficient to overcome the head or height of the Spray Header, then aligning the DH drop line to the RCS may initiate RB Spray and cause the RCS to depressurize.

4.12.11 Isolate 'A' train RB spray header as required and align DH drop line to 'A' train DH suction	<ol style="list-style-type: none"> 1. ____ IF the 4 PSIG Isolation ES feature has actuated, AND it has been BYPASSED, THEN place BSV-3 into MANUAL and close BSV-3 IF NOT actuated then verify BSV-3 closed 2. ____ Open DHV-3 3. ____ Open DHV-4 4. ____ Open DHV-41
	_____ Initial/Date

4.12.12 Establish DHR flow	<ol style="list-style-type: none"> 1. ____ Start DHP-1A 2. ____ Establish \approx 3000 gpm flow by adjusting DHV-110, A-Train flow control valve
	_____ Initial/Date

4.12 DH OPERATION DURING A LOCA (Cont'd)

ACTIONS	DETAILS
---------	---------

NOTE: Clockwise rotation of DCV-177-MS simultaneously opens DCV-177 (increasing cooling flow) and closes DCV-17 (decreasing bypass flow). Counterclockwise rotation causes the opposite results. The purpose of this is to maintain DCP-1A flow within a minimum and maximum range to prevent pump runout and deadhead conditions.

NOTE: When required, the details for adjusting/controlling, (DCV-177-MS) DHHE-1A outlet temperature can be achieved by manually throttling DCV-177 and DCV-17 to obtain the desired position and action of the detail. For local manual operation of DCV-17 and DCV-177, refer to Enclosure 6 for guidance.

4.12.13 Lower RCS temperature to
≤ 200°F

o Adjust DHHE cooling using DCV-177-MS for DHHE-1A

Initial/Date

4.12.14 Reduce RCS pressure as low as possible to reduce the leakage from the RCS

o Reduce RCS pressure in the following order:

1. ____ IF PZR bubble exists
 THEN use PZR AUX spray
2. ____ Reduce operating HPI pumps to one
3. ____ Throttle HPI flow
4. ____ OPEN PORV

Initial/Date

4.12 DH OPERATION DURING A LOCA (Cont'd)

ACTIONS


DETAILS

NOTE: The following step is to protect DHP-1B and should be performed at the lowest possible RCS pressure but MUST be performed prior to exceeding 10 hrs of operating DHP-1B in the restricted flow region (Indicated flow <1400 gpm).

4.12.15 Reduce RCS pressure to ≤ 100 PSIG

- o Reduce RCS pressure in the following order:
 1. — IF PZR bubble exists
 THEN use PZR AUX spray
 IF RCS pressure ≤ 100 PSIG,
 THEN GO TO Step 4.12.16
 2. — Reduce operating HPI pumps to one
 IF RCS pressure ≤ 100 PSIG,
 THEN GO TO Step 4.12.16
 3. — Throttle HPI flow
 IF RCS pressure ≤ 100 PSIG,
 THEN GO TO Step 4.12.16
 4. — OPEN PORV
 IF RCS pressure ≤ 100 PSIG,
 THEN GO TO Step 4.12.16

Initial/Date



4.12 DH OPERATION DURING A LOCA (Cont'd)

ACTIONS	DETAILS
4.12.16 Secure DHP supplying Decay Heat Removal	<ul style="list-style-type: none">o <input type="checkbox"/> STOP DHP-1A AND CLOSE DHV-110 <div style="text-align: right;"><u> </u> Initial/Date</div>

NOTE: The following step aligns the dropline to the RB sump. A rapid RCS depressurization will occur.


4.12.17 Depressurize RCS to RB Sump	<ul style="list-style-type: none">1. <input type="checkbox"/> CLOSE DHV-412. <input type="checkbox"/> OPEN DHV-423. <input type="checkbox"/> OPEN DHV-41 <div style="text-align: right;"><u> </u> Initial/Date</div>
-------------------------------------	---

4.12.18 Establish LPI flow to RCS	<ul style="list-style-type: none">1. <input type="checkbox"/> Ensure DHV-111 in AUTO with setpoint at 3000 GPM2. <input type="checkbox"/> OPEN DHV-73. <input type="checkbox"/> OPEN DHV-84. <input type="checkbox"/> Throttle DHV-5 and DHV-6 to establish balanced LPI flow \geq HPI flow5. <input type="checkbox"/> Secure running HPI pump(s)6. <input type="checkbox"/> OPEN DHV-5 and DHV-67. <input type="checkbox"/> Ensure CLOSED:<ul style="list-style-type: none">o MUV-23o MUV-24o MUV-25o MUV-26o DHV-11o DHV-128. <input type="checkbox"/> Exit this procedure <div style="text-align: right;"><u> </u> Initial/Date</div>
-----------------------------------	--

4.12 DH OPERATION DURING A LOCA (Cont'd)

ACTIONS

DETAILS



CAUTION: IF LPI is providing suction to MUP(s),
 THEN MUP amps and flow should be carefully monitored while
 securing a DH pump.

4.12.19 IF DHP-1A is providing
 suction to HPI pumps,
 THEN ensure the MUP suction
 flow path is properly aligned

- o ☐ OPEN/Ensure OPEN the following:
- o ☐ DHV-11
- o ☐ MUV-62
- o ☐ MUV-69

 Initial/Date

4.12.20 STOP DHP-1B

 Initial/Date

4.12 DH OPERATION DURING A LOCA (Cont'd)

ACTIONS	DETAILS	
4.12.21 Ensure DH cooler is properly aligned for DHR Operation	o Refer to Step 4.5.1.7	<u>Initial/Date</u>

4.12.22 Establish DHP-1B for DHR	1. <u> </u> Ensure the following valves are closed: <u> </u> DHV-7 <u> </u> DHV-12 <u> </u> DHV-35 <u> </u> DHV-43 <u> </u> DHV-75 <u> </u> DHV-76 <u> </u> DHV-105 <u> </u> DHV-106 <u> </u> DHV-39 2. <u> </u> Open the following valves: <u>IF</u> DHV-40 binds when opening, <u>THEN</u> DHV-121 may be opened to equalize pressure <u> </u> DHV-40 <u> </u> DHV-6	<u>Initial/Date</u>
----------------------------------	---	---------------------

4.12.23 Ensure DH/LPI train cooling water pumps are operating	o DCP-1B o RWP-3B	<u>Initial/Date</u>
---	----------------------	---------------------

NOTE: Violation of the RCP NPSH may be necessary to establish DHR. Operation in this condition with RCP(s) running should be minimized in both magnitude and duration.

4.12.24 Establish RCS conditions to enable placing DHR in service	o Ensure RCS temperature \leq 280°F o Ensure RCS pressure \leq 200 PSIG	<u>Initial/Date</u>
---	--	---------------------

4.12 DH OPERATION DURING A LOCA (Cont'd)

ACTIONS	DETAILS
4.12.25 Trip all running RCPs	o RCP-1A o RCP-1B o RCP-1C o RCP-1D
	_____ Initial/Date

NOTE: Whenever the RB 4 PSIG Isolation ES feature actuates and the RCS pressure is sufficient to overcome the head or height of the Spray Header, then aligning the DH drop line to the RCS may initiate RB Spray and cause the RCS to depressurize.

4.12.26 Isolate 'B' train RB spray header as required and align DH drop line to 'B' train DH suction	1. — IF the 4 PSIG Isolation ES feature has actuated, AND it has been BYPASSED, THEN place BSV-4 into MANUAL and close BSV-4 IF NOT actuated then verify BSV-4 closed 2. — Open DHV-3 3. — Open DHV-4 4. — Open DHV-41
	_____ Initial/Date

4.12.27 Establish DHR flow	1. — Start DHP-1B 2. — Establish \approx 3000 gpm flow by adjusting DHV-111, B-Train flow control valve
	_____ Initial/Date

4.12 DH OPERATION DURING A LOCA (Cont'd)

ACTIONS

DETAILS

NOTE: Clockwise rotation of DCV-178-MS simultaneously opens DCV-178 (increasing cooling flow) and closes DCV-18 (decreasing bypass flow). Counterclockwise rotation causes the opposite results. The purpose of this is to maintain DCP-1B flow within a minimum and maximum range to prevent pump runout and deadhead conditions.

NOTE: When required, the details for adjusting/controlling, (DCV-178-MS) DHHE-1B outlet temperature can be achieved by manually throttling DCV-178 and DCV-18 to obtain the desired position and action of the detail. For local manual operation of DCV-18 and DCV-178, refer to Enclosure 6 for guidance.

4.12.28 Lower RCS temperature to
≤ 200°F

o Adjust DHHE cooling using DCV-178-MS for DHHE-1B

Initial/Date

4.12.29 Reduce RCS pressure as low as possible to reduce the leakage from the RCS

o Reduce RCS pressure in the following order:
1. ____ IF PZR bubble exists,
 THEN use PZR AUX spray
2. ____ Reduce operating HPI pumps to one
3. ____ Throttle HPI flow
4. ____ OPEN PORV

Initial/Date

4.12 DH OPERATION DURING A LOCA (Cont'd)

ACTIONS

DETAILS

NOTE: The following step is to protect DHP-1B and should be performed at the lowest possible RCS pressure but MUST be performed prior to exceeding 10 hrs of operating DHP-1B in the restricted flow region (Indicated flow 1400 gpm)

4.12.30 Reduce RCS pressure to \leq 100 PSIG


- o Reduce RCS pressure in the following order:
1. IF PZR bubble exists,
THEN use PZR AUX spray
IF RCS pressure \leq 100 PSIG,
THEN GO TO Step 4.12.31
 2. Reduce operating HPI pumps to one
IF RCS pressure \leq 100 PSIG,
THEN GO TO Step 4.12.31
 3. Throttle HPI flow
IF RCS pressure \leq 100 PSIG,
THEN GO TO Step 4.12.31
 4. OPEN PORV
IF RCS pressure \leq 100 PSIG,
THEN GO TO Step 4.12.31

Initial/Date

4.12 DH OPERATION DURING A LOCA (Cont'd)

ACTIONS

DETAILS



4.12.31 Secure DHP supplying Decay Heat Removal

o STOP DHP-1B AND CLOSE DHV-111

Initial/Date

NOTE: The following step aligns the dropline to the RB sump. A rapid RCS depressurization will occur.

4.12.32 Depressurize RCS to RB Sump

1. CLOSE DHV-41
2. OPEN DHV-43
3. OPEN DHV-41

Initial/Date

4.12 DH OPERATION DURING A LOCA (Cont'd)

ACTIONS	DETAILS
4.12.33 Establish LPI flow to RCS	<ol style="list-style-type: none">1. ___ Ensure DHV-110 in AUTO with setpoint at 3000 GPM2. ___ OPEN DHV-73. ___ OPEN DHV-84. ___ Throttle DHV-5 and DHV-6 to establish balanced LPI flow \geq HPI flow5. ___ Secure running HPI pump(s)6. ___ OPEN DHV-5 and DHV-67. ___ Ensure CLOSED<ol style="list-style-type: none">o MUV-23o MUV-24o MUV-25o MUV-26o DHV-11o DHV-128. ___ Exit this procedure

Initial/Date

4.13 LONG-TERM POST-ACCIDENT COOLING

ACTIONS

DETAILS

NOTE: To avoid boron precipitation, the ECCS shall be placed in one of the following conditions within 24 hours after the accident.

4.13.1 IF the "A" DH train is in service taking suction from the RB sump,
THEN GO TO Step 4.13.2

IF the "B" DH train is in service taking suction from the RB sump,

OR

IF the "A" DH train is NOT available,
THEN GO TO Step 4.13.6

Initial/Date

4.13.2 Ensure the "A" decay heat train is in service taking suction from the RB sump

o Refer to EOP-08, LOCA Cooldown

Initial/Date

4.13 LONG-TERM POST-ACCIDENT COOLING (Cont'd)

ACTIONS

DETAILS

NOTE: DH-45-FI is located on back section of Main Control Board by the RCP seal charts. DH-45-FI1 is located at 95' Aux. Building, in hallway, on south wall of the Triangle Room, near the "B" decay heat pit.

4.13.3 Establish core cooling using DHP-1A and the DH drop line (preferred method)

1. ☐ Open LPI crossover valves:
 - ☐ DHV-7
 - ☐ DHV-8
2. ☐ Stop the following pumps:
 - ☐ DHP-1B
 - ☐ BSP-1B
3. ☐ Ensure closed:
 - ☐ DHV-111
 - ☐ DHV-39
4. Open/ensure open:
 - ☐ DHV-3
 - ☐ DHV-4
 - ☐ DHV-41
 - ☐ DHV-40
 - ☐ DHV-43
 - ☐ DHV-42
5. ☐ Verify flowrate on drop line flow indicator (DH-45-FI or DH-45-FI1) > 40 gpm

Initial/Date

4.13 LONG-TERM POST-ACCIDENT COOLING (Cont'd)

ACTIONS	DETAILS
4.13.4 IF Step 4.13.3 was performed successfully, <u>THEN</u> GO TO Step 4.13.5. IF NOT, <u>THEN</u> perform this step to establish flow through the auxiliary spray line.	<ol style="list-style-type: none"> 1. <input type="checkbox"/> Ensure open DHV-42 2. <input type="checkbox"/> Close: <ol style="list-style-type: none"> <input type="checkbox"/> DHV-3 <input type="checkbox"/> DHV-4 <input type="checkbox"/> DHV-41 <input type="checkbox"/> DHV-43 <input type="checkbox"/> DHV-34 <input type="checkbox"/> DHV-35 <input type="checkbox"/> DHV-40 <input type="checkbox"/> BSV-16 3. <input type="checkbox"/> Close/ensure closed PZR spray valves: <ol style="list-style-type: none"> <input type="checkbox"/> RCV-13 and/or <input type="checkbox"/> RCV-14 4. <input type="checkbox"/> Open auxiliary spray valves: <ol style="list-style-type: none"> <input type="checkbox"/> DHV-91 <input type="checkbox"/> RCV-53 5. <input type="checkbox"/> Throttle DHV-5 and/or DHV-6 as necessary to maintain auxiliary spray flowrate > 40 gpm as indicated on DH-46-FI 6. <input type="checkbox"/> GO TO Step 4.13.10
	_____ Initial/Date

4.13.5 Establish flow through the auxiliary spray line.	<ol style="list-style-type: none"> 1. <input type="checkbox"/> Close PRZ spray valves: <ol style="list-style-type: none"> <input type="checkbox"/> RCV-13 and/or <input type="checkbox"/> RCV-14 2. <input type="checkbox"/> Open auxiliary spray valves: <ol style="list-style-type: none"> <input type="checkbox"/> DHV-91 <input type="checkbox"/> RCV-53 3. <input type="checkbox"/> Throttle DHV-5 and/or DHV-6 as necessary to maintain auxiliary spray flowrate > 40 gpm as indicated on DH-46-FI 4. <input type="checkbox"/> GO TO Step 4.13.10
	_____ Initial/Date

4.13 LONG-TERM POST-ACCIDENT COOLING (Cont'd)

ACTIONS	DETAILS
4.13.6 Ensure the "B" decay heat train is in service taking suction from the RB sump	<ul style="list-style-type: none">o Refer to EOP-08, LOCA Cooldown <div>Initial/Date</div>

- | | |
|--|---|
| 4.13.7 Establish core cooling using DHP-1B and the DH drop line (preferred method) | <ol style="list-style-type: none">1. <input type="checkbox"/> Open LPI crossover valves:<ul style="list-style-type: none">o DHV-7o DHV-82. <input type="checkbox"/> Stop the following pumps:<ul style="list-style-type: none">o DHP-1Ao BSP-1A3. <input type="checkbox"/> Ensure closed:<ul style="list-style-type: none">o DHV-110o DHV-404. Open/ensure open:<ul style="list-style-type: none"><input type="checkbox"/> DHV-3<input type="checkbox"/> DHV-4<input type="checkbox"/> DHV-41<input type="checkbox"/> DHV-39<input type="checkbox"/> DHV-43<input type="checkbox"/> DHV-425. <input type="checkbox"/> Verify flowrate on drop line flow indicator (DH-45-FI or DH-45-FI1) > 40 gpm |
|--|---|

Initial/Date

4.13 LONG-TERM POST-ACCIDENT COOLING (Cont'd)

ACTIONS	DETAILS
4.13.8 IF Step 4.13.7 was performed successfully, <u>THEN</u> GO TO Step 4.13.9 IF NOT, <u>THEN</u> perform this step to establish flow through the auxiliary spray line	<ol style="list-style-type: none"> 1. <input type="checkbox"/> Ensure open DHV-43 2. <input type="checkbox"/> Close/ensure closed: <ul style="list-style-type: none"> <input type="checkbox"/> DHV-42 <input type="checkbox"/> DHV-34 <input type="checkbox"/> DHV-35 <input type="checkbox"/> DHV-39 <input type="checkbox"/> BSV-17 3. <input type="checkbox"/> Close/ensure closed PZR spray valves: <ul style="list-style-type: none"> <input type="checkbox"/> RCV-13 AND/OR <input type="checkbox"/> RCV-14 4. <input type="checkbox"/> Open auxiliary spray valves: <ul style="list-style-type: none"> <input type="checkbox"/> DHV-91 <input type="checkbox"/> RCV-53 5. <input type="checkbox"/> Open DHV-110 5. <input type="checkbox"/> Throttle DHV-5 and/or DHV-6 as necessary to maintain auxiliary spray flowrate > 40 gpm as indicated on DH-46-FI 6. <input type="checkbox"/> GO TO Step 4.13.10

Initial/Date

4.13.9 Establish flow through the auxiliary spray line	<ol style="list-style-type: none"> 1. <input type="checkbox"/> Ensure open DHV-43 2. <input type="checkbox"/> Close DHV-21 3. <input type="checkbox"/> Close/ensure closed: <ul style="list-style-type: none"> <input type="checkbox"/> DHV-34 <input type="checkbox"/> DHV-35 <input type="checkbox"/> BSV-17 4. <input type="checkbox"/> Close PZR spray valves: <ul style="list-style-type: none"> <input type="checkbox"/> RCV-13 AND/OR <input type="checkbox"/> RCV-14 5. <input type="checkbox"/> Open auxiliary spray valves: <ul style="list-style-type: none"> <input type="checkbox"/> DHV-91 <input type="checkbox"/> RCV-53 6. <input type="checkbox"/> Open DHV-110 7. <input type="checkbox"/> Throttle DHV-5 and/or DHV-6 as necessary to maintain auxiliary spray flowrate > 40 gpm as indicated on DH-46-FI
--	--

Initial/Date

4.13 LONG-TERM POST-ACCIDENT COOLING (Cont'd)

ACTIONS	DETAILS
4.13.10 Notify Chemistry to sample RB sump water for boron concentration	<p><u>IF</u> Chemistry results indicate the RB sump is being diluted, <u>THEN</u> perform the following as required:</p> <ul style="list-style-type: none">— Check for and attempt to isolate any leaks into the reactor building— Determine if any unborated water is being admitted to the reactor building— Increase flowrate through the reactor vessel to minimize boron precipitation— Commence boron addition to the RCS as necessary to maintain adequate shutdown margin

Initial/Date

4.14 ISOLATION AND RESTORATION OF INDIVIDUAL DECAY HEAT PUMPS AND HEAT EXCHANGERS

ACTIONS

DETAILS

NOTE: The components listed below may be tagged per CP-115 as requested by Maintenance at the discretion of the SSOD.

4.14.1 Isolate DHP-1A and DHHE-1A

1. ___ Ensure "B" DH train is operable
2. ___ Rack out DHP-1A breaker
3. CLOSE the following:
 - o ___ DHV-110, Flow Control
 - o ___ DHV-105, MU&P Inlet
 - o ___ DHV-92, Aux Spray Isol
 - o ___ DHV-21, DHP-1A Suction
 - o ___ DHV-39, Suction Crosstie
 - o ___ DHV-120, DHV-39 Bypass
 - o ___ DHV-34, BWST Suction Isol
4. Isolate cooling water to DHP-1A if required
 - o ___ DCV-95, DHP-1A Brg Inlet
 - o ___ DCV-96, DHP-1A Brg Outlet
 - o ___ DCV-29, DHP-1A Mtr Inlet
 - o ___ DCV-35, DHP-1A Mtr Outlet
5. OPEN the following:
 - o ___ DHV-15 DHHE-1A Drain
 - o ___ DHV-20 DHP-1A Drain
 - o ___ DHV-16, Line Vent
 - o ___ DHV-19, DHP-1A Vent

Initial/Date

4.14.2 IF desired to isolate DHHE-1A DC cooling water and drain DHHE-A, THEN position valves as follows:

1. ___ Close DCV-5, DHHE-1A DC Inlet Valve
2. ___ Close DCV-7, DHHE-1A DC Outlet Valve
3. ___ Open DCV-183, DHHE-1A DC Drain Valve
4. ___ Open DCV-125, DHHE-1A DC Vent Valve
5. ___ Open DCV-129, DHHE-1A DC Vent Valve

Initial/Date

4.14 ISOLATION AND RESTORATION OF INDIVIDUAL DECAY HEAT PUMPS AND HEAT EXCHANGERS (Cont'd)

ACTIONS	DETAILS
4.14.3 IF DHHE-1A DC cooled side is to be isolated but not drained, <u>THEN</u> position valves as follows:	1. <input type="checkbox"/> Close DCV-7, DHHE-1A DC Outlet Valve 2. <input type="checkbox"/> Close DCV-5, DHHE-1A DC Inlet Valve 3. <input type="checkbox"/> Open DCV-125, DHHE-1A Vent Valve 4. <input type="checkbox"/> Open DCV-129, DHHE-1A Vent Valve

Initial/Date

4.14.4 <u>WHEN</u> DHP-1A maintenance is complete, <u>THEN</u> fill and vent DHP-1A and DHHE-1A	1. Install temporary vent lines from the following to available floor drain: o <input type="checkbox"/> DHV-16, Line Vent o <input type="checkbox"/> DHV-19, DHP-1A Vent 2. CLOSE the following: o <input type="checkbox"/> DHV-16 o <input type="checkbox"/> DHV-19 o <input type="checkbox"/> DHV-20, DHP-1A Drain o <input type="checkbox"/> DHV-15, DHHE-1A Drain 3. OPEN the following: o <input type="checkbox"/> DHV-34, BWST Isolation o <input type="checkbox"/> DHV-21 (sealed), DHP-1A Suction 4. OPEN the following until water flow is detected, <u>THEN</u> CLOSE: o <input type="checkbox"/> DHV-16 o <input type="checkbox"/> DHV-19
--	--

Initial/Date

4.14 ISOLATION AND RESTORATION OF INDIVIDUAL DECAY HEAT PUMPS AND HEAT EXCHANGERS (Cont'd)

ACTIONS	DETAILS
4.14.5 Restore DHP-1A	<ol style="list-style-type: none"> 1. OPEN/THROTTLE the following (refer to Valve Check List II for specified DC valve positions): <ul style="list-style-type: none"> o <input type="checkbox"/> DCV-95 (sealed), DHP-1A Brg Inlet o <input type="checkbox"/> DCV-96 (sealed), DHP-1A Brg Outlet o <input type="checkbox"/> DCV-29 (sealed), DHP-1A Mtr Inlet o <input type="checkbox"/> DCV-35 (sealed), DHP-1A Mtr Outlet o <input type="checkbox"/> DHV-92, Aux Spray Isol 2. CLOSE the following: <ul style="list-style-type: none"> o <input type="checkbox"/> DHV-105, MU&P Inlet o <input type="checkbox"/> DHV-39, Suction Crosstie o <input type="checkbox"/> DHV-120, DHV-39 Bypass 3. <input type="checkbox"/> Place DHV-110 controller in manual and throttle open for 10 - 15 seconds 4. <input type="checkbox"/> Place DHV-110 in AUTO and controller at 3000 gpm 5. <input type="checkbox"/> Rack in DHP-1A breaker
	<div style="display: flex; justify-content: space-between;"> <div><u>Initial/Date</u></div> <div><u>Verified by/Date</u></div> </div>

4.14.6 <u>IF</u> DHHE-1A DC cooled side has been isolated and drained, <u>THEN</u> restore as follows:	<ol style="list-style-type: none"> 1. Install temporary vent lines from the following to available floor drains <ul style="list-style-type: none"> o <input type="checkbox"/> DCV-125, Vent Valve o <input type="checkbox"/> DCV-129, Vent Valve 2. <input type="checkbox"/> Close DCV-183, Drain Valve <ul style="list-style-type: none"> <input type="checkbox"/> Close DCV-125, Vent Valve <input type="checkbox"/> Close DCV-129, Vent Valve 3. <input type="checkbox"/> Open DCV-5, DHHE-1A Inlet Valve 4. Open the following until water flow is detected <u>THEN</u> Close: <ul style="list-style-type: none"> o <input type="checkbox"/> DCV-125, Vent Valve o <input type="checkbox"/> DCV-129, Vent Valve 5. <input type="checkbox"/> Open DCV-7, DHHE-1A Outlet Valve
	<u>Initial/Date</u>

4.14 ISOLATION AND RESTORATION OF INDIVIDUAL DECAY HEAT PUMPS AND HEAT EXCHANGERS (Cont'd)

ACTIONS	DETAILS
4.14.7 IF DHHE-1A DC cooled side has been isolated but not drained, <u>THEN</u> restore as follows:	1. <input type="checkbox"/> Close DCV-125, Vent Valve 2. <input type="checkbox"/> Close DCV-129, Vent Valve 3. <input type="checkbox"/> Open DCV-5, Inlet Valve 4. <input type="checkbox"/> Open DCV-7, Outlet Valve

Initial/Date

- 4.14.8 Isolate DHP-1B and DHHE-1B
1. ☐ Ensure "A" DH train is operable
 2. ☐ Rack out DHP-1B breaker
 3. CLOSE the following:
 - o ☐ DHV-111, Flow Control
 - o ☐ DHV-106, MU&P Inlet
 - o ☐ DHV-32, DHP-1B Suction
 - o ☐ DHV-40, Suction Crosstie
 - o ☐ DHV-121, DHV-40 Bypass
 - o ☐ DHV-35, BWST Suction Isol
 4. Isolate DHP-1B Cooling water if required
 - o ☐ DCV-119, DHP-1B Brg Inlet
 - o ☐ DCV-120, DHP-1B Brg Outlet
 - o ☐ DCV-30, DHP-1B Mtr Inlet
 - o ☐ DCV-36, DHP-1B Mtr Outlet
 5. OPEN the following:
 - o ☐ DHV-27 DHHE-1B Drain
 - o ☐ DHV-31 DHP-1B Drain
 - o ☐ DHV-26, Line Vent
 - o ☐ DHV-30, DHP-1B Vent

Initial/Date

4.14 ISOLATION AND RESTORATION OF INDIVIDUAL DECAY HEAT PUMPS AND HEAT EXCHANGERS (Cont'd)

ACTIONS	DETAILS
4.14.9 IF desired to isolate DC cooling water and drain DHHE-1B, THEN position valves as follows:	1. — Close DCV-6, DHHE-1B DC Inlet Valve 2. — Close DCV-8, DHHE-1B DC Outlet Valve 3. — Open DCV-184, DHHE-1B DC Drain Valve 4. — Open DCV-126, DHHE-1B DC Vent Valve 5. — Open DCV-130, DHHE-1B DC Vent Valve
	Initial/Date

4.14.10 IF DHHE-1B DC cooled side is to be isolated but not drained, THEN position valves as follows:	1. — Close DCV-8, DHHE-1B DC Outlet Valve 2. — Close DCV-6, DHHE-1B DC Inlet Valve 3. — Open DCV-126, DHHE-1B DC Vent Valve 4. — Open DCV-130, DHHE-1B DC Vent Valve
	Initial/Date

4.14.11 WHEN DHP-1B maintenance is complete, THEN fill and vent DHP-1B and DHHE-1B	1. Install temporary vent lines from the following to available floor drain: o — DHV-26, Line Vent o — DHV-30, DHP-1B Vent 2. CLOSE the following: o — DHV-26 o — DHV-30 o — DHV-31, DHP-1B Drain o — DHV-27, DHHE-1B Drain 3. OPEN the following: o — DHV-35, BWST Isolation o — DHV-32 (sealed), DHP-1B Suction 4. OPEN the following until water flow is detected, THEN CLOSE: o — DHV-26 o — DHV-30
	Initial/Date

4.14 ISOLATION AND RESTORATION OF INDIVIDUAL DECAY HEAT PUMPS AND HEAT EXCHANGERS (Cont'd)

ACTIONS	DETAILS
4.14.12 Restore DHP-1B	<ol style="list-style-type: none"> 1. OPEN/THROTTLE the following (refer to Valve Check List II for specified DC valve positions): <ul style="list-style-type: none"> o <input type="checkbox"/> DCV-119 (sealed), DHP-1B Brg Inlet o <input type="checkbox"/> DCV-120 (sealed), DHP-1B Brg Outlet o <input type="checkbox"/> DCV-30 (sealed), DHP-1B Mtr Inlet o <input type="checkbox"/> DCV-35 (sealed), DHP-1B Mtr Outlet 2. CLOSE the following: <ul style="list-style-type: none"> o <input type="checkbox"/> DHV-106, MU&P Inlet o <input type="checkbox"/> DHV-40, Suction Crosstie o <input type="checkbox"/> DHV-121, DHV-40 Bypass 3. <input type="checkbox"/> Place DHV-111 controller in manual and throttle open for 10 - 15 seconds 4. <input type="checkbox"/> Place DHV-111 in AUTO and controller at 3000 gpm 5. <input type="checkbox"/> Rack in DHP-1B breaker
	<div style="display: flex; justify-content: space-between;"> <div><u>Initial/Date</u></div> <div><u>Verified by /Date</u></div> </div>

- | | |
|--|---|
| <p>4.14.13 <u>IF</u> DHHE-1B DC cooled side has been isolated and drained, <u>THEN</u> restore as follows:</p> | <ol style="list-style-type: none"> 1. Install temporary vent lines from the following to available floor drains <ul style="list-style-type: none"> o <input type="checkbox"/> DCV-126, Vent Valve o <input type="checkbox"/> DCV-130, Vent Valve 2. <input type="checkbox"/> Close DCV-184, Drain Valve <ul style="list-style-type: none"> <input type="checkbox"/> Close DCV-126, Vent Valve <input type="checkbox"/> Close DCV-130, Vent Valve 3. <input type="checkbox"/> Open DCV-6, DHHE-1B Inlet Valve 4. Open the following until water flow is detected
 <u>THEN</u> Close: <ul style="list-style-type: none"> o <input type="checkbox"/> DCV-126, Vent Valve o <input type="checkbox"/> DCV-130, Vent Valve 5. <input type="checkbox"/> Open DCV-8, DHHE-1B Outlet Valve |
|--|---|

Initial/Date

4.14 ISOLATION AND RESTORATION OF INDIVIDUAL DECAY HEAT PUMPS AND HEAT EXCHANGERS (Cont'd)

ACTIONS	DETAILS
4.14.14 IF DHHE-1B DC cooled side has been isolated but not drained, <u>THEN</u> restore as follows:	1. <input type="checkbox"/> Close DCV-126, Vent Valve 2. <input type="checkbox"/> Close DCV-130, Vent Valve 3. <input type="checkbox"/> Open DCV-6, Inlet Valve 4. <input type="checkbox"/> Open DCV-8, Outlet Valve

Initial/Date

4.15 DCHE ISOLATION/RESTORATION FOR MAINTENANCE

ACTIONS

DETAILS

NOTE: Ensure RWV-33 is open prior to closing RWV-32.

NOTE: The following components may be tagged per CP-115 as requested by Maintenance at the discretion of the SSOD.

4.15.1 Isolate DCHE-1A for maintenance

1. ☐ STOP RWP-3A and rack out breaker if required
2. ☐ CLOSE the following:
 - o RWV-18, Inlet Isolation
 - o RWV-32, SWHE Outlet Cross Connect
 - o RWV-28, RW Drain
 - o DOV-124, DO Fill
 - o RWV-110, RML-7 Outlet
3. ☐ De-energize cathodic protection
4. ☐ OPEN the following:
 - o RWV-77, DCHE-1A Inlet Drain
 - o RWV-75, DCHE-1A Outlet Drain
 - o RWV-73, DCHE-1A Vent
 - o RWV-9, RW-29-PI Isolation

Initial/Date

4.15.2 WHEN maintenance is complete, THEN fill and vent DCHE-1A

1. ☐ CLOSE RWV-77, Inlet Drain
2. ☐ Attach hose from DWV-336 to RWV-75, Outlet Drain
3. ☐ OPEN DWV-336, and RWV-75 to fill DCHE-1A
4. ☐ WHEN water issues from RWV-73, vent, THEN close DWV-336
5. ☐ Close the following valves:
 - ☐ RWV-73, Vent
 - ☐ RWV-75, Outlet Drain
6. ☐ Remove and store DW hose

Initial/Date

4.15 DCHE ISOLATION/RESTORATION FOR MAINTENANCE (Cont'd)

ACTIONS	DETAILS
4.15.3 Restore DCHE-1A	<ol style="list-style-type: none"> 1. <input type="checkbox"/> OPEN the following: <ul style="list-style-type: none"> o RWV-18 (sealed), Inlet Isolation o RWV-32, SWHE Outlet Cross Connect 2. <input type="checkbox"/> Ensure OPEN: <ul style="list-style-type: none"> o RWV-9, RW-29-PI Isolation 3. <input type="checkbox"/> Energize cathodic protection
	<div style="display: flex; justify-content: space-between;"> <div><u>Initial/Date</u></div> <div><u>Verified by /Date</u></div> </div>

NOTE: Ensure RWV-32 is open prior to closing RWV-33.

NOTE: The following components may be tagged per CP-115 as requested by Maintenance at the discretion of the SSOD.

4.15.4 Isolate DCHE-1B for maintenance	<ol style="list-style-type: none"> 1. <input type="checkbox"/> STOP RWP-3B and rack out breaker if required 2. <input type="checkbox"/> CLOSE the following: <ul style="list-style-type: none"> o RWV-17, Inlet Isolation o RWV-33, SWHE Outlet Cross Connect o RWV-44, RW Drain o DOV-125, DO Fill o RWV-109, RML-7 Outlet 3. <input type="checkbox"/> De-energize cathodic protection 4. <input type="checkbox"/> OPEN the following: <ul style="list-style-type: none"> o RWV-78, DCHE-1B Inlet Drain o RWV-76, DCHE-1B Outlet Drain o RWV-74, DCHE-1B Vent o RWV-4, RW-28-PI Isolation
	<u>Initial/Date</u>

4.15 DCHE ISOLATION/RESTORATION FOR MAINTENANCE (Cont'd)

ACTIONS	DETAILS
4.15.5 <u>WHEN</u> maintenance is complete, <u>THEN</u> fill and vent DCHE-1B	1. <input type="checkbox"/> CLOSE RWV-78, Inlet Drain 2. <input type="checkbox"/> Attach hose from DWV-336 to RWV-76, Outlet Drain 3. <input type="checkbox"/> OPEN DWV-336 and RWV-76 to fill DCHE-1B 4. <input type="checkbox"/> <u>WHEN</u> water issues from RWV-74, Vent, <u>THEN</u> close DWV-336 5. <input type="checkbox"/> CLOSE the following valves: <input type="checkbox"/> RWV-74, Vent <input type="checkbox"/> RWV-76, Outlet Drain 6. <input type="checkbox"/> Remove and store DW hose

Initial/Date

4.15.6 Restore DCHE-1B

1. ☐ OPEN the following:
 - o RWV-17 (sealed), Inlet Isolation
 - o RWV-33, SWHE Outlet Cross Connect
2. ☐ Ensure OPEN:
 - o RWV-4, RW-28-PI Isolation
3. ☐ Energize cathodic protection

Initial/Date

Verified by/Date

4.16 DHCCC PUMP ISOLATION/RESTORATION FOR MAINTENANCE

ACTIONS

DETAILS

NOTE: The following components may be tagged per CP-115 as requested by Maintenance at the discretion of the SSOD.

4.16.1 Isolate and drain DCP-1A for maintenance

1. ☐ STOP DCP-1A
2. ☐ CLOSE the following:
 - o DCV-1, DCP-1A Suction
 - o DCV-3, DCP-1A Discharge
 - o DCV-19, Surge Tank Outlet
3. ☐ Install temporary drain line between DCV-121, Surge Line Drain, and available floor drain
4. ☐ OPEN the following:
 - o DCV-121
 - o DCP-1A casing vent
5. ☐ Reinstall casing vent when pump is drained

Initial/Date

4.16.2 WHEN DCP-1A maintenance is complete,
THEN fill and vent pump

1. ☐ CLOSE DCV-121, Surge Line Drain
2. ☐ OPEN DCP-1A casing vent
3. ☐ OPEN DCV-19, Surge Tank Outlet, 1-3 turns to fill pump
4. ☐ CLOSE DCV-19 and reinstall pump casing vent when water flows from vent

Initial/Date

4.16 DHCCC PUMP ISOLATION/RESTORATION FOR MAINTENANCE (Cont'd)

ACTIONS	DETAILS
4.16.3 Restore DCP-1A lineup	<ul style="list-style-type: none"> o OPEN and seal the following: o DCV-1, DCP-1A Suction o DCV-3, DCP-1A Discharge o DCV-19, Surge Tank Outlet <div style="display: flex; justify-content: space-between; margin-top: 10px;"> <div style="text-align: center;"> <u> </u> Initial/Date </div> <div style="text-align: center;"> <u> </u> Verified by /Date </div> </div>
4.16.4 Isolate and drain DCP-1B for maintenance	<ol style="list-style-type: none"> 1. <u> </u> STOP DCP-1B 2. <u> </u> CLOSE the following: <ul style="list-style-type: none"> o DCV-2, DCP-1B Suction o DCV-4, DCP-1B Discharge o DCV-20, Surge Tank Outlet 3. <u> </u> Install temporary drain line between DCV-122, Surge Line Drain, and available floor drain 4. <u> </u> OPEN the following: <ul style="list-style-type: none"> o DCV-122 o DCP-1B casing vent 5. <u> </u> Reinstall casing vent when pump is drained <div style="text-align: right; margin-top: 10px;"> <u> </u> Initial/Date </div>
4.16.5 <u>WHEN</u> DCP-1B maintenance is complete, <u>THEN</u> fill and vent pump	<ol style="list-style-type: none"> 1. <u> </u> CLOSE DCV-122, Surge Line Drain 2. <u> </u> OPEN DCP-1B casing vent 3. <u> </u> OPEN DCV-20, Surge Tank Outlet, 1-3 turns to fill pump 4. <u> </u> CLOSE DCV-20 and reinstall pump casing vent when water flows from vent <div style="text-align: right; margin-top: 10px;"> <u> </u> Initial/Date </div>

4.16 DHCCC PUMP ISOLATION/RESTORATION FOR MAINTENANCE (Cont'd)

ACTIONS	DETAILS
4.16.6 Restore DCP-1B lineup	<ul style="list-style-type: none">o OPEN and seal the following:o DCV-2, DCP-1B Suctiono DCV-4, DCP-1B Dischargeo DCV-20, Surge Tank Outlet
<u>Initial/Date</u>	<u>Verified by /Date</u>

4.17 FILLING THE FUEL TRANSFER CANAL: "A" DH SYSTEM IN SERVICE, "B" DH SYSTEM RECIRC OF BWST

ACTIONS	DETAILS	
4.17.1 Fuel transfer tube flanges removed and FTC Drain Flange installed	o Flanges removed per MP-125, Fuel Transfer Tube Covers (FHX-1A & FHX-1B) and Drain Line Cover	<u> </u> Initial/Date
4.17.2 Cavity seal plate port covers installed	o Plate port covers installed per FP-411, Seal Plate Inspection and Port Cover Installation	<u> </u> Initial/Date
4.17.3 Ensure drain line screen installed in FTC 4" deep end drain to RB sump		<u> </u> Initial/Date
4.17.4 Notify Maintenance Supt. or designee of impending FTC fill operation	o Inspection of seal plate welds may be required prior to fill o Maintenance personnel are required for seal plate leak checks per FP-411	<u> </u> Initial/Date
4.17.5 Pre-job briefing conducted with all personnel (Operations, Maintenance, Health Physics) involved		<u> </u> Initial/Date
4.17.5.1 BWST boron concentration meets the requirements of Technical Specification 3.9.1		<u> </u> Initial/Date

4.17 FILLING THE FUEL TRANSFER CANAL: "A" DH SYSTEM IN SERVICE, "B" DH SYSTEM RECIRC OF BWST (Cont'd)

ACTIONS	DETAILS	
4.17.6 Test FTC level alarm	<ul style="list-style-type: none">o — Close annunciator link 0347, "Fuel Xfer Canal Lvl"o — At local station, turn "Horn Silence" on, then off, to verify alarm operability	<u> </u> Initial/Date
4.17.7 Ensure "A" DH System is in service	<ul style="list-style-type: none">o Refer to Section 4.5	<u> </u> Initial/Date
4.17.8 Align "B" DH System to recirculate the BWST	<ul style="list-style-type: none">1. — CLOSE DHV-402. — CLOSE DHV-83. — OPEN DHV-354. — Adjust DHV-111 controller to approx. 1500 gpm5. — OPEN DHV-76. — OPEN DHV-9	<u> </u> Initial/Date

NOTE: Minimum continuous DH pump flow is 1400 gpm.

NOTE: RWV-150 will not properly control SW temperature if RWP-3B is running.

4.17.9 Commence BWST recirculation	<ul style="list-style-type: none">1. — START DCP-1B2. — START RWP-3B if required3. — START DHP-1B4. — THROTTLE DHV-111 to maintain approximately 1500 gpm5. — Adjust DHP-1B low amp alarm as desired per Section 4.31	<u> </u> Initial/Date
------------------------------------	---	-----------------------------------

4.17 FILLING THE FUEL TRANSFER CANAL: "A" DH SYSTEM IN SERVICE. "B" DH SYSTEM RECIRC OF BWST (Cont'd)

ACTIONS	DETAILS
4.17.9.1 Ensure proper lubrication of DHP-1B	<ul style="list-style-type: none"> <input type="checkbox"/> Observe proper operation of Slinger Rings <input type="checkbox"/> Ensure proper oil levels
	<u> </u> Initial/Date

NOTE: Technical Specification cooldown rates do not apply when filling the Fuel Transfer Canal IF step changes of $\leq 60^{\circ}\text{F}$ are maintained.

4.17.10 Verify delta temperature between Reactor Coolant and BWST is less than 60°F	<ol style="list-style-type: none"> 1. Record DH Pump Suction and BWST temperatures: <ul style="list-style-type: none"> <input type="checkbox"/> DH Pump (Supplying Core Cooling) Suction Temperature <u> </u>$^{\circ}\text{F}$ <input type="checkbox"/> BWST Temperature <u> </u>$^{\circ}\text{F}$ 2. Calculate the delta temperature: $\frac{\text{ }^{\circ}\text{F}}{(\text{DH Suct})} - \frac{\text{ }^{\circ}\text{F}}{(\text{BWST})} = \frac{\text{ }^{\circ}\text{F}}{(\Delta\text{T})}$ 3. <u> </u> Delta temperature is less than or equal to 60°F
	<u> </u> Initial/Date

4.17.11 Ensure proper Fuel Transfer Canal valve alignment	<ul style="list-style-type: none"> <input type="checkbox"/> SFV-180 Closed <input type="checkbox"/> SFV-181 Closed <input type="checkbox"/> RCV-38 Closed <input type="checkbox"/> RCV-37 Closed <input type="checkbox"/> SFV-83 Closed <input type="checkbox"/> SFV-84 Closed
	<u> </u> Initial/Date

4.17 FILLING THE FUEL TRANSFER CANAL: "A" DH SYSTEM IN SERVICE, "B" DH SYSTEM RECIRC OF BWST (Cont'd)

ACTIONS	DETAILS
4.17.12 Station operators to monitor level while filling	<ul style="list-style-type: none">o Station operators at the following:<ul style="list-style-type: none">— Reactor vessel level indication— Fuel transfer canal— 95 foot elevation of Reactor Building

Initial/Date

CAUTION: Do not remove or alter any permanent or temporary radiation shielding while checking for seal plate leakage without authorization from Health Physics and the SSOD.

NOTE: The primary method of seal plate leakage detection is R.B. sump level indication. Should drains to the sump become blocked then water seepage from between lead bricks at "doghouse" will be indicative of seal plate leakage. Seepage from lead bricks may not appear for several hours.

4.17.13 Begin periodic monitoring for leakage from Fuel Transfer Canal	<ul style="list-style-type: none">o — Monitor shielded access ("doghouse") to reactor vessel vessel cavity for water leakageo — Monitor R.B. sump level in the Control Room
--	--

Initial/Date

NOTE: During FTC fill, DH flow is maintained at approximately 1500 gpm to minimize the transport of corrosion products from the core to the FTC water surface.

4.17.14 Commence FTC fill	<ul style="list-style-type: none">1. — OPEN DHV-62. — CLOSE DHV-7 if required3. — Throttle DHV-111 to maintain ~1500 gpm
---------------------------	--

Initial/Date

4.17 FILLING THE FUEL TRANSFER CANAL: "A" DH SYSTEM IN SERVICE, "B" DH SYSTEM RECIRC OF BWST (Cont'd)

ACTIONS	DETAILS	
4.17.15 <u>WHEN</u> FTC level increases to approximately 146 foot elevation, <u>THEN</u> stop FTC fill, <u>AND</u> monitor for seal plate leakage	1. <input type="checkbox"/> OPEN DHV-7 if closed 2. <input type="checkbox"/> CLOSE DHV-6	<u> </u> Initial/Date
4.17.16 <u>IF</u> Fuel Transfer Canal leakage is unsatisfactory, <u>THEN</u> inform SSOD, <u>AND</u> drain FTC to approx. 6 inches below shallow end elevation, <u>OTHERWISE</u> "N/A" this step	1. <input type="checkbox"/> STOP DHP-1B 2. <input type="checkbox"/> STOP RWP-3B 3. <input type="checkbox"/> STOP DCP-1B 4. <input type="checkbox"/> CLOSE DHV-7 5. <input type="checkbox"/> CLOSE/ENSURE CLOSED DHV-6 6. <input type="checkbox"/> CLOSE DHV-35 7. <input type="checkbox"/> GO TO Section 4.19	<u> </u> Initial/Date
4.17.17 Continue FTC fill	1. <input type="checkbox"/> OPEN DHV-6 2. <input type="checkbox"/> CLOSE DHV-7 if required 3. <input type="checkbox"/> Throttle DHV-111 to maintain ~1500 gpm 4. <input type="checkbox"/> Monitor BWST for level and DHP-1B for cavitation 5. <input type="checkbox"/> When BWST level decreases to 5 ft place the "BWST HTR3A/3B" control switch in the "Local" position	<u> </u> Initial/Date

4.17 FILLING THE FUEL TRANSFER CANAL: "A" DH SYSTEM IN SERVICE. "B" DH SYSTEM RECIRC OF BWST (Cont'd)

ACTIONS	DETAILS
4.17.18 <u>WHEN</u> FTC level increases to approximately 158 foot elevation, <u>THEN</u> stop FTC fill	1. <input type="checkbox"/> OPEN DHV-7 if closed 2. <input type="checkbox"/> CLOSE DHV-6 3. <input type="checkbox"/> STOP DHP-1B 4. <input type="checkbox"/> STOP RWP-3B if started 5. <input type="checkbox"/> STOP DCP-1B

Initial/Date

4.17.19 Restore "B" DH train to normal	1. Perform and verify the following lineup: <input type="checkbox"/> CLOSE DHV-35 <input type="checkbox"/> CLOSE DHV-7 <input type="checkbox"/> CLOSE DHV-9 <input type="checkbox"/> DHV-111 in AUTO and controller adjusted to 3000 gpm <input type="checkbox"/> CLOSE DHV-8 <input type="checkbox"/> CLOSE DHV-40 2. <input type="checkbox"/> Monitor BWST level for approx. 5 min for abnormal level change
--	---

Performed By

Verified By

4.17.20 Enable FTC low level horn <u>and</u> energize canal lighting	o <input type="checkbox"/> Enable local horn for low FTC level by turning horn switch to "ON" (located near Incore pit) o <input type="checkbox"/> Energize FTC lights if desired by closing Bkr 4, on ACDP-16 (feeder to ACDP-28, the supply to all FTC lighting)
--	---

Initial/Date

4.18 FILLING THE FUEL TRANSFER CANAL: "B" DH SYSTEM IN SERVICE, "A" DH SYSTEM RECIRC OF BWST

ACTIONS	DETAILS	
4.18.1 Fuel transfer tube flanges removed and FTC Drain Flange installed	o Flanges removed per MP-125, Fuel Transfer Tube Covers (FHX-1A & FHX-1B) and Drain Line Cover	<u> </u> Initial/Date
4.18.2 Cavity seal plate port covers installed	o Plate port covers installed per FP-411, Seal Plate Inspection and Port Cover Installation	<u> </u> Initial/Date
4.18.3 Ensure drain line screen installed in FTC 4" deep end drain to RB sump		<u> </u> Initial/Date
4.18.4 Notify Maintenance Supt. or designee of impending FTC fill operation	o Inspection of seal plate welds may be required prior to fill o Maintenance personnel are required for seal plate leak checks per FP-411	<u> </u> Initial/Date
4.18.5 Pre-job briefing conducted with all personnel (Operations Maintenance, Health Physics) involved		<u> </u> Initial/Date
4.18.5.1 BWST boron concentration meets the requirements of Technical Specification 3.9.1		<u> </u> Initial/Date

4.18 FILLING THE FUEL TRANSFER CANAL: "B" DH SYSTEM IN SERVICE. "A" DH SYSTEM RECIRC OF BWST (Cont'd)

ACTIONS	DETAILS	
4.18.6 Test FTC level alarm	<ul style="list-style-type: none">o — Close annunciator link 0347 "Fuel Xfer Canal Lvl"o — At local station, turn "Horn Silence" on, then off, to verify alarm operability	<div>Initial/Date</div>
4.18.7 Ensure "B" DH System is in service	<ul style="list-style-type: none">o Refer to Section 4.5	<div>Initial/Date</div>
4.18.8 Align "A" DH System to recirculate the BWST	<ul style="list-style-type: none">1. — CLOSE DHV-392. — CLOSE DHV-73. — OPEN DHV-344. — Adjust DHV-110 controller to approx. 1500 gpm5. — OPEN DHV-86. — OPEN DHV-9	<div>Initial/Date</div>

NOTE: Minimum continuous DH pump flow is 1400 gpm.

4.18.9 Commence BWST recirculation	<ul style="list-style-type: none">1. — START DCP-1A2. — START RWP-3A3. — START DHP-1A4. — THROTTLE DHV-110 to maintain approximately 1500 gpm5. — Adjust DHP-1A low amp alarm as desired per Section 4.31	<div>Initial/Date</div>
------------------------------------	---	-------------------------

4.18 FILLING THE FUEL TRANSFER CANAL: "B" DH SYSTEM IN SERVICE, "A" DH SYSTEM RECIRC OF BWST (Cont'd)

ACTIONS	DETAILS
4.18.9.1 Ensure proper lubrication of DHP-1A	<input type="checkbox"/> Observe proper operation of Slinger Rings <input type="checkbox"/> Ensure proper oil levels
	_____ Initial/Date

NOTE: Technical Specification cooldown rates do not apply when filling the Fuel Transfer Canal IF step changes of $\leq 60^{\circ}\text{F}$ are maintained.

4.18.10 Verify delta temperature between Reactor Coolant and BWST is less than 60°F	1. Record DH Pump Suction and BWST temperatures: <input type="checkbox"/> DH Pump (Supplying Core Cooling) Suction Temperature _____ $^{\circ}\text{F}$ <input type="checkbox"/> BWST Temperature _____ $^{\circ}\text{F}$ 2. Calculate the delta temperature: $\frac{\text{_____}^{\circ}\text{F}}{(\text{DH Suct})} - \frac{\text{_____}^{\circ}\text{F}}{(\text{BWST})} = \frac{\text{_____}^{\circ}\text{F}}{(\Delta T)}$ 3. _____ Delta temperature is less than or equal to 60°F
	_____ Initial/Date

4.18.11 Ensure proper Fuel Transfer Canal valve alignment	<input type="checkbox"/> SFV-180 Closed <input type="checkbox"/> SFV-181 Closed <input type="checkbox"/> RCV-38 Closed <input type="checkbox"/> RCV-37 Closed <input type="checkbox"/> SFV-83 Closed <input type="checkbox"/> SFV-84 Closed
	_____ Initial/Date

4.18 FILLING THE FUEL TRANSFER CANAL: "B" DH SYSTEM IN SERVICE, "A" DH SYSTEM RECIRC OF BWST (Cont'd)

ACTIONS	DETAILS	
4.18.12 Station operators to monitor level while filling	<ul style="list-style-type: none">o Station operators at the following:<ul style="list-style-type: none">— Reactor vessel level indication— Fuel transfer canal— 95 foot elevation of Reactor Building	<div>Initial/Date</div>

CAUTION: Do not remove or alter any permanent or temporary radiation shielding while checking for seal plate leakage without authorization from Health Physics and the SSOD.

NOTE: The primary method of seal plate leakage detection is R.B. sump level indication. Should drains to the sump become blocked then water seepage from between lead bricks at "doghouse" will be indicative of seal plate leakage. Seepage from lead bricks may not appear for several hours.

4.18.13 Begin periodic monitoring for leakage from Fuel Transfer Canal	<ul style="list-style-type: none">o — Monitor shielded access ("doghouse") to reactor vessel cavity for water leakageo — Monitor R.B. sump level in the Control Room	<div>Initial/Date</div>
--	---	-------------------------

NOTE: During FTC fill, DH flow is maintained at approximately 1500 gpm to minimize the transport of corrosion products from the core to the FTC water surface.

4.18.14 Commence FTC fill	<ul style="list-style-type: none">1. — OPEN DHV-52. — CLOSE DHV-8 if required3. — Throttle DHV-110 to maintain ~1500 gpm	<div>Initial/Date</div>
---------------------------	--	-------------------------

4.18 FILLING THE FUEL TRANSFER CANAL: "B" DH SYSTEM IN SERVICE, "A" DH SYSTEM RECIRC OF BWST (Cont'd)

ACTIONS	DETAILS	
4.18.15 <u>WHEN</u> FTC level increases to approximately 146 foot elevation, <u>THEN</u> stop FTC fill <u>AND</u> monitor for seal plate leakage	1. <input type="checkbox"/> OPEN DHV-8 if closed 2. <input type="checkbox"/> CLOSE DHV-5	<u>Initial/Date</u>
4.18.16 <u>IF</u> Fuel Transfer Canal leakage is unsatisfactory, <u>THEN</u> inform SSOD <u>AND</u> drain FTC to approx. 6 inches below shallow end elevation, <u>OTHERWISE</u> "N/A" this step	1. <input type="checkbox"/> STOP DHP-1A 2. <input type="checkbox"/> STOP RWP-3A 3. <input type="checkbox"/> STOP DCP-1A 4. <input type="checkbox"/> CLOSE DHV-8 5. <input type="checkbox"/> CLOSE/ENSURE CLOSED DHV-5 6. <input type="checkbox"/> CLOSE DHV-34 7. <input type="checkbox"/> GO TO Section 4.20	<u>Initial/Date</u>
4.18.17 Continue FTC fill	1. <input type="checkbox"/> OPEN DHV-5 2. <input type="checkbox"/> CLOSE DHV-8 if required 3. <input type="checkbox"/> Throttle DHV-110 to maintain ~1500 gpm 4. <input type="checkbox"/> Monitor BWST for level and DHP-1A for cavitation 5. <input type="checkbox"/> When BWST level decreases to 5 ft place the "BWST HTR 3A/3B" control switch in the "Local" position	<u>Initial/Date</u>

4.18 FILLING THE FUEL TRANSFER CANAL: "B" DH SYSTEM IN SERVICE, "A" DH SYSTEM RECIRC OF BWST (Cont'd)

ACTIONS	DETAILS
4.18.18 <u>WHEN</u> FTC level increases to approximately 158 foot elevation, <u>THEN</u> stop FTC fill	1. <input type="checkbox"/> OPEN DHV-8 if closed 2. <input type="checkbox"/> CLOSE DHV-5 3. <input type="checkbox"/> STOP DHP-1A 4. <input type="checkbox"/> STOP RWP-3A 5. <input type="checkbox"/> STOP DCP-1A

Initial/Date

4.18.19 Restore "A" DH train to normal	1. Perform and verify the following lineup: <input type="checkbox"/> CLOSE DHV-34 <input type="checkbox"/> CLOSE DHV-8 <input type="checkbox"/> CLOSE DHV-9 <input type="checkbox"/> DHV-110 in AUTO and controller adjusted to 3000 gpm <input type="checkbox"/> CLOSE DHV-7 <input type="checkbox"/> CLOSE DHV-39 2. <input type="checkbox"/> Monitor BWST level for approx. 5 min to detect any abnormal level change
--	---

Performed By

Verified By

4.18.20 Enable FTC low level <u>and</u> energize canal lighting	<input type="checkbox"/> Enable local horn for low FTC level by turning horn switch to "ON" (located near Incore pit) <input type="checkbox"/> Energize FTC lights if desired by closing Bkr 4, on ACDP-16 (feeder to ACDP-28, the supply to all FTC lighting)
---	---

Initial/Date

4.19 DRAINING FUEL TRANSFER CANAL VIA "A" DH SYSTEM

ACTIONS		DETAILS
4.19.1	Ensure "A" DH train in service and removing decay heat	_____ Initial/Date
4.19.2	Ensure Fuel Transfer Tubes are isolated	1. Ensure Transfer Tube isolation valve seats are clear prior to closing isolation valves, per FP-601D, Operation of Fuel Transfer Carriages and Upenders FHCR-4A/4B 2. ____ Close SFV-119 ____ Close SFV-120 _____ Initial/Date
4.19.3	Disable FTC low level alarm and turn off FTC underwater lights	o ____ Turn local horn switch to "OFF" o ____ Open annunciator link #0347, "Fuel Transfer Canal Level Low" o ____ Open breaker #4 on ACDP-16 (feeder to ACDP-28 for FTC underwater lighting panel RB-4) <u>AND</u> red tag to CEOD in accordance with CP-115 o Clearance number _____ o Accepted by _____ _____ Initial/Date
4.19.4	Station operators to monitor level	o Station operators at: ____ Fuel transfer canal ____ Reactor vessel level indication _____ Initial/Date

4.19 DRAINING FUEL TRANSFER CANAL VIA "A" DH SYSTEM (Cont'd)

ACTIONS	DETAILS
---------	---------

 CAUTION: Carefully monitor "A" decay heat cooler outlet temperature and DHP-1A parameters (flow, pressures, and amperage) while adjusting flow.

4.19.5 Commence FTC drain

1. — OPEN DHV-8
2. — OPEN DHV-9
3. — THROTTLE DHV-5 to establish desired flowrate to BWST
4. — When the BWST level is > 5 ft, place the "BWST HTR 3A/3B" control switch to Auto 3A or Auto 3B

 Initial/Date

NOTE: Lowering FTC level < 136 feet via the SF system, taking a suction on the deep end, is the desired method to limit the amount of debris that can enter the vessel.

NOTE: Maintain DHP Flow and Vessel Level Within the Acceptable regions of OP-103B, curves 16 and 18.

4.19.6 Determine the final level desired in the Fuel Transfer Canal or Vessel

- o — IF desired to draindown the FTC and maintain vessel level, THEN Go to Step 4.19.7 and N/A Steps 4.19.9 through 4.19.14
- o — IF the vessel is defueled and it is desired to lower the FTC and vessel level using the DHP THEN Go to Step 4.19.9 and N/A Steps 4.19.7 and 4.19.8

 Initial/Date

4.19.7 WHEN FTC level decreases to approximately 136 feet, THEN stop FTC draindown

1. — Fully open DHV-5
2. Close:
 - DHV-8
 - DHV-9
3. Monitor BWST level for approximately 5 min to detect any abnormal level change

 Initial/Date

4.19 DRAINING FUEL TRANSFER CANAL VIA "A" DH SYSTEM (Cont'd)

ACTIONS	DETAILS
4.19.8 Continue draining per OP-406, Spent Fuel Cooling System	o ____ GO TO OP-406, Section 4.8
	<u>Initial/Date</u>

CAUTION: Vessel level will lower very rapidly when water level drops below the vessel flange if flow rate to the BWST is not decreased.

4.19.9 <u>WHEN</u> FTC level decreases to approximately 136 feet, <u>THEN</u> reduce DHP flow to ≈1700 gpm	1. ____ Mon. or vessel level and DHP operating conditions closely 2. ____ Adjust DHV-110 as required to attain ≈1700 gpm DHP flow 3. ____ Adjust DHV-5 to maintain desired flow to the BWST
	<u>Initial/Date</u>

4.19.10 <u>WHEN</u> the vessel level decreases below 135'6" (below the seal plate flange), <u>THEN</u> concurrently perform FTC draindown to the desired level per OP-406, Spent Fuel Cooling System	o ____ GO to OP-406, section 4.8 o ____ Draindown FTC to desired level (Normally ≈ 6" below the shallow end lip if the plenum is in the deep end)
	<u>Initial/Date</u>

4.19.11 <u>WHEN</u> Vessel level decreases to approximately 133 feet, <u>THEN</u> stop the draindown and vent the RCP seal packages	1. ____ Fully open DHV-5 2. ____ Close DHV-8 3. ____ Maintain DHP flow ≥ 1500 gpm 4. Vent all RCP seals: ____ Break Seal Injection flanges ____ or ____ Open top hat vents or ____ Open Seal Injection line vents
	<u>Initial/Date</u>

4.19 DRAINING FUEL TRANSFER CANAL VIA "A" DH SYSTEM (Cont'd)

ACTIONS	DETAILS
4.19.12 <u>WHEN</u> all RCP seals have been verified to be vented, <u>THEN</u> continue draindown	1. <input type="checkbox"/> Open DHV-8 2. <input type="checkbox"/> Adjust DHV-110 as required to maintain ≈ 1700 gpm 3. <input type="checkbox"/> Adjust DHV-5 to control flow to the BWST <div style="text-align: right;">_____ Initial/Date</div>
4.19.13 <u>WHEN</u> Vessel level has decreased to $\geq 129.5'$, <u>THEN</u> stop vessel draindown	1. <input type="checkbox"/> Fully open DHV-5 2. <input type="checkbox"/> Close: <input type="checkbox"/> DHV-8 <input type="checkbox"/> DHV-9 3. <input type="checkbox"/> Monitor BWST and Vessel level for approximately 5 min to detect any abnormal level changes <div style="text-align: right;">_____ Initial/Date</div>
4.19.14 Establish an activity to restore RCP seal packages to normal prior to subsequent refill to ≥ 133 feet	o <input type="checkbox"/> Activity established to restore RCP Seal Packages prior to refill to include the following as required: - Seal Injection flanges restored - Top hat vents closed - Seal Injection line vents closed <div style="text-align: right;">_____ Initial/Date</div>

4.20 DRAINING FUEL TRANSFER CANAL VIA "B" DH SYSTEM

ACTIONS	DETAILS
4.20.1 Ensure "B" DH train in and removing decay heat	<div>Initial/Date</div>
4.20.2 Ensure Fuel Transfer Tubes are isolated	<div>1. Ensure Transfer Tube isolation valve seats are clear prior to closing isolation valves, per FP-601D, Operation of Fuel Transfer Carriages and Upenders FHCR-4A/4B</div> <div>2. <input type="checkbox"/> Close SFV-119</div> <div><input type="checkbox"/> Close SFV-120</div> <div>Initial/Date</div>
4.20.3 Disable FTC low level alarm and turn off FTC underwater lights	<div><input type="checkbox"/> Turn local horn switch to "OFF"</div> <div><input type="checkbox"/> Open annunciator link #0347, "Fuel Transfer Canal Level Low"</div> <div><input type="checkbox"/> Open breaker #4 on ACDP-16 (feeder to ACDP-28 for FTC underwater lighting panel RB-4) <u>AND</u> red tag to the CEOD in accordance with CP-115</div> <div><input type="checkbox"/> Clearance number</div> <div><input type="checkbox"/> Accepted by</div> <div>Initial/Date</div>
4.20.4 Station operators to monitor level	<div><input type="checkbox"/> Station operators at:</div> <div><input type="checkbox"/> Fuel transfer canal</div> <div><input type="checkbox"/> Reactor vessel level indication</div> <div>Initial/Date</div>

4.20 DRAINING FUEL TRANSFER CANAL VIA "B" DH SYSTEM (Cont'd)

ACTIONS	DETAILS
---------	---------

CAUTION: Carefully monitor "B" decay heat cooler outlet temperature
and DHP-1B parameters (flow, pressures, and amperage) while
adjusting flow.

4.20.5 Commence FTC drain

1. ☐ OPEN DHV-7
2. ☐ OPEN DHV-9
3. ☐ THROTTLE DHV-6 to establish
desired flowrate to BWST
4. ☐ When the BWST level is > 5 ft,
place the "BWST HTR 3A/3B"
control switch to Auto 3A or
Auto 3B

Initial/Date

NOTE: Lowering FTC level < 136 feet via the SF system, taking a
suction on the deep end, is the desired method to limit the
amount of debris that can enter the vessel.

NOTE: Maintain DHP Flow and Vessel Level Within the Acceptable
regions of OP-103B, curves 16 and 18.

4.20.6 Determine the final level desired in the Fuel Transfer Canal or Vessel

- o ☐ IF desired to draindown the
FTC and maintain vessel level,
THEN Go to Step 4.20.7 and N/A
Steps 4.20.9 through 4.20.14
- o ☐ IF the vessel is defueled and
it is desired to lower the FTC
and vessel level using the
DHP,
THEN Go to Step 4.20.9 and N/A
Steps 4.20.7 and 4.20.8

Initial/Date

4.20 DRAINING FUEL TRANSFER CANAL VIA "B" DH SYSTEM (Cont'd)

ACTIONS	DETAILS
4.20.7 <u>WHEN</u> FTC level decreases to approximately 136 feet, <u>THEN</u> stop FTC draindown	<ol style="list-style-type: none"> 1. <u> </u> Fully open DHV-6 2. <u>Close:</u> <ol style="list-style-type: none"> <u> </u> DHV-7 <u> </u> DHV-9 3. Monitor BWST level for approximately 5 min to detect any abnormal level change

Initial/Date

4.20.8 Continue draining per OP-406, Spent Fuel Cooling System	o <u> </u> GO TO OP-406, Section 4.8
--	---

Initial/Date

CAUTION: Vessel level will lower very rapidly when water level drops below the vessel flange if flow rate to the BWST is not decreased.

4.20.9 <u>WHEN</u> FTC level decreases to approximately 136 feet, <u>THEN</u> reduce DHP flow to ≈ 1700 gpm	<ol style="list-style-type: none"> 1. <u> </u> Monitor vessel level and DHP operating conditions closely 2. <u> </u> Adjust DHV-111 as required to attain ≈ 1700 gpm DHP flow 3. <u> </u> Adjust DHV-6 to maintain desired flow to the BWST
--	--

Initial/Date

4.20.10 <u>WHEN</u> the vessel level decreases below 135'6" (below the seal plate flange), <u>THEN</u> concurrently perform FTC draindown to the desired level per OP-406, Spent Fuel Cooling System	<ol style="list-style-type: none"> o <u> </u> GO to OP-406, Section 4.8 o <u> </u> Draindown FTC to desired level (Normally ≈ 6" below the shallow end lip if the plenum is in the deep end)
---	---

Initial/Date

4.20 DRAINING FUEL TRANSFER CANAL VIA "B" DH SYSTEM (Cont'd)

ACTIONS	DETAILS
4.20.11 <u>WHEN</u> Vessel level decreases to approximately 133 feet, <u>THEN</u> stop the draindown and vent the RCP seal packages	1. <input type="checkbox"/> Fully open DHV-6 2. <input type="checkbox"/> Close DHV-7 3. <input type="checkbox"/> Maintain DHP flow ≥ 1500 gpm 4. Vent all RCP seals: <input type="checkbox"/> Break Seal Injection flanges or <input type="checkbox"/> Open top hat vents or <input type="checkbox"/> Open Seal Injection line vents <div style="text-align: right;">Initial/Date</div>
4.20.12 <u>WHEN</u> all RCP seals have been verified to be vented, <u>THEN</u> continue draindown	1. <input type="checkbox"/> Open DHV-7 2. <input type="checkbox"/> Adjust DHV-111 as required to maintain ≈ 1700 gpm 3. <input type="checkbox"/> Adjust DHV-6 to control flow to the BWST <div style="text-align: right;">Initial/Date</div>
4.20.13 <u>WHEN</u> Vessel level has decreased to $\geq 129.5'$, <u>THEN</u> stop vessel draindown	1. <input type="checkbox"/> Fully open DHV-6 2. Close: <input type="checkbox"/> DHV-7 <input type="checkbox"/> DHV-9 3. <input type="checkbox"/> Monitor BWST and Vessel level for approximately 5 min to detect any abnormal level changes <div style="text-align: right;">Initial/Date</div>
4.20.14 Establish an activity to restore RCP seal packages to normal prior to subsequent refill to ≥ 133 feet	o <input type="checkbox"/> Activity established to restore RCP Seal Packages prior to refill to include the following as required: - Seal Injection flanges restored - Top hat vents closed - Seal Injection line vents closed <div style="text-align: right;">Initial/Date</div>

4.21 BWST RECIRCULATION WITH ALTERNATE SUCTION TO DECAY HEAT PUMPS

ACTIONS	DETAILS
4.21.1 Ensure the Spent Fuel Cooling System is shut down	<ul style="list-style-type: none"> o Ensure STOPPED: o SFP-1A o SFP-1B o SFP-2 o These components may be tagged per CP-115 at the discretion of the SSOD
	Initial/Date

 CAUTION: Carefully monitor spent fuel pool and BWST levels while performing this section. Be alert for the possibility of an inadvertent water transfer.

- | | |
|---|--|
| 4.21.2 Establish BWST recirc path via the SF system | <ol style="list-style-type: none"> 1. CLOSE the following: <ul style="list-style-type: none"> ___ SFV-8, "A" SF Pool Outlet ___ SFV-10, SFP-1A Suction ___ SFV-11, SFP-1B Suction ___ SFV-14, SFP-2 Return Isol ___ SFV-134, RML-4 Isolation ___ SFV-21, SFP-2 Suction X-tie ___ SFV-88, Fuel Transfer Canal Outlet ___ SFV-9, "B" SF Pool Outlet ___ SFV-6, Boric Acid Pump Outlet ___ DHV-39, DHP-1A Inlet ___ DHV-40, DHP-1B Inlet 2. OPEN the following: <ul style="list-style-type: none"> ___ SFV-12, Suction Header Isol ___ SFV-13, BWST Outlet ___ SFV-7, SFP Suction Crosstie ___ SFV-89, SF Outlet to DH ___ DHV-9, BWST Recirc Isolation |
|---|--|

Initial/Date

4.21 BWST RECIRCULATION WITH ALTERNATE SUCTION TO DECAY HEAT PUMPS (Cont'd)

ACTIONS

DETAILS

NOTE: RWP-3A is not required to be started if DC temperature is expected to remain less than 105°F without RW heat removal.

4.21.3 IF DHP-1A is to be used,
THEN perform this step,
OTHERWISE GO TO Step 4.21.6

1. ☐ OPEN the following:
 - o DHV-39, DHP-1A Inlet
 - o DHV-8, "A" DH Recirc Isol
2. ☐ START DCP-1A
3. ☐ START RWP-3A if required
4. ☐ CLOSE DHV-34, BWST Outlet
5. ☐ Adjust DHV-110 controller to control flow at 1500-1800 gpm
6. ☐ START DHP-1A
7. ☐ Adjust DHP-1A low amp alarm as desired per Section 4.31

Initial/Date

4.21.3.1 Ensure proper lubrication of DHP-1A

- o ☐ Observe proper operation of Slinger Rings
- o ☐ Ensure proper oil levels

Initial/Date

4.21.4 WHEN BWST recirc is no longer desired,
THEN secure recirc and realign decay heat system

1. ☐ STOP DHP-1A
2. ☐ STOP RWP-3A if running
3. ☐ STOP DCP-1A
4. ☐ CLOSE the following:
 - o DHV-39
 - o DHV-8
5. ☐ OPEN DHV-34
6. ☐ Adjust DHV-110 controller to control flow at approx. 3000 gpm and select "AUTO"
7. ☐ Monitor BWST level for approx. 5 min to detect any abnormal level changes

Initial/Date

4.21 BWST RECIRCULATION WITH ALTERNATE SUCTION TO DECAY HEAT PUMPS (Cont'd)

ACTIONS	DETAILS
4.21.5 Realign SF and DH Systems to normal	<ol style="list-style-type: none">1. Close/Ensure closed the following:<ul style="list-style-type: none">— SFV-89— SFV-132. Perform Valve Check List IV (Enclosure 4)3. Exit this procedure <div style="text-align: right;">_____ Initial/Date</div>

NOTE: RWP-3B is not required to be started if DC temperature is expected to remain less than 105°F without RW heat removal.

NOTE: RWV-150 will not properly control SW temperature if RWP-3B is running.

4.21.6 Commence BWST recirculation	<ol style="list-style-type: none">1. — OPEN the following:<ul style="list-style-type: none">o DHV-40, DHP-1B Inleto DHV-7, "B" DH Recirc Isol2. — START DCP-1B3. — START RWP-3B if required4. — CLOSE DHV-35, BWST Outlet5. — Adjust DHV-111 controller to control flow at 1500-1800 gpm6. — START DHP-1B7. — Adjust DHP-1B low amp alarm as desired per Section 4.31 <div style="text-align: right;">_____ Initial/Date</div>
------------------------------------	---

4.21.6.1 Ensure proper lubrication of DHP-1B	<ol style="list-style-type: none">o — Observe proper operation of Slinger Ringso — Ensure proper oil levels <div style="text-align: right;">_____ Initial/Date</div>
--	---

4.21 BWST RECIRCULATION WITH ALTERNATE SUCTION TO DECAY HEAT PUMPS (Cont'd)

ACTIONS	DETAILS
4.21.7 <u>WHEN</u> BWST recirc is no longer desired, <u>THEN</u> secure recirc and realign decay heat system	<ol style="list-style-type: none"> 1. <input type="checkbox"/> STOP DHP-1B 2. <input type="checkbox"/> STOP RWP-3B if running 3. <input type="checkbox"/> STOP DCP-1B 4. <input type="checkbox"/> CLOSE the following: <ol style="list-style-type: none"> o DHV-40 o DHV-7 5. <input type="checkbox"/> OPEN DHV-35 6. <input type="checkbox"/> Adjust DHV-111 controller to control flow at approx. 3000 gpm and select "AUTO" 7. <input type="checkbox"/> Monitor BWST level for approx. 5 min to detect any abnormal level changes
	_____ Initial/Date

4.21.8 Realign SF and DH Systems to normal	<ol style="list-style-type: none"> 1. Close/Ensure closed the following: <ol style="list-style-type: none"> <input type="checkbox"/> SFV-13 <input type="checkbox"/> SFV-89 2. Perform Valve Check List IV (Enclosure 4)
	_____ Initial/Date

4.22 CROSS TIE OF DECAY HEAT FLOW TO REACTOR VESSEL "A" DECAY HEAT PUMP IN SERVICE

ACTIONS	DETAILS
4.22.1 Ensure "A" DH train in service	o Refer to Section 4.5
	<u>Initial/Date</u>

NOTE: If DHV-7 or 8 do not open electrically due to high differential pressure across the valve(s), it may be necessary to open the valve(s) manually.

4.22.2 Cross-connect DH trains	1. <u> </u> CLOSE DHV-111, "B" DH Train Flow Control
	2. <u> </u> OPEN the following:
	o DHV-8, "A" DH Crosstie
	o DHV-7, "B" DH Crosstie
	o DHV-6, "B" DH Outlet
	<u>Initial/Date</u>

4.22.3 Transfer DHP-1A flow to "B" DH train	1. <u> </u> Monitor crossover flow on DH-38-FI
	2. <u> </u> CLOSE DHV-5, "A" DH Outlet
	3. <u> </u> Adjust DHV-110 to maintain desired flowrate
	4. <u> </u> Adjust DHP-1A low amp alarm as desired per Section 4.31
	<u>Initial/Date</u>

4.22.4 <u>WHEN</u> cross connected operation is no longer desired, <u>THEN</u> restore normal lineup	1. <u> </u> OPEN DHV-5
	2. <u> </u> CLOSE the following:
	o DHV-7
	o DHV-8
	o DHV-6
	3. <u> </u> Adjust DHV-110 to maintain desired flowrate
	4. <u> </u> Adjust DHV-111 controller to control at approximately 3000 and place in "AUTO"
	<u>Initial/Date</u> <u>Verified by/Date</u>

4.23 CROSS TIE OF DECAY HEAT FLOW TO REACTOR VESSEL "B" DECAY HEAT PUMP IN SERVICE

ACTIONS	DETAILS
4.23.1 Ensure "B" DH train in service	<ul style="list-style-type: none">o Refer to Section 4.5 <div style="text-align: right;">_____ Initial/Date</div>

NOTE: If DHV-7 or 8 do not open electrically due to high differential pressure across the valve(s), it may be necessary to open the valve(s) manually.

4.23.2 Cross-connect DH trains	<ul style="list-style-type: none">1. ____ CLOSE DHV-110, "A" DH Train Flow Control2. ____ OPEN the following:<ul style="list-style-type: none">o DHV-8, "A" DH Crosstieo DHV-7, "B" DH Crosstieo DHV-5, "A" DH Outlet <div style="text-align: right;">_____ Initial/Date</div>
--------------------------------	---

4.23.3 Transfer DHP-1B flow to "A" DH train	<ul style="list-style-type: none">1. ____ Monitor crossover flow on DH-38-FI2. ____ CLOSE DHV-6, "B" DH Outlet3. ____ Adjust DHV-111 to maintain desired flowrate4. ____ Adjust DHP-1B low amp alarm as desired per Section 4.31 <div style="text-align: right;">_____ Initial/Date</div>
---	--

4.23.4 <u>WHEN</u> cross connected operation is no longer desired, <u>THEN</u> restore normal lineup	<ul style="list-style-type: none">1. ____ OPEN DHV-62. ____ CLOSE the following:<ul style="list-style-type: none">o DHV-7o DHV-8o DHV-53. ____ Adjust DHV-111 to maintain desired flowrate4. ____ Adjust DHV-110 controller to control at approximately 3000 gpm and place in "AUTO" <div style="display: flex; justify-content: space-between;"><div style="text-align: right;">_____ Initial/Date</div><div style="text-align: right;">_____ Verified by/Date</div></div>
---	--

4.24 RAISING LEVEL IN PARTIALLY DRAINED RCS

ACTIONS	DETAILS	
4.24.1 Ensure the decay heat system is on purification using the MU&P System	o Refer to Section 4.10	<u>Initial/Date</u>
4.24.2 Establish RCS level watch	<u>IF</u> tygon tube level indication is unavailable in the Control Room via a camera/monitor, <u>THEN</u> assign a level watch at the tygon level indicator and establish communications capability while changing level	<u>Initial/Date</u>
4.24.3 <u>IF</u> at anytime during the RCS level increase, RC-202-L1 (Computer Point R330) does not agree within $\pm 3"$ with the clear tygon tubing level indication, <u>THEN</u> investigate the abnormality. Perform SP-195, Remote Reactor Vessel Level Instrumentation Calibration, if required		<u>Initial/Date</u>
***** CAUTION: RC level instrumentation must be monitored continuously while changing level. *****		
4.24.4 Reduce purification flow to approximately 25-30 gpm	o Adjust DHV-105 or DHV-106 as applicable	<u>Initial/Date</u>

4.24 RAISING LEVEL IN PARTIALLY DRAINED RCS (Cont'd)

ACTIONS	DETAILS
***** CAUTION: Ensure the boron concentration of water added to the RCS is equal to or greater than required boron concentration for shutdown margin per Curve 18 or 19 of OP-103C. *****	
NOTE: Batch feeds from two sources may be used provided that:	
1) The resultant boron concentration of the batch feed is greater than or equal to the required boron concentration for shutdown margin per Curve 18 or 19 of OP-103C;	
<u>AND</u>	
2) The source of higher boron concentration is added to the RCS first.	
4.24.5 Add desired water volume from a suitable source to the RCS	<ul style="list-style-type: none">o Make a batch addition per Section 4.6 of OP-402, Makeup & Purification System <div>Initial/Date</div>
4.24.6 Monitor RCS level for at least 15 min after making addition <u>WHEN</u> level readings have stabilized, <u>THEN</u> record level	<ul style="list-style-type: none">1. — Record level readings in Nuclear Operator's Log2. — Secure watch (if applicable) at RC level instrumentation if reactor vessel level is \geq 132 feet <div>Initial/Date</div>
4.24.7 Restore purification flow to previous flowrate	<ul style="list-style-type: none">o Adjust DHV-105 or DHV-106 as applicable <div>Initial/Date</div>

4.25 LOWERING LEVEL IN PARTIALLY DRAINED RCS

ACTIONS	DETAILS
4.25.1 Ensure the decay heat system is on purification using the MU&P System	<p>o Refer to Section 4.10</p> <p>_____ Initial/Date</p>
4.25.2 Ensure RCS conditions are monitored during level change	<p>o Refer to SP-301, Enclosure 2, "RCS Level and Temperature Logsheet" for monitoring requirements</p> <p>_____ Initial/Date</p>
4.25.3 Establish RCS level watch	<p><u>IF</u> tygon tube level indication is unavailable in the Control Room via a camera/monitor, <u>THEN</u> assign a level watch at the tygon level indicator and establish communications capability while changing level</p> <p>_____ Initial/Date</p>
4.25.4 <u>IF</u> at any time during the RCS Draindown, RC-202-L1 (Computer Point R330) does not agree within ± 3 " with the Clear Tygon Tubing Level Indication, <u>THEN</u> stop the Draindown and investigate the abnormality. Perform SP-195, Remote Reactor Vessel Level Instrumentation Calibration, if required	<p>_____ Initial/Date</p>

4.25 LOWERING LEVEL IN PARTIALLY DRAINED RCS (Cont'd)

ACTIONS	DETAILS
---------	---------

NOTE: Maintain DHP Flow and Vessel Level Within the Acceptable regions of OP-103B, curves 16 and 18.

- | | |
|---|--|
| 4.25.5 Remove water from the RCS to achieve desired level | o Make a batch bleed per Section 4.5 of OP-402, Makeup & Purification System |
|---|--|

Initial/Date

- | | |
|--|---|
| 4.25.6 Monitor RCS level for at least 15 min after level is lowered
<u>WHEN</u> level readings have stabilized,
<u>THEN</u> record level | 1. ____ Record level readings in Nuclear Operator's Log |
|--|---|

Initial/Date

NOTE: Maintain DHP Flow and Vessel Level Within the Acceptable regions of OP-103B, curves 16 and 18.

- | | |
|---|--|
| 4.25.7 <u>IF</u> RC level is <132',
<u>THEN</u> maintain level watch | <u>IF</u> tygon tube level indication is unavailable in the Control Room via a camera/monitor,
<u>THEN</u> maintain a level watch at the tygon level indicator <u>and</u> maintain continuous communications capability with the Control Room |
|---|--|

Initial/Date

4.26 BWST RECIRCULATION WITH DHP-1A

ACTIONS	DETAILS
4.26.1 Align the DH System for recirculation using DHP-1A	<ol style="list-style-type: none"> 1. — OPEN the following: <ul style="list-style-type: none"> o DHV-34, BWST Suction Iso o DHV-8, "A" DH Recirc Iso o DHV-9, BWST Recirc Hdr Iso 2. — THROTTLE DHV-110 to approx. 3000 gpm 3. — Ensure CLOSED: <ul style="list-style-type: none"> o DHV-39, "A" DH Isolation o DHV-7, "B" DH Recirc Iso
	_____ Initial/Date

NOTE: RWP-3A is not required to be started if DC temperature is expected to remain less than 105°F without RW heat removal.

4.26.2 Commence BWST recirculation	<ol style="list-style-type: none"> 1. — START DCP-1A 2. — START RWP-3A if required 3. — START DHP-1A
	_____ Initial/Date

4.26.2.1 Ensure proper lubrication of DHP-1A	<ul style="list-style-type: none"> o — Observe proper operation of Slinger Rings o — Ensure proper oil levels
	_____ Initial/Date

4.26.3 <u>WHEN</u> BWST recirculation is no longer desired, <u>THEN</u> stop recirc flow	<ol style="list-style-type: none"> 1. — Ensure DHV-110 controller to approximately 3000 gpm and in "AUTO" 2. — STOP DHP-1A 3. — STOP RWP-3A if started 4. — STOP DCP-1A
	_____ Initial/Date

4.26 BWST RECIRCULATION WITH DHP-1A (Cont'd)

ACTIONS	DETAILS
4.26.4 Secure recirculation lineup	<ol style="list-style-type: none">1. — CLOSE the following:<ul style="list-style-type: none">o DHV-34o DHV-8o DHV-92. — Monitor BWST level for approx. 5 min to detect any abnormal level change
	<div>Initial/Date</div> <div>Verified By/Date</div>

4.27 BWST RECIRCULATION WITH DHP-1B

ACTIONS	DETAILS
4.27.1 Align the DH System for recirculation using DHP-1B	<ol style="list-style-type: none"> 1. <input type="checkbox"/> OPEN the following: <ul style="list-style-type: none"> o DHV-35, BWST Suction Iso o DHV-7, "B" DH Recirc Iso o DHV-9, BWST Recirc Hdr Iso 2. <input type="checkbox"/> THROTTLE DHV-111 to approx. 3000 gpm 3. <input type="checkbox"/> Ensure CLOSED: <ul style="list-style-type: none"> o DHV-40, "B" DH Isolation o DHV-8, "A" DH Recirc Iso
	_____ Initial/Date

NOTE: RWP-3B is not required to be started if DC temperature is expected to remain less than 105°F without RW heat removal.

NOTE: RWV-150 will not properly control SW temperature if RWP-3B is running.

4.27.2 Commence BWST recirculation	<ol style="list-style-type: none"> 1. <input type="checkbox"/> START DCP-1B 2. <input type="checkbox"/> START RWP-3B if required 3. <input type="checkbox"/> START DHP-1B
	_____ Initial/Date

4.27.2.1 Ensure proper lubrication of DHP-1B	<ul style="list-style-type: none"> o <input type="checkbox"/> Observe proper operation of Slinger Rings o <input type="checkbox"/> Ensure proper oil levels
	_____ Initial/Date

4.27.3 <u>WHEN</u> BWST recirculation is no longer desired, <u>THEN</u> secure recirc flow	<ol style="list-style-type: none"> 1. <input type="checkbox"/> Ensure DHV-111 controller to approximately 3000 gpm and in "AUTO" 2. <input type="checkbox"/> STOP DHP-1B 3. <input type="checkbox"/> STOP RWP-3B if started 4. <input type="checkbox"/> STOP DCP-1B
	_____ Initial/Date

4.27 BWST RECIRCULATION WITH DHP-1B (Cont'd)

ACTIONS	DETAILS
4.27.4 Secure recirculation lineup	<ol style="list-style-type: none">1. — CLOSE the following:<ul style="list-style-type: none">o DHV-35o DHV-7o DHV-92. — Monitor BWST level for approx. 5 min to detect any abnormal level change <div><div>Initial/Date</div><div>Verified By/Date</div></div>

4.28 FEED AND BLEED OF DC SYSTEM FOR CHEMISTRY CONTROL

ACTIONS	DETAILS
4.28.1 Ensure that the DC surge tank level alarms are operable and tank levels are maintained by DCV-10 or DCV-12 as applicable	<ul style="list-style-type: none">o High level alarm - 11 ft 4 ino Low level alarm - 8 ft 6 in <div>Initial/Date</div>
4.28.2 Start feed and bleed as requested by Chemistry	<ul style="list-style-type: none">1. — Designate an operator to monitor drain valve and close as required2. — OPEN applicable drain valve and adjust flow to approx. 1.5 gpm<ul style="list-style-type: none">o DCV-181, DCHE-1A Draino DCV-182, DCHE-1B Drain <div>Initial/Date</div>
4.28.3 Secure feed and bleed when; 1. Notified by Chemistry that DC System water chemistry is within specifications	<ul style="list-style-type: none">o CLOSE applicable drain:<ul style="list-style-type: none">o DCV-181o DCV-182
<u>OR</u> 2. Automatic Engineered Safeguards Actuation Occurs	<div>Initial/Date</div>

4.29 COOLDOWN OF PRESSURIZER WITH AUXILIARY SPRAY (RCV-53)

ACTIONS

DETAILS

CAUTION: Do not use Aux spray to degas the PZR.

NOTE: Whenever Auxiliary Pressurizer spray is required then the pressurizer heaters must be off and the A THOT temperature should be monitored.

NOTE: "A" DH train is preferred due to increased auxiliary spray flow.

4.29.1 Ensure sufficient
pressurizer heaters
available

/_____
Initial/Date

4.29.2 Ensure No OTSG's are on
recirculation

Ensure CGP-2 is off
Ensure closed:

____ MSV-130
____ MSV-148
____ CGV-17
____ CGV-18

/_____
Initial/Date

CAUTION: Verify subcooled conditions in both A and B loop hot legs
while pressurizer is on spray.

4.29.3 Ensure RCV-53 is closed

Close RCV-53

/_____
Initial/Date

4.29.4 Open DHV-91

/_____
Initial/Date

4.29 COOLDOWN OF PRESSURIZER WITH AUXILIARY SPRAY (RCV-53) (Cont'd)

ACTIONS	DETAILS
4.29.5 Throttle open RCV-53 to achieve desired spray flow Throttle open RCV-53	<u>Initial/Date</u>
4.29.6 <u>WHEN</u> auxiliary spray flow is no longer desired, <u>THEN</u> secure spray flow	1. <input type="checkbox"/> Close RCV-53 2. <input type="checkbox"/> Close DHV-91 <u>Initial/Date</u>

4.30 SECURING DECAY HEAT REMOVAL

ACTIONS

DETAILS

CAUTION: Ensure cooling water is maintained to operating makeup pumps
 prior to securing DCP-1A/1B.

4.30.1 IF securing DHP-1A,
THEN continue with this
 step,
OTHERWISE GO TO Step 4.30.2

1. ☐ STOP DHP-1A
2. ☐ STOP RWP-3A
3. ☐ STOP DCP-1A
4. ☐ CLOSE the following:
 ☐ DHV-39
 ☐ DHV-5
5. ☐ GO TO Step 4.30.3

 Initial/Date

4.30.2 Secure "B" DH flow

1. ☐ STOP DHP-1B
2. ☐ STOP RWP-3B
3. ☐ STOP DCP-1B
4. ☐ CLOSE the following:
 ☐ DHV-6
 ☐ DHV-40

 Initial/Date

4.30.3 IF terminating DH removal,
THEN continue with this
 step,
OTHERWISE mark "N/A"

- o ☐ CLOSE the following:
- ☐ DHV-3 ☐ DHV-39
- ☐ DHV-4 ☐ DHV-40
- ☐ DHV-5 ☐ DHV-41
- ☐ DHV-6 ☐ DHV-91
- ☐ RCV-53

 Initial/Date

4.30 SECURING DECAY HEAT REMOVAL (Cont'd)

ACTIONS	DETAILS
4.30.4 Return ES valves to standby	<ul style="list-style-type: none">o <input type="checkbox"/> CLOSE/ensure CLOSED the following:<ul style="list-style-type: none"><input type="checkbox"/> DHV-34<input type="checkbox"/> DHV-35o <input type="checkbox"/> Place the following in AUTO with controller set at 300° gpm:<ul style="list-style-type: none"><input type="checkbox"/> DHV-110<input type="checkbox"/> DHV-111o <input type="checkbox"/> Close/Ensure closed the following valves with breaker in lock/reset<ul style="list-style-type: none"><input type="checkbox"/> DHV-3*<input type="checkbox"/> DHV-105<input type="checkbox"/> DHV-106 <div style="display: flex; justify-content: space-between; margin-top: 10px;"><div><u> </u> Initial/Date</div><div><u> </u> Verified by /Date</div></div>

*DHV-3 must have breaker locked to eye bolt on breaker cubicle door

NOTE: Refer to Enclosure 5.

4.30.5 Align DHHE-1A to ES standby	<ol style="list-style-type: none">1. <input type="checkbox"/> Position the DCV-177-MS rheostat to "0" (minimum cooling)2. <input type="checkbox"/> CLOSE DCV-194, IA Supply from DCV-177-MS to temperature control valves3. <input type="checkbox"/> OPEN DCV-195, IA Vent from DCV-177-MS <div style="display: flex; justify-content: space-between; margin-top: 10px;"><div><u> </u> Initial/Date</div><div><u> </u> Verified by /Date</div></div>
------------------------------------	--

4.30 SECURING DECAY HEAT REMOVAL (Cont'd)

ACTIONS

DETAILS

NOTE: Refer to Enclosure 5.

4.30.6 Align DHHE-1B to ES standby

1. — Position the DCV-178-MS rheostat to "0" (minimum cooling)
2. — CLOSE DCV-196, IA Supply from DCV-178-MS to temperature control valves
3. — OPEN DCV-197, IA Vent from DCV-178-MS

Initial/Date

Verified by /Date

4.31 SETTING DHP LOW AMPS ALARM SETPOINT

ACTIONS	DETAILS
4.31.1 <u>IF</u> desired to adjust the Decay Heat Pump low amperage alarm, <u>THEN</u> perform this section	o Adjustment will normally be required following a pump start or a flow change <u>when</u> the RCS is in a draindown condition

Initial/Date

4.31.2 <u>WHEN</u> DH flow has stabilized and flow is at the desired setpoint, <u>THEN</u> adjust potentiometer until alarm is just received (or clears)	o Pots are located inside the MCB on DH-56-IR for DHP-1A and DH-57-IR for DHP-1B o Pots are a 0-100%, 10 turn vernier dials
---	--

Initial/Date

NOTE: An alarm setpoint as close to the operating amps of the pump without causing nuisance alarms is desired.

4.31.3 Lower the setpoint to an operator desired value below the existing pump amp value	o Decrease setting on the potentiometer to a value as desired such that the alarm is clear and the setpoint is slightly below the operating amperage of the running DHP
--	---

Initial/Date

4.31.4 Periodically verify the setpoint is close to the DHP operating amps	o This will ensure that as conditions change (equipment warms up, RCS temperature changes, etc.) the setpoint will not drift too far away from the operating amps
--	---

Initial/Date

5.0 FOLLOW-UP ACTIONS

ACTIONS

DETAILS

None

6.0 RESTORATION INSTRUCTIONS

ACTIONS

DETAILS

None

VALVE CHECK LIST I

ENCLOSURE 1

(Page 1 of 2)

System: Decay Heat Seawater System		Flow Diagram No. FD-302-611	
Valve No.	Description	Position	Initials Perform/Verify
** "A" Train **			
RWV-31	Isolation to RW-62-PS and RW-7-PI	Open	/
RWV-39	Isolation to RW-9-PI	Open	/
RWV-18	3A Decay Heat Seawater Pump Discharge Valve	Sealed Open	/
RWV-28	Drain	Closed	/
RWV-9	RW-29-PI Root Valve	Open	/
RWV-50	RW-44-CX Root Valve	Closed	/
RWV-40	3A DH Seawater Train Isolation to Discharge Canal	Sealed Open	/
RWV-73	3A DHHE Seawater Vent	Closed	/
RWV-75	3A DHHE Seawater Drain	Closed	/
RWV-77	3A DHHE Seawater Drain	Closed	/
RWV-32	SW-RW Outfall Valve	*Sealed Open/Closed	/
RWV-110	Secondary Release Outlet	Locked Closed	/
RWV-111	RW Sample	Closed	/
RWV-146	Flow Instrument Isolation Vlv	Closed	/
** "B" Train **			
RWV-47	RW-8-PT Root Valve	Open	/
RWV-48	RW-6-PI and RW-61-PS Root Valves	Open	/
RWV-17	3B Decay heat Seawater Pump Discharge Valve	Sealed Open	/
RWV-44	Drain	Closed	/
RWV-4	RW-28-PI Root Valve	Open	/
RWV-49	RW-43-CX Root Valve	Closed	/
RWV-41	Isolation of DH Seawater to Discharge Canal	Sealed Open	/
RWV-74	3B DHHE Seawater Vent	Closed	/
RWV-76	3B DHHE Seawater Drain	Closed	/

NOTE: *At least 1 valve (RWV-32 or 33) open at all times.

VALVE CHECK LIST 1

ENCLOSURE 1

(Page 2 of 2)

System: Decay Heat Seawater System		Flow Diagram No. FD-302-611	
Valve No.	Description	Position	Initials Perform/Verify
RWV-78	3B DHHE Seawater Drain	Closed	/
RWV-33	SW-RW Outfall Valve	*Sealed Open/Closed	/
RWV-109	Secondary Release Outlet	Locked Closed	/
RWV-147	Flow Instrument Isolation Vlv.	Closed	/
Secondary Release Sample Station, Turb. Exterior Wall			
RWV-124	Secondary Release Sample (A)	Closed	/
RWV-126	Secondary Release Flush	Closed	/
RWP-4 Pump House at Discharge Canal			
RWV-127	RWP-4 Suction	Open	/
RWV-120	Suction Crossconnect	Closed	/
RW Flush Water to DO Seawater Room Aux. 95			
RWV-145	RWP-3A Flush Water to DO	Sealed Open	/
RWV-135	"A" Train Flush Water RW to DO	Sealed Open	/
RWV-144	Line Drain	Closed	/
RWV-138	Line Drain	Closed	/
RWV-143	RWP-3B Flush Water to DO	Sealed Open	/
RWV-139	Line Drain	Closed	/
RWV-140	Line Drain	Closed	/
RWV-136	"B" Train RW Flush Water to DO	Sealed Open	/
RWV-137	RWP-2A Flush Water to DO	Sealed Open	/
RWV-142	RWP-2B Flush Water to DO	Sealed Open	/
RWV-141	RWP-1 Flush Water to DO	Open	/

NOTE: *At least 1 valve (RWV-32 or 33) open at all times.

VALVE CHECK LIST IIENCLOSURE 2
(Page 1 of 9)

System: Decay Heat CCC System		Flow Diagram No. FD-302-631	
Valve No.	Description	Position	Initials Perform/Verify
** 3A DHCCC Surge Tank **			
DCV-67	3A Surge Tank Level Indication Isolation Valve	Open	/
DCV-101	DC-59-PI Instrument Isolation	Open	/
DCV-61	WD Vent 3A Surge Tank	Open	/
DCV-168	Vent 3A Surge Tank	Closed	/
DCV-176	Demineralized Water Line Drain at 3A Surge Tank	Closed	/
DCV-59	Demineralized Water Inlet to 3A Surge Tank Note 1	Open	/
DCV-169	Level Transmitter Isolation for 3A Surge Tank	Open	/
DCV-68	Level Indication Isolation for 3A Surge Tank	Open	/
DCV-72	Level Transmitter Isolation for 3A Surge Tank	Open	/
DCV-100	Level Indication Drain for 3A Surge Tank	Closed	/
DCV-63	3A Surge Tank Drain	Closed	/
DCV-19	3A Surge Tank Discharge	Sealed Open	/
DCV-121	3A Surge Tank Drain	Closed	/
DCV-187	WD Vent 3A Surge Tank	Closed	/
DCV-186	Nitrogen Supply Note 1	Open	/
** 3B DHCCC Surge Tank **			
DCV-69	3B Surge Tank Level Indication Isolation Valve	Open	/
DCV-102	DC-60-PI Instrument Isolation	Open	/
DCV-62	3B Surge Tank WD Vent	Open	/
DCV-167	3B Surge Tank Vent	Closed	/
DCV-175	Demineralized Water Drain at 3B Surge Tank	Closed	/
DCV-60	3B Surge Tank Demineralized Water Inlet Note 1	Open	/
DCV-170	Level Transmitter Isolation 3B Surge Tank	Open	/
DCV-70	Level Indication Isolation 3B Surge Tank	Open	/

NOTE 1: Ensure system integrity prior to opening these valves.

System: Decay Heat CCC System		Flow Diagram No. FD-302-631	
Valve No.	Description	Position	Initials Perform/Verify
DCV-74	Level Transmitter Isolation 3B Surge Tank	Open	/
DCV-99	Level Indication Drain 3B Surge Tank	Closed	/
DCV-64	3B Surge Tank Drain	Closed	/
DCV-20	3B Surge Tank Discharge	Sealed Open	/
DCV-122	3B Surge Tank Drain	Closed	/
DCV-189	WD Vent 3B Surge Tank	Closed	/
DCV-188	Nitrogen Supply	Note 1 Open	/
** 3A DHCCC Train **			
DCV-1	3A DHCCC Pump Suction	Sealed Open	/
DCV-91	Chemical Addition Isolation to 3A DHCCC Pump	Closed	/
DCV-75	Isolation to DC-1-PI	Open	/
DCV-88	Isolation to RM-L5	Open	/
DCV-171	Flush Line RML-5	Closed	/
DCV-202	RM-L5 Outlet Isolation	Open	/
DCV-201	RM-L5 Vent	Closed	/
DCV-200	RM-L5 Flush Line	Closed	/
DCV-204	RM-L5 Drain	Closed	/
DCV-203	RM-L5 Inlet Isolation	Open	/
DCV-172	Flush Line RML-5	Closed	/
DCV-87	Isolation to DC-45-FI	Open	/
DCV-3	3A DHCCC Pump Discharge	Sealed Open	/
DCV-77	PI-3 Isolation	Closed	/
DCV-79	PT-5 Isolation	Open	/
DCV-73	DC-61-FI Isolation	Open	/
DCV-71	DC-61-FI Isolation	Open	/
DCV-85	PS-55 Isolation	Open	/
DCV-97	Sample Isolation	Closed	/
** 3B DHCCC Train **			
DCV-2	3B DHCCC Pump Suction	Sealed Open	/
DCV-92	Chemical Addition Isolation to 3B DHCCC Pump	Closed	/

NOTE 1: Ensure system integrity prior to opening these valves.

System: Decay Heat CCC System		Flow Diagram No. FD-302-631	
Valve No.	Description	Position	Initials Perform/Verify
DCV-76	Isolation to DC-2-PI	Open	/
DCV-89	RM-L6 Sample Line Isolation	Open	/
DCV-173	RML-6 Drain	Closed	/
DCV-209	RM-L6 Isolation	Open	/
DCV-208	RML-6 Vent	Closed	/
DCV-207	Flush Line RML-6	Closed	/
DCV-211	RM-L6 Drain	Closed	/
DCV-210	RM-L6 Isolation	Open	/
DCV-174	RML-6 Drain	Closed	/
DCV-90	RML-6 Sample Line Isolation	Open	/
DCV-4	3B DHCCC Pump Discharge	Sealed Open	/
DCV-78	Isolation to DC-4-PI	Closed	/
DCV-80	Isolation to DC-6-PT	Open	/
DCV-93	DC-62-FI Isolation	Open	/
DCV-94	DC-62-FI Isolation	Open	/
DCV-86	Isolation to DC-56-PS	Open	/
DCV-98	Sample Isolation	Closed	/
** 3A DHCCC Train **			
DCV-131	Drain	Closed	/
DCV-123	Vent	Closed	/
DCV-5	3A Decay Heat Removal Heat Exchanger Inlet	Sealed Open	/
DCV-17 Manual Handjack	3A Decay Heat Removal Heat Exchanger Inlet/Outlet X-tie Manual Handjack	Sealed in Full Counterclockwise Position	/
DCV-177 Manual Handjack	3A Decay Heat Removal Heat Exchanger Outlet Manual Handjack	Sealed 1-1/4 Turns from the Full Counterclockwise Position	/
DCV-125	3A Decay Heat Exchanger Vent	Closed	/
DCV-129	3A Decay Heat Exchanger Vent	Closed	/
DCV-127	Drain	Closed	/
DCV-7	3A Decay Heat Exchanger Isolation	Sealed Open	/
DCV-160	Vent	Closed	/

VALVE CHECK LIST IIENCLOSURE 2
(Page 4 of 9)

System: Decay Heat CCC System		Flow Diagram No. FD-302-631	
Valve No.	Description	Position	Initials Perform/Verify
DCV-13	3A DHCCCS Heat Exchanger Inlet	Sealed Open	/
DCV-81	Isolation to DC-41-PI	Open	/
DCV-82	Isolation to DC-42-PI	Open	/
DCV-181	3A DHCCC Heat Exch. Drain	Closed	/
DCV-183	3A DH Removal HE Drain	Closed	/
** 3B DHCCC Train **			
DCV-146	Drain	Closed	/
DCV-124	Vent	Closed	/
DCV-6	3B Decay Heat Removal Heat Exchanger Inlet	Sealed Open	/
DCV-18 Manual Handjack	3B Decay Heat Removal Heat Exchanger Inlet/Outlet X-tie Manual Handjack	Sealed in Full Counterclockwise Position	/
DCV-178 Manual Handjack	3B Decay Heat Removal Heat Exchanger Outlet Manual Handjack	Sealed 5-3/4 Turns from the Full Counterclockwise Position	/
DCV-126	3B Decay Heat Exchanger Vent	Closed	/
DCV-130	3B Decay Heat Exchanger Vent	Closed	/
DCV-128	Drain	Closed	/
DCV-8	3B Decay Heat Exchanger Isolation	Sealed Open	/
DCV-159	Vent	Closed	/
DCV-14	3B DHCCCS Heat Exchanger Inlet	Sealed Open	/
DCV-83	Isolation to DC-43-PI	Open	/
DCV-84	Isolation to DC-44-PI	Open	/
DCV-182	3B DHCCC Heat Exch. Drain	Closed	/
DCV-184	3B DH Removal HE Drain	Closed	/
** 3A DHCCC Train **			
DCV-15	3A DHCCCS Heat Exchanger Outlet	Sealed Open	/
DCV-164	Vent	Closed	/
DCV-179	Vent	Closed	/

VALVE CHECK LIST II

ENCLOSURE 2

(Page 5 of 9)

System: Decay Heat CCC System		Flow Diagram No. FD-302-631	
Valve No.	Description	Position	Initials Perform/Verify
** 3A Decay Heat Pump Air Handling Unit **			
DCV-32	3A Air Handling Fan Inlet	Sealed Open	/
DCV-38	3A Air Handling Fan Outlet	Sealed 1-3/4 Turns Open	/
DCV-161	Vent	Closed	/
3A Decay Heat Pump Motor			
DCV-95	3A Stuffing Box and Bearing Inlet	Sealed 1-1/4 Turns Open	/
DCV-96	3A Stuffing Box and Bearing Outlet	Sealed Open	/
DCV-29	3A Decay Heat Pump Motor Inlet	Sealed Open	/
DCV-35	3A Decay Heat Pump Motor Outlet	Sealed 1 Turn Open	/
** 3B DHCCC Train **			
DCV-16	3B DHCCCS Heat Exchanger Outlet	Sealed Open	/
DCV-163	Vent	Closed	/
DCV-180	Vent	Closed	/
** 3B Decay Heat Pump Air Handling Unit **			
DCV-31	3B Air Handling Fan Inlet	Sealed Open	/
DCV-37	3B Air Handling Fan Outlet	Sealed 1-3/4 Turns Open	/
DCV-162	Vent	Closed	/
** 3B Decay Heat Pump Motor **			
DCV-119	3B Stuffing Box and Bearing Inlet	Sealed 1-1/2 Turns Open	/
DCV-120	3B Stuffing Box and Bearing Outlet	Sealed Open	/
DCV-30	3B Decay Heat Pump Motor Inlet	Sealed Open	/
DCV-36	3B Decay Heat Pump Motor Outlet	Sealed 7/8 Turn Open	/

VALVE CHECK LIST II

ENCLOSURE 2

(Page 6 of 9)

System: Decay Heat CCC System		Flow Diagram No. FD-302-631	
Valve No.	Description	Position	Initials Perform/Verify
** 3A DHCCC Train **			
** Reactor Building Spray Pump 3A Motor **			
DCV-115	3A Stuffing Box and Bearing Inlet	Sealed 2 Turns Open	/
DCV-116	3A Stuffing Box and Bearing Outlet	Sealed Open	/
DCV-27	3A Building Spray Pump Motor Inlet	Sealed Open	/
DCV-33	3A Building Spray Pump Motor Outlet	Sealed 3/4 Turn Open	/
** 3A Decay Heat Seawater Pump Motor **			
DCV-43	3A Raw Water Pump Inlet	Sealed Open	/
DCV-45	3A Raw Water Pump Outlet	Sealed 2 Turns Open	/
DCV-166	Drain	Closed	/
DCV-205	RWP-3A Motor Cooler Vent	Closed	/
** 3B DHCCC Train **			
** Reactor Building Spray Pump 3B Motor **			
DCV-117	3B Stuffing Box and Bearing Inlet	Sealed 2 Turns Open	/
DCV-118	3B Stuffing Box and Bearing Outlet	Sealed Open	/
DCV-28	3B Building Spray Pump Motor Inlet	Sealed Open	/
DCV-34	3B Building Spray Pump Motor Outlet	Sealed 7/8 Turns Open	/
** 3B Decay Heat Seawater Pump Motor **			
DCV-44	3B Raw Water Pump Inlet	Sealed Open	/
DCV-46	3B Raw Water Pump Outlet	Sealed 4 Turns Open	/
DCV-165	Drain	Closed	/
DCV-206	RWP03B Motor Cooler Vent	Closed	/

VALVE CHECK LIST II

ENCLOSURE 2

(Page 7 of 9)

System: Decay Heat CCC System		Flow Diagram No. FD-302-631	
Valve No.	Description	Position	Initials Perform/Verify
** 3A DHCCC Train ** ** Makeup and Purification 3A Pump Motor **			
DCV-132	Vent	Closed	/
DCV-133	Drain	Closed	/
DCV-134	Vent	Closed	/
DCV-135	Drain	Closed	/
DCV-136	Vent	Closed	/
DCV-137	Drain	Closed	/
DCV-21	DHCCC Isolation Inlet 3A Makeup and Purif. Motor	*Sealed Closed	/
DCV-39	3A Makeup and Purification	Sealed Open	/
DCV-47	3A Makeup and Purification	Sealed Open	/
DCV-48	3A Makeup and Purification	Sealed Open	/
DCV-41	3A Makeup and Purification	Sealed 5-1/2 Turns Open	/
DCV-51	3A Makeup and Purification	Sealed 2-1/2 Turns Open	/
** 3B DHCCC Train ** ** Makeup and Purification 3C Pump Motor **			
DCV-147	Vent	Closed	/
DCV-148	Drain	Closed	/
DCV-149	Vent	Closed	/
DCV-150	Drain	Closed	/
DCV-151	Vent	Closed	/
DCV-152	Drain	Closed	/

* App. R requires MUP-3A to be cooled by SW cooling.

VALVE CHECK LIST IIENCLOSURE 2
(Page 8 of 9)

System: Decay heat CCC System		Flow Diagram No. FD-302-631	
Valve No.	Description	Position	Initials Perform/Verify
DCV-22	DHCCC Isolation Inlet 3C Makeup and Purif. Motor	*Sealed Closed/ Open	/
DCV-153	Vent	Closed	/
DCV-40	3C Makeup and Purification Motor Inlet	Sealed Open	/
DCV-49	3C Makeup and Purification Motor Inlet	Sealed Open	/
DCV-50	3C Makeup and Purification Motor Inlet	Sealed Open	/
DCV-42	3C Makeup and Purification Motor Outlet	Sealed 9 Turns Open	/
DCV-53	3C Makeup and Purification Motor Outlet	Sealed 2-1/2 Turns Open	/
** 3A DHCCC Train ** ** Makeup and Purification 3A Pump Motor **			
DCV-52	3A Makeup and Purification Motor Outlet	Sealed 3 Turns Open	/
DCV-139	Vent	Closed	/
DCV-140	Drain	Closed	/
DCV-25	NOTE 1 DHCCC Isolation Discharge 3A Makeup and Purif. Motor	Sealed Closed	/
DCV-141	Vent	Closed	/
DCV-142	Drain	Closed	/
DCV-143	Vent	Closed	/
DCV-144	Drain	Closed	/
** DHR Cooler 3A Temperature Controls **			
DCV-194	Air Supply Line Iso. Vlv	Open	/
DCV-195	Air Supply Line Vent Vlv	Closed	/

* DC is the normal cooling for MUP 3C.

NOTE 1: App. R requires MUP-3A to be cooled by SW cooling.

ENCLOSURE 2
(Page 9 of 9)

NOTE 2: DC is the normal cooling for MUP-3C.

System: Decay Heat Removal System			Flow Diagram No. FD-302-641
Valve No.	Description	Position	Initials Perform/Verify
** "A" Train ** ** Intermediate Area **			
DHV-39	RC System Isolation to Decay Heat Suction NOTE 2	Open/Closed	/
DHV-86	Drain	Closed	/
DHV-87	Vent	Closed	/
DHV-88	Vent	Closed	/
DHV-41	Motor-Operated Iso.-RC System to Decay Heat Suction NOTE 1	Open/Closed	/
DHV-85	Drain	Closed & Capped	/
DHV-8	Root Valve to Recirculation Header	Closed	/
DHV-48	Decay Heat to Spent Fuel System	Closed	/
DHV-49	Drain to Miscellaneous Waste Storage Tank	Closed	/
DHV-9	Decay Heat Recirculation to BWST	Closed	/
DHV-10	DHV-9 Bypass	Closed	/
DHV-120	DHV-39 Bypass	Closed	/
DHV-5	Decay Heat Isolation to RC System NOTE 2	Open/Closed	/
DHV-79	Drain	Closed & Capped	/
DHV-95	Pressurizer Spray Header Drain	Closed	/
DHV-126	MU to DH Crossconnect throttle Vlv.	Closed	/
DHV-91	Decay Heat Isolation to Pressurizer Spray	Closed	/
DHV-96	Drain	Closed & Capped	/
** "B" Train ** ** Intermediate Area **			
DHV-40	RC System Isolation to Decay Heat Suction NOTE 3	Open/Closed	/
DHV-121	DHV-40 Bypass	Closed	/
DHV-7	Root Valve to Recirculation Header	Closed	/
DHV-6	Decay Heat Isolation to RC System NOTE 3	Open/Closed	/
DHV-80	Drain	Closed & Capped	/

NOTE 1: Open if DH Removal is in operation.

NOTE 2: Open if "A" Train DH Removal is in operation.

NOTE 3: Open if "B" Train DH Removal is in operation.

System: Decay Heat Removal System		Flow Diagram No. FD-302-641	
Valve No.	Description	Position	Initials Perform/Verify
***A" Train** **Decay Heat Pit Area**			
DHV-34	BWST Isolation to Decay Heat System	Closed	/
DHV-42	RB Sump Iso. to DHP Suction	Closed	/
DHV-84	Vent	Closed	/
DHV-82	Drain	Closed	/
DHV-21	3A DHP Suction	Sealed Open	/
DHV-20	3A DHP Drain	Closed	/
DHV-50	3A DHP Suction Test Conn.	Open	/
DHV-19	3A DHP Vent	Closed	/
DHV-59	3A DH Disch. Press. Indication Root Vlv	Closed	/
DHV-16	Vent	Closed	/
DHV-58	3A DHP Disch. Press. Test Conn.	Closed	/
DHV-57	3A DHHE Press. Test Conn.	Closed	/
DHV-15	Drain	Closed	/
DHV-92	Pzr. Spray Root Vlv	Open	/
DHV-102	3A DHP Cyclone Separator Inlet	Sealed Open	/
DHV-104	3A DHP Cyclone Separator Outlet	NOTE 4 Sealed \approx 1½ Turns Open	/
DHV-103	3A DHP Gland Water Supply	NOTE 4 Sealed \approx 1½ Turns Open	/
DHV-110	3A Decay Heat Pump Discharge Valve	Auto/3000	/
DHV-51	3A Decay Heat Pump Flow Transmitter Root Valve	Open	/
DHV-52	3A Decay Heat Pump Flow Transmitter Root Valve	Open	/
DHV-13	Chemical Sample Root Valve	Open	/
DHV-122	DHP-1A Suction Gauge Isolation	Open	/
DHV-123	DHP-1A Suction Gauge Isolation	Closed	/
DHV-198	DHV-42 Guard Pipe Drain	Open	/

NOTE 4: This is a course setting, DHP Cyclone Separator Outlet and Gland Water Supply valves must be throttled while the DHP is running. Refer to Section 4.5 of this procedure.

System: Decay Heat Removal System		Flow Diagram No. FD-302-641	
Valve No.	Description	Position	Initials Perform/Verify
** "B" Train ** ** Decay Heat Pit Area **			
DHV-35	BWST Isolation to Decay Heat System	Closed	/
DHV-43	RB Sump Iso. to DHP Suction	Closed	/
DHV-83	Vent	Closed	/
DHV-81	Drain	Closed	/
DHV-32	3B DHP Suction	Sealed Open	/
DHV-31	3B DHP Drain	Closed	/
DHV-62	3B DHP Suction Test Conn.	Open	/
DHV-30	3B DHP Vent	Closed	/
DHV-29	3B DH Disch. Press. Indication Root Vlv	Closed	/
DHV-26	Vent	Closed	/
DHV-61	3B DHP Disch. Press. Test Conn.	Closed	/
DHV-60	3B DHHE Press. Test Conn.	Closed	/
DHV-27	Drain	Closed	/
DHV-111	3B DHP Disch. Vlv	Auto/3000	/
DHV-99	3B DHP Cyclone Separator Inlet	Sealed Open	/
DHV-101	3B DHP Cyclone Separator Outlet	NOTE 4 Sealed $\approx 1\frac{1}{2}$ Turns Open	/
DHV-100	3B DHP Gland Water Supply	NOTE 4 Sealed $\approx 1\frac{1}{2}$ Turns Open	/
DHV-53	3B Decay Heat Pump Flow Transmitter Root Valve	Open	/
DHV-54	3B Decay Heat Pump Flow Transmitter Root Valve	Open	/
DHV-24	Chemical Sample Root Valve	Open	/
DHV-124	DHP-1B Suction Gauge Isolation	Open	/
DHV-125	DHP-1B Suction Gauge Isolation	Closed	/
DHV-199	DHV-43 Guard Pipe Drain	Open	/

NOTE 4: This is a course setting, DHP Cyclone Separator Outlet and Gland Water Supply valves must be throttled while the DHP is running. Refer to Section 4.5 of this procedure.

VALVE CHECK LIST III


ENCLOSURE 3
(Page 4 of 5)

[illegible]


System: Decay Heat Removal System		Flow Diagram No. FD-302-641	
Valve No.	Description	Position	Initials Perform/Verify
DHV-18	Reactor Building Spray Recirculation	Open	/
DHV-46	Spent Fuel Isolation to BWST	Open	/
DHV-65	BWST Instrument Root Valve	Open	/
DHV-117	BWST Instrument Root Valve	Open	/
** Reactor Building Area **			
DHV-94	Decay Heat to Pressurizer Spray Drain	Closed	/
DHV-4	Motor-Operated Iso.-RC System to Decay Heat System NOTE 1	Open/Closed	/
DHV-3	Motor-Operated Iso.-RC System to Decay Heat System NOTE 1	Open/Closed	/
** "B" Train **			
** Miscellaneous Areas **			
DHV-90	Spent Fuel Header Drain	Closed	/
DHV-89	Vent on Line to SF Cooler	Closed	/
DHV-97	Iso. Vlv DH-38-DPT	Open	/
DHV-98	Iso. Vlv DH-38-DPT	Open	/
DHV-112	Vent on Loop "A" to RV	Closed	/
DHV-113	Vent on Loop "B" to RV	Closed	/
DHV-114	Equalization Line	Locked 1/2 Turn Open	/
DHV-116	Equalization Line	Locked 1/2 Turn Open	/
DHV-118	Level Tap Isolation	Open	/
DHV-119	Level Tap Isolation	Open	/

- NOTE 1: Open if DH Removal is in operation.

System: BWST Recirc with Alternate Suction to D.H. Pumps			
Valve No.	Description	Position	Initials Perform/Verify
SFV-10	SF Pump "A" Suction	Open	/
SFV-11	SF Pump "B" Suction	Open	/
SFV-14	SF Cask Area Isolation	Closed	/
SFV-21	BWR Pump Suction Isolation	Open	/
SFV-88	FTC to SF Pump Suction	Open	/
SFV-9	"B" Pool Outlet	Open	/
SFV-6	BA Pump	Closed	/
SFV-8	"A" Pool Outlet	Open	/
SFV-12	SF BWR Pump Suction Crosstie	Closed	/
SFV-7	SF Pump Suction Crosstie	Open	/
SFV-134	RML-4 Outlet	Closed	/
DHV-39	RC System Isolation to Decay Heat Suction	Closed	/
DHV-40	RC System Isolation to Decay Heat Suction	Closed	/
DHV-110	3A Decay Heat Pump Discharge Valve	Auto/3000	/
DHV-111	3B Decay Heat Pump Discharge Valve	Auto/3000	/
DHV-7	Root Valve to Recirculation Header	Closed	/
DHV-8	Root Valve to Recirculation Header	Closed	/
DHV-9	Decay Heat Recirculation to BWST	Closed	/
DHV-34	BWST Isolation to Decay Heat System	Closed	/
DHV-35	BWST Isolation to Decay Heat System	Closed	/



**'A' DC SYSTEM
DCV-177-MS**



**'B' DC SYSTEM
DCV-178-MS**

GUIDELINES FOR OPERATING DCV-17 [DCV-18]
AND DCV-177 [DCV-178] MANUALLY

NOTE: Prior to performing this enclosure, the preferred Operating Practice is to place the other DH Train in service if available.

NOTE: Instructions in Steps 1, 2, 5 and 6 are duplicated in the field. Ensure any changes made to these instructions are similarly made to the engraved plaques.

NOTE: Valve pairs DCV-17/DCV-177 are for 'A' train and valve pairs [DCV-18]/[DCV-178] are for 'B' train.

1. IF operating 'A' DH train,
THEN transfer both DCV-17 and
DCV-177 from AUTOMATIC to
MANUAL by performing details 1
through 3 for each valve

DCV-17

1. — Unseal and rotate hand-wheel clockwise until contact exists between handjack and actuator diaphragm.
2. — Close filter regulator supply valve V-3.
3. — Vent air off filter regulator.

Initial/Date

DCV-177

1. — Unseal and rotate hand-wheel clockwise until contact exists between handjack and actuator diaphragm.
2. — Close filter regulator supply valve V-3.
3. — Vent air off filter regulator.

Initial/Date

2. IF operating 'B' DH train,
THEN transfer both DCV-18 and
DCV-178 from AUTOMATIC to
MANUAL by performing details 1
through 3 for each valve

DCV-18

1. ☐ Unseal and rotate hand-wheel clockwise until contact exists between handjack and actuator diaphragm.
2. ☐ Close filter regulator supply valve V-3.
3. ☐ Vent air off filter regulator.

Initial/Date

DCV-178

1. ☐ Unseal and rotate hand-wheel clockwise until contact exists between handjack and actuator diaphragm.
2. ☐ Close filter regulator supply valve V-3.
3. ☐ Vent air off filter regulator.

Initial/Date

NOTE: Changes to positioning or throttling of DCV-177, [DCV-178] must always be accompanied by the same changes to DCV-17, [DCV-18] in both direction and magnitude of handwheel rotation.

NOTE: Suspected failures of DCV-17, [DCV-18] and/or DCV-177, [DCV-178] can be cross-checked against expected DHHE-1A, [DHHE-1B] outlet temperatures DH-2-TI1, [DH-2-TI2], DCP-1A, [DCP-1B] discharge pressure, and DC 'A', ['B'] system flow DC-61-FI, [DC-62-FI], local at DCPs.

3. Throttle operating DH train DC cooling flow as required to obtain desired cooling
 1. — Manually throttle DCV-177, [DCV-178], as required to increase or decrease DC cooling flow
 2. — Manually throttle DCV-17, [DCV-18] the same amount and direction as DCV-177, [DCV-178]
 3. — Following throttling adjustments, monitor the following:
 - o DHHE-1A, [DHHE-1B] outlet temperature to ensure SP-422 heatup or cooldown limits are not exceeded
 - o DCHE-1A, [DCHE-1B] delta RW temperature is maintained $< 10^{\circ}\text{F}$
 - o Monitor PZR level for decreasing trends; i.e. Potential RCS overcooling, DH system leaks or lifting reliefs
 - o Monitor DC system flow, DC-61-FI, [DC-62-FI] and adjust DCV-17, [DCV-18] as required to maintain near constant flow

/_____
Initial/Date

4. Establishment of administrative control over affected valves should be considered

- o — As required install a blue tag on the handwheel(s) and instrument air supply valve(s) of the appropriate valve(s)
- o — Issue blue tags to NSS
- o — Install required blue tags in accordance with CP-115

Initial/Date

5. IF it is desired to return DHHE-1A from MANUAL to AUTOMATIC control, THEN perform details 1 through 4 for both DCV-177 and DCV-17

- DCV-17
- 1. — Close filter regulator vent.
 - 2. — Open filter regulator supply valve V-3.
 - 3. — Monitor DHHE-1A outlet temperature during performance of detail 4.
 - 4. — Rotate handwheel to full counterclockwise position and seal.

Initial/Date

- DCV-177
- 1. — Close filter regulator vent.
 - 2. — Open filter regulator supply valve V-3.
 - 3. — Monitor DHHE-1A outlet temperature during performance of detail 4.
 - 4. — Rotate handwheel to full counterclockwise position, then rotate in the clockwise direction 1-1/4 turns and seal.

Initial/Date

6. IF it is desired to return DHHE-1B from MANUAL to AUTOMATIC control, THEN perform details 1 through 4 for both DCV-178 and DCV-18

DCV-18

1. ☐ Close filter regulator vent.
2. ☐ Open filter regulator supply valve V-3.
3. ☐ Monitor DHHE-1B outlet temperature during performance of detail 4.
4. ☐ Rotate handwheel to full counterclockwise position and seal.

Initial/Date

DCV-178

1. ☐ Close filter regulator vent.
2. ☐ Open filter regulator supply valve V-3.
3. ☐ Monitor DHHE-1B outlet temperature during performance of detail 4.
4. ☐ Rotate handwheel to full counterclockwise position, then rotate in the clockwise direction 5-3/4 turns and seal.

Initial/Date