

Duquesne Light Company

Beaver Valley Power Station
P.O. Box 4
Shippingport, PA 15077-0004

SUSHIL C. JAIN
Division Vice President
Nuclear Services
Nuclear Power Division

August 2, 1996

(412) 393-5512
Fax (412) 643-8069

U. S. Nuclear Regulatory Commission
Attention: Document Control Desk
Washington, DC 20555-0001

Subject: Beaver Valley Power Station, Unit No. 1
Docket No. 50-334, License No. DPR-66
1996 Steam Generator Tube Inspection 90 Day Report

Reference 1: Safety Evaluation by the Office of Nuclear Reactor Regulation Related to Amendment No. 198 to Facility Operating License No. DPR-66, Duquesne Light Company, Beaver Valley Power Station Unit No. 1 Docket No. 50-334.

Enclosed is a copy of the "Beaver Valley Unit 1, 1996 Alternate Repair Criteria 90 Day Report," which is provided to satisfy a commitment, identified in Reference 1, providing main steam line break leak rates, tube burst probabilities and supporting data within 90 days following restart from the eleventh refueling outage of Beaver Valley Unit 1.

Our previous report, "Beaver Valley Unit 1, Interim Plugging Criteria 90 Day Report," was forwarded by letter dated June 9, 1995. In Table 8-2 of that report, the projected end of cycle 11 steam line break leak rate for the "A" steam generator was 0.31 gpm. The projected leak rate in the attached report for the end of cycle 11 is shown to be 2.37 gpm. An investigation of the differences was performed by Duquesne Light Company. This investigation has concluded that an error had been made in the previous calculation performed by Westinghouse where the leak rate variability was not addressed. The correct projected leak rate for the end of cycle 11 is 2.37 gpm as noted above.

120094


9608130028 960802
PDR ADOCK 05000334
R PDR



Beaver Valley Power Station, Unit No. 1
1996 Steam Generator Tube Inspection
90 Day Report
Page 2

If you have any questions regarding the attached information, please contact
Mr. R. K. Brosi, Manager, Nuclear Safety Department, at (412) 393-5210.

Sincerely,



Sushil C. Jain

Enclosures

c: Mr. L. W. Rossbach, Sr. Resident Inspector
Mr. H. J. Miller, NRC Region I Administrator
Mr. D. S. Brinkman, Sr. Project Manager