


Sandia Laboratories

Albuquerque, New Mexico
Livermore, California

date: March 26, 1980

to: Walter Oliu - NRC


from: W. Lee Garner - 3151

ERRATA SHEET

subject: SAND79-2311 (Supplement), NUREG/CR1191, Confirmation of the Original Qualification Test for Electrical Connectors Used at Browns Ferry Nuclear Power Plant Unit 3, L. L. Bonzon, W. H. Buckalew, D. W. Dugan, F. V. Thome, Sandia Laboratories, Albuquerque, NM, February 1980

The subject document supplement is a repeat of the original document with the addition of raw data from the project study. The distribution designation "RV" was incorrectly included since only specific individuals are interested in this version of the report.

Please strike the letters RV from both the cover and title pages of your copy(ies) of this supplement.

WLG:jz

3141 - Library

8004240 505

NUREG/CR-1191
SAND79-2311 (SUPPLEMENT)
RV

Confirmation of the Original Qualification Test for Electrical Connectors Used at Browns Ferry Nuclear Power Plant Unit 3

Lloyd L. Bonzon, William H. Buckalew, Douglas W. Dugan, Frank V. Thome

Prepared by Sandia Laboratories, Albuquerque, New Mexico 87185
and Livermore, California 94550 for the United States Department
of Energy under Contract DE-AC04-76DP00789

Printed February 1980



Sandia Laboratories

This report documents a part of the Qualification Testing Evaluation
(QTE) Program being conducted by Sandia Laboratories

55 2900 Q(7-73)

Prepared for
U. S. NUCLEAR REGULATORY COMMISSION

POOR ORIGINAL

NOTICE

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, or any of their employees, makes any warranty, expressed or implied, or assumes any legal liability or responsibility for any third party's use, or the results of such use, or any information, apparatus, product or process disclosed in this report, or represents that its use by such third party would not infringe privately owned rights.

The views expressed in this report are not necessarily those of the U. S. Nuclear Regulatory Commission.

Available from
National Technical Information Service
Springfield, VA 22161

POOR ORIGINAL

NUREG/CR-1191
SAND79-2311 (SUPPLEMENT)
RV

CONFIRMATION OF THE ORIGINAL QUALIFICATION TEST
FOR ELECTRICAL CONNECTORS USED
AT BROWNS FERRY NUCLEAR POWER PLANT UNIT 3

Lloyd L. Bonzon
William H. Buckalew
Douglas W. Dugan
Frank V. Thome

February 1980

Sandia Laboratories
Albuquerque, NM 87185
operated by
Sandia Corporation
for the
U.S. Department of Energy

Prepared for
Research Support Branch
Office of Water Reactor Safety Research
U.S. Nuclear Regulatory Commission
Washington, DC 20555
Under Interagency Agreement DOE 40-550-75
NRC Fin No. A-1051-0

CONTENTS

	<u>Page</u>
1.0 Background, Program Objective	7
2.0 Test Items Descriptions and Assembly	9
3.0 Description of Test Profiles	10
3.1 Radiation	11
3.2 Temperature Aging	12
3.3 Accident Test	13
4.0 Test Results, Conclusions	15
5.0 Test Documentation	19
A Connector Assembly Test Plan for Browns Ferry, Unit 3, Connectors; Fourth Draft, 8/30/79	A-1
B Test Procedures Browns Ferry, Unit 3, Connectors, Accident Simulation 10/26/79	B-1
C Specific Tests; Procedures and Data	
I. Acceptance Tests	I
II. Baseline Functional Tests	II
III. Baseline Mechanical/Dimensional Tests.....	III
IV. Radiation Test	IV
V. Post-Radiation Functional/Mechanical	V
VI. Temperature Aging Test	VI
VII. Post-Aging Functional/Mechanical Tests	VII
VIII. Accident Test	VIII
IX. Post-Accident Functional/Mechanical Test ...	IX
X. Post-Tests Inspections	X

FIGURES

1. View of Connector Boxes in Irradiation Cell	12
2. Oven and Associated Controller, with Connector Boxes In-Place in the Oven	14
3. Specified BF3-Connector Accident Test Profile and Data from November 1 and 2, 1979 Test	16
4. Post-Tests Disassembly of 250-VDC Connectors	17
5. Post-Tests Disassembly of 480-VAC Connectors	18

CONFIRMATION OF THE ORIGINAL QUALIFICATION TEST
FOR ELECTRICAL CONNECTORS USED
AT BROWNS FERRY NUCLEAR POWER PLANT UNIT 3

1. Background, Program Objective

Following the Union of Concerned Scientist's petition of November 4, 1977, the NRC Commissioners directed the NRC staff to:

"Arrange for a repeat of the tests to obtain data for the verification of current methodology for environmental qualification of electrical components. These tests should be performed with a representative sample of commercially available electrical connectors qualified in accordance with IEEE-323 (1974) and in use in nuclear power reactor safety systems. When available, the test results are to be promptly provided to the Commission."

The NRC staff interpreted this action to be aimed at providing information on the methodology of qualification testing using electrical connectors which meet the provisions of IEEE-323. Since no connectors in use at that time had been actually qualified to IEEE-323-1974 (a relatively new standard), the staff responded by directing that electrical connectors previously qualified by licensees for use in operating plants be tested in accordance with the provisions of IEEE-323-1971.

To the extent practicable, connector assemblies were to be subjected to the actual aging, radiation, and LOCA-simulation tests for which the connector assemblies had been qualified. In a letter dated May 22, 1978,

D. G. McDonald (SEP/DOR) to R. Feit (RA/RSR), DOR and IE recommended that the following plants/connectors be considered for testing:

BWR (a) Peach Bottom - Pyle National Connectors; or

(b) Browns Ferry - Bendix Connectors

PWR (a) Palisades - Viking Connectors; or

(b) Oconee - Viking Connectors

However, other plants or connectors would also be appropriate due to "... availability of the connectors to be tested, extensive procurement time, or other constraints."

From that date, Inspection and Enforcement (IE) staff evaluated some of the various utilities' connector hardware and qualification documents and directed that Sandia proceed with the first test in this series using Browns Ferry-Bendix (BF3) connectors. The principal objective was that the test was to duplicate, as closely as practicable, the actual Browns Ferry Connector tests; it is understood that these original tests were intended to conform to the requirements of IEEE-323-71, with the addition of a (Browns Ferry specified) thermal aging preconditioning requirement.

The order for the connector hardware was placed through a Bendix-authorized distributor on August 2, 1978 with delivery completed on November 1, 1978. Concurrently, Draft 1 of the Sandia-generated implementing test plan was forwarded to NRC staff, for review and approval, on August 11, 1978. Based on staff comments, Draft 2 of the plan was submitted on February 16, 1979 followed by Draft 3 on May 1 and Draft 4 on August 30.

The test plan specifically applied to the Browns Ferry Unit 3 (BF3) connector assemblies; the applicable (background) documents for this test plan are:

- (a) Tennessee Valley Authority, Purchase Requisition 150639, dated April 18, 1978.
- (b) "Assembling Browns Ferry Nuclear Plant Bendix Connectors," dated June 22, 1978.
- (c) "Test Procedure for Browns Ferry Bendix Connectors, Revision," undated.

The primary document, which the test plan intended to duplicate is:

- (d) "Qualification Test for Electrical Connectors Used at Browns Ferry Nuclear Power Plant Unit 3," Report No. 43854-2, Wyle Laboratories, March 28, 1978.

2. Test Items Descriptions and Assembly

Three each of two different types of electrical connectors were tested. Both types are manufactured by Bendix and used inside containment at Browns Ferry, Unit 3 (BF3), operated by the Tennessee Valley Authority (TVA).

<u>Qty</u>	<u>Manufacturer</u>	<u>Identification Numbers</u>	<u>Operating Voltage</u>	<u>Maximum Operating Current (A)</u>
3	Bendix	Plug: 10-214628-51S Receptacle: 10-214028-51P	250 Vdc	1.0
3	Bendix	Plug: 10-214636-78S Receptacle: 10-214036-78P	480 Vac	17.5

These Bendix connectors were purchased by Sandia through a Bendix-authorized distributor. Electric cable was furnished by TVA from spare

cable of the same type used at BF3. The Bendix 250-Vdc connector assemblies consisted of wire size No. 12 CPJ cable on the plug end and wire size No. 12 Vulkene cable on the receptacle end of the connectors. The Bendix 480-Vac connector assemblies consisted of wire size No. 10 CPJ cable on the plug end and wire size No. 10 Vulkene cable on the receptacle end of the connectors. CPJ and Vulkene cables consist of cross-linked polyethylene with the CPJ cable having a PVC insulating jacket.

Construction of six of each of the connector assemblies was conducted by BF3 staff using an assembly and potting procedure developed by BF3 staff (used in field assembling connectors) and approved/certified by IE staff. Initial assembly took place on January 29-30, 1979 at the BF3 site and was completed on February 26-27. All connectors were potted to appropriate specifications prior to any testing. The actual assembly was observed by IE staff; after completion of the assemblies, IE certified that they were acceptably equivalent to the in-place connectors at BF3 before any simulation tests were conducted.

The Bendix 250-Vdc connectors are equipped with 12 pins. Its wiring configuration was such that all pins were used during testing. The Bendix 480-Vac connectors are equipped with 14 pins: 12 were wired into a single-phase circuit. In each case, the 12 pins were wired to form a series/parallel circuit that gave a voltage difference between pins within the connector as well as passing current to simulate a load.

Following final assembly, six of each of the wired and potted assemblies were shipped to Sandia Laboratories (Albuquerque) for completion of the entire confirmation-of-qualification test series.

3. Description of Test Profiles

Three of each of two types of connectors were subjected to the prescribed series of tests with the remaining six connector assemblies saved as spares. This test series consisted of the following:

- I - Acceptance
- II - Baseline Functional
- III - Baseline Mechanical/Dimensional
- IV - Radiation
- V - Postradiation Functional/Mechanical
- VI - Temperature Aging
- VII - Postaging Functional/Mechanical
- VIII - Accident Test
- IX - Postaccident Functional/Mechanical
- X - Posttests Inspections

3.1 Radiation

The connector assemblies were exposed to Cobalt-60 radiation doses totalling 68.5 Mrads (air) at an averaged dose rate of 0.76 Mrad/h during the period April 4-9, 1979. By comparison, the specified values were 69 Mrad and 0.77 Mrad/h, respectively, to be attained within +10%.

The total 90-h irradiation interval was accomplished in four 22.5-h periods with the specimens rotated to achieve a more uniform total dose. Concurrently, selected temperatures were recorded; the maximum measured temperature was 35°C with the temperatures generally ranging between 30° to 34°C. Figure 1 shows a view of the connector boxes in place inside the irradiation facility.




Figure 1. View of Connector Boxes in Irradiation Cell

3.2 Temperature Aging

All of the electrical connectors were subjected to a two-part simulated aging test during the period, April 10-24, 1979. The specified aging times/temperatures/tolerances are shown below; the humidity was not controlled (i.e., was ambient).

<u>Aging Temperature</u>	<u>Aging Time</u>	<u>Aging Atmosphere</u>
217° +6°F	60 +0.1 h ^a	Air
217° -6°F	180 +0.1 h ^b	Nitrogen

^a60 h in air at 217°F is intended to simulate 6 mo in air at 130°F.

^b180 h is intended to simulate 18 mo in 130°F nitrogen with a maximum of 4% oxygen.

POOR ORIGINAL

Each test item was placed in the temperature chamber (i.e., oven) in a manner to avoid overheating from radiant effects from the chamber-heating elements (Figure 2). The temperature chamber was vented to the atmosphere to prevent buildup of outgasing products, particularly chlorine gas, from the test item inside the chamber. The air inside the chamber was distributed uniformly at an average velocity of about 250 ft/min; pretest flow measurements in an open chamber were made and recorded. The air-aging was conducted for 59 2/3 h at 217° \pm 3°F and was completed on April 13, 1979.

Following the air aging, the oven was purged with flowing nitrogen and the oven chamber brought to, and restabilized at, 217°F. The temperature was maintained (\pm 3°F) for 179 2/3 h and was completed on April 24. During nitrogen-aging, a continuous flow of nitrogen was maintained, averaging about 1/5 ft³/m.

During all phases of the aging tests, selected specimen and environment temperatures were recorded; the data indicated stabilized temperatures ranging between 218° and 220°F.

3.3 Accident Test

Programmatic delays in completing the test series were experienced during the period April 24 to November 1, 1979. The delays were a result of two factors. First, it was necessary for NRC staff to define the desired test profile so as to envelope both the originally specified and actual test profiles. Second, the necessary steam-generation equipment had to be assembled and a number of demonstration runs conducted to prove that the profile could be attained. During this 6-mo period, the connectors were stored in locked cabinets under ambient conditions; Sandia staff believes that the storage resulted in insignificant additional degradation and "age."




Figure 2. Oven and Associated Controller With Connector Boxes
In-Place in the Oven

POOR ORIGINAL

The connector assemblies were installed in the autoclave test chamber on October 31, 1979. Circuit continuity checks were performed and the assemblies instrumented to load and measure voltage and current. The test chamber was instrumented with numerous temperature and pressure sensors located to provide indications that the environments were correctly attained and maintained.

The electrical connector test assemblies were subjected to the accident test profile shown in Figure 3 and as detailed in established test procedures on November 1-2, 1979. The 250-Vdc connector assemblies were energized throughout the entire test. The 480-Vac connector assemblies were energized during the first 5 minutes, between minutes 15 and 18, and between minutes 57 and 60.

All aspects of the test were within the specified tolerances except for a few minutes at approximately 2 h when the temperature exceeded the desired (110°C) value by +7°C.

4. Test Results, Conclusions

All aspects of the test were considered satisfactorily completed. All connector assemblies passed the specifications of the test series; in particular, the assemblies carried their specified current/voltage loads during the accident-test phase. Posttest inspections (Figures 4 and 5) indicated little or no degradation of the connectors.

It is concluded that the test series completed on the specified BF3 connectors confirms the original qualification tests on the same type connectors as documented in Wyle Laboratories Report No. 43854-2, dated March 28, 1978.




Figure 3. Specified BF3-Connector Accident Test Profile and Data From November 1 and 2, 1979 Test




Figure 4. Posttest Disassembly of 250-Vdc Connectors

POOR ORIGINAL

POOR ORIGINAL




Figure 5. Posttests Disassembly of 480-Vac Connectors

5.0 Test Documentation

The preceding sections summarized the background, test items, test profiles, and general test results. In the sections which follow, the specific test plans, procedures and data sheets are provided. The arrangement of the information is provided to allow almost direct one-to-one comparison with the Wyle Laboratories Report No. 43854-2, dated March 28, 1978.

SECTION A
CONNECTOR ASSEMBLY TEST PLAN
FOR
BROWNS FERRY, UNIT 3, CONNECTORS

CONNECTOR ASSEMBLY TEST PLAN
for
BROWNS FERRY, UNIT 3, CONNECTORS

to be coordinated for the
U. S. Nuclear Regulatory Commission
Research Support Branch, RSR

by
Sandia Laboratories, Albuquerque

Submitted: 8/11/78
Second Draft: 2/16/79
Third Draft: 5/1/79
Fourth Draft: 8/30/79

8/11/78
2/16/79
5/1/79
8/30/79

Program Objective

Following the Union of Concerned Scientist's petition of November 4, 1977, the NRC Commissioners directed the NRC staff to:

"Arrange for a repeat of the tests to obtain data for the verification of current methodology for environmental qualification of electrical components. These tests should be performed with a representative sample of commercially available electrical connectors qualified in accordance with IEEE-323 (1974) and in use in nuclear power reactor safety systems. When available, the test results are to be promptly provided to the Commission."

The staff have interpreted this action to be aimed at providing information on the methodology of qualification testing using electrical connectors which meet the provisions of IEEE-323. Since no connectors have been actually qualified to IEEE-323-1974 (a relatively new standard), the staff responded by directing that electrical connectors previously qualified by licensees for use in operating plants be tested in accordance with the provisions of IEEE-323-1971.

To the extent practicable, connector assemblies will be subjected to the actual aging, radiation, and LOCA-simulation tests for which the connector assemblies have been qualified. In a letter dated May 22, 1978, D. G. McDonald (SEP/DOR) to R. Feit (RA/RSR), DOR and IE recommended that the following plants/connectors be considered for testing:

- BWR (1) Peach Bottom - Pyle National Connectors; or
- (2) Browns Ferry - Bendix Connectors
- PWR (1) Palisades - Viking Spec Connectors; or
- (2) Oconee - Viking Spec Connectors

However, other plants or connectors would also be appropriate due to "... availability of the connectors to be tested, extensive procurement time, or other constraints."

Since that date, IE staff have evaluated some of the various utilities' connector hardware and qualification documents and have directed that Sandia proceed with the first test in this series using Browns Ferry-Bendix connectors. This test plan has the objective that the test is to duplicate, as closely as practicable, the actual Browns Ferry Connector tests; it is understood that the actual tests were intended to conform to the requirements of IEEE-323-71, with the addition of a (Browns Ferry specified) thermal aging pre-conditioning requirement.

8/11/78
2/16/79
5/1/79
8/30/79

Test Components

This test plan applies to the Browns Ferry Unit 3 (BF3) connector assemblies; the applicable background documents for this test plan are:

- (1) Tennessee Valley Authority, Purchase Requisition 150639, dated 4/18/78.
- (2) "Assembling Browns Ferry Nuclear Plant Bendix Connectors," dated 6/22/78.
- (3) "Test Procedure for Browns Ferry Bendix Connectors, Revision," undated.

The primary document, which this test plan intends to duplicate is:

- (4) "Qualification Test for Electrical Connectors Used at Browns Ferry Nuclear Power Plant Unit 3," Report No. 43854-2, Wyle Laboratories, March 28, 1978.

Test Items Descriptions

Three each of two different types of electrical connectors are to be tested. Both types are manufactured by Bendix and used inside containment at Browns Ferry, Unit 3.

<u>Qty</u>	<u>Manufacturer</u>	<u>Identification Numbers</u>	<u>Operating Voltage</u>	<u>Maximum Operating Current</u>
3	Bendix	Plug: 10-214628-51S	250VDC	1.0 Amp
3	Bendix	Receptacle: 10-214028-51P		
3	Bendix	Plug: 10-214636-78S	480VAC	17.5 Amp
3	Bendix	Receptacle: 10-214036-78P		

These Bendix connectors will be purchased by Sandia through a Bendix-authorized distributor. Electric cable will be furnished by TVA from spare cable of the same type used at BF3. The Bendix 250-VDC connector assemblies will consist of wire size No. 12 CPJ cable on the plug end and wire size No. 12 Vulkene cable on the receptacle end of the connectors. The Bendix 480-VAC connector assemblies will consist of wire size No. 10 CPJ cable on the

8/11/78
2/16/79
5/1/79
8/30/79

plug end and wire size No. 10 Vulkene cable on the receptacle end of the connectors. CPJ and Vulkene cables consist of cross-linked polyethylene with the CPJ cable having a PVC insulating jacket.

NRC/IE staff will certify that these connector components and cables are acceptably equivalent to those in place at BF3 before construction of the connector assemblies.

Assembly of Test Items

Construction of the connector assemblies will be conducted by BF3 staff using an assembly and potting procedure developed by BF3 (used in field assembling connectors) and approved/certified by IE staff. The assembly document, item 2 above, is also applicable. All connectors will be potted to appropriate specifications prior to any testing. The actual assembly will be observed by IE staff; after completion of the assemblies, IE will certify that they are acceptably equivalent to the in-place connectors at BF3 before simulation tests are conducted.

The Bendix 250-VDC connectors (plug 10-214628-51S and receptacle 10-214028-51P) are equipped with 12 pins. Its test configurations will be such that all pins will be utilized during testing. The Bendix 480-VAC connectors (plug 10-214636-78S and receptacle 10-214036-78P) are equipped with 14 pins, 12 of which will be utilized by being wired into a single-phase circuit. In each case, the 12 pins will be wired to form a series parallel circuit which will give a voltage difference between pins within the connector as well as passing current to simulate a load.

Non-Destructive Examination (NDE) Tests

Prior to performing accelerated aging on the test items, certain non-destructive examination tests will be made at Sandia Laboratories. These will include:

- (1) Continuity checks to assure circuit integrity.
- (2) 500-VDC insulation resistance measurements between circuit loops and between each circuit loop and the connector case.
- (3) X-radiographs and neutron-radiographs of the connector bodies as deemed necessary or desirable.

Sandia staff will examine all NDE data and make recommendations to IE staff on the fitness of the connector assemblies for test. As appropriate, IE will certify that they are acceptable and can undergo the planned test series.

8/11/78
2/16/79
5/1/79
8/30/79

Housing for Connector Assemblies

To provide structural support for the assemblies, in the qualification tests (report 4 above) a metal box was used to hold three or four assemblies. This box was about 8-inches square, about 20-inches long, open only on one end (8-inch square end). The connectors mating plane was located about 8 inches from the open end.

In these tests, a similar support will be constructed to house the assemblies; however, it will be slightly foreshortened (to about 18 inches) to fit within the test chamber.

Test Procedures

To the extent practicable, the test series previously conducted on Browns Ferry, Unit 3, connector assemblies will be repeated in these tests; the previous test results are reported in Wyle Laboratories Report 43854-2. This test series will be performed in the following sequence:

1. Baseline Functional Tests
2. Nuclear Radiation
3. Post-Radiation Functional Tests
4. Temperature Aging Test
5. Post-Temperature Aging Functional Tests
6. Accident Test
7. Post-Accident Functional Tests
8. Dimensional Test
9. Post-Test Inspection

Test equipment, from sensor to final readout device, will be selected to provide the accuracies specified below:

- | | |
|-----------------------------|---|
| - Aging Chamber Temperature | $\pm 6^{\circ}\text{F}$ (stratification $\pm 7^{\circ}\text{F}$) |
| - LOCA Chamber Temperature | $\pm 5^{\circ}\text{F}$ |
| - Chamber Pressure | ± 5 psig |
| - Voltage | $\pm 3\%$ |
| - Current | $\pm 3\%$ |

Test equipment used for these tests and date of its most recent calibration will be shown on Instrumentation Equipment Sheets attached to a final test report to be issued.

A full test report will be issued which completely describes the test series, which indicates deviations from the prescribed test program, and which includes equipment documentation and data sheets.

8/11/78
2/16/79
5/1/79
8/30/79

Baseline Functional Tests

The insulation resistance of each test item shall be determined; the value of resistance will be determined as outlined below.

Each test item will be powered with its operating voltage and loaded to produce the maximum operating current in its circuit. The resistance value of the load required to produce the maximum operating current at operating voltage will be measured and recorded for each test item. The values will determine the loading criteria for each test item for the remainder of the program. (Reference Figures 1 & 2.)

Each test item is to be subjected to an insulation resistance test. The insulation resistance is measured without power using a 500VDC megohmmeter. Value of resistance is to be determined:

- between the circuit on one side of the load and connector case,
- between the circuit on the other side of the load and connector case,
- between each side of circuit for each item.

Each test item is to be powered with its operating voltage and loaded to produce the maximum operating current in its circuit. The resistance value of the load required to produce the maximum operating current at operating voltage will be measured and recorded. These resistance values will be used throughout the remainder of the test program.

Nuclear Radiation

All connector assemblies will be exposed to a specified, uniform, radiation dose of 6.9×10^7 rads(air) at an average dose rate of about $.77 \times 10^6$ rads/hour, for approximately 90 hours, using a Cobalt-60 simulator; total dose and dose rate will be attained within 10% accuracy. The specimens may be rotated and/or repositioned periodically to achieve a more uniform total dose.

During the irradiation of the connector assemblies, the specimens temperatures will be periodically monitored and recorded.

8/11/78
2/16/79
5/1/79
8/30/79

Post-Radiation Functional Test

After the electrical connectors have been irradiated, each item will be subjected to insulation resistance, voltage, and load tests as described above. The test items will also be subjected to a dimensional test as specified in a later section of this test procedure. The insulation resistance will be measured using a 500VDC megohmmeter. Values of resistance shall be recorded. Each test item shall carry its required load at no more than a 10 percent reduction in operating voltage.

Temperature Aging Test

All of the electrical connectors will be subjected to a simulated aging test. The aging time and conditions are shown below. The humidity during aging will be uncontrolled.

<u>Aging Temperature</u>	<u>Aging Time</u>	<u>Aging Atmosphere</u>
217 \pm 6°F	60 Hours \pm 0.1 Hour ¹	Air
217 \pm 6°F	180 Hours \pm 0.1 Hour ²	Nitrogen

¹60 hours in air at 217°F is intended to simulate 6 months in air at 130°F.

²180 hours is intended to simulate 18 months in 130°F nitrogen with a maximum of 4 percent oxygen.

Each test item will be placed in a temperature chamber (i.e. oven) in a manner to avoid overheating from radiant effects from the chamber heating elements. The temperature chamber will be vented to the atmosphere to prevent buildup of outgasing products, particularly chlorine gas, from the test item inside the chamber. The air inside the chamber will be distributed uniformly throughout the chamber at an average velocity of about 250 feet per minute; pre-test flow measurements in an open chamber will be made and recorded. The test items will be aged in air at 217 \pm 6°F for a time period of 60 hours.

8/11/78
2/16/79
5/1/79
8/30/79

Following air aging, the test specimens will be removed from the oven. The oven will be purged with flowing nitrogen; the specimens will then be repositioned in the oven. The oven temperature will be stabilized at $217 \pm 6^{\circ}\text{F}$, with this temperature maintained for a total of 180 hours. During nitrogen aging, a continuous flow of nitrogen, about 1/4 cfm, will be introduced into the chamber at ambient pressure. This purge will prevent the outgassing products from accumulating inside the oven.

During the aging of the connector assemblies, the specimens and environment temperatures will be periodically monitored and recorded.

Post-Temperature Aging Functional Tests

After the electrical connectors have been temperature-aged, each item will be subjected to insulation resistance, voltage, and load tests. The test items will also be subjected to a dimensional test, as specified in a later section of this report. The insulation resistance will be measured using a 500 VDC megohmmeter and a volt-ohmmeter. Values of resistance shall be recorded; the megohmmeter is for supplemental information only. Each test item shall carry its required load at no more than a 10 percent reduction in operating voltage.

Accident Test

The electrical connector test assemblies will be subjected to an accident test profile enveloping that shown in Figure 3. The 250-VDC connector assemblies will be energized throughout the entire test. The 480-VAC connector assemblies will be energized only during the first 5 minutes, between minutes 15 and 18, and between minutes 57 and 60.

The connector assemblies will be installed in the test chamber. (To make electrical connection through the test chamber seals, Anaconda 3/c #12 nuclear grade cable may be butt spliced to the connector assembly and the splices covered with Raychem nuclear grade (WCSF series) heat shrink tubing.) Circuit continuity and circuit resistance tests will then be performed with the assemblies installed in the test chamber. The assemblies will be instrumented to measure voltage and current; the test chamber will be instrumented with temperature and pressure sensors. Periodic measurements of all parameters will be made.

All test items will be subject to an accident profile approximating the specified time, temperature, pressure conditions displayed in Figure 4. Also shown in Figures 4A, B, and C is the NRC specified enveloping profile for temperature and its $\pm 6^{\circ}\text{C}$ error band. This, along with the actual pressure profile with its ± 5 psig error band, constitute the desired accident test signature. These profiles were developed from NRC staff letters:

8/11/78
2/16/79
5/1/79
8/30/79

- (1) June 22, 1979, Murley to Schroeder and Eisenhut,
"Commission-Requested Connector Tests"
- (2) August 1, 1979, Schroeder and Eisenhut to Murley,
"Commission-Requested Connector Tests"

The 250-VDC connector assemblies will be energized throughout the entire test. The 480-VAC connector assemblies will be energized only during the first five minutes, between minutes 15 and 18, and between minutes 57 and 60. (The energizing schedule is construed to imply that the connector assemblies are energized just prior to introduction of the steam environment.)

The major features of the originally specified profile are:

- ramp to chamber conditions of 325°F (163°C), 55 psig, in approximately 2 minutes.
- maintain stablized conditions for 5 minutes.
- at 7 minutes, reduce pressure to 30 psig while holding temperature at 325°F (163°C).
- between minutes 7 and 30 reduce temperature to 304°F (151°C), while holding pressure at 30 psig.
- between minutes 30 and 75, reduce temperature to 282°F (139°C) and pressure to 20 psig.
- at 75 minutes, reduce temperature to 230°F (110°C) while holding pressure at 20 psig.
- reduce pressure and temperature at an average rate of 3.5°F/hour for 24 hours or until a chamber condition of 150°F (65°C) is attained.

The actual adjustments of the pressure and temperature of the test chamber are to be accomplished by manually manipulating the superheater controls and pressure regulators in a systematic way.

During the environmental exposure of the connector assemblies the specimens and environment temperatures will be periodically monitored and recorded and the connectors will be powered with their operating voltage/current loads as described above. Failure to carry the required voltage/current loads will be considered as failure of the assembly.

Generalized sketches of the sensor placements, test specimen placements, and of the voltage/current loading circuits are shown in Figures 5 and 6.

Post-Accident Functional Tests

After the connectors have been subjected to the accident test, each item will be subjected to insulation resistance,

8/11/78
2/16/79
5/1/79
8/30/79

voltage, and load tests. The test items will also be subjected to a dimensional test, as specified in a later section of this report. The insulation resistance will be measured using a 500VDC megohmmeter and a volt-ohmmeter. Values of resistance shall be recorded; the megohmmeter is for supplemental information only. Each test item shall carry its required load at no more than a 10 percent reduction in operating voltage.

These post-accident functional tests are for information only and do not constitute any acceptance criteria.

Dimensional Test

The purpose of the dimensional test is to determine if any part of the neoprene on the two types of connectors become physically distorted during testing.

There are two parts to this test. The first part is the durometer test, which measures the hardness of the neoprene. The second part is the dimensional measurement of the connectors and cables. The dimensional test will be done four times:
(1) Acceptance Dimensional, (2) Post-Radiation Dimensional,
(3) Post-Aging Dimensional, and (4) Post-Accident Dimensional.

Durometer Test

It is imperative that the durometer tests be performed in the same place each time. Location of test points is identified in Figures 7 and 8.

Bendix 250-VDC Connector - measure each connector receptacle face at a point between pins H, J, K, and N; between pins K, L, M, and N; and between B, C, D, and L. See Figure 7 for orientation.

Bendix 480-VAC Connector - measure each connector receptacle face at a point between pins 9, 10, 11, and 14; between pins 11, 12, 13, and 14; and between pins 4, 5, 12, and 13. See Figure 8 for orientation.

Connector and Cable Measurements

Place a straightedge across the neoprene face of the receptacle and determine if the neoprene extends beyond the edge of the connector barrel.

Measure the depth of the neoprene from the face of the receptacle to the pin. For the 250-VDC connectors, use pins A, K, M, and E; for the 480-VAC connectors, use pins 1, 14, and 6.

Measure the outside diameter of a selected wire in each connector assembly with a micrometer. Three measurements will be taken on each wire. One measurement will be taken adjacent to the wire identifier; the other two will be taken one inch

8/11/78
2/16/79
5/1/79
8/30/79

apart toward the bare end of the wire. For the 250-VDC connectors, use wire "A"; for the 480-VAC connectors, use wire "14".

Post-Test Inspection

Disassemble and inspect each test item as detailed below. Record results of any degradation that may have occurred.

1. The insulation will be inspected for surface texture, discoloration, cracks, or splitting.
2. The connector shells, threads, and cable clamps will be inspected for general conditions.
3. The connector pins on the face side will be inspected for corrosion, oxidation, pitting, or burning.

Discussion

These test procedures attempt to duplicate the actual test, previously conducted, as reported in Wyle Laboratories Report 43854-2, "Qualification Test for Electrical Connectors used at Browns Ferry Nuclear Power Plant Unit 3." There are some differences reflected in these procedures.

* All connector assemblies will be potted to appropriate specifications before the accelerated aging tests are initiated; that is, only fully assembled connectors will be subjected to this test series. In the previous test, the potting was done after the radiation was complete.

* Under Test Items Description, wire sizes (#12 and #10) were inadvertently transposed in report 3. They have been corrected in this test plan.

* The section on Housing for Connector Assemblies has been added for completeness.

* In various places, the control on aging chamber temperature has been increased to reflect Sandia capability per Process Standard 9,958,000.

* Under (several) Functional Test sections, a 500 VDC megohmmeter is specified instead of a volt-ohmmeter.

* Under Nuclear Radiation, some clarification is added on "average" dose rate and sample repositioning. It is not certain how this may differ from the original test conditions.

* On the Temperature Aging Table and in the text, $+6^{\circ}\text{F}$ has been called out. The original specification was $\pm 2^{\circ}\text{F}$ for the temperature control.

8/11/78
2/16/79
5/1/79
8/30/79


* The method of nitrogen aging varies from that reported in Report 4, which describes this procedure as follows:

"Each of the test items was placed in a sealed chamber as shown in photographs in Appendix I of this section. A vacuum pump was attached to this chamber and evacuated to 100 micron (Abs.) pressure. The chamber was then back filled with dry nitrogen to 14.7 psia and valved off to trap the nitrogen inside the chamber.

"The nitrogen-filled container was then placed inside a temperature chamber which was increased to, and stabilized at, $217 \pm 2^{\circ}\text{F}$. This temperature was maintained for a total of 180 hours. During this time period the nitrogen inside the container was purged every 24 hours to prevent out-gassing of materials from accumulating inside the container."

* Anaconda 3/c nuclear-grade cable and Raychem nuclear-grade splices may be used to exit from the LOCA test chamber if existing cable on the connector is not long enough.


* In the accident test, the temperature and pressure changes will be accomplished using manual adjustments of pressure regulators, superheaters, flow regulators, and the like; "averaged" rate is a key word.



12 PIN BENDIX

FIGURE 1
WIRING DIAGRAM

1-14 J-27



14 PIN BENDIX

FIGURE 2
WIRING DIAGRAM

ASCC B CURVE LEGEND

Curve Code	Explanation
△	Containment response to a postulated LOCA as defined in GE Letter No. G-ER-6175 to GOMILU at TVA dated May 1976, and GE Letter No. G-ER-6170 to PR Patterson at TVA dated May 1976.
○	Containment response to a postulated PST steam hot as defined in Figure 4-22 of the Response to All Quaternary Fuel Melt System, contained in Volume 6 of the BNP EBAR.
○	Pin cluster environmental qualification curve derived to encompass the postulated LOCA and G-ER-6175 steam line break containment response curves. △ and ○ and to be used in pin cluster testing after 1/1/79.

NUMERICAL CODE LEGEND

Code Number	Response Code	Pressure (PSI)	Temperature (°F)	Explanation
1	△	50	245	N/R
2	○	55	325	N/R
3	○	74	322	N/R
4	○	30	325	start 15% pin cluster decrease for 24 minutes
5	○	30	304	start 15% pin cluster decrease for 45 minutes
6	○	20	282	N/R
7	○	20	250	start 15% pin cluster decrease for the remainder of test
8	○	10	227	N/R
9	○	5	224	N/R
10	○	2	219	N/R
11	○	0	216	N/R




FIGURE 3 - ACCIDENT ENVIRONMENTAL QUALIFICATION CURVE

REPORT 43854-2

FIGURE 4A

BROWNS FERRY UNIT 3
CONNECTORS




FIGURE 4B

BROWNS FERRY UNIT 3
CONNECTORS

WYLE
REPORT
43854-2
3/28/78

— SPECIFIED PROFILES
 [○ TEMPERATURE DATA
 [△ PRESSURE DATA
 --- "BEST" REPRESENTATION






FIGURE 4C

BROWNS FERRY UNIT 3
CONNECTORS






STEAM BAFFLE WILL PREVENT ANY DIRECT STEAM IMPINGEMENT,
 HANGER FOR CONNECTOR BOXES IS NOT SHOWN,
 THERMOCOUPLES (TC) MAY NOT BE ATTACHED TO CONNECTOR(S)
 CONNECTOR BOXES ARE OPEN DOWNWARD IF CABLE LENGTHS
 WILL ALLOW. OTHERWISE EXTRA CABLE/PIPES MAY BE NECESSARY.

NOTES:
 1.
 2.
 3.
 4.

GENERALIZED/
 APPROXIMATE
 LOCATIONS
 FOR
 TEST

FIGURE 5



12 PIN BENDIX
250 VDC

REPEATED FOR EACH CONNECTOR

FIGURE 6A




FIGURE 6 B




Figure 7 Bendix 250 VDC




Figure 8 Bendix 480 VAC

SECTION B
TEST PROCEDURES
BROWNS FERRY, UNIT 3, CONNECTORS,
ACCIDENT SIMULATION

10/26/79

Test Procedures
Browns Ferry, Unit 3, Connectors
Accident Simulation

Objective:

These procedures describe the functional processes to achieve the accident-simulation tests of Browns Ferry Unit 3 Bendix connectors in accordance with the (effective revision of) "Connector Assembly Test Plan for Browns Ferry, Unit 3, Connectors."

Apparatus:

The simulation apparatus consists of a steam autoclave and pressure generation system (principally the boiler, accumulator, test chamber, and pressure regulators/throttles), steam or temperature conditioning equipment (principally the external strip heaters, and an inline superheater), and the connector-assemblies electrical loading and diagnostic equipment.

Associated with the simulation apparatus are the various diagnostic equipment such as pressure gauges, thermocouples, data acquisition system (data logger), and the like.

Personnel and Function:

To accomplish the simulation test, up to five functional operations must be manned. The initial test phases require five individuals; later during the quasi steady-state test phases fewer people are required, but never less than two individuals.

The test coordinator directs all operations based on the real-time data compared with the desired test profiles.

The environments regulator performs all adjustments of pressure regulators, superheater, throttle valves, and the like as directed by the test coordinator.

The connector assemblies loader performs all electrical loading and diagnostics of the connector assemblies as directed by the test coordinator.

The data taker records the various data derived from the environments monitors and other data as necessary.

The generalist provides backup support as required or as directed by the test coordinator.

External Strip Heaters:

These have two functions and modes of operation. First, to achieve an elevated chamber temperature prior to the accident-simulation test, and second, to control the long-term temperature rampdown of approximately $-2^{\circ}\text{C}/\text{hour}$.

To achieve the elevated chamber temperature, the strip heaters are energized (in advance of the simulation test) for approximately 12 minutes, until the exterior skin thermocouple reaches about 70°C . The strip heaters are then deenergized and the test chamber is allowed to equilibrate for about 1 hour (or as necessary) until the interior selected thermocouple(s) reach $60-80^{\circ}\text{C}$.

Second, to control the temperature rampdown (after the steam phase), the strip heaters are periodically

energized (10-60 seconds) as required to follow the desired temperature profile. (Empirically, 10 seconds results in approximately a 1°C temperature rise.)

Boiler/Accumulator:

The accumulators are brought to approximately 150 psig in advance of the accident test in accordance with established safe operation procedures (SOP) and the valving is similarly lined-up preparatory to steam delivery to the test chamber according to the SOP.

Electrical Loading of the Connector Assemblies:

In accordance with the test plan, the 250-VDC connector assemblies will be energized throughout the entire accident test and the 480-VAC connector assemblies will be energized only during the first 5 minutes, between minutes 15 and 18, and between minutes 57 and 60.

For at least 5 minutes prior to the accident test initiation, all electrical loads will be applied to the connector assemblies to provide baseline data. The electrical loading during the test is according to the schedule described above.

In-Line Superheater:

The 20 kilowatt in-line superheater provides initial surge and quasi-steady-state superheat to the incoming steam.

Prior to test start, the superheater is energized

and its controller set at 400+°C (with a continuous flow of steam through it). The superheater is allowed to reach the desired temperature and to equilibrate as necessary.

During the test, the controller/superheater is manually adjusted as directed by the test coordinator to follow the desired temperature profile.

Accident Test Sequence:

The test coordinator will use the attached (appendix) test sequence sheets to achieve the test profile. These provide desired time/temperature/pressure/heaters/loading signatures. Based on these sequence sheets, he will direct the personnel to make necessary adjustments in the control apparatus. They also serve as a checklist to sequence operations prior to the start of the accident test.

Data Retrieval and Records

Chamber environment and connector-assemblies loading data will be periodically recorded on data logger printouts, strip charts, and/or data sheets as appropriate. During the early test phase, data will be recorded frequently (e.g., every 20-60 seconds). Later in the test the recording frequency will be adjusted to reflect the quasi-steady-state test aspects; the appropriate data will be recorded at least hourly.

Appendix -- Pre-Accident Test Checklist

- _____ 1. Desired elevated chamber temperature has been accomplished.
Date/Time _____
- _____ 2. Boiler/accumulators at working pressures and valving lineup completed.
Date/Time _____
- _____ 3. In-line superheater is at desired temperature with steam flow.
Date/Time _____
- _____ 4. Electrical loading of the connector assemblies is completed and baseline data taken.
Date/Time _____
- _____ 5. All support staff in place to accomplish test.
Date/Time _____
- _____ 6. All prepared to initialize data loggers and data time intervals.
Date/Time _____

Note: This form to be checked, initialed, and dated as specified.

10/26/79

Appendix -- Time from 23 Hours, 57 Minutes to 2 Minutes

<u>Data Logger</u> <u>Hours-Min-Sec</u>	<u>Desired</u> <u>Pressure</u> <u>(Psig)</u>	<u>Desired</u> <u>Temperature</u> <u>(°C)</u>	<u>Electrical</u> <u>Loads</u> <u>ON/OFF</u>	<u>Remarks</u>
Initialize, start, data loggers to 23-57-0				
23-57-0	0	60-80	All On	
23-58	0	60-80	All On	
23-59	0	60-80	All On	
0-0-0	0	60-80	All On	Valve alignment
0-10	-----	75	All On	1. Chamber bypass open
0-20	Ramp	83	All On	2. Chamber inlet open
0-30	to	92	All On	3. Superheater bypass
0-40	60	100	All On	closed
0-50	60	109	All On	4. Exit throttle open
1-0	60	117	All On	1/4 turn
1-10	60	125	All On	5. Open inline 1/4 turn
1-20	60	133	All On	regulator valve
1-30	60	142	All On	(Regulator preset;
1-40	60	150	All On	65 psig against
1-50	60	159	All On	deadhead)
2-0	60	167	All On	6. Bring up on regulator
				bypass valve

10/26/79

Appendix -- Time from 2 Minutes to 7 Minutes

<u>Data Logger</u> <u>Min-Sec</u>	<u>Desired</u> <u>Pressure</u> <u>(Psig)</u>	<u>Desired</u> <u>Temperature</u> <u>°C</u>	<u>Electrical</u> <u>Loads</u> <u>On/Off</u>
2-0	60	167	All On
3-0	60	167	All On
4-0	59	167	All On
5-0	59	167	480V Off
6-0	58	167	250V On
7-0	58	167	Minute-5

Appendix -- Time from 7 Minutes to 1 Hour

<u>Data Logger</u> <u>Min</u>	<u>Desired</u> <u>Pressure</u> <u>(Psig)</u>	<u>Desired</u> <u>Temperature</u> <u>(°C)</u>	<u>Electrical</u> <u>Loads</u> <u>On/Off</u>
7	58	167	
8	55	167	
9	52	166	
10	49	166	
11	47	166	
12	43.5	165	
13	40	165	
14	37.5	164	
15	35	164	480V on
16	32.5	164	for 3 minutes
17	30	164	15-18
18	29	163	
19	28	163	
20	27	163	
21	26.5	162	
22	26	162	
23	25.5	161	
24	25	161	
25	25	161	
26	24.5	160	
28	24	159	
30	24	159	(Remarks: Change print interval to 1 minute; change tape.)
32	23.5	158	
34	23.5	157	
36	23	157	
38	22.5	156	
40	22	156	
42	21.5	155	
44	21	154	
46	20	154	
48	19	153	
50	17.5	152	
52	16	151	
54	15	151	
56	14	150	
57	14	150	480V on
58	14	149	for 3 minutes
59	14	149	57-60
60	14	148	

NOTE: 1. 250V loads ON during entire test.
 2. 480V OFF after Minute 60 for accident-test duration.

10/26/79

Appendix -- Time from 1 Hour to 3 Hours

<u>Data Logger Hours-Min</u>	<u>Desired Pressure (Psig)</u>	<u>Desired Temperature (°C)</u>	<u>Remarks</u>
1-0	14	148	(117+ Saturated)
-5	14	147	
-10	15.5	145	
-15	17	143	
-20	17.5	139	(121+ Saturated)
-25	17	136	
-30	16	132	
-35	15	128	Change print interval to 5 minutes
-40	14	124	
-45	13	121	
-50	12	117	
-55	11	114	
2-0	10	110	(112+ Saturated)
-5	9.5	110	
-10	9.5	110	
-15	9	110	
-20	8.5	109	
-25	8	109	
-30	8	109	
-35	8	109	
-40	8	109	
-45	7.5	108	(109+ Saturated)
-50	7.5	108	
-55	7.5	108	
3-0	7	108	

Note: 1. 250V Loads ON during accident test.
2. 480V Loads OFF for accident-test duration.

10/26/79

Appendix -- Time from 3 Hours to 24 Hours

<u>Data Logger Hours-Min</u>	<u>Desired Pressure (Psig)</u>	<u>Desired Temperature (°C)</u>	<u>Remarks</u>
3-0	7	108	Start wall temperature to 108°C Open top center port to allow heat flow
-15	6.5	108	
-30	5	107	
-45	3.5	107	
4-0	1.5	106	
-15	0	106	
-30	0	105	
-45	0	105	
5-0	0	104	
6	0	102	
7	0	100	
8	0	98	
9	0	96	
10	0	94	
11	0	92	
12	0	90	
13	0	88	
14	0	86	
15	0	84	
16	0	82	
17	0	80	
18	0	78	
19	0	76	
20	0	74	
21	0	72	
22	0	70	
23	0	68	
24	0	66	
ALL LOADS OFF			


Note: 1. 250V loads ON to end of test.
2. 480V loads OFF

SECTION I
ACCEPTANCE TESTS

Acceptance/NDE Tests Procedure


Each test item will be inspected and tested as described below, to assess the physical/electrical integrity of the connectors assemblies. All results and observations will be recorded on data sheets and supplemented with other pertinent documentation:

- check pin-to-pin wiring against the wiring diagrams, Figures 1 and 2, using a Simpson meter, or equivalent.
- check circuit continuity against wiring diagrams using a Simpson meter, or equivalent.
- perform X-radiographs and/or neutron-radiographs of the connector bodies as deemed necessary or desirable.



12 PIN BENDIX

FIGURE 1
WIRING DIAGRAM



14 PIN BENDIX

FIGURE 2
WIRING DIAGRAM

DATA SHEET

Project B-3 CONNECTORS

Specimen — ALL

Part No _____

Ident. _____

Start Date 4/3/77

TEST ITEM DESCRIPTION

<u>ITEMS</u>	<u>TYPE</u>	<u>BENDIX ID NUMBERS</u>
1, 2, 3	250VDC	{ 1C-214625-512 ¹ 1C-214625-512 ²
7, 8, 9	480VAC	{ 1C-214636-752 ¹ 1C-214636-752 ²

Remarks _____

Tested by _____ Date _____

Witness _____ Date _____

Sheet No. 1 of 1

Approved Alexander 4/3/77

DATA SHEET

Project HTS CONNECTORS

Specimen ALL

Part No _____

Ident. _____

Start Date 4/3/79

ACCEPTANCE TESTS - CONTINUITY

ITEM #	PIN-to-PIN	CIRCUIT	
	FIGURES 1/2	CONTINUITY	
1	✓	A-K ✓	N-J ✓
2	✓	A-K ✓	N-J ✓
3	✓	A-K ✓	N-J ✓
7	✓	12-9 ✓	10-14 ✓
8	✓	12-9 ✓	10-14 ✓
9	✓	12-9 ✓	10-14 ✓

Remarks ALL ITEMS AS

DEPicted IN FIGURES 1/2.

ALL OK.

Tested by [Signature] Date 4/3/79

Witness [Signature] Date 4/3/79

Sheet No. 1 of 1

Approved _____

INSTRUMENTATION EQUIPMENT SHEET

Date April 3, 1979

Test Area Box 5403

Technician D. DeGano

Project BF3 Counters Type Test Acceptance - Continuity

No.	Instrument	Manufacturer	Model No.	Serial No.	Ident No.	Range	Accuracy	Calibration	
								On	Due
1	Digital Multimeter	FUKE	500A	3305	21343	C-10mV	$\pm 0.1\% + 200.00$	3/1/78	9/12/79

CERTIFICATION SHEET ATTACHED

Instrument Test Engineer _____ Checked & Received by _____



Sandia Laboratories

Albuquerque, New Mexico 87115

Standards Laboratory Certificate

DIGITAL MULTIMETER
JOHN FLUKE
MODEL NO. 8100A
SERIAL NO. 517
PROPERTY NO. 12043

E3

SHIPPED BY 4442

CERTIFIED 2 MAR 1979
EXPIRES 2 SEP 1979

THIS MULTIMETER WAS TESTED AT SELECTED CHECKPOINTS ON ALL RANGES
AND WAS FOUND TO BE WITHIN THE FOLLOWING MANUFACTURERS ACCURACY
CLAIMS,

DC $\pm (0.05\% \text{ OF READING} + 1 \text{ DIGIT})$ 0.1 VOLT TO
1000 VOLTS

RESISTANCE $\pm (0.1\% \text{ OF READING} + 2 \text{ DIGITS})$ 10 OHMS TO 10
MEG OHMS

AC $\pm (0.2\% \text{ OF READING} + 5 \text{ DIGITS})$ 50 HZ TO 10 KHZ
 $\pm (0.5\% \text{ OF READING} + 10 \text{ DIGITS})$ FOR 20 KHZ

METROLOGIST, R. T. SALAZAR - 2553

G. F. McFall
CERTIFIED BY G. F. MCFALL - 2553

Conditions of Certification: Neither Sandia Laboratories nor the Government assume any responsibility with respect to the use of this document, the information contained therein, or the physical device or instrument certified, by any person other than the contractor to whom originally issued. Any such use will be at the sole risk and responsibility of such other user.

If this document is issued to a Sandia Laboratories supplier, neither Sandia Laboratories nor the Government assumes any responsibility for the use of this document, the information contained therein, or the physical device or instrument certified, at any time beyond the resubmittal date or any order or contract other than the order or contract, including changes, under which the certification is given.

In no case will Sandia Laboratories or the Government assume responsibility for consequential damages. SA 5710-DAB(9-72)

DATA SHEET

Project BF3 CONNECTORS

Specimen ALL

Part No. _____

Ident. _____

Start Date 4/2/79

NEUTRON RADIOGRAPHS - ACCEPTANCE

NEUTRON RADIOGRAPHS WERE MADE OF ITEMS 1, 2, 3
AND 7, 8, 9 USING A CALIFORNIUM NEUTRON SOURCE
LOCATED IN JA-5 OF SANDIA LABORATORIES. FILM
WAS AA READIPACK.

ALL APPEARED TO BE WITHOUT SIGNIFICANT
VOIDS OR CRACKS IN THE FITTING.


Remarks _____

Tested by [Signature] Date 4/2/79

Witness [Signature] Date 4/2/79

Sheet No. 1 of 1

Approved _____



PHOTOGRAPH D79-744

NEUTRON RADIOGRAPHS OF TEST
ITEMS 1, 2, 3; 250-VDC CONNECTOR
ASSEMBLIES

POOR ORIGINAL



PHOTOGRAPH D79-745

NEUTRON RADIOGRAPHS OF TEST
ITEMS 7, 8, 9; 480-VAC CONNECTOR
ASSEMBLIES

POOR ORIGINAL

I-11,12

SECTION II
BASELINE FUNCTIONAL TESTS

Baseline Functional Tests Procedure

The insulation resistance of each test item shall be determined; the value of resistance will be determined as outlined below.

Each test item will be powered with its operating voltage and loaded to produce the maximum operating current in its circuit. The resistance value of the load required to produce the maximum operating current at operating voltage will be measured and recorded for each test item. The values will determine the loading criteria for each test item for the remainder of the program. (Reference Figures 1 and 2).

Each test item is to be subjected to an insulation resistance test. The insulation resistance will be measured without power using a 500VDC megohmmeter. Value of resistance is to be determined

- between the circuit on one side of the load and connector case,
- between the circuit on the other side of the load and connector case,
- between each side of circuit for each item.

DATA SHEET

Project BFS CONNECTORS

Specimen ALL

Part No _____

Ident. WIRELINE FUNCTIONAL - IR Start Date 4/3/79

INSULATION RESISTANCE

PINS (250 VDC CONNECTORS)

ITEM	K to CASE	N TO CASE	K TO N
1	$2.5 \times 10^9 \Omega$	$2.5 \times 10^9 \Omega$	$2.5 \times 10^9 \Omega$
2	$> 2.5 \times 10^9 \Omega$	$> 2.5 \times 10^9 \Omega$	$2.5 \times 10^9 \Omega$
3	$2.5 \times 10^9 \Omega$	$> 2.5 \times 10^9 \Omega$	$2.5 \times 10^9 \Omega$

PINS (48 VAC CONNECTORS)

ITEM	9 TO CASE	10 TO CASE	9 TO 10
7	$1.5 \times 10^9 \Omega$	$2.5 \times 10^9 \Omega$	$2.5 \times 10^9 \Omega$
8	$2.5 \times 10^9 \Omega$	$2.5 \times 10^9 \Omega$	$2.5 \times 10^9 \Omega$
9	$2.5 \times 10^9 \Omega$	$2.5 \times 10^9 \Omega$	$2.5 \times 10^9 \Omega$

Remarks _____

Tested by [Signature] Date 4-3-79

Witness [Signature] Date 4/3/79

Sheet No. 1 of 3

Approved _____

DATA SHEET

Project PT-5 CONNECTORS

Specimen 250VDC

Part No 1, 2, 3

Ident. PAULINE FUNCTIONAL - LEAD/VOLTAGE

Start Date 4/3/79

ITEM	EXIT VOLTAGE	LEAD RESISTANCE	LEAD VOLTAGE	INLET CURRENT
1	250VDC	244.2	251VDC	1.000 Amps
2	250VDC	246.2	251VDC	1.002 Amps
3	250VDC	244.2	251VDC	0.995 Amps

Remarks _____

Tested by [Signature] Date 4-3-79

Witness [Signature] Date 4/21/79

Sheet No. 2 of 3

Approved _____

DATA SHEET

Project NT3 (Connections)

Specimen 450 VAC

Part No 7, 8, 9

Ident. Baseline Functional - Lead/Contact

Start Date 4/4/19

ITEM	INPUT VOLTAGE	LEAD (PS) RESISTANCE	LEAD VOLTAGE	INPUT CURRENT
7	455 VAC	~ 31.2 Ω	454 VAC	17.5 Amps
8	470 VAC	~ 27.2 Ω	455 VAC	17.37 Amps
9	470 VAC	~ 27.2 Ω	455 VAC	17.4 Amps

Remarks _____

Tested by [Signature] Date 4-4-19

Witness [Signature] Date 4/4/19

Sheet No. 3 of 3

Approved _____

INSTRUMENTATION EQUIPMENT SHEET

Date April 3, 1977

Test Area 1000 5000

Technician P. DeLan

Project ITS CONNECTIONS

Type Test WELLING - FUNCTIONAL

No.	Instrument	Manufacturer	Model	Serial	Ident	Range	Accuracy	Calibration	
			No.	No.	No.			On	Due
1	MICROMETER	AMERICAN HL TEST SYSTEMS	PM 250	5-17-112	RICH	0.05 - 250 MM	$\pm 4 \mu F$	3/4/77	4/1/77
2	DIGITAL MULTIMETER	FLUKE	800A	3318	21243	C-100V C-1-100VDC	$\pm 0.1\% + 0.001$ $\pm 0.02\% + 10000$	3/4/77	4/1/77
3	POWER ANALYZER	MAATEL	4010	5067	250755	C-50A C-100V	$\pm 0.5\% + 10000$	3/4/77	4/1/77
4	POWER SUPPLY	HEWLETT PACKARD	595A		217619	C-320VDC C-1.5A	NOT ATTACHED		

CERTIFICATION SHEET ATTACHED

Instrument Test Engineer _____

Checked & Received by _____



Sandia Laboratories

Albuquerque, New Mexico 87185


Standards Laboratory Certificate

MEGOhmmETER
American HV Test Systems
Model No. PM2500
Serial No. S-77-112
Property No. R10220

Submitted by: Organization 4442
Certified: March 19, 1979
Expires: September 19, 1979

The meters on this instrument were tested and found to be within $\pm 2.0\%$ of full scale on all ranges. Thus, the overall results when used as a megohm meter can be expected to be within $\pm 4.0\%$ of F.S. ranges.

Metrologist: G. F. McFall, 2553


Certified by: G. F. McFall, 2553

GFM:2553:bh

Conditions of Certification. Neither Sandia Laboratories nor the Government assumes any responsibility with respect to the use of this document, the information contained therein, or the physical device or instrument certified, by any person other than the contractor to whom originally issued. Any such use will be at the sole risk and responsibility of such other user.

If this document is issued to a Sandia Laboratories supplier, neither Sandia Laboratories nor the Government assumes any responsibility for the use of this document, the information contained therein, or the physical device or instrument certified, at any time beyond the resubmission date or any order or contract other than the order or contract, including changes, under which the certification is given.

In no case will Sandia Laboratories or the Government assume responsibility for consequential damages. SA 5710-DA(8-78)





Sandia Laboratories

Albuquerque, New Mexico 87115

Standards Laboratory Certificate

ANALYZER POWER
Magtrol
Model No. 4610
Serial No. 8C67
Property No. 250985

Submitted by: Organization 4442

Certified: March 1, 1979

Expires: September 1, 1979

This instrument was tested and adjusted to meet the following accuracy specification:

$\pm 0.5\% + 1$ digit on all ranges and functions

Metrologist: W. W. Rowe, 2553

Certified by: G. F. McFall, 2553

WWR:2553:bh

Conditions of Certification. Neither Sandia Laboratories nor the Government assumes any responsibility with respect to the use of this document, the information contained therein, or the physical device or instrument certified by any person other than the contractor to whom originally issued. Any such use will be at the sole risk and responsibility of such other user.

If this document is issued to a Sandia Laboratories supplier, neither Sandia Laboratories nor the Government assumes any responsibility for the use of this document, the information contained therein, or the physical device not certified, at any time beyond the resubmittal date or any order or contract other than the order or contract, or ranges, under which the certification is given.

In no case will Sandia Laboratories or the Government assume responsibility for consequential damages. DA-19-721

SECTION III

BASELINE MECHANICAL/DIMENSIONAL TESTS

Baseline Mechanical/Dimensional Tests Procedures

Each test item will be subjected to durometer and connector and cable measurements tests to assess any physical distortion. The baseline tests provide initial data for comparison.

The durometer tests will be performed in the same place each time. Location of test points is identified in Figures 3 and 4.

Bendix 250-VDC Connector -- measure each connector receptacle face at a point between pins H, J, K, and N; between pins K, L, M, and N; and between B, C, D, and L. See Figures 3 for orientation.

Bendix 480-VAC Connector -- measure each connector receptacle face at a point between pins 9, 10, 11, and 14; between pins 11, 12, 13, and 14; and between pins 4, 5, 12, and 13. See Figure 4 for orientation.

Place a straightedge across the neoprene face of each receptacle and determine if the neoprene extends beyond the edge of the connector barrel. Measure the depth of the neoprene from the face of each receptacle to the pin. For the 250-VDC connectors, use pins A, K, M, and E; for the 480-VAC connectors, use pins 1, 14, and 6.

Measure the outside diameter of a selected wire in each connector assembly with a micrometer. Three measurements will be taken on each wire. One measurement will be taken adjacent to the wire identifier; the other two will be taken one inch apart toward the bare end of the wire. For the 250-VDC connectors, use wire "A"; for the 480-VAC connectors, use wire "14".




Figure 3 Bender 250 VDC




Figure 4 Bendix 480 VAC

DATA SHEET

Project B-3 CONNECTORS

Specimen 250 VDC

Part No 1

Ident. ACCEPTANCE DIMENSIONAL

Start Date 4/3/77

ALIGNING INSULATOR		DIAMETER		WIRE A	
<u>IN</u>	<u>DEPTH</u>	<u>LOCATION</u>	<u>VALUE</u>	<u>LOCATION</u>	<u>CD</u>
A	C.102"	I	77	1	C.133"
K	C.095"	II	80	2	C.134"
M	C.041"	III	71	3	C.133"
E	C.119"				

ALIGNING INSULATOR WAS ADJACENT THE END OF THE CONNECTOR PILE BARREL.

BARREL DIAMETER: 1.512"


Remarks _____

Tested by [Signature] Date 4/1/77

Witness [Signature] Date 4/1/77

Sheet No. 1 of 1

Approved _____



DATA SHEET

Project PTS CONNECTORS

Specimen ASC 200

Part No 2

Ident. ACCEPTANCE DIMENSIONAL

Start Date 4/3/74

ACCEPTANCE INSULATION		DIAMETER		WIRE A	
LINE	DEPTH	LOCATION	DATE	LOCATION	DATE
A	C. 114"	I	76	1	C. 155"
B	C. 108"	II	75	2	C. 183"
C	C. 111"	III	77	3	C. 182"
E	C. 104"				

ACCEPTANCE INSULATION WAS ABOVE THE END OF THE
CONNECTOR B.C. BARREL.

BARREL DIAMETER: 1.507 - 1.513"

Remarks _____

Tested by [Signature] Date 4/3/74

Witness [Signature] Date 4/3/74

Sheet No. 2 of 6

Approved _____

DATA SHEET

Project 1073 CONNECTORS

Specimen 250 VDC

Part No 3

Ident. APPROXIMATE DIMENSIONS

Start Date 4/3/71

APPROXIMATE DIMENSIONS		DIAMETER		WIRE A	
Pin	DEPTH	LOCATION	VALUE	LOCATION	C.D.
A	C. 0.15"	I	77	1	C. 156"
B	C. 0.102"	II	75	2	C. 154"
C	C. 0.099"	III	74	3	C. 155"
D	C. 0.121"				

APPROXIMATE INSULATOR WAS ABOVE THE END OF THE
CONNECTOR BELL JACKET

JACKET DIAMETER: 1.505 - 1.512"

Remarks _____

Tested by [Signature] Date 4/3/71

Witness Lloyd Bengert Date 4/3/71

Sheet No. 3 of 6

Approved _____

DATA SHEET

Project BFB CONNECTORS

Specimen 480 VAC

Part No 7

Ident. ACCEPTANCE DIMENSIONAL

Start Date 4/3/79

ACQUINE INSULATOR		DIAMETER		WIRE 14	
IN	DEPTH	LOCATION	VALUE	LOCATION	C.D.
1	0.113"	IV	77	1	0.116"
14	0.114"	V	77	2	0.116"
6	0.112"	VI	75	3	0.116"

ACQUINE INSULATOR WAS ABOVE THE END OF THE CONNECTOR PER BARREL.

BARREL DIAMETER: 1.165"

Remarks _____

Tested by [Signature] Date _____

Witness [Signature] Date 4/3/79

Sheet No. 4 of 6

Approved _____



DATA SHEET

Project BF3 CONNECTORS

Specimen 480 VAC

Part No 8

Ident. ACCEPTANCE DIMENSIONAL

Start Date 4/3/79

NEEDLE INSULATOR		DINOMETER		NOTE	
<u>IN</u>	<u>DEPTH</u>	<u>LOCATION</u>	<u>VALUE</u>	<u>LOCATION</u>	<u>VALUE</u>
1	C.111"	15	81	1	C.201"
14	C.105"	1	77	2	C.200"
6	C.126"	11	78	3	C.201"

NEEDLE INSULATOR WAS ABOVE THE END OF THE
CONNECTOR PUG BARREL

BARREL DIAMETER: 1.968"

Remarks _____

Tested by [Signature] Date _____

Witness [Signature] Date 4/3/79

Sheet No. 5 of 6

Approved _____

DATA SHEET

Project DT-3 CONCRETE

Specimen 450 VAC

Part No 9

Ident. APPEARANCE DIMENSIONAL

Start Date 4/3/17

APPEARANCE		DIMENSIONAL		WIRE 14	
SIZE	DEPTH	LOCATION	VALUE	LOCATION	C.D.
1	C.107"	II	71	1	C.203"
14	C.107"	I	74	2	C.211"
6	C.132"	II	82	3	C.212"

APPEARANCE INSULATOR WAS ABOVE THE END OF THE CONCRETE PILE BARREL

WIRE DIAMETER: 1.467"

Remarks _____

Tested by [Signature] Date 4/3/17

Witness [Signature] Date 4/3/17

Sheet No. 6 of 6

Approved _____

INSTRUMENTATION EQUIPMENT SHEET

Date 4/3/77

Test Area DEK. 5701

Technician D. H. GAN

Project DEK. (CONCRETE)

Type Test ADJUSTANCE DIAMETER

No.	Instrument	Manufacturer	Model	Serial	Ident	Range	Accuracy	Calibration	
			No.	No.	No.			On	Due
<u>1</u>	<u>SHORE TYPE A2</u>	<u>SHORE INSTRUMENT</u>	<u>TYPE A2</u>	<u>—</u>	<u>1641 3</u>	<u>C-100</u>	<u>0.01</u>	<u>ATL</u>	<u>ADJUSTANCE</u>
		<u>CONF. CO.</u>							
<u>2</u>	<u>CALIPERS</u>	<u>PRIMA / SHARP</u>	<u>579</u>	<u>—</u>	<u>—</u>	<u>C-6"</u>	<u>.001</u>	<u>ATL</u>	<u>ADJUSTANCE</u>

Instrument Test Engineer _____ Checked & Received by _____

SECTION IV
RADIATION TEST

Nuclear Radiation Test Procedure

Perform a pre-test mapping in the irradiation cell in the volume where the connector assemblies are expected to be located. Record the general radiation profile and from these select specific locations for placement of the assemblies. All radiation measurements will be done using calibrated passive dosimetry; record all pertinent information.

From this data select the positions where the dose rate is most uniform at the specified rate of 0.77 Megarads/hours. Perform a second pre-test mapping using the metal housing box to confirm the selection of position. (This step may be repeated as necessary.) Record all pertinent information.

With the connector assemblies installed in the metal housing box, position these with respect to the Cobalt-60 source at the final selected positions. The total irradiation period of 90 hours (69 Megarads total dose) will be conducted in four 22.5 hour periods. After each irradiation period the box will be rotated 90° keeping its centerline at the selected position (i.e., each of the four sides of the box will face the Cobalt-60 source during one irradiation period). The rotation is to assure a more uniform averaged dose rate and dose to the connector assemblies. Dosimetry may be used as desired during the actual irradiation process. Record all pertinent information.

Select specimen temperatures are to be monitored and recorded. Record results, thermocouples (TC) locations, and observations on data sheets and/or other pertinent documentation.

DATA SHEET


Project BF3 CONNECTORSSpecimen —Part No. —Ident. —Start Date 3/5/79PRE-TEST RADIATION MAPS - 1

BASED ON TLD-400 MAPS OF THE
NORTH GUT CELL OF THE PLATE, THE DATA
IS PLOTTED IN THE FIGURES FOR ROWS A, B, C, D
AND PLATE POSITIONS 3 - 11.

FROM THESE THE Q POSITION TO
ACHIEVE ~ 0.77 MR/hr WAS OBTAINED AS SHOWN
IN THE ATTACHMENT. BECAUSE OF SOURCE GEOMETRY,
THIS DOSE RATE OCCURS ON TWO LINES (INTERSECTING)
FROM ABOUT B3 THROUGH D9 AND D6 THROUGH ~ B11.
THE DOSE RATES IN THE CAN ARE ALSO SHOWN.

Remarks —Tested by Lloyd Kenyon Date 3/20/79Witness — Date —Sheet No. 1 of 1Approved —

Dose rate estimates with can on
chassis (.77 MR/hr) \pm .



$$\begin{array}{r} 1.3 \\ 1.0 \\ .6 \\ .5 \\ \hline 4 \quad 3.4 \quad 0.85 \text{ MR/hr} \end{array}$$

3/5/79
Fenger

$$\begin{array}{r} 1.15 \\ .7 \\ .55 \\ .85 \\ \hline 4 \quad 3.25 \quad 0.81 \text{ MR/hr} \end{array}$$

DATA SHEET

Project BT-3 CONNECTORS

Specimen


Part No

Ident.

Start Date 3/20/79

PRE-TEST RADIATION MAPS - Z₁

BASED ON PREVIOUS MAP, THE STAINLESS STEEL CANS WERE PLACED IN THE ϕ DETERMINED. TLD-400 DETECTORS WERE PLACED ON THE CANS (BOTTOM AND AT CONNECTOR MIDLINE).



Remarks

Tested by Lloyd R. Jones Date 3/20/79

Witness Date

Sheet No. 1 of 1

Approved

Measurements of the radiation field intensity are made using calcium fluoride thermoluminescent dosimeters (Harshaw TLD-400's). The dosimeters (luminescence) are read with a Harshaw 2000 reader. Calibration curves of TLD response (see attached), for each batch of TLD's, are made using a Cobalt-60 source which has an NBS-traceable certification. Doses are recorded as rads (material), i.e., rads (TLD-400); these can be related to any other material as desired.

DATA SHEET

Project HF-3 CONNECTORS

Specimen _____

Part No _____

Ident. PRE-TEST RADIATION MAPS - 3

Start Date 4/4/79

BASED ON MAP 2, THE STAINLESS STEEL CANS
WERE PLACED ON A NEW CL, 1-INCH (PERPENDICULAR
FROM THE CL FOR MAP 2) TOWARDS THE SOURCE, TWO CANS
WERE PLACED IN 5 LOCATIONS ON THE CONNECTOR RACK.

		CONNECTION AND	
POSITION	"SPECULATED"	EAST CAN	WEST CAN
1	1.3	1.03 M/K	.99
2	0.6	.533	.53
3	0.77	.15	.152
4	1.0	1.16	1.14
5	0.5	.54	.50

Remarks BASED ON MAP 3 AND

Tested by _____ Date _____

ATTACHED FIGURES

Witness Alfred D. Brown Date 4/5/79

RADIATION WILL BE DONE AT

Sheet No. 1 of 1

MAP 3 LOCATION

Approved _____

DATA SHEET


Project RF3 CONNECTIONS

Specimen ALL

Part No. _____

Ident. CONNECTIONS RELATIVE TO SOURCE

Start Date 4/5/19



EAST CAN

WEST CAN

450VAC CONNECTIONS

250VDC CONNECTIONS

↑ UP

X IS DIAMETER PLACEMENT

Remarks _____


Tested by _____ Date _____

Witness Lloyd Penney Date 4/5/19

Sheet No. 1 of 1

Approved _____

45 1328



DATA SHEET

Project SF3 CONNECTORS

Specimen 1, 2, 3, 7, 8, 9

Part No. _____

Ident. RADIATION, FIRST 22.5 HR PERIOD

Start Date 4/5/79

TC # POSITIONED

SIDE 1 CP

ON CONNECTOR #

ALUM (1.14) DENSITY

(1)1 1

WEST (1/4) EAST (1/4)

(1)2 2

1 (23%) 12.1 (24%) 11.5

(1)3 3

2 (75%) 25.1 (75%) 25.1

(1)4 AMBIENT - WEST CAN

3 (12.5%) 20.1 (12.5%) 20.1

(1)5 7

4 (07%) 16.4 (34%) 11.3

(1)6 8

5 (5%) 27.1 (5%) 27.1

(1)7 9

(1)8 AMBIENT - EAST CAN

START: 4/5/79 15:27

END: 4/6/79 13:57

Remarks _____

Tested by [Signature] Date 4-6-79

Witness [Signature] Date 4/6/79

Sheet No. 1 of 9

Approved _____

DATA SHEET

Project DE-5 COLLECTIONS

Specimen 1, 2, 3, 7, 8, 9

Part No _____

Ident. ADDITION, TEST 22.5 HR PERIOD, SIDE 4 OF Start Date 4/5/79

TEMPERATURES: TYPE K TC / DATALOGGER, °C

TC #	CONNECTION #	ICE TEST	4/5/79		4/6/79		
			16°C	24°C	27°C	32°C	35°C
1	1	25°C	27	31	27	32	35
2	2	25	27	31	27	32	34
3	3	25	28	30	27	31	32
4	ADDITION ICE CAN	25	28	28	27	27	30
5	7	25	27	24	30	32	34
6	5	25	27	28	28	30	31
7	7	25	27	28	28	30	31
8	ADDITION ICE CAN	25	27	27	27	28	30

ADDITION START: 4/6/79 CO 15:27 ; END: 4/6/79 13:51

Remarks _____

Tested by [Signature] Date 4/7/79

Witness [Signature] Date 4/9/79

Sheet No. 2 of 9

Approved _____

DATA SHEET

Project ITS (CONCRETE)

Specimen 1, 2, 3, 7, 8, 9

Part No. _____

Ident. NAVATION, SECTION 22.514 REFID

Start Date 4/6/79

TEST 4/6/79 14:21

SIDE 2 LF

END 4/7/79 13:51

ALPHA (1.4) DENSITY

#	WET G/A	UNIT (G/A)
1	(5.5%) 26.4	(7.5%) 26.1
2	(5%) 27.1	(5.0%) 27.4
3	(5.5%) 26.1	(11%) 22.5
4	(15%) 15.6	(2%) 12.3
5	(17%) 14.9	(15.5%) 15.2

Remarks _____

Tested by Ally Bogan Date 4/7/79

Witness A. H. C. C. Date 4/7/79

Sheet No. 3 of 9

Approved _____

DATA SHEET

Project RTS CONNECTIONS

Specimen 1, 2, 3, 7, 8, 9

Part No _____

Ident. RADIATION, ROUND 22.5 HR PERIOD, SIDE 2 LP Start Date 4/6/79

TEMPERATURES: TYPE K TC / DATA LOGGER, °C

4/6/79

4/7/79

TC #	LOCATION #	INITIAL	1524	2324	0724	0924	1224
1	1	33°C	31°C	30°C	29°C	29°C	31°C
2	2	33	32	31	30	30	33
3	3	32	32	31	30	30	32
4	AMBIENT WEST CAN	28	29	28	27	28	29
5	7	33	30	28	27	28	30
6	8	31	31	28	28	28	30
7	7	27	32	31	30	30	33
8	AMBIENT EAST CAN	32	25	25	24	26	25

RADIATION START: 4/6/79 14:21 4/7/79 12:51

Remarks _____

Tested by Angela Benner Date 4/7/79

Witness [Signature] Date 4/9/79

Sheet No. 4 of 9

Approved _____

DATA SHEET

Project HTS CANNOTERS

Specimen 1, 2, 3, 7, 8, 9

Part No _____

Ident. RADIATION, THICK 22.5 HC PERIOD, SIDE S VI Start Date 4/1/79

START: 4/1/79 13:14

SIDE S VI

END: 4/6/79 11:44

NYLON (1.12) DISMETHY

WEST CAN EAST CAN

- 1 (9.25%) 25.5Mr (8.75%) 26.4Mr
- 2 (23.75%) 11.9Mr (26.25%) 13.4Mr
- 3 (12.5%) 20.9Mr (13%) 20.3Mr
- 4 (10.75%) 23.2Mr (9.5%) 25.1Mr
- 5 (17%) 16.4Mr (30%) 9.05Mr

Remarks _____

Tested by [Signature] Date 4-8-79

Witness William A. Visher Date 4/8/79

Sheet No. 5 of 9

Approved _____

DATA SHEET

Project BF3 CONNECTORS

Specimen 1, 2, 3, 7, 5, 9

Part No. _____

Ident. RADIATION, THIRD 22.5 HR PERIOD, SIDE 3 LF Start Date 4/7/79

TEMPERATURES: TYPE K TC / INSTALLER, °C

TC #	CONNECTOR #	4/7/79		4/8/79		
		1324	2324	0524	0724	1124
1	1	29°C	21°C	28°C	28°C	31°C
2	2	30	29	28	28	31
3	3	30	30	29	28	31
4	AMBIENT HOT CAN	28	27	26	26	29
5	7	29	28	27	26	30
6	5	29	30	29	28	31
7	9	30	30	29	28	31
8	AMBIENT COLD CAN	27	24	23	23	27

RADIATION START: 4/7/79 13:14 END: 4/8/79 11:44

Remarks _____

Tested by [Signature] Date 4/9/79

Witness [Signature] Date 4/9/79

Sheet No. 6 of 9

Approved _____

DATA SHEET

Project 107 (CONCRETE)

Specimen 1, 2, 3, 75, 1

Part No. _____

Ident. ANALYSIS, FORTH 22.5 HR PERIOD

Start Date 4/5/77

FACTOR: 4/8/77 12:00

SIDE 4 CI

LAB: 4/9/77 10:37

ANAL (1, 12) DENSITY

#	WESTERN	EAST (in)
1	(2.5%) 14.0	(2.5%) 12.5
2	(2.1%) 13.5	(2.1%) 14
3	(2.25%) 21.2	(1.5%) 18.2
4	(10.25%) 23.7	(10.25%) 23.4
5	(7.5%) 25.1	(5.75%) 26.4

Remarks _____

Tested by Allyl B. J. J. Date 4/8/77

Witness 2.16.1.1.1.1 Date 4/1/77

Sheet No. 7 of 9

Approved _____

DATA SHEET

Project PT3 CONNECTORS

Specimen 1, 2, 3, 7, 8, 9

Part No _____

Ident. RADIATION, FOURTH 22 HR PERIOD, SIDE 4 UP Start Date 4/8/79

TEMPERATURES: TYPE K TC / DATALOGGER, °C

TC #	Connector #	4/8/79			4/9/79		
		1966	1966	2306	0306	0406	1006
1	1	27°C	33°C	31°C	31°C	30°C	30°C
2	2	29	32	30	30	29	29
3	3	27	32	30	27	29	27
4	AMBIENT WGA CAN	28	30	28	28	27	27
5	7	27	34	32	31	30	31
6	5	27	34	32	31	30	31
7	9	28	31	29	28	28	28
8	AMBIENT EAT CAN	26	28	28	27	27	29

RADIATION START: 4/8/79 12:01 END: 4/9/79 10:39

Remarks _____

Tested by [Signature] Date 4/9/79

Witness [Signature] Date 4/9/79

Sheet No. 8 of 9

Approved _____

DATA SHEET

Project IF3 CONNECTORS

Specimen 1, 2, 3, 7, 8, 9

Part No. _____

Ident. RADIATION : SUMMARY

Start Date 4/1/79

— RADIATION WAS CONDUCTED IN FOUR 22.5 HR PERIODS, WITH ROTATION OF THE CONNECTORS (CANS) AS PREVIOUSLY DESCRIBED

— PERIODS 1 & 2 WERE CONDUCTED AT MAP'S LOCATION; PERIODS 3 & 4 AT $\frac{1}{2}$ " FURTHER FROM THE SOURCE. CORRESPONDING CONNECTOR LOCATIONS ARE SHOWN IN THE FIGURES.

— MAXIMUM MEASURED CONNECTOR TEMPERATURE WAS 35°C. TEMPERATURES GENERALLY RANGED BETWEEN 30 - 34°C.

— BASED ON THE PRETEST TLD-400 MAPS AND THE CONNECTOR LOCATIONS, THE AVERAGED DOSE RATE WAS 0.76 MRAD/HOUR, THE TOTAL DOSE WAS 68.5 MRAD. THESE VALUES ARE CONSIDERED TO BE ACCURATE TO $\pm 10\%$

Remarks _____

Tested by Aloyd Bingen Date 4/1/79

Witness _____ Date _____

Sheet No. 9 of 9

Approved _____

INSTRUMENTATION EQUIPMENT SHEET

Date 4/5 - 4/6/79 Technician D. DUGAN Test Area TA-V, NORTH GIFF
Project B73 CANTONERS Type Test RADIATION

No.	Instrument	Manufacturer	Model No.	Serial No.	Ident No.	Range	Accuracy	Calibration	
								On	Due
1	DANALOGIC	ACCUREX	AN101	1654	01467	-100-100C	$\pm 1^{\circ}C$	3/6/79	5/6/79

CERTIFICATION SHEET ATTACHED

Instrument Test Engineer _____ Checked & Received by _____



Sandia Laboratories

Albuquerque, New Mexico 87115

Standards Laboratory Certificate

DATALOGGER

Acurex

Model No. A901

Serial No. 1694

Property No. 011409

Submitted by: Organization 4442

Certified: March 9, 1979

Expires: September 9, 1979

This instrument was adjusted according to manufacturer's calibration procedure and was found to be within these specifications:

Voltage Measurements: $\pm 0.005\%$ of full scale $\pm 0.005\%$
of reading after one hour warmup

Thermocouple Measurements: -170°C to $+1280^{\circ}\text{C} \pm 1^{\circ}\text{C}$
(Type K Thermocouple)

Metrologist: H. H. Pike, 2553


Certified by: G. F. McFall, 2552

HHP:2553:bb

Conditions of Certification: Neither Sandia Laboratories nor the Government assumes any responsibility with respect to the use of this document, the information contained therein, or the physical device or instrument certified, by any person other than the contractor to whom originally issued. Any such use will be at the sole risk and responsibility of such other user.

If this document is issued to a Sandia Laboratories supplier, neither Sandia Laboratories nor the Government assumes any responsibility for the use of this document, the information contained therein, or the physical device or instrument certified, at any time beyond the resubmittal date or any order or contract other than the order or contract, including charges, under which the certification is given.

In no case will Sandia Laboratories or the Government assume responsibility for consequential damages. SA 5710 DA(9-72)

April 5, 1979

L. L. Bonzon, 4442

L D Posev


L. D. Posev, 4452

Calibration of the CaF_2 TLD's used by the Area V Diagnostics Lab

The present batch of Harshaw TLD 400 dosimeters was calibrated in the following manner. The low-dose range, up to 100 rads, was calibrated using the vertical range in Area I. The dose received by the dosimeters during this part of the calibration is determined from the exposure dose measured by Victoreen R-chambers which are calibrated by NBS at regular intervals. Prior to the summer of 1978, the south Co^{60} -source of the Sandia GIF was an NBS secondary standard and the high-dose (> 100 rads) calibration data was obtained using this source. At that time, the source configuration was modified and the new configuration has not as yet been calibrated. As a result, TLD dosimeters from the batch presently in use were calibrated at high-dose by Far West Technology Inc. using the EG&G NBS certified Co^{60} -source in Santa Barbara, California. Although the entire calibration procedure is not currently carried out in-house, the calibration can be traced to two separate NBS certifications.


LDP:4452:dj

Copy to:
4452 M. Hauer



PHOTOGRAPH C79-3936


VIEW OF CONNECTOR BOXES IN
IRRADIATION CELL



PHOTOGRAPH C79-3938

VIEW OF CONNECTOR BOXES IN
IRRADIATION CELL

POOR ORIGINAL



PHOTOGRAPH C79-3944

VIEW OF CONNECTOR BOXES IN
IRRADIATION CELL

POOR ORIGINAL

SECTION V

POST-RADIATION FUNCTIONAL/MECHANICAL TESTS

Post-Radiation Functional/Mechanical Tests Procedures

After the electrical connectors have been irradiated, each item will be subjected to insulation resistance, voltage, load, and dimensional tests. The test procedures outlined in the previous two applicable (Baseline) sections will be followed here as well, except that the electrical loads are held constant and the operating current/voltage is recorded.

DATA SHEET

Project BF3 CONNECTORS

Specimen ALL

Part No _____

Ident. PCT-RADIATION FUNCTIONAL IR

Start Date 4/10/79

PINS (250VDC CONNECTORS)

ITEM	K TO CASE	N TO CASE	K TO N
1	$>2.5 \times 10^9 \Omega$	$>2.5 \times 10^9 \Omega$	$>2.5 \times 10^9 \Omega$
2	$>2.5 \times 10^9 \Omega$	$>2.5 \times 10^9 \Omega$	$>2.5 \times 10^9 \Omega$
3	$2.5 \times 10^9 \Omega$	$2.5 \times 10^9 \Omega$	$2.5 \times 10^9 \Omega$

PINS (480VAC CONNECTORS)

ITEM	G TO CASE	IC TO CASE	G TO IC
7	$7.5 \times 10^8 \Omega$	$1.3 \times 10^9 \Omega$	$6.25 \times 10^8 \Omega$
8	$2.5 \times 10^9 \Omega$	$2.5 \times 10^9 \Omega$	$1.5 \times 10^9 \Omega$
9	$2.0 \times 10^9 \Omega$	$2.5 \times 10^9 \Omega$	$1.25 \times 10^9 \Omega$

Remarks _____

Tested by [Signature] Date 4-10-79

Witness [Signature] Date 4/10/79

Sheet No. 1 of 3

Approved _____

DATA SHEET

Project DPS CONNECTORS

Specimen AST-DC

Part No 1, 2, 3

Ident. POST-RADIATION FUNCTIONAL LOAD/VOLTAGE Start Date 4/10/79

	INPUT	LOAD	LOAD	INPUT
	VOLTAGE	RESISTANCE	VOLTAGE	CURRENT
1	25.00V	240.0 (CAL)	25.1VDC	1.010 A
2	25.00V	240.0 (CAL)	25.1VDC	0.985 A
3	25.00V	241.0 (CAL)	25.1VDC	1.003 A

Remarks _____

Tested by [Signature] Date 4/10/79

Witness [Signature] Date 4/10/79

Sheet No. 2 of 3

Approved _____

DATA SHEET

Project BF3 CONNECTORS

Specimen 480 VAC

Part No 7, 8, 9

Ident. POST-RADIATION FUNCTIONAL LOAD/VOLTAGE Start Date 4/10/79

	INPUT	LOAD (DC)	LOAD	INPUT
ITEM	VOLTAGE	RESISTANCE	VOLTAGE	CURRENT
7	480 VAC	25.3 Ω (cold)	480 VAC	17.43 A
8	480 VAC	25.6 Ω (cold)	482 VAC	17.24 A
9	490 VAC	25.6 Ω (cold)	484 VAC	17.36 A

Remarks _____

Tested by [Signature] Date 4/10/79

Witness [Signature] Date 4/10/79

Sheet No. 3 of 3

Approved _____

INSTRUMENTATION EQUIPMENT SHEET

Date 4/10/79

Test Area Bldg 5106

Technician D. Dugan

Project BT3 CAPACITORS

Type Test POT-RADIATION FUNCTIONAL

No.	Instrument	Manufacturer	Model	Serial	Ident	Range	Accuracy	Calibration	
			No.	No.	No.			On	Due
1	PRECISEMETER	AMERICAN	8A12500	5-77-112	RK220	0.05-250000	$\pm 4\% F.S.$	3/1/79	9/14/79

HL TEST SYSTEMS

2	DIGITAL MULTIMETER	FLUKE	8700A	3318	213043	C-1000000	$\pm 0.1\% + 2 \text{ DIGITS}$	3/1/79	9/1/79
3	POWER ANALYZER	NAAGROL	4610	8067	250183	C-50A 0-600V	$\pm 0.5\% + 1 \text{ DIGIT}$	3/1/79	9/1/79
4	POWER SUPPLY	HEWLETT PACKARD	8154	-	237671	C-32VDC 0-1.5A	NOT AVAILABLE	-	-

Instrument Test Engineer _____

Checked & Received by _____

DATA SHEET

Project BT3 CONNECTORS

Specimen 550VDC

Part No 1

Ident. POST-RADIATIONAL DIMENSIONAL

Start Date 4/10/79

ACROBONE INSULATOR		DIAMETER		WIRE A	
<u>Pos</u>	<u>DEPTH</u>	<u>LOCATION</u>	<u>VALUE</u>	<u>LOCATION</u>	<u>CR</u>
A	C.100"	I	8'	1	C.135"
K	C.094"	II	92	2	C.136"
M	C.091"	III	8'	3	C.137"
E	C.118"				

ACROBONE INSULATOR WAS ABOVE THE END OF THE
CONNECTOR PLUG BARREL.

BARREL DIAMETER : 1.504 - 1.512 "


Remarks _____

Tested by [Signature] Date 4-10-79

Witness [Signature] Date 4/10/79

Sheet No. 1 of 4

Approved _____



DATA SHEET

Project FT-1 CONNECTORS

Specimen 250 VDC

Part No 2

Ident. FT-1 RADIATION DIMENSIONAL

Start Date 4/10/79

ACCORDING INSULATOR		PERIMETER		WIRE A	
<u>POINT</u>	<u>DEPTH</u>	<u>LOCATION</u>	<u>VALUE</u>	<u>LOCATION</u>	<u>CD</u>
A	C.110"	I	92	1	C.153"
B	C.100"	II	93	2	C.151"
C	C.105"	III	91	3	C.153"
E	C.100"				

ACCORDING INSULATOR WAS ABOVE THE END OF THE
CONNECTOR RIG BARREL

BARREL DIAMETER: 1.505 - 1.512"

Remarks _____

Tested by [Signature] Date 4-10-79

Witness [Signature] Date 4/10/79

Sheet No. 2 of 6

Approved _____

DATA SHEET

Project BT-3 CONNECTORS

Specimen 25C-DC

Part No 3

Ident. RET-RADIATION DIMENSIONAL

Start Date 4/10/71

MICRONE INSULATOR		DERIVETER		WIRE A	
<u>IN</u>	<u>DEPTH</u>	<u>LOCATION</u>	<u>VALUE</u>	<u>LOCATION</u>	<u>CD</u>
A	C.075"	I	93	1	C.156"
K	C.105"	II	91	2	C.187"
M	C.100"	III	90	3	C.185"
E	C.120"				

MICRONE INSULATOR WAS ABOVE THE END OF THE
CONNECTOR PLUG BARREL.

BARREL DIAMETER: 1.505 - 1.512"

Remarks _____

Tested by [Signature] Date 4-12-71

Witness [Signature] Date 4/10/71

Sheet No. 3 of 6

Approved _____

DATA SHEET

Project ST-3 CONNECTORS

Specimen 450 VAC

Part No 7

Ident. 1071 - RADIATION DIMENSIONAL

Start Date 4/10/79

MEASURE	INDICATOR	DENOMINATOR	WIRE	14
17A	DEPTH	LOCATION	VALUE	LOCATION
1	C.102"	14	91	1 C.107"
14	C.101"	1	85	2 C.107"
6	C.103"	11	87	3 C.107"

ALL DIMENSIONAL INDICATOR WAS ABOVE THE END OF THE CONNECTOR PLUG BARREL

BARREL DIAMETER: 1.965"

Remarks _____

Tested by [Signature]


Date 4/10-79

Witness [Signature]

Date 4/10/79

Sheet No. 4 of 6

Approved _____



DATA SHEET

Project BFS CONNECTORS

Specimen 480 VAC

Part No 8

Ident. POST-IRRADIATION DIMENSIONAL

Start Date 4/11/77

NEEDLE INSULATOR		DIAMETER		WIRE 14	
PIN	DEPTH	LOCATION	VALUE	LOCATION	CS
1	0.115"	IV	88.89	1	0.207"
14	0.098"	I	86	2	0.211"
6	0.123"	II	87.85	3	0.201"

NEEDLE INSULATOR WAS ABOVE THE END OF THE
CONNECTOR RUB BARREL.

BARREL DIAMETER 1.467"

Remarks _____

Tested by [Signature] Date 4.10.77

Witness [Signature] Date 4/10/77

Sheet No. 5 of 6

Approved _____

DATA SHEET

Project BT 3 CONNECTORS

Specimen 48C VAC

Part No 9

Ident. FOR INVIATION

DIMENSIONAL

Start Date 4/10/79

ACCIDENT		INVIATION		DIMENSIONAL		WIRE 14	
IN	DEPTH	LOCATION	VALUE	LOCATION	CD		
1	C. 110"	IV	91	1	C. 210"		
14	C. 110"	I	90	2	C. 210"		
6	C. 131"	II	90	3	C. 210"		

ACCIDENT INVIATION WAS ABOVE THE END OF THE
CONNECTOR REG. BARREL.

BARREL DIAMETER: 1.965"

Remarks _____

Tested by [Signature] Date 4-10-79

Witness [Signature] Date 4/10/79

Sheet No. 6 of 6

Approved _____

INSTRUMENTATION EQUIPMENT SHEET

Date 9/1/77

Test Area BDC, 5K D

Technician D. OGAN

Project BT-3 Conn. 7-5 Type Test POST-RADIATION DIMENSIONAL

No.	Instrument	Manufacturer	Model No.	Serial No.	Ident No.	Range	Accuracy	Calibration	
								On	Due
1	SHORE TYPE A2	SHORE INSTRUMENT TRIA ²	—	16-213	C-100	NOT AVAILABLE			
		LAUREL C.C.							

2	CALIPERS	BRUNN & SHARPE	571	—	—	C-6"/.01	±.01	NOT AVAILABLE
---	----------	----------------	-----	---	---	----------	------	---------------

Instrument Test Engineer _____ Checked & Received by _____

SECTION VI
TEMPERATURE AGING TEST

Temperature Aging Test Procedure

All of the test items will be subjected to a thermal aging test, with uncontrolled (ambient) humidity. The test is to be conducted in two parts: in circulating air at 217°F for 60 hours, followed by a test in flowing nitrogen at 217°F for 180 hours.

Pre-test flow measurements in the empty oven (chamber) will be made and recorded to determine approximate air circulation flow rates. Pertinent information on the oven, controllers, and other instrumentation will be recorded on data sheets and/or other pertinent documentation.

All test items will be placed in the temperature chamber in a manner to avoid overheating from radiant effects from the chamber heating elements. The temperature chamber will be vented to the atmosphere to prevent buildup of outgasing products, particularly chlorine gas, from the test item inside the chamber. The air inside the chamber will be distributed as uniformly as possible. The test items will be aged in air at 217°F for a time period of 60 hours. Besides the TC's associated with the oven controller and environment monitors, select specimen temperatures are to be monitored and recorded. Record results, TC locations, and observations on data sheets and/or other pertinent documentation.

Following air aging, the test specimens will be removed from the oven. The oven will be purged with flowing nitrogen; the specimens will then be repositioned in the oven.

The oven temperature will be then returned to, and stabilized at 217°F, with this temperature maintained for a total of 180 hours. During nitrogen aging, a continuous flow of nitrogen, about 1/4 cfm, will be introduced into the chamber at ambient pressure. This purge will prevent the outgasing products from accumulating inside the oven. Specimen temperatures will be monitored and recorded as described above.

After completion of the aging test in the nitrogen atmosphere, the test chamber will be normally returned to ambient temperature, under flowing nitrogen conditions, and the test items removed from the oven for post-test examination.

DATA SHEET

Project BF3 CONNECTORS

Specimen ALL

Part No _____

Ident. TEMPERATURE AGING - PLACEMENT Start Date 4/10/79

ALL CONNECTORS, IN THE STEEL CANS, WERE PLACED IN A PACK IN OVEN #16 (BODG SEC/RM 110); THEY WERE APPROXIMATELY CENTERED IN THE OVEN.

A CALIBRATED TEMPERATURE PROBE WAS PLACED NEAR THE CANS AS THE OVEN MONITOR.

THERMOCOUPLES WERE ATTACHED TO THE CONNECTORS EXACTLY AS THEY WERE FOR THE RADIATION PHASE:

TC#	CONNECTOR#	TC#	CONNECTOR#
1	1	5	7
2	2	6	8
3	3	7	9
4	AMBIENT IN CAN	8	AMBIENT IN CAN

Remarks _____

Tested by _____ Date _____

Witness Alfred Berger Date 4/10/79

Sheet No. 1 of 2

Approved _____

DATA SHEET

Project BFS CONNECTORS

Specimen ALL

Part No _____

Ident. TEMPERATURE AGING - AIRFLOW

Start Date 4/10/79

— Using An Anemometer, AIRFLOW WAS MEASURED
IN THE CHAMBER (#16):

CENTER 170 - 190 CFM

EDGE 350 - 360 CFM

EXHAUST FAN ~ 450 CFM

AIRFLOW INDICATORS ARE THAT THE FLOW IS
ABOUT 250 ± 50 CFM IN THE REGION WHERE
THE CONNECTORS ARE TO BE PLACED

Remarks _____

Tested by David B. B... Date 4/10/79

Witness John T. St... Date 4/10/79

Sheet No. 2 of 2

Approved _____

DATA SHEET

Project BTS CONNECTORS

Specimen ALL

Part No. _____

Ident. TEMPERATURE AGING - AIR - #16

Start Date 4/10/79

- STARTED AGING 4/10/79, 1431,

- TWO VENT PLUGS REMOVED ON CHAMBER #16

- REACHED AIR TEMPERATURE $217^{\circ}\pm 2^{\circ}\text{F}$ AT 1500,

- DUGAN CHECKED SYSTEM AT 2045 (4/11/79); 217°F CHAMBER,

- DUGAN CHECKED SYSTEM AT 2030 (4/12/79); 217°F CHAMBER,

- SYSTEM AUTOMATIC SHUTDOWN AT 2044 ON 4/13/79,

TOTAL TIME AT 217°F WAS $\sim 59\frac{2}{3}$ HOURS.

- TOOK PHOTOS OF CEN/CONNECTORS.

- SOME CABLE DISCOLORATION WAS NOTED; SOME TC's WERE LOOSE

Remarks _____


Tested by [Signature] Date 4-13-79

Witness [Signature] Date 4/13/79


Sheet No. 1 of 1

Approved _____


AIR - CEN CHAMBER TEMPERATURE
4/10-11/79



AIR-CLIN CHAMBER TEMPERATURE
4/11-12/79



AIR-CLIN CHAMBER TEMPERATURE
4/11-12/79




BF3 CONNECTORS

AIR OVEN AGING (60 HOURS)

1500 (4/10/79) — 0240 (4/13/79)

4/11/79
Lloyd Longm

X HIGHEST TC READING
□ LOWEST TC READING] OF 8 TC's



Project F43 CONNECTOR

Specimen ALL

Part No _____

Ident. THERMAL AGING - NITROGEN - #16 Start Date 4/16/79

- SAME TC PLACEMENT + CHECKUP AS AIR AGING
- SAME CUA #16; SAMPLES ^{REMAINED} IN PLACE *
- HOOKED UP NITROGEN SUPPLY, OUTLET IN CHAMBER
- INSTALLED DIGITAL THERMOMETER + PLATINUM PROBE
- STARTED NITROGEN FLOW AT 1447 (4/16/79)
- APPROXIMATELY 600 PSI CUA @ 1437
- STARTED TEMPERATURE AT 1441
- REACHED NO TEMPERATURE AT 1540; AT 1551
- CHECKED SYSTEM ON 4/17/79, 1500; ALL OK
- PULAN CHECKED SYSTEM ON 4/18/79, 1600; ALL OK
- PULAN CHECKED SYSTEM ON 4/19/79, 1600; ALL OK
- PULAN CHECKED SYSTEM ON 4/20/79, 1600; ALL OK

Remarks * SEE PROCEDURE

Tested by [Signature] Date 4/24/79

Witness [Signature] Date 4/24/79

Sheet No. 1 of 2

Approved _____

DATA SHEET

Project GPS CONNECTORS

Specimen All

Part No _____

Ident. THERMAL AGING - NITROGEN - #16 Start Date 4/16/79

- BONAN CHECKED SYSTEM ON 4/20/79, 1400; ALL IS READY FOR WEEKEND.
- DUNN & BONAN CHECKED SYSTEM ON 4/21/79 ~ 0700; ALL OKAY.
- DUNN & BONAN CHECKED SYSTEM ON 4/22/79 ~ 0700; ALL OKAY.
- DUNN CHECKED SYSTEM ON 4/23/79, ~ 0700; ALL OK.
- SYSTEM AUTOMATIC SHUTDOWN AT ~ 0300 ON 4/24/79.
- TOTAL TIME AT 217°F WAS ~ 179 ²/₃ HOURS.
- TOOK PICTURES OF CEN/CONNECTORS.
- N₂ OIL AT ~ 0945 ON 4/24/79.
- ALL TCA'S STILL ATTACHED

Remarks DISCLOCCATION AT END

Tested by [Signature] Date 4/24/79

CF N₂ AGING; BUT HAD SUCH

Witness Aloyd [Signature] Date 4/24/79


DISCLOCCATION AT END CF

Sheet No. 2 of 2


AIR AGING ALSO

Approved _____

N_2 - Oven CHAMBER TEMPERATURE 4/16-17/79




A₂-C₁ CHAMBER TEMPERATURE
4/17-19/79




N₂-EVEN CHAMBER TEMPERATURE

4/19-20/79




N₂-OVEN CHAMBER TEMPERATURE

4/20-21/79




N₂ - (VEN) CHAMBER TEMPERATURE
4/21-22/19




N₂-OVEN CHAMBER TEMPERATURE

4/22-23/77



N₂-LVEN CHAMBER TEMPERATURE

4/23-24/79



BF3 CONNECTED

NITROGEN OVEN AGING (180 HOURS)


1540 (4/24/79) - 0320 (4/24/79)

X HIGHEST TC READING

□ LOWEST TC READING

OF 8 TC's

4/24/79
Allyl Fluoride



HOURS, NITROGEN OVEN AGING

DATA SHEET

Project BFS CONNECTORS

Specimen ALL

Part No. _____

Ident. NITROGEN FLOW/CONCENTRATION

Start Date 4/24/79

THE USE OF NITROGEN DURING THERMAL AGING WAS
RECORDED AS A CHECK ON FLOW THROUGH THE CHAMBER;
FLOW RECORDING WAS FROM 1443 (4/16/79) TO 1445 (4/24/79):

BOTTLE VALVE
ON OFF USED

153 μ^3 173 μ^3 10 μ^3

285 54 231

297 32 265

276 18 256

275 6.3 212

281 15 (3 TANKS) 784

116 35 (3 TANKS) 234

1997 μ^3

FOR THE 187 HOURS OF

N_2 FLOW, THE FLOW RATE

IS $\sim 10.7 \mu^3/\text{HR}$ OR $0.18 \mu^3/\text{min.}$

Remarks DURING THE TEST

THE C_2 ANALYZER INDICATED
 $\sim 600-700$ PPM C_2 , AND WAS
RELATIVELY INSENSITIVE TO
TEMPERATURE.

Tested by _____ Date _____

Witness Kloyd Benson Date 4/24/79

Sheet No. 1 of 1

Approved _____

INSTRUMENTATION EQUIPMENT SHEET

Date 4/10/79 Test Area Box 360 / Km 116
 Technician F. Potts Project DFS CONNECTION Type Test THERMAL ANAL.

No.	Instrument	Manufacturer	Model No.	Serial No.	Ident No.	Range	Accuracy	Calibration	
								On	Due
1	ANEMOMETER	ALARK	8500	1934	203445	10-4000 Cfm			
2	DATALOGGER	ACCURX	A901	1054	011409	-12°C - 125°C	± 1°C	3/6/79	5/6/79
3	DIGITAL THERMOMETER	DERIC	DS100T	1/2 2233	5217489	-20°F - 400°F	± 1°F	10/6/75	10/2/79
4	PLATINUM PROBE								
				15152					
5	OVER ECHIL	CONRAD	EI-27-3-3	7012	555577	-10°F - 425°F	BASED ON DIGITAL THERMOMETER		

} FILE 24186

Instrument Test Engineer _____ Checked & Received by _____

Standards Laboratory Certificate



Sandia Laboratories

Albuquerque, New Mexico 87115

File No. 2418 G

DIGITAL THERMOMETER
Doris Scientific Corporation
Model DS100T, S/N 2233
Sensor S/N 15152

Submitted by: Division 1541

Certified: October 20, 1978
Expires: October 20, 1979

Test Results

<u>Ref. Temp.</u> <u>°F</u>	<u>Readings</u> <u>°F</u>
-90.22	-90.6
-49.76	-50.0
- 0.04	-00.3
50.09	49.8
99.93	99.7
150.53	150.2
199.94	199.7
250.23	250.0
300.27	300.0
349.93	349.7
399.99	399.8

Uncertainties in the reference temperature are estimated not to exceed $\pm 0.02^{\circ}\text{F}$.

It is estimated that this instrument may be relied upon to within $\pm 1.0^{\circ}\text{F}$.

Technical Consultant: G. Gleicher - 2551

Original Signed By
R. B. FOSTER, JR

GG:2551:omb

Certified by: R. B. Foster - 2551

Copy to:


1541 Organization (2)

2551 File (2)

Conditions of Certification: Neither Sandia Laboratories nor the Government assumes any responsibility with respect to the use of this document, the information contained therein, or the physical device or instrument certified, by any person other than the contractor to whom originally issued. Any such use will be at the sole risk and responsibility of such other user.

If this document is issued to a Sandia Laboratories supplier, neither Sandia Laboratories nor the Government assumes any responsibility for the use of this document, the information contained therein, or the physical device or instrument certified, at any time beyond the resubmittal date or any order or contract other than the order or contract, including changes, under which the certification is given.


In no case will Sandia Laboratories or the Government assume responsibility for consequential damages. SA 5710-DA(9-72)



PHOTOGRAPH C79-3062

OVEN AND ASSOCIATED CONTROLLER
WITH CONNECTOR BOXES IN-PLACE
IN THE OVEN


POOR ORIGINAL



PHOTOGRAPH C79-3061

CONNECTOR BOXES IN TEMPERATURE
AGING CHAMBER


POOR ORIGINAL



PHOTOGRAPH C79-3060

480-VAC CONNECTORS;
ITEMS 7, 8, 9

POOR ORIGINAL



PHOTOGRAPH C79-3059

CONNECTOR BOXES IN TEMPERATURE
AGING CHAMBER








IMAGE EVALUATION TEST TARGET (MT-3)



MICROCOPY RESOLUTION TEST CHART






PHOTOGRAPH C79-3058

250-VDC CONNECTORS:
ITEMS 1, 2, 3

POOR ORIGINAL



PHOTOGRAPH C79-3057

CONNECTOR BOXES IN TEMPERATURE
AGING CHAMBER

POOR ORIGINAL

SECTION VII

POST-AGING FUNCTIONAL/MECHANICAL TESTS

Post-Temperature Aging Functional/Mechanical Tests Procedures

After the electrical connectors have been aged, each item will be subjected to insulation resistance, voltage, load, and dimensional tests. The test procedures outlined in the previous two applicable (Baseline) sections will be followed here as well, except (1) that the electrical loads are held constant and the operating current/voltage is recorded and (2) that the insulation resistance measurement will also be made with a volt-ohmmeter.

DATA SHEET

Project DEF3 CONNECTIONS

Specimen ALL

Part No _____

Ident. POT-THERMAL AGING FUNCTIONAL IR Start Date 4/24/79

Pins (250 VDC CONNECTORS)

ITEM	K TC CASE	N TC CASE	K TC N
1	$1.7 \times 10^9 \Omega$	$1.4 \times 10^9 \Omega$	$1.25 \times 10^9 \Omega$
2	$1.6 \times 10^9 \Omega$	$1.5 \times 10^9 \Omega$	$1.25 \times 10^9 \Omega$
3	$1.6 \times 10^9 \Omega$	$1.25 \times 10^9 \Omega$	$1.0 \times 10^8 \Omega$

Pins (480 VAC CONNECTORS)

ITEM	9 TC CASE	10 TC CASE	9 TC 10
7	$4.5 \times 10^8 \Omega$	$5 \times 10^8 \Omega$	$3 \times 10^8 \Omega$
8	$5 \times 10^8 \Omega$	$6.25 \times 10^8 \Omega$	$2.75 \times 10^8 \Omega$
9	$5 \times 10^8 \Omega$	$5 \times 10^8 \Omega$	$2.5 \times 10^8 \Omega$

Remarks AFTER THERMAL AGING,
"1" WAS TIGHT ; 2, 3, 7, 8, 9
WERE TIGHTENED 1/16 - 1/8 TURN
EACH.

Tested by [Signature] Date 4/24/79

Witness Lloyd Benson Date 4/24/79

Sheet No. 1 of 3

Approved _____

DATA SHEET

Project BF3 CONNECTORS

Specimen 250 VDC

Part No 1, 2, 3

Ident. POST-THERMAL AGING, FUNCTIONAL LOAD/VOLTAGE Start Date 4/24/79

	INIT	LOAD	LOAD	INIT
ITEM	VOLTAGE	RESISTANCE	VOLTAGE	CURRENT
1	250VDC	242.52 (cold)	250VDC	1.005A
2	250VDC	246.2 (cold)	250VDC	0.992A
3	250VDC	244.2 (cold)	250VDC	0.994A

Remarks _____

Tested by [Signature] Date 4/24/79

Witness [Signature] Date 4/24/79

Sheet No. 2 of 3

Approved _____

DATA SHEET

Project BES CONNECTORS

Specimen 480 VAC

Part No 7, 8, 9

Ident. POST-THERMAL AGING FUNCTIONAL LOAD/VOLTAGE Start Date 4/24/19

	INPUT	LOAD (Ω)	LOAD	INPUT
ITEM	VOLTAGE	RESISTANCE	VOLTAGE	CURRENT
7	480 VAC	25.6 Ω (COLD)	48 480 VAC	17.42 A
8	480 VAC	25.6 Ω (COLD)	485 VAC	17.2 A
9	480 VAC	25.6 Ω (COLD)	485 VAC	17.32 A

Remarks _____

Tested by [Signature] Date 4/24/19

Witness [Signature] Date 4/24/19

Sheet No. 3 of 3

Approved _____

INSTRUMENTATION EQUIPMENT SHEET

Date 4/24/79Test Area BUDG. 8406Technician D. D. GAWProject DF-3 Converter Type Test Post-Thermal Functional

No.	Instrument	Manufacturer	Model No.	Serial No.	Ident No.	Range	Accuracy	Calibration	
								On	Due
1	MICROMETER	AMERICAN	60A 2500	5-17-113	210220	± 0.0001 250000	$\pm 4\% F.S.$	3/5/79	4/14/79
HV TEST SYSTEMS									
2	DIGITAL MULTIMETER	FLUKE	500A	3318	21343	C-100A2C ± 0.08 + 200000 C-1-1000000 ± 0.002 + 10000		3/6/79	4/2/79
3	POWER ANALYZER	WATTEL	4610	5007	150105	C-20A C-600V	$\pm 0.5\%$ + 10000	3/1/79	4/1/79
4	POWER SUPPLY	HEWLETT PACKARD	505A	--	137617	C-1000V C-1.5A	N-T AVAILABLE		

Instrument Test Engineer _____

Checked & Received by _____

DATA SHEET

Project BF3 CONNECTORS

Specimen 250VDC

Part No 1

Ident. PST-THERMAL AGING DIMENSIONAL

Start Date 4/24/79

NEOPRENE INSULATOR		DURCHMETER		WIRE A	
PIN	DEPTH	LOCATION	VALUE	LOCATION	OD
A	0.054"	I	91	1	0.181"
K	0.080"	II	93	2	0.155"
M	0.078"	III	91	3	0.180"
E	0.105"				

NEOPRENE INSULATOR WAS SLIGHTLY ABOVE THE END OF THE CONNECTOR PLUG BARREL, UNDOULTING SURFACE

BARREL DIAMETER: 1.507-1.513"


Remarks _____

Tested by [Signature] Date 4/24/79

Witness [Signature] Date 4/24/79

Sheet No. 1 of 7

Approved _____



DATA SHEET

Project PTS CONNECTORS

Specimen 250 VDC

Part No 2

Ident. 1001 THERMAL Aging DIMENSIONAL

Start Date 4/24/79

NEOPRENE INSULATOR		DURIMETER		WIRE A	
PIN	DEPTH	LOCATION	VALUE	LOCATION	CD
A	0.100"	I	91	1	0.183"
K	0.153"	II	92	2	0.181"
M	0.015"	III	89	3	0.183"
E	0.081"				

NEOPRENE INSULATOR WAS SLIGHTLY ABOVE TILE END
 OF THE CONNECTOR PLUG BARREL, INDICATING
 SURFACE.

BARREL DIAMETER: 1.510 - 1.512"

Remarks _____

Tested by [Signature] Date 4/24/79

Witness Lloyd Rogers Date 4/24/79

Sheet No. 2 of 7

Approved _____

DATA SHEET

Project RF3 CONNECTORS

Specimen 250 VDC

Part No 3

Ident. RST - THERMAL AGING DIMENSIONAL

Start Date 4/24/79

NEOPRENE INDULATOR		DIROMETER		WIRE A	
IN	DEPTH	LOCATION	VALUE	LOCATION	CD
A	0.056"	I	1/6	1	0.156"
K	0.057"	II	1/3	2	0.184"
M	0.085"	III	1/3	3	0.183"
E	0.105"				

NEOPRENE INDULATOR WAS SLIGHTLY ABOVE THE END OF THE CONNECTOR PLUG BARREL, UNDUATING SURFACE,

BARREL DIAMETER: 1.505-1.512"

Remarks _____

Tested by [Signature] Date 4/24/79

Witness [Signature] Date 4/24/79

Sheet No. 3 of 7

Approved _____

DATA SHEET

Project DF3 CONNECTORS

Specimen 4th VAC

Part No 7

Ident. POST-THERMAL AGING DIMENSIONAL

Start Date 4/24/79

NEOPRENE INSULATOR		DURIMETER		WIRE 14	
ID	DEPTH	LOCATION	VALUE	LOCATION	CD
1	0.091"	II	87	1	0.207"
14	0.081"	IV	84	2	0.207"
6	0.054"	II	80	3	0.209"

NEOPRENE INSULATOR WAS BELOW THE END OF THE
CONNECTOR PLUG BARREL.

BARREL DIAMETER: 1.968 - 1.970"


Remarks _____

Tested by [Signature] Date 4/24/79

Witness Floyd Dwyer Date 4/24/79

Sheet No. 4 of 7

Approved _____



DATA SHEET

Project BFB CONNECTORS

Specimen 430 VAC

Part No 8

Ident. PJT - THERMAL AGING DIMENSIONAL

Start Date 4/24/77

NEOPRENE INSULATOR		DURIMETER		WIRE 14	
<u>PIN</u>	<u>DEPTH</u>	<u>LOCATION</u>	<u>VALUE</u>	<u>LOCATION</u>	<u>OD</u>
1	0.031"	<u>IV</u>	85	1	0.207"
14	0.012"	<u>V</u>	86	2	0.207"
6	0.098"	<u>VI</u>	83	3	0.207"

NEOPRENE INSULATOR WAS BELOW THE END OF THE
CONNECTOR PLUG BARREL.

BARREL DIAMETER: 1.765"

Remarks _____

Tested by [Signature] Date 4/24/77

Witness [Signature] Date 4/24/77

Sheet No. 5 of 7

Approved _____

DATA SHEET

Project BF3 CONNECTORS

Specimen 482 LAC

Part No 9

Ident. POST-THERMAL AGING DIMENSIONAL

Start Date 4/24/79

NEOPRENE INSULATOR		DILATOMETER		WIRE 14	
<u>IN</u>	<u>DEPTH</u>	<u>LOCATION</u>	<u>VALUE</u>	<u>LOCATION</u>	<u>CD</u>
1	0.090"	IV	83	1	0.205"
14	0.079"	I	86	2	0.210"
6	0.105"	II	85	3	0.209"

NEOPRENE INSULATOR WAS BELOW THE END OF THE
CONNECTOR PLUG BARREL.

BARREL DIAMETER: 1.968"

Remarks _____

Tested by [Signature] Date 4/24/79

Witness Lloyd Benson Date 4/24/79

Sheet No. 6 of 7

Approved _____

DATA SHEET

Project BTS CONNECTORS

Specimen ALL

Part No _____

Ident. POST-THERMAL MATING DIMENSION

Start Date 4/24/79

CONNECTOR	DISTANCE TOP OF RING MATING PLATE
1	1.223"
8	1.208"
9	1.226"
1	1.106"
2	1.107"
3	1.106"

Remarks USED AS CHECK OF
FUTURE TIGHTNESS.

Tested by [Signature] Date 4/24/79

Witness [Signature] Date 4/24/79

Sheet No. 7 of 7

Approved _____

INSTRUMENTATION EQUIPMENT SHEET

Date 4/24/79 Technician D. DeLo Project IT-3 Concrete Test Area Bldg. 3106
 Type Test POST-TENSIONAL DIAPHRAGM

No.	Instrument	Manufacturer	Model No.	Serial No.	Ident No.	Range	Accuracy	Calibration	
								On	Due
1	DIAPHRAGM TYPE A ³	INSURGENT	—	—	16273	C-100	NOT	APPLICABLE	

2. NOT A CC.

2 CALIPERS BROWNE & SHARP 579 — — C-6"/.001 ± .001 NOT APPLICABLE

Instrument Test Engineer _____

Checked & Received by _____

DATA SHEET

Project BF3 CONNECTORS

Specimen ALL

Part No _____

Ident. PRE-LOCA BASELINE FUNCTIONAL
IR (WITH MULTIMETER)

Start Date 6/26/79

PINS (250 VDC CONNECTORS)

<u>ITEM</u>	<u>K TO CASE</u>	<u>N TO CASE</u>	<u>K TO N</u>
1	>100 MΩ	>100 MΩ	>100 MΩ
2	>100 MΩ	>100 MΩ	>100 MΩ
3	>100 MΩ	>100 MΩ	>100 MΩ

PINS (450 VAC CONNECTORS)

<u>ITEM</u>	<u>9 TO CASE</u>	<u>10 TO CASE</u>	<u>9 TO 10</u>
7	>100 MΩ	>100 MΩ	>100 MΩ
8	>100 MΩ	>100 MΩ	>100 MΩ
9	>100 MΩ	>100 MΩ	>100 MΩ

Remarks _____

Tested by [Signature] Date 6/26/79

Witness [Signature] Date 6/26/79

Sheet No. 1 of 1

Approved _____


INSTRUMENTATION EQUIPMENT SHEET

Date 6/26/79 Test Area T42/R45

Technician D. DUGAN Project BF3 COMPARIS Type Test PPE - LMA IR WITH MULTIMETER

No.	Instrument	Manufacturer	Model		Serial	Ident		Range	Accuracy	Calibration	
			No.	No.		No.	No.			On	Due
1	MULTIMETER	KEITHLEY	161	36135	22224	C-RANGE	±1% ±0.0006	6/6/79	12/6/79		

Instrument Test Engineer _____ Checked & Received by _____



VII-17

DATA SHEET

Project BF3 CONNECTORS

Specimen ALL

Part No _____

Ident. PRE-ACCIDENT TEST COLD RESISTANCE LOAD Start Date 9/21/79

<u>ITEM</u>	<u>SIZE</u> <u>CONNECTOR</u>	<u>DC COLD-LOAD</u> <u>RESISTANCE</u>
1	250 VDC	242.6 Ω
2	250	252.6 Ω
3	250	250.5 Ω
7	450 VAC	25.8 Ω
8	450	25.7 Ω
9	450	25.8 Ω

Remarks _____

Tested by [Signature] Date 9-21-79

Witness A. Bingen Date 9/21/79

Sheet No. 1 of 1

Approved _____

INSTRUMENTATION EQUIPMENT SHEET

Date 9/21/79

Test Area GIF, TA-V

Technician D. R. GAR

Project BT3 Computers

Type Test PRE-ACCIDENT

COLD RESISTANCE LOADS

No.	Instrument	Manufacturer	Model	Serial	Ident	Range	Accuracy	Calibration	
			No.	No.	No.			On	Due
<u>1</u>	<u>MULTIMETER</u>	<u>JOHN FLUKE</u>	<u>810A</u>	<u>3318</u>	<u>213043</u>	<u>0-10mA</u>	<u>±0.1% + 20dB</u>	<u>9/1/79</u>	<u>3/1/80</u>
						<u>0.1-1000VDC</u>	<u>±0.5% + 10dB</u>		

Instrument Test Engineer _____

Checked & Received by _____



Sandia Laboratories

Albuquerque, New Mexico 87115

Standards Laboratory Certificate

DIGITAL MULTIMETER
JOHN FLUKE
MODEL NO. 8100A
SERIAL NO. 3318
PROPERTY NO. 213043

E3

SUBMITTED BY 4442

CERTIFIED 1 SEP 1979
EXPIRES 1 MAR 1980

THIS MULTIMETER WAS TESTED AT SELECTED CHECKPOINTS ON ALL RANGES
AND WAS FOUND BE WITHIN THE FOLLOWING MANUFACTURERS ACCURACY
CLAIMS.

DC $\pm (0.05\% \text{ OF READING} + 1 \text{ DIGIT})$ 0.1 VOLT TO
1000 VOLTS

RESISTANCE $\pm (0.1\% \text{ OF READING} + 2 \text{ DIGITS})$ 10 OHMS TO 10
MEG OHMS

AC $\pm (0.2\% \text{ OF READING} + 5 \text{ DIGITS})$ 50 HZ TO 10 KHZ
 $\pm (0.5\% \text{ OF READING} + 10 \text{ DIGITS})$ FOR 20 KHZ

METROLOGIST, R. E. PEDERSEN -2553

R. E. Pedersen
CERTIFIED BY G. F. MCALL -2553

Conditions of Certification. Neither Sandia Laboratories nor the Government assumes any responsibility with respect to the use of this document, the information contained therein, or the physical device or instrument supplied, by any person other than the contractor to whom originally issued. Any such use will be at the sole risk and responsibility of such other user.

If this document is issued to a Sandia Laboratories supplier, neither Sandia Laboratories nor the Government assumes any responsibility for the use of any document, the information contained therein, or the physical device or instrument certified, at any time beyond the resubmittal date or any order or contract other than the order or contract, including change orders, which the certification is given.

DATA SHEET

Project BF3 CONNECTORS

Specimen 2, 8, 9, (480 VAC)

Part No 480 VAC

Ident. SECONDARY CHECK OF PANEL METERS

Start Date 9/21/79

<u>LOAD</u>		<u>MAGTROL (250985)</u>		<u>PANEL METERS (480V)</u>	
<u>TIME (min)</u>		<u>VOLT (AC)</u>	<u>AMPS</u>	<u>LINE</u>	<u>LOAD</u>
#7	0	478	17.6	17.8	17.5
#7	1	477	17.3	17.8	17.6
#7	2	478	17.3	17.8	17.6
#7	3	478	17.3	17.8	17.6
#8	0	477	18.2	17.6	17.4
#8	1	477	17.2	17.3	17.1
#8	2	478	17.1	17.2	17.0
#8	3	478	17.1	17.2	17.0
#9	0	483	18.3	17.3	18.0
#9	1	484	17.1	17.0	17.8
#9	2	484	17.0	17.0	17.7
#9	3	483	16.9	17.0	17.6

Remarks DEAD SHORT REPAIRING
CONNECTOR ASSEMBLY

Tested by [Signature] Date 9-21-79

Witness [Signature] Date 9-21-79

Sheet No. 1 of 1

Approved _____

INSTRUMENTATION EQUIPMENT SHEET

Date 9/21/79 Technician D. DUGAN Project BF3 CANNISTERS Test Area GIF, TA-2

Type Test SECONDARY CHECK OF RANGE METERS (480 AC)

No.	Instrument	Manufacturer	Model No.	Serial No.	Ident No.	Range	Accuracy	Calibration	
								On	Due
1	Power Analyzer	METROL	4410	8267	28885	C-52 A	±.5% 106π	7/12/79	7/12/79

Instrument Test Engineer _____ Checked & Received by _____



Sandia Laboratories

Albuquerque, New Mexico 87185

Standards Laboratory Certificate

ANALYZER POWER

Magtrol

Model No. 4610

Serial No. 8C67

Property No. 25098

Submitted by: Organization 4442

Certified: September 12, 1979

Expires: March 12, 1980

This instrument was tested and adjusted to meet the following accuracy specification:

$\pm 0.5\% \pm 1$ digit on all ranges and functions

Metrologist: W. W. Rowe, 2553

Certified by: G. F. McFall, 2553

WWR:2553:bh

Conditions of Certification. Neither Sandia Laboratories nor the Government assumes any responsibility with respect to the use of this document, the information contained therein, or the physical device or instrument certified, by any person other than the contractor to whom originally issued. Any such use will be at the sole risk and responsibility of such other user. If this document is issued to a Sandia Laboratories supplier, neither Sandia Laboratories nor the Government assumes any responsibility for the use of this document, the information contained therein, or the physical device or instrument certified at any time beyond the resubmittal date or any order or contract, other than the original contract, including future orders, which the certification is given.

DATA SHEET

Project BF3 CONNECTORS

Specimen 1, 2, 3 (250 VDC)

Part No 250 VDC

Ident. <u>SECONDARY</u>		<u>CHECK OF PANEL METERS</u>				Start Date <u>9/25/79</u>			
<u>LOAD</u>	<u>TIME (MIN)</u>	<u>MAGNET (250VDC)</u>		<u>DC SUPPLY</u>		<u>PANEL METER</u>		<u>DATA LOGGER (C1140)</u>	
		<u>VDC</u>	<u>AMPS</u>	<u>VOLTS</u>	<u>CURRENT</u>	<u>LINE</u>	<u>LOAD</u>	<u>VOLTS</u>	<u>CURRENT</u>
1	0	251	1.044	242	1.0	1.1	> 1	249	1.047
1	2	251	.990	242	.95	1.05	1.0	249	.999
1	4	251	.986	242	.95	1.05	1.0	249	.996
2	0	252	1.006	258	1.02	1.0	1.0	250	1.01
2	2	252	.994	258	1.02	1.0	1.0	250	1.005
2	4	252	.992	259	1.01	1.0	1.0	250	1.002
3	0	251	.987	253	.975	.975	.98	249	.98
3	2	252	.984	252	.975	.975	.98	249	.994
3	4	251	1.006	253	1.0	1.0	1.0	249	1.01

Remarks _____

Tested by [Signature] Date 9-24-79

Witness [Signature] Date 9-24-79

Sheet No. 1 of 1

Approved _____

INSTRUMENTATION EQUIPMENT SHEET

Date 9/25/79 Test Area GIF, 1A-V
 Technician D. DUGAN Project BF3 CONNECTORS Type Test SECONDARY CHECK OF
PANEL/LOGGER METERS (2500X)

No.	Instrument	Manufacturer	Model No.	Serial No.	Ident No.	Range	Accuracy	Calibration	
								On	Due
1.	POWER ANALYZER	MAGTRON	4610	8167	25C985	0-50A 0-60V (VOLTAGE)	+0.5%+1 DIGIT	9/12/79	3/12/79
2.	DATALOGGER	ACUREX	A901	1694	011409	TOTAL'S FUEL DONE ± 0.05% READING		9/14/79	3/14/79

Instrument Test Engineer _____ Checked & Received by _____



Sandia Laboratories

Albuquerque, New Mexico 87185

Standards Laboratory Certificate

DATALOGGER

Acurex

Model No. A901

Serial No. 1694

Property No. 011409

Submitted by: Organization 4442

Certified: September 14, 1979

Expires: March 14, 1980

This instrument was adjusted according to manufacturer's calibration procedure and was found to be within these specifications:

Voltage Measurements: $\pm 0.005\%$ of full scale $\pm 0.005\%$
of reading after one hour warmup

Metrologist: H. H. Pike, 2553

Certified by: G. F. McFall, 2553

HHP:2553:hh

Conditions of Certification: Neither Sandia Laboratories nor the Government assumes any responsibility with respect to the use of this document, the information contained therein, or the physical device or instrument certified by any person other than the individual to whom originally issued. Any such use will be at the sole risk and responsibility of such other user. If this document is issued to a Sandia Laboratories supplier, neither Sandia Laboratories nor the Government assumes any responsibility for the use of this document, the information contained therein, or the physical device or instrument certified at a time beyond the resubmittal date or any order or contract other than the original contract, including changes, which which the certification is given.

SECTION VIII
ACCIDENT TEST

Accident Test Procedure

All test items will be subject to an accident profile approximating the specified time, temperature, pressure conditions displayed in Figure 5 (A, B and C). The 250-VDC connector assemblies will be energized throughout the entire test. The 480-VAC connector assemblies will be energized only during the first 5 minutes, between minutes 15 and 18, and between minutes 57 and 60. (The energizing schedule is construed to imply that the connector assemblies are energized prior to introduction of the steam environment.)

The major features of the originally specified profile are:

- ramp to chamber conditions of 325°F (163°C), 55 psig, in approximately 2 minutes.
- maintain stabilized conditions for 5 minutes.
- at 7 minutes, reduce pressure to psig while holding temperature at 325°F (163°C).
- between minutes 7 and 30 reduce temperature to 304°F (151°C), while holding pressure at 30 psig.
- between minutes 30 and 75, reduce temperature to 283°F (139°C) and pressure to 20 psig.
- at 75 minutes, reduce temperature to 230°F (110°C) while holding pressure at 20 psig.
- reduce pressure and temperature at an average rate of 3.5°F/hour for 24 hours or until a chamber condition of 150°F (65°C) is attained.

Prior to tests of the connector assemblies, numerous pre-tests to determine capabilities of the autoclave system will be made. The best approximation to the specified profiles will be achieved and the data overplotted against the specified profiles. This best effort profile will be forwarded to NRC staff for review/concurrence before proceeding with the connector assemblies tests. Results and observations will be recorded on data sheets and supplemented with other pertinent documentation. To assure adequate repetition during the actual connector assemblies tests, the final procedures are to be documented as they evolve during the pre-test phase.

The actual adjustments of the pressure and temperature of the test chamber are to be accomplished by manually manipulating the superheater controls and pressure regulators in a systematic way.

FIGURE 5A

BROWNS FERRY UNIT 3 CONNECTORS





FIGURE 5B

BROWNS FERRY UNIT 3 CONNECTORS

WYLE
REPORT
43854-2
3/28/78

— SPECIFIED PROFILES
[○ TEMPERATURE DATA
[△ PRESSURE DATA

--- "BEST" REPRESENTATION




9/6/79

FIGURE 5C

BROWNS FERRY UNIT 3
CONNECTORS

WYLE
REPORT
43854-2
3/29/78

— SPECIFIED PROFILES
 [\odot TEMPERATURE DATA
 [Δ PRESSURE DATA
 --- "BEST" REPRESENTATION



LXP 9/10/78

All test items will be subject to an accident profile approximating the specified time, temperature, pressure conditions displayed in Figure 5. Also shown in Figures 5A, B, and C is the final NRC-specified enveloping profile for temperature and its $\pm 6^{\circ}\text{C}$ error band. This, along with the actual pressure profile with its ± 5 psig error band, constitute the desired accident test signature. These profiles were developed from NRC staff letters:

- (1) June 22, 1979, Murley to Schroeder and Eisenhut, "Commission-Requested Connector Tests"
- (2) August 1, 1979, Schroeder and Eisenhut to Murley, "Commission-Requested Connector Tests"

Following formal NRC approval of the achievable test chamber conditions, the connector assemblies will be installed in the test chamber. (To make electrical connection through the test chamber seals, Anaconda 3/c #12 nuclear grade cable may be butt spliced to the connector assembly and the splices covered with Raychem nuclear grade (WCSF-series) heat shrink tubing.) Circuit continuity and circuit resistance tests will then be performed with the assemblies installed in the test chamber. The assemblies will be instrumented to measure and record voltage and current; the test chamber will be instrumented with temperature and pressure sensors. Periodic measurements of all parameters will be made during the accident test phase.

During the environmental exposure of the connector assemblies the specimens and environment temperatures will be periodically monitored and recorded and the connectors will be powered with their operating voltage/current loads as described above. Failure to carry the required voltage/current loads will be considered as failure of the assembly.

After achieving the 150°F (65°C) condition, the test chamber will be opened and the connector assemblies removed for examination.

DATA SHEET

Project BF3 CONNECTORS

Specimen ALL

Part No _____

Ident. PRE-ACCIDENT TEST AUTOClave
DEMONSTRATIONS

Start Date 10/29-30/79

AS REQUIRED BY THE TEST PROCEDURES, DEMONSTRATION
RUNS WERE MADE TO VERIFY THE CAPABILITIES
TO ACHIEVE THE DESIRED PRESSURE/TEMPERATURE
PROFILES.

TWO OF THESE ARE SHOWN IN THE ATTACHMENTS
OF TABULATED DATA AND PRESSURE-RISE CURVES DATED
10/29 and 10/30/79.

THESE TESTS WERE WITNESSED BY R. FET,
M. CHIRAMAL, AND J. ZWILINSKI OF THE ARC.

Remarks _____

Tested by Al Buzyn Date 10/31/79

Witness Ronald F. Fet Date 10/31/79

Sheet No. 1 of 1

Approved _____

PREPARED BY <u>LB</u>	DWG CLASSIFICATION LEVEL (If class, also show category of information. If not line through this block)	PAGE NO. <u>01</u>
CHECKED BY	<u>GENERALIZED SKETCH OF</u>	<u>EFS CONNECTOR</u> REPORT NO.
DATE	<u>TEST CHAMBER AND CONTENTS</u>	MODEL NO.

STEAM INPUT

HIGH PRESSURE GAUGE

STEAM BAFFLE

EXITING CONNECTOR LEADS

CONNECTOR

MIDBANK

BAFFLE PLATE

1, 2

3, 4, 5

6, 7, 8

20

21

22

THERMOCOUPLE POSITIONS

1+2 INLINE STEAM

3, 4, +5 NEAR BASE OF CANS

6, 7, +8 MIDWAY (17 1/2") BETWEEN CANS AND BAFFLE PLATE

20 ATTACHED TO DUMMY CONNECTOR MASS

21 IN FREE SPACE AT TOP OF CONNECTOR CAN

22 IN FREE SPACE AT TOP OF CONNECTOR CAN

IN TABULATED DATA

LABELLED AS POSITION	TC'S AT THIS POSITION
1	1+2
2	20
3	21
4	22
5	3, 4, +5
6	6, 7, +8

DWG CLASSIFICATION LEVEL

10/26/79


15-26-74 15 min

Time	Temperature °C					FREE + FIED		Pressure
m.s. min	P01.1	P01.2	P01.3	P01.4	P01.5	P01.6	P01.9	P01.9 Pressure
0:05	59	59	58	54	64-69-64	69-64-64	49	0.0 [6.12]
0:20	4	91	71	73	67-65-64	76-74-74	49	0.0 [6.12]
0:26	142	148	144	128	141-141-144	142-144-145	113	10.8 [11.1]
0:40	215	156	151	145	156-152	151-151-152	138	6.0 [12.1]
1:00	201-226	153	152	144	153-152	162-163-166	148	6.0 [12.1]
1:20	241-237	153	154	151	142-154	164-168-167	127	5.5 [12.1]
1:40	244-239	151	154	149	164-157	170-168-169	151	5.5 [12.1]
2:00	241-235	156	158	154	163-159	170-164-170	153	5.5 [12.1]
2:20	236-231	157	161	159	166-162	172-171-172	152	5.5
2:40	236-230	156	162	161	166-164	170-164-171	150	5.5
3:00	231-225	157	168	164	164-165	171-170-171	150	5.5 [12.1]
4:00	224-220	156	170	166	162-162	169-167-168	150	5.5 [12.1]
5:00	222-217	157	174	168	168-164	169-166-168	150	5.5 [12.1]
6:00	212-207	158	176	173	168-166	170-168-169	150	5.5 [12.1]
7:00	203-200	157	177	176	166-167	170-168-170	151	5.5 [12.1]
8:00	196-192	156	178	177	166-166	169-164-169	150	5.5 [12.1]
9:00	190-188	155	177	176	166-166	167-167-168	149	4.9 [12.1]
10:00	188-186	154	176	175	165-165	167-167-167	150	4.7 [12.1]
11:00	182-180	150	173	173	163-165	165-165-165	152	4.0 [12.1]
12:00	176-175	149	171	171	162-162	164-163-164	154	4.0 [12.1]
13:00	182-180	144	169	169	162-163	164-164-165	155	3.8 [12.1]
14:00	185-184	144	170	170	162-163	164-164-164	156	2.4 [12.1]
20:00	172-172	144	169	170	162-162	163-163-163	157	2.7 [12.1]
22:00	172-175	144	167	168	162-160	161-161-162	157	2.6 [12.1]
24:00	181-179	150	167	167	162-162	163-162-162	158	2.5 [12.1]
26:00	179-172	151	167	167	162-162	161-161-162	158	2.4 [12.1]
28:00	164-168	151	165	166	160-160	160-164-160	158	2.0 [12.1]
30:00	181-178	150	163	163	154-154	154-154-154	157	2.0 [12.1]
	TC 1.2	TC 2.0	TC 2.1	TC 2.2	TC 4.1	TC 6.1-8	TC 9	

Chamber Given 10 minute skin pre heat T(0) = 50°C @ 10 min, T(0) = 81°C @ 23 min
 Chamber given additional 8 minutes pre heat

Ramp procedure same as 10-26-74 test

10-70-74 1000									
Time	Temperature °C					FREE FIELD		CHART	REMARKS
Min-Sec	Pos 1	Pos 2	Pos 3	Pos 4	Pos 5	Pos 6	Pos 7	Scale	Notes
0:00	52-58	58	84	84	65-65	69-69-69	91	0.0	65-0.0
1:00	52-66	102	84	84	64-67	74-74-73	91	0.0	65-0.0
2:20	149-144	149	146	140	144-143	142-146-147	115	45	65-0.0
3:40	205-169	152	181	187	187-187	188-187-160	147	60	100-50
4:00	218-219	153	184	181	181-181	184-184-165	150	60	117-50
5:20	223-217	153	186	183	183-186	184-187-160	151	60	135-50
6:40	222-216	150	185	183	184-185	188-180-171	152	60	150-50
8:00	221-214	151	185	181	182-183	187-185-169	150	55	167-50
9:20	218-212	152	186	183	183-183	188-188-170	149	55	
10:40	215-211	154	184	187	186-185	189-188-170	150	55	
12:00	218-209	154	184	184	181-183	188-187-168	150	55	167-50
13:20	207-202	185	182	182	181-183	187-188-167	150	55	167-50
14:40	200-196	186	188	185	188-183	188-188-167	150	55	167-50
16:00	194-191	187	170	189	182-182	186-185-166	150	58	167-50
17:20	192-190	187	171	181	182-182	188-186-167	157	58	167-50
18:40	212-188	188	174	173	188-187	171-171-173	150	56	167-50
20:00	208-205	188	177	175	188-187	171-170-170	150	52	167-50
21:20	205-206	188	179	188	188-187	170-170-170	151	50	167-49
22:40	199-191	189	179	177	188-187	188-188-168	153	40	167-40
24:00	198-196	188	176	175	187-186	186-186-166	155	35	167-35
25:20	196-194	181	176	175	187-186	187-187-167	156	30	167-30
26:40	188-186	187	175	175	186-185	188-186-166	157	28	167-28
28:00	180-178	181	173	173	184-184	184-184-164	157	27	167-27
29:20	172-171	180	170	171	187-186	186-186-166	157	25.5	167-26
30:40	168-167	180	167	167	181-181	180-180-160	157	25.0	167-25
32:00	181-179	187	166	166	181-181	181-181-161	157	24.5	160-24.5
33:20	172-175	189	166	166	181-181	180-180-161	157	24.0	154-24
34:40	171-170	181	164	165	180-189	189-189-189	157	24.0	154-24
36:00	TC-182	TC-20	TC-31	TC-42	TC-48.5	TC-6-7-8	TC-9		
Repeat of 10-74-74 1000									
Same chamber present									
Same sample - no procedure									
Chamber head removed & replaced prior to test									



INSTRUMENTATION EQUIPMENT SHEET

Date 10/29-30/79

Technician D. DUGAN

Test Area GIF, TA-V

Project PF3 CUMMICK'S

Type Test PRE-ACCIDENT TEST

AUTOCALVE DEMONSTRATIONS

No.	Instrument	Manufacturer	Model No.	Serial No.	Ident No.	Range	Accuracy	Calibration	
								On	Due
1	PRESSURE GAUGE	HEISE		29155		0-150 PSI	$\pm 0.1\%$	5/6/79	5/6/80
2	DATACORDER	ACORN	A901	1694	011409	$\pm 10\%$ 0-100 PSI	$\pm 0.005\%$ $\pm 0.005\%$	9/4/77	3/4/80

Instrument Test Engineer _____

Checked & Received by _____

DATA SHEET

Project B-1 - Controls

Specimen A11

Part No _____

Ident. _____

Start Date 10-31-79

Part 1 continuity check of all connectors

AC Connectors

continuity - terminals

opens - terminals

#1 10-14, 9-12

10-(9 & 12); 14-(9 & 12)

#2 10-14, 9-12

10-(9 & 12); 14-(9 & 12)

#3 10-14, 9-12

10-(9 & 12); 14-(9 & 12)

DC Connectors

continuity

open

#1 7-9; 8-10

7-(8 & 10); 9-(8 & 10)

#2 7-9; 8-10

7-(8 & 10); 9-(8 & 10)

#3 7-9; 8-10

7-(8 & 10); 9-(8 & 10)

Remarks _____

Tested by [Signature] Date 10-31-79

Witness W. H. Binkley Date 10-31-79

Sheet No. 1 of 1

Approved _____

SANDIA LABORATORIES
STANDARDS LAB

File 5699E

DATE 5/9/79 EXPIRES 5/31/80

2551 4442

S/N 29155
See Certificate



Sandia Laboratories

Albuquerque, New Mexico 87115

laboratory Certificate

File No. 5699E

PRESSURE GAUGE
Heise
Serial No. 29155
P/N S-

Submitted by: Organization 4442

Date Calibrated: May 9, 1979
Expires: May 31, 1980

Reference Pressure psig	Gauge Reading psig
0.00	0.00
14.98	14.90
29.97	30.00
44.95	45.30
59.93	60.00
74.92	74.80
89.90	89.90
104.89	105.00
119.87	119.90
134.85	134.90
149.84	149.95

When corrections are applied, it is estimated that the error in the above gauge is no greater than $\pm 0.1\%$ of full scale.

Technical Consultant: H. L. Myers, 2551

Certified by: J. L. Hartley, 2551

Copy to:
Organization 4442 (2)
2551 File

Conditions of Certification. Neither Sandia Laboratories nor the Government assumes any responsibility with respect to the use of this document, the information contained therein, or the physical device or instrument certified, by any person other than the contractor to whom originally issued. Any such use will be at the sole risk and responsibility of such other user.

If this document is issued to a Sandia Laboratories supplier, neither Sandia Laboratories nor the Government assumes any responsibility for the use of this document, the information contained therein, or the physical device or instrument certified, at any time beyond the resubmittal date or any order or contract other than the order or contract, including changes, under which the certification is given.

In no case will Sandia Laboratories or the Government assume responsibility for consequential damages. SA 5710 DA19 721



Sandia Laboratories

Albuquerque, New Mexico 87185

Standards Laboratory Certificate

DATALOGGER

Acurex

Model No. A901

Serial No. 1694

Property No. 011409

Submitted by: Organization 4442

Certified: September 14, 1979

Expires: March 14, 1980

This instrument was adjusted according to manufacturer's calibration procedure and was found to be within these specifications:

Voltage Measurements: $\pm 0.005\%$ of full scale $\pm 0.005\%$
of reading after one hour warmup

Metrologist: H. H. Pike, 2553

Certified by: G. E. McFall, 2553

HHP:2553:bb

Conditions of Certification. Neither Sandia Laboratories nor the Government assumes any responsibility with respect to the use of this document, the information contained therein, or the physical device or instrument certified, by any person other than the contractor to whom originally issued. Any such use will be at the sole risk and responsibility of such other user.

If this document is issued to a Sandia Laboratories supplier, neither Sandia Laboratories nor the Government assumes any responsibility for the use of this document, the information contained therein, or the physical device or instrument certified, at any time beyond the resubmittal date of any order or contract other than the order or contract, including changes, under which the certification is given.

DATA SHEET

Project BF3 CONNECTORS

Specimen ALL

Part No. _____

Ident. ACCIDENT TEST / DATA

Start Date 11/1/79

THE (33) DATA SHEETS DESCRIBE THE
TEST DATA AND CONNECTOR ASSEMBLIES
PERFORMANCE. THE THERMOCOUPLE READINGS
ARE THOSE AT POSITION #6 (TC's 6, 7 & 8)
AGREED TO BY USNRC STAFF.

ALL CONNECTOR ASSEMBLIES REMAINED
FUNCTIONAL THROUGHOUT THE TEST.

Remarks _____

Tested by L. Beyer Date 11/2/79

Witness _____ Date _____

Sheet No. 1 of 1

Approved _____

Date 11-1-79

DATA SHEET--ACCIDENT SIMULATION
BF3 CONNECTOR ASSEMBLIES: 1, 2, 3, 7, 8, 9

Time 0:01 hours $T_0 - 1 \text{ min}$
Chamber Environments: Temperature 63-62-63 °C
Pressure 0.0 psig
Test Items: Assembly
1 250.0 volts 1.0016 amps LOAD 1/2
2 249.7 volts 1.007 amps
3 249.6 volts 1.0134 amps
7 volts 17.4/17.1 amps
8 volts 17.4/16.9 amps
9 volts 17.4/16.5 amps

Time 0:01 hours $T_0 + 1 \text{ min}$
Chamber Environments: Temperature 153-141-153 °C
Pressure 0.0 psig
Test Items: Assembly
1 250.0 volts 1.9957 amps
2 249.8 volts 1.002 amps
3 249.3 volts 1.0161 amps
7 volts 17.4/17.1 amps
8 volts 16.6/17.0 amps
9 volts 17.1/16.5 amps

Time 0:02 hours $T_0 + 2 \text{ min}$
Chamber Environments: Temperature 170-170-169 °C
Pressure 55 psig
Test Items: Assembly
1 250.0 volts 1.9998 amps
2 249.6 volts 1.0010 amps
3 249.3 volts 1.0149 amps
7 volts 17.4/17.1 amps
8 volts 16.7/17.0 amps
9 volts 17.4/16.5 amps

Remarks: _____
Recorded by W. H. Gunkler
Witnessed by 580
Sheet No. 1 of 33

Date 11-1-79DATA SHEET--ACCIDENT SIMULATION
BF3 CONNECTOR ASSEMBLIES: 1, 2, 3, 7, 8, 9Time 0103 hours T₀+3 minChamber Environments: Temperature 169-169-170 °CPressure 55 psig

Test Items: Assembly

1	<u>250.0</u> volts	<u>.9937</u> amps
2	<u>244.6</u> volts	<u>1.0001</u> amps
3	<u>249.2</u> volts	<u>1.014</u> amps
7	_____ volts	<u>17.0/17.1</u> amps
8	_____ volts	<u>16.8/17.0</u> amps
9	_____ volts	<u>17.4/16.6</u> amps

Time 0104 hours T₀+4 minChamber Environments: Temperature 161-167-167 °CPressure 55.0 psig

Test Items: Assembly

1	<u>250.0</u> volts	<u>.9936</u> amps
2	<u>244.7</u> volts	<u>.9997</u> amps
3	<u>249.2</u> volts	<u>1.0134</u> amps
7	_____ volts	<u>17.4/17.2</u> amps
8	_____ volts	<u>16.6/17.0</u> amps
9	_____ volts	<u>17.4/16.5</u> amps

Time 01045 hours T₀+4.5 minChamber Environments: Temperature 167-167-168 °CPressure 56.0 psig

Test Items: Assembly

1	<u>250.1</u> volts	<u>.9931</u> amps
2	<u>244.6</u> volts	<u>.9994</u> amps
3	<u>249.3</u> volts	<u>1.0139</u> amps
7	_____ volts	<u>17.4/17.1</u> amps
8	_____ volts	<u>16.6/17.0</u> amps
9	_____ volts	<u>17.4/16.1</u> amps

Remarks: _____

Recorded by W.H. BenkelmanWitnessed by SRSheet No. 2 of 33

Date 11-1-74

DATA SHEET--ACCIDENT SIMULATION
BF3 CONNECTOR ASSEMBLIES: 1, 2, 3, 7, 8, 9

Time 0:05 hours 7.5 minChamber Environments: Temperature 167-168-170 °CPressure 56 psig

Test Items: Assembly

1	<u>250.0</u> volts	<u>.9933</u> amps
2	<u>249.6</u> volts	<u>.9992</u> amps
3	<u>244.2</u> volts	<u>1.0129</u> amps
7	<u> </u> volts	<u> </u> amps
8	<u> </u> volts	<u> </u> amps
9	<u> </u> volts	<u> </u> amps

Time 0:06 hours 7.6 minChamber Environments: Temperature 168-168-168 °CPressure 55.0 psig

Test Items: Assembly

1	<u>250.1</u> volts	<u>.9931</u> amps
2	<u>249.6</u> volts	<u>.9991</u> amps
3	<u>244.2</u> volts	<u>1.0125</u> amps
7	<u> </u> volts	<u> </u> amps
8	<u> </u> volts	<u> </u> amps
9	<u> </u> volts	<u> </u> amps

Time 0:07 hours 7.7 minChamber Environments: Temperature 167-168-168 °CPressure 55.0 psig

Test Items: Assembly

1	<u>250.0</u> volts	<u>.9933</u> amps
2	<u>249.6</u> volts	<u>.9994</u> amps
3	<u>244.3</u> volts	<u>1.0125</u> amps
7	<u> </u> volts	<u> </u> amps
8	<u> </u> volts	<u> </u> amps
9	<u> </u> volts	<u> </u> amps

Remarks: _____

Recorded by W. H. GaudinWitnessed by SRSheet No. 3 of 33

Date 11-1-79

DATA SHEET--ACCIDENT SIMULATION
BF3 CONNECTOR ASSEMBLIES: 1, 2, 3, 7, 8, 9

Time 0:05 hours $T_0 + 8 \text{ min}$
 Chamber Environments: Temperature 167-167-167 °C
 Pressure 52.0 psig

Test Items: Assembly

1	<u>250.0</u> volts	<u>.9931</u> amps
2	<u>249.6</u> volts	<u>.9988</u> amps
3	<u>249.2</u> volts	<u>1.0124</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Time 0:09 hours $T_0 + 9 \text{ min}$
 Chamber Environments: Temperature 167-168-167 °C
 Pressure 52.0 psig

Test Items: Assembly

1	<u>250.2</u> volts	<u>.9929</u> amps
2	<u>249.7</u> volts	<u>.9988</u> amps
3	<u>249.2</u> volts	<u>1.0124</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Time 0:10 hours $T_0 + 10 \text{ min}$
 Chamber Environments: Temperature 166-166-166 °C
 Pressure 49.0 psig

Test Items: Assembly

1	<u>250.0</u> volts	<u>.9927</u> amps
2	<u>249.7</u> volts	<u>.9988</u> amps
3	<u>249.2</u> volts	<u>1.0123</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Remarks: _____

Recorded by W. H. BrubakerWitnessed by SDSheet No. 4 of 33

Date 11-1-79DATA SHEET--ACCIDENT SIMULATION
BF3 CONNECTOR ASSEMBLIES: 1, 2, 3, 7, 8, 9

Time 0:15 hours T₀ + 15 min
Chamber Environments: Temperature 163.163-164 °C
Pressure 37.5 psig
Test Items: Assembly
1 250.1 volts .9944 amps
2 249.7 volts .9985 amps
3 249.3 volts 1.0123 amps
7 _____ volts 17.6/17.5 amps
8 _____ volts 17.1/17.2 amps
9 _____ volts 17.6/16.5 amps

Time 0:16 hours T₀ + 16 min
Chamber Environments: Temperature 163.163-164 °C
Pressure 35.0 psig
Test Items: Assembly
1 250.1 volts .9942 amps
2 249.7 volts .9986 amps
3 249.2 volts 1.0123 amps
7 _____ volts 17.5/17.4 amps
8 _____ volts 16.9/17.0 amps
9 _____ volts 17.4/16.5 amps

Time 0:17 hours T₀ + 17 min
Chamber Environments: Temperature 164.164-164 °C
Pressure 30.0 psig
Test Items: Assembly
1 250.1 volts .9944 amps
2 249.7 volts .9944 amps
3 249.3 volts 1.0126 amps
7 _____ volts 17.5/17.4 amps
8 _____ volts 16.9/17.0 amps
9 _____ volts 17.0/16.5 amps

Remarks: _____

Recorded by W.H. BuchlerWitnessed by SKSheet No. 5 of 23

Date 11-1-79

DATA SHEET--ACCIDENT SIMULATION
BFB CONNECTOR ASSEMBLIES: 1, 2, 3, 7, 8, 9

Time 0:175 hours T₀ + 17.5"
 Chamber Environments: Temperature 165-165-165 °C
 Pressure 30.0 psig

Test Items: Assembly

1	<u>250.1</u> volts	<u>.9944</u> amps
2	<u>244.6</u> volts	<u>.9982</u> amps
3	<u>244.2</u> volts	<u>1.0123</u> amps
7	_____ volts	<u>17.5/17.2</u> amps
8	_____ volts	<u>16.9/16.9</u> amps
9	_____ volts	<u>17.4/16.5</u> amps

Time 0:18 hours T₀ + 18 min
 Chamber Environments: Temperature 165-165-165 °C
 Pressure 29.0 psig

Test Items: Assembly

1	<u>250.0</u> volts	<u>.9943</u> amps
2	<u>244.7</u> volts	<u>.9982</u> amps
3	<u>244.3</u> volts	<u>1.0124</u> amps
7	_____ volts	_____ amps
8	_____ volts	_____ amps
9	_____ volts	_____ amps

Time 0:20 hours T₀ + 20 min
 Chamber Environments: Temperature 162-162-162 °C
 Pressure 27.0 psig

Test Items: Assembly

1	<u>250.1</u> volts	<u>.9944</u> amps
2	<u>244.7</u> volts	<u>.9985</u> amps
3	<u>244.3</u> volts	<u>1.0123</u> amps
7	_____ volts	_____ amps
8	_____ volts	_____ amps
9	_____ volts	_____ amps

Remarks: _____

Recorded by W.H. BenfanteWitnessed by Y.D.Sheet No. 6 of 33

Date 1-1-79

DATA SHEET--ACCIDENT SIMULATION
BF3 CONNECTOR ASSEMBLIES: 1, 2, 3, 7, 8, 9

Time 01:45 hours T₀ + 25 min
 Chamber Environments: Temperature 161-167-161 °C
 Pressure 25.0 psig

Test Items: Assembly

1	<u>250.1</u> volts	<u>.9946</u> amps
2	<u>249.7</u> volts	<u>.9986</u> amps
3	<u>249.3</u> volts	<u>1.0145</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Time 01:50 hours T₀ + 30 min
 Chamber Environments: Temperature 159-159-162 °C
 Pressure 24.0 psig

Test Items: Assembly

1	<u>250.1</u> volts	<u>.9946</u> amps
2	<u>249.7</u> volts	<u>.9983</u> amps
3	<u>249.3</u> volts	<u>1.0113</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Time 01:55 hours T₀ + 35 min
 Chamber Environments: Temperature 156-156-157 °C
 Pressure 23.5 psig

Test Items: Assembly

1	<u>250.1</u> volts	<u>.9950</u> amps
2	<u>249.7</u> volts	<u>.9989</u> amps
3	<u>249.4</u> volts	<u>1.0145</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Remarks: _____

Recorded by W.H. Burkholder
 Witnessed by SR
 Sheet No. 7 of 33

Date 10-22-72

DATA SHEET--ACCIDENT SIMULATION
BF3 CONNECTOR ASSEMBLIES: 1, 2, 3, 7, 8, 9

Time 0140 hours $T_0 + 40 \text{ min}$
 Chamber Environments: Temperature 150.58-151.0 °C
 Pressure 21.0 psig

Test Items: Assembly

1	<u>210.0</u> volts	<u>.9944</u> amps
2	<u>249.7</u> volts	<u>.9988</u> amps
3	<u>249.3</u> volts	<u>1.0128</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Time 0145 hours $T_0 + 45 \text{ min}$
 Chamber Environments: Temperature 150.56-151.0 °C
 Pressure 20.0 psig

Test Items: Assembly

1	<u>250.1</u> volts	<u>.9944</u> amps
2	<u>249.7</u> volts	<u>.9988</u> amps
3	<u>249.4</u> volts	<u>1.0129</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Time 0150 hours $T_0 + 50 \text{ min}$
 Chamber Environments: Temperature 151.01-151.2 °C
 Pressure 17.5 psig

Test Items: Assembly

1	<u>250.2</u> volts	<u>.9950</u> amps
2	<u>249.7</u> volts	<u>.9988</u> amps
3	<u>249.4</u> volts	<u>1.0130</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Remarks: _____

Recorded by W. H. G. and New
 Witnessed by ADJ
 Sheet No. 6 of 33

Date 11-1-74

DATA SHEET--ACCIDENT SIMULATION
BF3 CONNECTOR ASSEMBLIES: 1, 2, 3, 7, 8, 9

Time 0.55 hours $T_0 + 55$ min
Chamber Environments: Temperature 152-152-153 °C
Pressure 15.0 psig

Test Items: Assembly

1	<u>252.4</u> volts	<u>1.9951</u> amps
2	<u>244.7</u> volts	<u>1.9947</u> amps
3	<u>244.8</u> volts	<u>1.9919</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Time 0.57 hours $T_0 + 57$ min
Chamber Environments: Temperature 150-150-151 °C
Pressure 14.0 psig

Test Items: Assembly

1	<u>244.4</u> volts	<u>1.9944</u> amps
2	<u>244.7</u> volts	<u>1.9923</u> amps
3	<u>244.8</u> volts	<u>1.9929</u> amps
7	<u>/</u> volts	<u>17.5/17.5</u> amps
8	<u>/</u> volts	<u>17.0/17.1</u> amps
9	<u>/</u> volts	<u>17.5/17.4</u> amps

Time 0.58 hours $T_0 + 58$ min
Chamber Environments: Temperature 144-144-144 °C
Pressure 14.0 psig

Test Items: Assembly

1	<u>252.4</u> volts	<u>1.9950</u> amps
2	<u>244.7</u> volts	<u>1.9944</u> amps
3	<u>244.8</u> volts	<u>1.9919</u> amps
7	<u>/</u> volts	<u>17.5/17.4</u> amps
8	<u>/</u> volts	<u>16.9/17.0</u> amps
9	<u>/</u> volts	<u>17.4/17.5</u> amps

Remarks: _____

Recorded by W. H. Buehler
Witnessed by [Signature]
Sheet No. 9 of 33

Date 11-1-79

DATA SHEET--ACCIDENT SIMULATION
BF3 CONNECTOR ASSEMBLIES: 1, 2, 3, 7, 8, 9

Time 0159 hours $T_0 + 59$
Chamber Environments: Temperature 144-149-149 °C
Pressure 14.0 psig

Test Items: Assembly

1	<u>250.3</u> volts	<u>.9450</u> amps
2	<u>244.7</u> volts	<u>.9486</u> amps
3	<u>244.4</u> volts	<u>1.0128</u> amps
7	_____ volts	<u>17.4/17.4</u> amps
8	_____ volts	<u>16.7/17.0</u> amps
9	_____ volts	<u>17.4/16.5</u> amps

Time 0159.5 hours $T_0 + 59.5 \text{ min}$
Chamber Environments: Temperature 144-149-149 °C
Pressure 14.0 psig

Test Items: Assembly

1	_____ volts	_____ amps
2	_____ volts	_____ amps
3	_____ volts	_____ amps
7	_____ volts	<u>17.4/17.1</u> amps
8	_____ volts	<u>16.6/17.0</u> amps
9	_____ volts	<u>17.4/16.5</u> amps

Time 1.00 hours
Chamber Environments: Temperature 144-149-150 °C
Pressure 14.0 psig

Test Items: Assembly

1	<u>250.2</u> volts	<u>.9999</u> amps
2	<u>244.7</u> volts	<u>.9985</u> amps
3	<u>244.4</u> volts	<u>1.0128</u> amps
7	_____ volts	_____ amps
8	_____ volts	_____ amps
9	_____ volts	_____ amps

Remarks: _____

Recorded by W.H. Benschke
Witnessed by DT
Sheet No. 10 of 33

Date 11-1-79

DATA SHEET--ACCIDENT SIMULATION
BPS CONNECTOR ASSEMBLIES: 1, 2, 3, 7, 8, 9

Time 1:10 hours
Chamber Environments: Temperature 145-144 °C
Pressure 15.0 psig
Test Items: Assembly
1 250.2 volts .9998 amps
2 249.7 volts .9984 amps
3 249.4 volts 1.0129 amps
7 volts amps
8 volts amps
9 volts amps

Time 1:20 hours
Chamber Environments: Temperature 142-142-146 °C
Pressure 17.0 psig
Test Items: Assembly
1 250.2 volts .9999 amps
2 249.7 volts .9984 amps
3 249.5 volts 1.0129 amps
7 volts amps
8 volts amps
9 volts amps

Time 1:30 hours
Chamber Environments: Temperature 135-135-135 °C
Pressure 15 psig
Test Items: Assembly
1 250.2 volts .9946 amps
2 249.7 volts .9983 amps
3 249.5 volts 1.0131 amps
7 volts amps
8 volts amps
9 volts amps

Remarks: _____

Recorded by W. H. Bentley
Witnessed by W. H. Bentley
Sheet No. 11 of 833

Date 11-1-79DATA SHEET--ACCIDENT SIMULATION
BF3 CONNECTOR ASSEMBLIES: 1, 2, 3, 7, 8, 9

Time 1.40 hours
Chamber Environments: Temperature 123-125-124 °C
Pressure 14 psig

Test Items: Assembly

1	<u>210.4</u> volts	<u>.9946</u> amps
2	<u>244.7</u> volts	<u>.9890</u> amps
3	<u>244.4</u> volts	<u>1.0121</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Time 1.50 hours
Chamber Environments: Temperature 113-121-143 °C
Pressure 9.0 psig

Test Items: Assembly

1	<u>210.4</u> volts	<u>.9944</u> amps
2	<u>244.9</u> volts	<u>.9990</u> amps
3	<u>244.0</u> volts	<u>1.0131</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Time 2.00 hours
Chamber Environments: Temperature 118-117-117 °C
Pressure 5.0 psig

Test Items: Assembly

1	<u>210.4</u> volts	<u>.9944</u> amps
2	<u>244.7</u> volts	<u>.9889</u> amps
3	<u>244.5</u> volts	<u>1.0121</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Remarks: 1.40 1.50 2.00 2.20 2.40 2.60Recorded by W. H. SmithWitnessed W. H. SmithSheet No. 2 of 33

Date 11-1-74

DATA SHEET--ACCIDENT SIMULATION
BF3 CONNECTOR ASSEMBLIES: 1, 2, 3, 7, 8, 9

Time 2:10 hours
Chamber Environments: Temperature 113.1-114.1 °C
Pressure 5.0 psig
Test Items: Assembly
1 250.2 volts .4444 amps
2 244.7 volts .4444 amps
3 244.1 volts 1.0122 amps
7 _____ volts _____ amps
8 _____ volts _____ amps
9 _____ volts _____ amps

Time 2:20 hours
Chamber Environments: Temperature 112.1-113.1 °C
Pressure 6.0 psig
Test Items: Assembly
1 250.2 volts .4444 amps
2 244.7 volts .4444 amps
3 244.1 volts 1.0131 amps
7 _____ volts _____ amps
8 _____ volts _____ amps
9 _____ volts _____ amps

Time 2:40 hours
Chamber Environments: Temperature 109.1-109.1 °C
Pressure 7.0 psig
Test Items: Assembly
1 250.2 volts .4440 amps
2 244.7 volts .4444 amps
3 244.6 volts 1.0132 amps
7 _____ volts _____ amps
8 _____ volts _____ amps
9 _____ volts _____ amps

Remarks: _____

Recorded by W. A. [Signature]
Witnessed by [Signature]
Sheet No. 13 of 33

Date 11-79DATA SHEET--ACCIDENT SIMULATION
BF3 CONNECTOR ASSEMBLIES: 1, 2, 3, 7, 8, 9

Time 2:50 hours
Chamber Environments: Temperature 109-109.1W °C
Pressure 7.0 psig

Test Items: Assembly

1	<u>250.3</u> volts	<u>.9996</u> amps
2	<u>244.4</u> volts	<u>.9984</u> amps
3	<u>244.6</u> volts	<u>1.0132</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Time 3:00 hours
Chamber Environments: Temperature 109-109.1W °C
Pressure 7.0 psig

Test Items: Assembly

1	<u>250.4</u> volts	<u>.9947</u> amps
2	<u>244.7</u> volts	<u>.9989</u> amps
3	<u>244.5</u> volts	<u>1.0133</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Time 3:10 hours
Chamber Environments: Temperature 107-107.42 °C
Pressure 6.5 psig

Test Items: Assembly

1	<u>250.2</u> volts	<u>.9948</u> amps
2	<u>244.7</u> volts	<u>.9988</u> amps
3	<u>244.5</u> volts	<u>1.0121</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Remarks: _____

Recorded by W. H. HantleyWitnessed by W. H. HantleySheet No. 7 of 33

Date _____

DATA SHEET--ACCIDENT SIMULATION
BF3 CONNECTOR ASSEMBLIES: 1, 2, 3, 7, 8, 9

Time 2:20 hours
Chamber Environments: Temperature 108-107-106 °C
Pressure 6.5 psig

Test Items: Assembly

1	<u>250.3</u> volts	<u>.9949</u> amps
2	<u>244.4</u> volts	<u>.9989</u> amps
3	<u>244.0</u> volts	<u>1.0133</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Time 3:20 hours
Chamber Environments: Temperature 106-105-106 °C
Pressure 6.5 psig

Test Items: Assembly

1	<u>250.3</u> volts	<u>.9949</u> amps
2	<u>244.7</u> volts	<u>.9988</u> amps
3	<u>244.5</u> volts	<u>1.0133</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Time 3:40 hours
Chamber Environments: Temperature 106-105-105 °C
Pressure 6.5 psig

Test Items: Assembly

1	<u>250.2</u> volts	<u>.9947</u> amps
2	<u>244.7</u> volts	<u>.9989</u> amps
3	<u>244.0</u> volts	<u>1.0134</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Remarks: _____

Recorded by [Signature]
Witnessed by [Signature]
Sheet No. _____ of 033

Date 11-1-79

DATA SHEET--ACCIDENT SIMULATION
BF3 CONNECTOR ASSEMBLIES: 1, 2, 3, 7, 8, 9

Time 4.00 hours
Chamber Environments: Temperature 103-102-103 °C
Pressure 3.2 psig

Test Items: Assembly

1	<u>250.2</u> volts	<u>.9447</u> amps
2	<u>244.7</u> volts	<u>.9486</u> amps
3	<u>244.7</u> volts	<u>1.0135</u> amps
7	<u> </u> volts	<u> </u> amps
8	<u> </u> volts	<u> </u> amps
9	<u> </u> volts	<u> </u> amps

Time 4.10 hours
Chamber Environments: Temperature 104-103-104 °C
Pressure 3.5 psig

Test Items: Assembly

1	<u>250.3</u> volts	<u>.9444</u> amps
2	<u>244.7</u> volts	<u>.9487</u> amps
3	<u>244.5</u> volts	<u>1.0132</u> amps
7	<u> </u> volts	<u> </u> amps
8	<u> </u> volts	<u> </u> amps
9	<u> </u> volts	<u> </u> amps

Time 4.20 hours
Chamber Environments: Temperature 105-103-105 °C
Pressure 3.4 psig

Test Items: Assembly

1	<u>250.1</u> volts	<u>.9451</u> amps
2	<u>244.4</u> volts	<u>.9491</u> amps
3	<u>244.5</u> volts	<u>1.0135</u> amps
7	<u> </u> volts	<u> </u> amps
8	<u> </u> volts	<u> </u> amps
9	<u> </u> volts	<u> </u> amps

Remarks: _____

Recorded by [Signature]
Witnessed by [Signature]
Sheet No. 16 of 33

Date 14-1-74

DATA SHEET--ACCIDENT SIMULATION
BF3 CONNECTOR ASSEMBLIES: 1, 2, 3, 7, 8, 9

Time 4:30 hours
Chamber Environments: Temperature 105-104-101 °C
Pressure 3.4 psig
Test Items: Assembly
1 250.3 volts .9951 amps
2 249.8 volts .9991 amps
3 249.6 volts 1.0135 amps
7 / volts / amps
8 / volts / amps
9 / volts / amps

Time 4:40 hours
Chamber Environments: Temperature 104-103-101 °C
Pressure 3.2 psig
Test Items: Assembly
1 250.2 volts .9954 amps
2 249.7 volts .9991 amps
3 249.4 volts 1.0135 amps
7 / volts / amps
8 / volts / amps
9 / volts / amps

Time 4:50 hours
Chamber Environments: Temperature 104-103-101 °C
Pressure 3.2 psig
Test Items: Assembly
1 250.6 volts .9954 amps
2 249.7 volts .9991 amps
3 249.4 volts 1.0135 amps
7 / volts / amps
8 / volts / amps
9 / volts / amps

Remarks: _____

Recorded by [Signature]
Witnessed by [Signature]
Sheet No. 1 of 53

Date 11-1-77DATA SHEET--ACCIDENT SIMULATION
BF3 CONNECTOR ASSEMBLIES: 1, 2, 3, 7, 8, 9Time 5.00 hoursChamber Environments: Temperature 104.103-104 °CPressure 3.3 psig

Test Items: Assembly

1	<u>250.2</u> volts	<u>.9452</u> amps
2	<u>244.7</u> volts	<u>.9488</u> amps
3	<u>249.5</u> volts	<u>1.0136</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Time 5.20 hoursChamber Environments: Temperature 104.144 °CPressure 3.2 psig

Test Items: Assembly

1	<u>250.3</u> volts	<u>.9499</u> amps
2	<u>244.7</u> volts	<u>.9455</u> amps
3	<u>249.5</u> volts	<u>1.0158</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Time 5.20 hoursChamber Environments: Temperature 104.103-103 °CPressure 3.2 psig

Test Items: Assembly

1	<u>250.1</u> volts	<u>.9450</u> amps
2	<u>244.6</u> volts	<u>.9486</u> amps
3	<u>249.5</u> volts	<u>1.0134</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Remarks: _____

Recorded by W. H. BunkerWitnessed by [Signature]Sheet No. 1 of 33

Date 11-3-68

DATA SHEET--ACCIDENT SIMULATION
BF3 CONNECTOR ASSEMBLIES: 1, 2, 3, 7, 8, 9

Time 5.30 hours

Chamber Environments: Temperature 103 104 104 °C

Pressure 3.2 psig

Test Items: Assembly

1 250.3 volts .4448 amps

2 2442 volts .4405 amps

3 244.6 volts 1.0172 amps

7 volts amps

8 volts amps

9 volts amps

Time 5:40 hours

Chamber Environments: Temperature 102-102-102°C

Pressure 3.1 psig

Test Items: Assembly

1 250.3 volts .9451 amps

2 294.2 volts .4403 amps

3 249.6 volts 1.0136 amps

7 1 volts 1 amps

8 volts amps

9 / volts / amps

Time _____ 0000 hours

Chamber Environments: Temperature $172.41 \pm 0.3^{\circ}\text{C}$

Pressure 3.1 psig

Test Items: Assembly

1 250.6 volts 1.9444 amps

2 244.8 volts 1.97V amps

3 294.5 volts 1.0134 amps

7 volts amps

8	volts	amps
---	-------	------

9	volts	amps
---	-------	------

Remarks: _____

Recorded by *W. H. B. L. L. L.*

Witnessed by *A. [Signature]*

Sheet No. 14 of 33

Date 11-1-79

DATA SHEET--ACCIDENT SIMULATION
BFB CONNECTOR ASSEMBLIES: 1, 2, 3, 7, 8, 9

Time 6:00 hoursChamber Environments: Temperature 103-104-105 °CPressure 3.00 psig

Test Items: Assembly

1	<u>230.2</u> volts	<u>.9957</u> amps
2	<u>244.4</u> volts	<u>.9997</u> amps
3	<u>244.4</u> volts	<u>1.034</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Time 6:20 hoursChamber Environments: Temperature 103-104-105 °CPressure 2.90 psig

Test Items: Assembly

1	<u>230.2</u> volts	<u>.9950</u> amps
2	<u>244.4</u> volts	<u>.9997</u> amps
3	<u>244.7</u> volts	<u>1.0134</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Time 6:40 hoursChamber Environments: Temperature 103-104-105 °CPressure 2.5 psig

Test Items: Assembly

1	<u>230.3</u> volts	<u>.9944</u> amps
2	<u>244.4</u> volts	<u>.9997</u> amps
3	<u>244.7</u> volts	<u>1.0135</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Remarks: _____

Recorded by W. H. [Signature]Witnessed by [Signature]Sheet No. 11 of 33

Date 11-1-74DATA SHEET--ACCIDENT SIMULATION
BF3 CONNECTOR ASSEMBLIES: 1, 2, 3, 7, 8, 9

Time 7:00 hours
Chamber Environments: Temperature 99.98-99 °C
Pressure 1.4 psig

Test Items: Assembly

1	<u>250.3</u> volts	<u>.9494</u> amps
2	<u>249.7</u> volts	<u>.9474</u> amps
3	<u>249.1</u> volts	<u>1.0133</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Time 7:20 hours
Chamber Environments: Temperature 99.98-100 °C
Pressure 1.4 psig

Test Items: Assembly

1	<u>250.3</u> volts	<u>.9494</u> amps
2	<u>249.7</u> volts	<u>.9474</u> amps
3	<u>249.1</u> volts	<u>1.0133</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Time 7:40 hours
Chamber Environments: Temperature 99.88-99 °C
Pressure 1.3 psig

Test Items: Assembly

1	<u>250.3</u> volts	<u>.9447</u> amps
2	<u>249.8</u> volts	<u>.9480</u> amps
3	<u>249.7</u> volts	<u>1.0131</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Remarks: _____

Recorded by W.H. Bucklin
Witnessed by [Signature]
Sheet No. 20 of 833

Date 11-1-79

DATA SHEET--ACCIDENT SIMULATION
BF3 CONNECTOR ASSEMBLIES: 1, 2, 3, 7, 8, 9

Time 8:00 hours
 Chamber Environments: Temperature 91.20-99 °C
 Pressure 1.2 psig

Test Items: Assembly

1	<u>250.3</u> volts	<u>.4448</u> amps
2	<u>249.1</u> volts	<u>.4474</u> amps
3	<u>249.1</u> volts	<u>1.635</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Time 8:20 hours
 Chamber Environments: Temperature 91.40-97 °C
 Pressure 0.9 psig

Test Items: Assembly

1	<u>250.2</u> volts	<u>.4447</u> amps
2	<u>249.8</u> volts	<u>.4481</u> amps
3	<u>249.6</u> volts	<u>1.637</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Time 8:40 hours
 Chamber Environments: Temperature 97.4-97 °C
 Pressure / psig

Test Items: Assembly

1	<u>250.3</u> volts	<u>.4449</u> amps
2	<u>249.7</u> volts	<u>.4483</u> amps
3	<u>255.0</u> volts	<u>1.634</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Remarks: _____

Recorded by W. H. [signature]
 Witnessed by [signature]
 Sheet No. 21 of 33

Date 11-1-79DATA SHEET--ACCIDENT SIMULATION
BF3 CONNECTOR ASSEMBLIES: 1, 2, 3, 7, 8, 9Time 9:00 hoursChamber Environments: Temperature 93.44-95 °CPressure 0.0 psig

Test Items: Assembly

1	<u>2503</u> volts	<u>.9947</u> amps
2	<u>2477</u> volts	<u>.9992</u> amps
3	<u>2544</u> volts	<u>1.032</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Time 9:20 hoursChamber Environments: Temperature 95.43-95 °CPressure 0.0 psig

Test Items: Assembly

1	<u>2503</u> volts	<u>.9947</u> amps
2	<u>2477</u> volts	<u>.9992</u> amps
3	<u>2544</u> volts	<u>1.032</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Time 9:40 hoursChamber Environments: Temperature 95.44-95 °CPressure 0.0 psig

Test Items: Assembly

1	<u>2502</u> volts	<u>.9944</u> amps
2	<u>2477</u> volts	<u>.9990</u> amps
3	<u>2544</u> volts	<u>1.037</u> amps
7	<u>/</u> volts	<u>/</u> amps
8	<u>/</u> volts	<u>/</u> amps
9	<u>/</u> volts	<u>/</u> amps

Remarks: _____

Recorded by W. B. BunkerWitnessed by W. B. BunkerSheet No. 2 of 33

Date 11DATA SHEET--ACCIDENT SIMULATION
BF3 CONNECTOR ASSEMBLIES: 1, 2, 3, 7, 8, 9

Time 10:00 hours
Chamber Environments: Temperature 91.13/13 °C
Pressure 0.00 psig

Test Items: Assembly

1	<u>250.3</u> volts	<u>.9940</u> amps
2	<u>244.8</u> volts	<u>.9980</u> amps
3	<u>254.8</u> volts	<u>1.0340</u> amps
7	_____ volts	_____ amps
8	_____ volts	_____ amps
9	_____ volts	_____ amps

Time 10:20 hours
Chamber Environments: Temperature 92.12/12 °C
Pressure — psig

Test Items: Assembly

1	<u>250.3</u> volts	<u>.9944</u> amps
2	<u>249.7</u> volts	<u>.9952</u> amps
3	<u>254.9</u> volts	<u>1.0354</u> amps
7	_____ volts	_____ amps
8	_____ volts	_____ amps
9	_____ volts	_____ amps

Time 10:40 hours
Chamber Environments: Temperature 94.43/44 °C
Pressure — psig

Test Items: Assembly

1	<u>250.1</u> volts	<u>.9947</u> amps
2	<u>249.6</u> volts	<u>.9981</u> amps
3	<u>254.5</u> volts	<u>1.0340</u> amps
7	_____ volts	_____ amps
8	_____ volts	_____ amps
9	_____ volts	_____ amps

Remarks: _____

Recorded by [Signature]Witnessed by [Signature]Sheet No. 13 of 33

Time 11:00 hours
Chamber Environments: Temperature 92/92/92 °C
Pressure _____ psig

Test Items: Assembly
1 22.3 volts 0.9947 amps
2 249.6 volts 0.9981 amps
3 254.8 volts 1.0339 amps

Time 11:20 hours
Chamber Environments: Temperature 70/70/70 °C
Pressure _____ psig

Test Items: Assembly
1 250.2 volts 0.9947 amps
2 249.7 volts 0.9980 amps
3 254.7 volts 1.0341 amps

Time 11:40 hours
Chamber Environments: Temperature 90/90/90 °C
Pressure _____ psig

Test Items: Assembly
1 250.3 volts 0.9948 amps
2 249.7 volts 0.9979 amps
3 254.9 volts 1.0337 amps

Time 12:00 hours
Chamber Environments: Temperature 89/89/89 °C
Pressure _____ psig

Test Items: Assembly
1 22.3 volts 0.9949 amps
2 249.7 volts 0.9979 amps
3 254.9 volts 1.0337 amps

Remarks: _____

Recorded by [Signature]
Witnessed by [Signature]
Sheet No. 24 of 33

DATA SHEET--ACCIDENT SIMULATION
BFP CONNECTOR ASSEMBLIES: 1, 2, 3, 7, 8, 9

Date 11/1/79

Time 12:20 hours
Chamber Environments: Temperature 90/90/90 °C
Pressure psig

Test Items: Assembly

1 250.3 volts .9947 amps
2 249.7 volts .9980 amps
3 254.9 volts 1.0339 amps

Time 12:40 hours
Chamber Environments: Temperature 88/88/88 °C
Pressure psig

Test Items: Assembly

1 250.3 volts .9948 amps
2 249.7 volts .9980 amps
3 254.9 volts 1.0340 amps

Time 13:00 hours
Chamber Environments: Temperature 87/87/88 °C
Pressure psig

Test Items: Assembly

1 250.2 volts .9948 amps
2 249.7 volts .9978 amps
3 254.9 volts 1.0339 amps

Time 13:20 hours 22511
Chamber Environments: Temperature 87/87/87 °C on
Pressure psig 11/1/79

Test Items: Assembly

1 250.2 volts .9951 amps
2 249.7 volts .9980 amps
3 254.9 volts 1.0339 amps

Remarks: _____

Recorded by L. B. Berman
Witnessed by [Signature]
Sheet No. 25 of 33

DATA SHEET--ACCIDENT SIMULATION
BF3 CONNECTOR ASSEMBLIES: 1, 2, 3, 7, 8, 9 Date 11/1/77

Time 13:40 hours
Chamber Environments: Temperature 87/87/89 °C
Pressure psig

Test Items: Assembly

1	<u>250.3</u> volts	<u>0.9950</u> amps
2	<u>249.6</u> volts	<u>0.9980</u> amps
3	<u>254.9</u> volts	<u>1.0339</u> amps

Time 14:00 hours
Chamber Environments: Temperature 85/86/86 °C
Pressure psig

Test Items: Assembly

1	<u>250.2</u> volts	<u>0.9949</u> amps
2	<u>249.7</u> volts	<u>0.9979</u> amps
3	<u>254.9</u> volts	<u>1.0340</u> amps

Time 14:20 hours
Chamber Environments: Temperature 86/86/86 °C
Pressure psig

Test Items: Assembly

1	<u>250.2</u> volts	<u>0.9949</u> amps
2	<u>249.7</u> volts	<u>0.9979</u> amps
3	<u>254.9</u> volts	<u>1.0339</u> amps

Time 14:40 hours
Chamber Environments: Temperature 85/85/85 °C
Pressure psig

Test Items: Assembly

1	<u>250.3</u> volts	<u>0.9950</u> amps
2	<u>249.7</u> volts	<u>0.9979</u> amps
3	<u>254.9</u> volts	<u>1.0339</u> amps

Remarks: _____

Recorded by L. J. [Signature]

Witnessed by [Signature]

Sheet No. 26 of 33

DATA SHEET--ACCIDENT SIMULATION Date 11-1-79
BF3 CONNECTOR ASSEMBLIES: 1, 2, 3, 7, 8, 9

Time 15:00 hours
Chamber Environments: Temperature 85/85/85 °C
Pressure — psig

Test Items: Assembly

1 250.3 volts .9950 amps
2 249.7 volts .9950 amps
3 254.9 volts 1.0341 amps

Time 15:20 hours
Chamber Environments: Temperature 84/84/84 °C
Pressure — psig

Test Items: Assembly

1 250.2 volts .9949 amps
2 249.6 volts .9979 amps
3 254.9 volts 1.0339 amps

Time 15:40 hours
Chamber Environments: Temperature 83/83/83 °C
Pressure — psig

Test Items: Assembly

1 250.2 volts .9954 amps
2 249.7 volts .9979 amps
3 254.9 volts 1.0340 amps

Time 16:00 hours
Chamber Environments: Temperature 83/83/83 °C
Pressure — psig

Test Items: Assembly

1 250.1 volts .9954 amps
2 249.6 volts .9950 amps
3 254.9 volts 1.0340 amps

Remarks: _____

Recorded by L. Bryen

Witnessed by 383

Sheet No. 27 of 33

Time 16:20 hours
 Chamber Environments: Temperature 51/51/51 °C
 Pressure psig

Test Items: Assembly
 1 250.2 volts .9953 amps
 2 249.7 volts .9980 amps
 3 254.9 volts 1.0340 amps

Time 16:40 hours
 Chamber Environments: Temperature 82/82/82 °C
 Pressure psig

Test Items: Assembly
 1 250.3 volts .9955 amps
 2 249.7 volts .9979 amps
 3 254.9 volts 1.0340 amps

Time 17:00 hours
 Chamber Environments: Temperature 80/80/80 °C
 Pressure psig

Test Items: Assembly
 1 250.2 volts .9955 amps
 2 249.7 volts .9978 amps
 3 254.9 volts 1.0340 amps

Time 17:20 hours
 Chamber Environments: Temperature 80/80/80 °C
 Pressure psig

Test Items: Assembly
 1 250.2 volts .9953 amps
 2 249.7 volts .9979 amps
 3 254.9 volts 1.0340 amps

Remarks: _____

Recorded by J. Bergen

Witnessed by SK

Sheet No. 28 of 33

DATA SHEET--ACCIDENT SIMULATION
BF3 CONNECTOR ASSEMBLIES: 1, 2, 3, 7, 8, 9 Date 11/2/79

Time 17:40 hours
Chamber Environments: Temperature 78.78-79 °C
Pressure — psig

Test Items: Assembly

1 250.1 volts .9952 amps
2 249.7 volts .9978 amps
3 254.8 volts 1.0341 amps

Time 18:00 hours 0251
Chamber Environments: Temperature 78.78-78 °C on
Pressure — psig 11/2/79

Test Items: Assembly

1 250.2 volts .9953 amps
2 249.7 volts .998 amps
3 254.9 volts 1.0341 amps

Time 18:20 hours
Chamber Environments: Temperature 77.77-77 °C
Pressure — psig

Test Items: Assembly

1 250.2 volts .9954 amps
2 249.7 volts .9979 amps
3 254.9 volts 1.0340 amps

Time 18:40 hours
Chamber Environments: Temperature 77.77/77 °C
Pressure — psig

Test Items: Assembly

1 250.1 volts .9953 amps
2 249.7 volts .9979 amps
3 254.9 volts 1.0340 amps

Remarks: _____

Recorded by L. B. [Signature]

Witnessed by [Signature]

Sheet No. 29 of 33

DATA SHEET--ACCIDENT SIMULATION Date 11/1/79
BF3 CONNECTOR ASSEMBLIES: 1, 2, 3, 7, 8, 9

Time 19:00 hours 11/2/79
Chamber Environments: Temperature 76/75/76 °C ~0351
Pressure --- psig

Test Items: Assembly

1 250.2 volts .9955 amps
2 249.7 volts .9977 amps
3 254.8 volts 1.0340 amps

Time 19:20 hours
Chamber Environments: Temperature 76-75-75 °C
Pressure --- psig

Test Items: Assembly

1 250.2 volts .9953 amps
2 249.6 volts .9979 amps
3 254.8 volts 1.0341 amps

Time 19:40 hours
Chamber Environments: Temperature 75/75/75 °C
Pressure --- psig

Test Items: Assembly

1 250.3 volts .9954 amps
2 249.7 volts .9978 amps
3 254.7 volts 1.0341 amps

Time 20:00 hours 11/2/79
Chamber Environments: Temperature 75/75/75 °C ~0451
Pressure --- psig

Test Items: Assembly

1 250.2 volts .9954 amps
2 249.6 volts .9980 amps
3 254.4 volts 1.0342 amps

Remarks: _____

Recorded by L. Boush

Witnessed by L. Boush

Sheet No. 30 of 33

DATA SHEET--ACCIDENT SIMULATION Date 11/2/79
BT3 CONNECTOR ASSEMBLIES: 1, 2, 3, 7, 8, 9

Time 20:20 hours
Chamber Environments: Temperature 73/73/73 °C
Pressure — psig

Test Items: Assembly

1	<u>250.3</u> volts	<u>.9949</u> amps
2	<u>249.7</u> volts	<u>.9978</u> amps
3	<u>254.8</u> volts	<u>1.034</u> amps

Time 20:40 hours
Chamber Environments: Temperature 72/72/72 °C
Pressure — psig

Test Items: Assembly

1	<u>250.2</u> volts	<u>.9952</u> amps
2	<u>249.7</u> volts	<u>.9979</u> amps
3	<u>254.9</u> volts	<u>1.0341</u> amps

Time 21:00 hours 11/2/79
Chamber Environments: Temperature 70/70/69 °C 0551
Pressure — psig

Test Items: Assembly

1	<u>250.2</u> volts	<u>.9951</u> amps
2	<u>249.7</u> volts	<u>.9979</u> amps
3	<u>254.8</u> volts	<u>1.0341</u> amps

Time 21:20 hours
Chamber Environments: Temperature 71/70/71 °C
Pressure — psig

Test Items: Assembly

1	<u>250.2</u> volts	<u>.9952</u> amps
2	<u>249.6</u> volts	<u>.9955</u> amps
3	<u>254.8</u> volts	<u>1.0340</u> amps

Remarks: _____

Recorded by J. B. Bogen

Witnessed by J. B. Bogen

Sheet No. 31 of 33

DATA SHEET--ACCIDENT SIMULATION
BF3 CONNECTOR ASSEMBLIES: 1, 2, 3, 7, 8, 9 Date 11/2/77

Time 21:40 hours
Chamber Environments: Temperature 70/70/71 °C
Pressure psig

Test Items: Assembly

1 250.2 volts .9953 amps
2 249.7 volts .9974 amps
3 254.9 volts 1.0334 amps

Time 22:00 hours 11/2/77
Chamber Environments: Temperature 70/70/71 °C
Pressure psig 0651

Test Items: Assembly

1 250.3 volts .9952 amps
2 249.8 volts .9954 amps
3 254.9 volts 1.0338 amps

Time 22:20 hours
Chamber Environments: Temperature 69/68/69 °C
Pressure psig

Test Items: Assembly

1 250.2 volts .9953 amps
2 249.6 volts .9958 amps
3 254.9 volts 1.0338 amps

Time 22:40 hours
Chamber Environments: Temperature 69/69/69 °C
Pressure psig

Test Items: Assembly

1 250.3 volts .9951 amps
2 249.7 volts .9959 amps
3 254.9 volts 1.0338 amps

Remarks: _____

Recorded by [Signature]

Witnessed by [Signature]

Sheet No. 32 of 33

DATA SHEET--ACCIDENT SIMULATION
BF3 CONNECTOR ASSEMBLIES: 1, 2, 3, 7, 8, 9

Date 11/1/79

Time 23:00 hours
Chamber Environments: Temperature 68/68/69 °C
Pressure — psig

11/2/79

0751

Test Items: Assembly

1 250.3 volts .9951 amps
2 249.7 volts .9954 amps
3 255.0 volts 1.0339 amps

Time 23:20 hours
Chamber Environments: Temperature 68/68/68 °C
Pressure — psig

Test Items: Assembly

1 250.1 volts .9951 amps
2 249.7 volts .9958 amps
3 254.9 volts 1.0338 amps

Time 23:40 hours
Chamber Environments: Temperature 66/66/66 °C
Pressure — psig

Test Items: Assembly

1 250.3 volts .9951 amps
2 249.7 volts .9958 amps
3 254.8 volts 1.0337 amps

Time 24:00 hours
Chamber Environments: Temperature 64/64/64 °C
Pressure — psig

Test Items: Assembly

1 250.3 volts .9953 amps
2 249.7 volts .9915 amps
3 254.9 volts 1.0338 amps

Remarks: _____

Recorded by J. B. Buzen

Witnessed by J. B. Buzen

Sheet No. 33 of 33

Lead 785

1220

1230

1240

1250

1260

Penetration
0.5 V/cm


1270

12.100 Ticks #5

HGATE RS

OR

11-1-79 0907



BF 3 CONNECTOR ACCIDENT TEST PROFILE OF NOVEMBER 1 & 2, 1979.

Test Procedures
Browns Ferry, Unit 3, Connectors
Accident Simulation

Objective:

These procedures describe the functional processes to achieve the accident-simulation tests of Browns Ferry Unit 3 Bendix connectors in accordance with the (effective revision of) "Connector Assembly Test Plan for Browns Ferry, Unit 3, Connectors."

Apparatus:

The simulation apparatus consists of a steam autoclave and pressure generation system (principally the boiler, accumulator, test chamber, and pressure regulators/throttles), steam or temperature conditioning equipment (principally the external strip heaters, and an inline superheater), and the connector-assemblies electrical loading and diagnostic equipment.

Associated with the simulation apparatus are the various diagnostic equipment such as pressure gauges, thermocouples, data acquisition system (data logger), and the like.

Personnel and Function:

To accomplish the simulation test, up to five functional operations must be manned. The initial test phases require five individuals; later during the quasi steady-state test phases fewer people are required, but never less than two individuals.

- 2 -

The test coordinator directs all operations based on the real-time data compared with the desired test profiles.

The environments regulator performs all adjustments of pressure regulators, superheater, throttle valves, and the like as directed by the test coordinator.

The connector assemblies loader performs all electrical loading and diagnostics of the connector assemblies as directed by the test coordinator.

The data taker records the various data derived from the environments monitors and other data as necessary.

The generalist provides backup support as required or as directed by the test coordinator.

External Strip Heaters:

These have two functions and modes of operation. First, to achieve an elevated chamber temperature prior to the accident-simulation test, and second, to control the long-term temperature rampdown of approximately $-2^{\circ}\text{C}/\text{hour}$.

To achieve the elevated chamber temperature, the strip heaters are energized (in advance of the simulation test) for approximately 12 minutes, until the exterior skin thermocouple reaches about 70°C . The strip heaters are then deenergized and the test chamber is allowed to equilibrate for about 1 hour (or as necessary) until the interior selected thermocouple(s) reach $60-80^{\circ}\text{C}$.

Second, to control the temperature rampdown (after the steam phase), the strip heaters are periodically

energized (10-60 seconds) as required to follow the desired temperature profile. (Empirically, 10 seconds results in approximately a 1°C temperature rise.)

Boiler/Accumulator:

The accumulators are brought to approximately 150 psig in advance of the accident test in accordance with established safe operation procedures (SOP) and the valving is similarly lined-up preparatory to steam delivery to the test chamber according to the SOP.

Electrical Loading of the Connector Assemblies:

In accordance with the test plan, the 250-VDC connector assemblies will be energized throughout the entire accident test and the 480-VAC connector assemblies will be energized only during the first 5 minutes, between minutes 15 and 18, and between minutes 57 and 60.

For at least 5 minutes prior to the accident test initiation, all electrical loads will be applied to the connector assemblies to provide baseline data. The electrical loading during the test is according to the schedule described above.

In-Line Superheater:

The 20 kilowatt in-line superheater provides initial surge and quasi-steady-state superheat to the incoming steam.

Prior to test start, the superheater is energized

and its controller set at 400+°C (with a continuous flow of steam through it). The superheater is allowed to reach the desired temperature and to equilibrate as necessary.

During the test, the controller/superheater is manually adjusted as directed by the test coordinator to follow the desired temperature profile.

Accident Test Sequence:

The test coordinator will use the attached (appendix) test sequence sheets to achieve the test profile. These provide desired time/temperature/pressure/heaters/loading signatures. Based on these sequence sheets, he will direct the personnel to make necessary adjustments in the control apparatus. They also serve as a checklist to sequence operations prior to the start of the accident test.

Data Retrieval and Records

Chamber environment and connector-assemblies loading data will be periodically recorded on data logger printouts, strip charts, and/or data sheets as appropriate. During the early test phase, data will be recorded frequently (e.g., every 20-60 seconds). Later in the test the recording frequency will be adjusted to reflect the quasi-steady-state test aspects; the appropriate data will be recorded at least hourly.

Appendix -- Pre-Accident Test Checklist

- ✓ 1. Desired elevated chamber temperature has been accomplished.
Date/Time 11/1/79 0845
- ✓ 2. Boiler/accumulators at working pressures and valving lineup completed.
Date/Time 11/1/79 0835
- ✓ 3. In-line superheater is at desired temperature with steam flow.
Date/Time 11/1/79 0835
4. Electrical loading of the connector assemblies is completed and baseline data taken.
Date/Time 10 stat @ ~ 23:57
- ✓ 5. All support staff in place to accomplish test.
Date/Time 11/1/79 0845
- ✓ 6. All prepared to initialize data loggers and data time intervals.
Date/Time 11/1/79 0850

LB

Note: This form to be checked, initialed, and dated as specified.

10/26/79

Appendix -- Time from 23 Hours, 57 Minutes to 2 Minutes

<u>Data Logger Hours-Min-Sec</u>	<u>Desired Pressure (Psig)</u>	<u>Desired Temperature (°C)</u>	<u>Electrical Loads ON/OFF</u>	<u>Remarks</u>
Initialize, start, data loggers to 23-57-0				
23-57-0	0	60-80	All On	
23-58	0	60-80	All On	
23-59	0	60-80	All On	
0-0-0	0	60-80	All On	Valve alignment
	-----			1. Chamber bypass open
0-10	Ramp	75	All On	2. Chamber inlet open
	to			3. Superheater bypass
0-20	60	83	All On	closed
	psig			4. Exit throttle open
0-30		92	All On	1/4 turn
	-----			5. Open inline 1/4 tur
0-40	60	100	All On	regulator valve
				(Regulator preset;
0-50	60	109	All On	65 psig against
				deadhead)
1-0	60	117	All On	6. Bring up on regulat
				bypass valve
1-10	60	125	All On	
1-20	60	133	All On	
1-30	60	142	All On	
1-40	60	150	All On	
1-50	60	159	All On	
2-0	60	167	All On	

Appendix -- Time from 2 Minutes to 7 Minutes

<u>Data Logger</u> <u>Min-Sec</u>	<u>Desired</u> <u>Pressure</u> <u>(Psig)</u>	<u>Desired</u> <u>Temperature</u> <u>°C</u>	<u>Electrical</u> <u>Loads</u> <u>On/Off</u>
2-0	60	167	All On
3-0	60	167	All On
4-0	59	167	All On
5-0	59	167	480V Off
6-0	58	167	250V On
7-0	58	167	Minute-5

Appendix -- Time from 7 Minutes to 1 Hour

<u>Data Logger Min</u>	<u>Desired Pressure (Psig)</u>	<u>Desired Temperature (°C)</u>	<u>Electrical Loads On/Off</u>
7	58	167	
8	55	167	
9	52	166	
10	49	166	
11	47	166	
12	43.5	165	
13	40	165	
14	37.5	164	
15	35	164	480V on for 3 minutes 15-18
16	32.5	164	
17	30	164	
18	29	163	
19	28	163	
20	27	163	
21	26.5	162	
22	26	162	
23	25.5	161	
24	25	161	
25	25	161	
26	24.5	160	
28	24	159	
30	24	159	(Remarks: Change print interval to 1 minute; change tape.
32	23.5	158	
34	23.5	157	
36	23	157	
38	22.5	156	
40	22	156	
42	21.5	155	
44	21	154	
46	20	154	
48	19	153	
50	17.5	152	
52	16	151	
54	15	151	
56	14	150	
57	14	150	480V on for 3 minutes 57-60
58	14	149	
59	14	149	
60	14	148	

NOTE: 1. 250V loads ON during entire test.
 2. 480V OFF after Minute 60 for accident-test duration.

Appendix -- Time from 1 Hour to 3 Hours

<u>Data Logger</u> <u>Hours-Min</u>	<u>Desired</u> <u>Pressure</u> <u>(Psig)</u>	<u>Desired</u> <u>Temperature</u> <u>(°C)</u>	<u>Remarks</u>
1-0	14	148	(117+ Saturated)
-5	14	147	
-10	15.5	145	
-15	17	143	
-20	17.5	139	(121+ Saturated)
-25	17	136	
-30	16	132	Change print interval
-35	15	128	to 5 minutes
-40	14	124	
-45	13	121	
-50	12	117	
-55	11	114	
2-0	10	110	(112+ Saturated)
-5	9.5	110	
-10	9.5	110	
-15	9	110	
-20	8.5	109	
-25	8	109	
-30	8	109	
-35	8	109	
-40	8	109	
-45	7.5	108	(109+ Saturated)
-50	7.5	108	
-55	7.5	108	
3-0	7	108	

Note: 1. 250V Loads ON during accident test.
 2. 480V Loads OFF for accident-test duration.

Appendix -- Time from 3 Hours to 24 Hours

<u>Data Logger</u> <u>Hours-Min</u>	<u>Desired</u> <u>Pressure</u> <u>(Psig)</u>	<u>Desired</u> <u>Temperature</u> <u>(°C)</u>	<u>Remarks</u>
3-0	7	108	
-15	6.5	108	
-30	5	107	
-45	3.5	107	Start wall temperatur
4-0	1.5	106	to 108°C
-15	0	106	Open top center port
-30	0	105	to allow heat flow
-45	0	105	
5-0	0	104	
6	0	102	
7	0	100	
8	0	98	
9	0	96	
10	0	94	
11	0	92	
12	0	90	
13	0	88	
14	0	86	
15	0	84	
16	0	82	
17	0	80	
18	0	78	
19	0	76	
20	0	74	
21	0	72	
22	0	70	
23	0	68	
24	0	66	


ALL LOADS OFF

Note: 1. 250V loads ON to end of test.
 2. 480V loads OFF

INSTRUMENTATION EQUIPMENT SHEET


Date 11/1-2/79 Technician D. DUGAN Project DF3 CONNECTORS Test Area GIF, 1A-V Type Test ACCIDENT TEST

No.	Instrument	Manufacturer	Model No.	Serial No.	Ident No.	Range	Accuracy	Calibration	
								On	Due
1	PRESSURE GAUGE	HEISE		29155		0-18 PSI	$\pm 0.1\% FS$	5/6/79	5/31/80
2	DATA LOGGER	ACUREX	A901	1684	011409	$\pm 12^{\circ}C$ $\pm 12^{\circ}C$	$\pm 0.005\% FS$ $\pm 0.005\% FS$	9/14/79	3/14/80
SEE ALSO "SECONDARY CHECK OF PANEL METERS" ON 9/25/79									



PHOTOGRAPH C79-10073A

CONNECTORS/CANS IN POSITION IN
UPPER TEST CHAMBER SECTION; ALSO
SHOWS POSITION OF THERMOCOUPLES



PHOTOGRAPH C79-10072A

CONNECTORS/CANS IN POSITION IN
UPPER TEST CHAMBER SECTION; ALSO
SHOWS POSITION OF THERMOCOUPLES
AND EXITING CABLE

POOR ORIGINAL

SECTION IX

POST-ACCIDENT FUNCTIONAL/MECHANICAL TESTS

Post-Accident Functional/Mechanical Tests Procedures

After the electrical connectors have been exposed to the accident environments, each item will be subjected to insulation resistance, voltage, load, and dimensional tests. The test procedures outlined in the previous two applicable (Baseline) sections will be followed here as well, except (1) that the electrical loads are held constant and the operating current/voltage is recorded and (2) that the insulation resistance measurement will also be made with a volt-ohmmeter.

These post-accident functional tests are for information only and do not constitute any acceptance criteria.

DATA SHEET

Project BF3 CONNECTORS

Specimen 250 VDC

Part No 1, 2, 3

Ident. POST-ACCIDENT FUNCTIONAL LOAD/VOLTAGE Start Date 11/5/79

	INPUT	LOAD	LOAD	INPUT
<u>ITEM</u>	<u>VOLTAGE</u>	<u>RESISTANCE</u>	<u>VOLTAGE</u>	<u>CURRENT</u>
1	~250	227.3 (COLD)	249.9	.996
2	~250	234.4 (COLD)	249.6	.997
3	~250	243.2 (COLD)	254.6	.998

Remarks _____

Tested by [Signature] Date 11/5/79

Witness [Signature] Date 11/5/79

Sheet No. 1 of 3

Approved _____

DATA SHEET

Project BF3 CONNECTORS

Specimen 450 VAC

Part No 7, 8, 9

Ident. POST-ACCIDENT FUNCTIONAL LOAD/VOLTAGE Start Date 11/5/79

	INPUT	LOAD (DC.)	LOAD	INPUT
ITEM	VOLTAGE	RESISTANCE	VOLTAGE	CURRENT
7	477 VAC	28.6 (COLD)	475 VAC	17.5
8	477	25.52 (COLD)	476	16.8
9	476	26.22 (COLD)	474	17.4

Remarks _____

Tested by [Signature] Date 11/5/79

Witness [Signature] Date 11/5/79

Sheet No. 2 of 3

Approved _____

DATA SHEET

Project BF3 CONNECTORS

Specimen ALL

Part No _____

Ident. POST-ACCIDENT FUNCTIONAL IR

Start Date 11/5/79

PINS (250 VDC CONNECTORS)

ITEM	K TO CASE	N TO CASE	K TO N
1	>100 MΩ	>100 MΩ	>100 MΩ
2	>100 MΩ	>100 MΩ	>100 MΩ
3	32 1 MΩ	>100 MΩ	>100 MΩ

PINS (450 VAC CONNECTORS)

ITEM	9 TO CASE	10 TO CASE	9 TO 10
7	>100 MΩ	>100 MΩ	>100 MΩ
8	>100 MΩ	>100 MΩ	>100 MΩ
9	>100 MΩ	>100 MΩ	>100 MΩ

Remarks _____

Tested by [Signature] Date 11/5/79

Witness L. Benga Date 11/5/79

Sheet No. 3 of 3

Approved _____

INSTRUMENTATION EQUIPMENT SHEET

Date 11/5/79 Technician D. DUGAN Project DF3 CONVERTERS Test Area CeIF, TA-V
 Type Test POST-ACCIDENT FUNCTIONAL

No.	Instrument	Manufacturer	Model No.	Serial No.	Ident No.	Range	Accuracy	Calibration	
								On	Due
1	DIGITAL MULTIMETER	FLUKE	8100A	3318	213043	0-100mV 0.1-1000VDC	$\pm 0.1\%$ $\pm 0.05\% + 10\mu V$	8/1/79	3/1/80
2	DIGITAL MULTIMETER	KETTERLEY	100	56735	22224	0-100mVDC	$\pm 10\%$ READING $\pm 0.1\%$ READING	6/6/79	12/6/79

Instrument Test Engineer _____ Checked & Received by _____

DATA SHEET

Project BF3 CONNECTORS

Specimen 250VDC

Part No 1

Ident. POST- ACCIDENT DIMENSIONAL

Start Date 11/6/79

NEOPRENE INSULATOR		DIAMETER		WIRE A	
PIN	DEPTH	LOCATION	VALUE	LOCATION	CD
A	0.081"	I	88	1	0.188"
K	0.073"	II	94	2	0.183"
M	0.070"	III	91	3	0.185"
E	0.099"				

NEOPRENE INSULATOR WAS SLIGHTLY BELOW THE END OF THE CONNECTOR PLUG BARREL

BARREL DIAMETER: 1.506" - 1.513"


Remarks _____

Tested by [Signature] Date 11/6/79

Witness J. Benson Date 11/6/79

Sheet No. 1 of 6

Approved _____



DATA SHEET

Project BFS CONNECTORS

Specimen 250 VPC

Part No 2

Ident. POST-ACCIDENT DIMENSIONAL

Start Date 11/6/79

NEOPRENE INSULATOR		DURIMETER		WIRE A	
<u>PIN</u>	<u>DEPTH</u>	<u>LOCATION</u>	<u>VALUE</u>	<u>LOCATION</u>	<u>CD</u>
A	0.093"	I	88	1	0.185"
K	0.077"	II	92	2	0.192"
M	0.088"	III	86	3	0.187"
E	0.086"				

NEOPRENE INSULATOR WAS SLIGHTLY ABOVE THE END OF THE CONNECTOR PLUG BARREL.

BARREL DIAMETER: 1.510 - 1.513"

Remarks _____

Tested by [Signature]

Date 11/6/79

Witness L. Bouzon

Date 11/6/79

Sheet No. 2 of 6

Approved _____

DATA SHEET

Project BF3 CONNECTORSSpecimen 250 VDCPart No 3Ident. PET-ACCIDENT DIMENSIONALStart Date 11/6/79

NEOPRENE INSULATOR		DILMETER		WIRE A	
<u>PIN</u>	<u>DEPTH</u>	<u>LOCATION</u>	<u>VALUE</u>	<u>LOCATION</u>	<u>OD</u>
A	0.091"	I	89	1	0.154"
K	0.080"	II	93	2	0.154"
M	0.078"	III	84	3	0.154"
E	0.101"				

NEOPRENE INSULATOR WAS RAISED IN CENTER, EVEN WITH END OF THE CONNECTOR PLUG BARREL AT SIDES.

BARREL DIAMETER: 1.510 - 1.513"

Remarks _____

Tested by [Signature]Date 11/6/79Witness J. BrysonDate 11/6/79Sheet No. 3 of 6

Approved _____

DATA SHEET

Project BF3 CONNECTORS

Specimen 48L VAC

Part No 7

Ident. TEST- ACCIDENT DIMENSIONAL

Start Date 11/6/79

NEOPRENE INSULATOR		DURIMETER		WIRE 14	
<u>PIN</u>	<u>DEPTH</u>	<u>LOCATION</u>	<u>VALUE</u>	<u>LOCATION</u>	<u>CD</u>
1	0.074"	<u>IV</u>	82	1	0.208"
14	0.067"	<u>V</u>	83	2	0.206"
6	0.073"	<u>VI</u>	78	3	0.208"

NEOPRENE INSULATOR WAS CONSIDERABLY BELOW THE
END OF THE CONNECTOR PLUG BARREL.

BARREL DIAMETER: 1.968 - 1.969"


Remarks _____

Tested by [Signature] Date 11/6/79

Witness [Signature] Date 11/6/79

Sheet No. 4 of 6

Approved _____



DATA SHEET

Project BF3 CONNECTORS

Specimen 48 VAC

Part No 8

Ident. POST-ACCIDENT DIMENSIONAL

Start Date 11/6/79

NEOPRENE INSULATOR

DUPONETER

WIRE 14

PIN DEPTH

LOCATION VALUE

LOCATION CD

1 0.068"

IV 81

1 0.209"

14 0.057"

V 81

2 0.207"

6 0.057"

VI 73

3 0.208"

NEOPRENE INSULATOR WAS CONSIDERABLY BELOW THE
END OF THE CONNECTOR PLUG BARREL.

BARREL DIAMETER: 1.967 - 1.975"

Remarks _____

Tested by [Signature] Date 11/6/79

Witness A. Bouzon Date 11/6/79

Sheet No. 5 of 6

Approved _____

DATA SHEET

Project BF3 CONNECTORS

Specimen 480VAC

Part No 9

Ident. POST-ACCIDENT DIMENSIONAL

Start Date 11/6/79

NEOPRENE INSULATOR		DURMETER		WIRE 14	
PIN	DEPTH	LOCATION	VALUE	LOCATION	OD
1	0.068"	IV	77	1	0.212"
14	0.064"	V	85	2	0.203"
6	0.091"	VI	77	3	0.212"

NEOPRENE INSULATOR WAS CONSIDERABLY BELOW
THE END OF THE CONNECTOR PLUG BARREL.

BARREL DIAMETER: 1.968"

Remarks _____

Tested by [Signature] Date 11/6/79

Witness [Signature] Date 11/6/79

Sheet No. 6 of 6

Approved _____

INSTRUMENTATION EQUIPMENT SHEET

Date _____

Test Area Bldg 570 BTechnician D. DUGANProject BF3 CONNECTORS Type Test POST-ACCIDENT DIMENSIONAL

No.	Instrument	Manufacturer	Model No.	Serial No.	Ident No.	Range	Accuracy	Calibration	
								On	Due
1	SHORE TYPE A2	SHORE	TYPE A ²	-	162T3	0-100		NOT APPLICABLE	
2	CALIPERS	BROWNE & SHARPE	574	-	-	0-6" / 0.01	±0.001	NOT APPLICABLE	

Instrument Test Engineer _____ Checked & Received by _____

SECTION X
POST-TESTS INSPECTIONS

Post-Test Inspection Procedures

Each test item will be inspected and tested as described below, to assess the physical degradation of the connectors assemblies. All results and observations will be recorded on data sheets and supplemented with other pertinent documentation:

- the insulation will be inspected for surface texture, discoloration, cracks, or splitting.
- the connector shells, threads, and cable clamps will be inspected for general conditions.
- the connector pins on the face side will be inspected for corrosion, oxidation, pitting, or burning.

DATA SHEET

Project BF3 CONNECTORS

Specimen 250 VDC

Part No 1

Ident. POST-TEST INSPECTION

Start Date 11/6/79

INSULATION: DISCOLORED TO A BROWNISH-BLACK, SLIGHT SHRINKAGE, SOME SWELLING OF OUTER LAYER, NO CRACKS.

SHELLS: EXCELLENT, SLIGHT DISCOLORIZATION OF ANODIZED SURFACE, RUBBER STRAIN-RELIEF IS CRACKED.

PINS/INSERT: EXCELLENT, NO DEGRADATION.

Remarks _____

Tested by [Signature] Date 11/6/79

Witness A. Banger Date 11/6/79

Sheet No. 1 of 6

Approved _____

DATA SHEET

Project BF3 CONNECTORS

Specimen 250 VDC

Part No 3

Ident. POST-TEST INSPECTION

Start Date 11/6/79

INSULATION: DISCOLORED TO A BROWNISH-BLACK, SLIGHT SHRINKAGE, TWIRE SHOWED SOME PHYSICAL DAMAGE

SHELLS: EXCELLENT, SLIGHT DISCOLORIZATION OF ANODIZED SURFACE, RUBBER STRAIN-RELIEF IS CRACKED.

PINS/INSERT: EXCELLENT, NO DEGRADATION.

Remarks _____

Tested by [Signature] Date 11/6/79

Witness L. Bergen Date 11/6/79

Sheet No. 3 of 6

Approved _____

DATA SHEET

Project BF3 CONNECTORS

Specimen 250 VDC

Part No. 3

Ident. POST-TEST INSPECTION

Start Date 11/6/79

INSULATION: DISCOLORED TO A BROWNISH-BLACK, SLIGHT SHRINKAGE, J WIRE SHOWED SOME PHYSICAL DAMAGE.

SHELLS: EXCELLENT, SLIGHT DISCOLORATION OF ANODIZED SURFACE, RUBBER STRAIN-RELIEF IS CRACKED.

PINS/INSERTS: EXCELLENT, NO DEGRADATION.

Remarks _____

Tested by [Signature] Date 11/6/79

Witness J. Boyer Date 11/6/79

Sheet No. 3 of 6

Approved _____

DATA SHEET

Project BF3 CONNECTORS

Specimen 450 VAC

Part No 7

Ident. POST-TEST INSPECTION

Start Date 11/6/79

INSULATION: DISCOLORED TO A BURGUNDY, BUBBLES
IN COLOR LAYER

SHELLS: EXCELLENT, SLIGHT DISCOLORATION OF
ANODIZED SURFACE, RUBBER STRAIN-RELIEF
IS CRACKED.

PINS/INSERTS: EXCELLENT, NO DEGRADATION.

Remarks _____

Tested by [Signature]

Date 11/6/79

Witness [Signature]

Date 11/6/79

Sheet No. 4 of 6

Approved _____

DATA SHEET

Project BF3 CONNECTERS

Specimen 482 VAC

Part No 8

Ident. POST-TEST INSPECTION

Start Date 11/6/81

INSULATION: DISCOURED TO A BURGUNDY, BUBBLES
IN COLOR LAYER.

SHELLS: EXCELLENT, SLIGHT DISCOLORATION OF
ANODIZED SURFACE, RUBBER STRAIN-RELIEF
IS CRACKED.

PINS/INSERTS: EXCELLENT, NO DEGRADATION.

Remarks _____

Tested by [Signature] Date 11/6/81

Witness [Signature] Date 11/6/81

Sheet No. 5 of 6

Approved _____

DATA SHEET

Project BF3 CONNECTORS

Specimen 48CVAC

Part No 9

Ident. POST-TEST INSPECTION

Start Date 11/6/79

INSULATION: DISCOURED TO A BURGUNDY, BUBBLES
IN GOUR LAYER.

SHELLS: EXCELLENT, SLIGHT DISCOLORATION OF
ANCHORED SURFACE, RUBBER STRAIN-RELIEF
IS CRACKED.

RES/INSTRS: EXCELLENT, NO DEGRADATION.


Remarks _____

Tested by [Signature] Date 11/6/79

Witness L. Benson Date 11/6/79


Sheet No. 6 of 6

Approved _____



PHOTOGRAPH C79-10071A
POST-TESTS DISASSEMBLY OF
250-VDC CONNECTORS

POOR ORIGINAL



PHOTOGRAPH C79-10067A
POST-TESTS DISASSEMBLY OF
480-VAC CONNECTORS

POOR ORIGINAL

DISTRIBUTION:

R. Feit (20)
Division of Reactor Safety Research
Office of Nuclear Regulatory Research
Mail Stop 1130SS
U.S. Nuclear Regulatory Commission
Washington, DC 20555

4440 G. R. Otey
4445 L. O. Cropp
4445 L. L. Bonzon (10)
4445 W. H. Buckalew
4445 J. A. Lewin
4445 F. V. Thome
8266 E. A. Aas
3141 T. L. Werner (5)
3151 W. L. Garner (3)
for DOE/TIC (Unlimited Release)
3154-3 R. P. Campbell (25)
for NRC distribution to NTIS