

PRESERVICE INSPECTION PROGRAM
FOR THE
VIRGIL C. SUMMER STATION
(REVISION 2)

OWNER: South Carolina Electric and Gas Company
P.O. Box 328 Main Street
Columbia, South Carolina 29218

PLANT: V.C. Summer Station
Located - Twenty-Six Miles Northwest of
Columbia in Jenkinsville, South Carolina

CAPACITY: 900 MWe

PREPARED BY:

John D. Moore

4/23/81

PLAN APPROVALS:

S. J. Smith

INSERVICE INSPECTION COORDINATOR

4/23/81
DATE

J. R. Moore

QA GROUP SUPERVISOR

4/23/81
DATE

O. S. Bradham

MANAGER, V.C. SUMMER NUCLEAR
STATION

4/23/81
DATE

H. Radin

MANAGER, NUCLEAR ENGINEERING

4/28/81
DATE

CONCURRENCE:

C. E. McTeath

AUTHORIZED NUCLEAR INSERVICE
INSPECTOR

4-23-81
DATE

TABLE OF CONTENTS

	<u>PAGE</u>
<u>SECTION A</u>	
Introduction	
AP-014 "Preservice Inspection Program"	A-1 through A-3
<u>SECTION B NDE</u>	
1. Introduction	B-3 through B-7B
2. Tables of Class 1 and 2 Systems.....	B-8 through B-27
and Components	
3. Relief Request	B-28 through B-41
4. PSI Weld Reference Index	B-42 through B-49
5. PSI File No. to Weld No. Index	B-50 through B-55B
6. Scoped Drawings	B-56 through B-74
7. Isometric Drawings	
a. Regular Program	B-75 through B-186
b. Augmented Program	B-187 through B-198
<u>SECTION C HYDROSTATIC TESTING</u>	
Introduction	C-2
Index	C-3
1. ISI Hydro Reference Index	C-4 through C-10A
2. Scoped Drawings	C-11 through C-69
3. Sample PSI File Packet	C-70 through C-87
4. Sample PSI Routing Sheet	C-89 through C-90
5. Sample Data Sheets	C-92 through C-93
6. Sample Completed Procedure.....	C-94 through C-109
<u>SECTION D PUMPS</u>	
Introduction	D-2
Index	D-3
1. List of Pumps	D-4 through D-8
2. Symbols (Definitions).....	D-9 through D-10
3. ISI Test Quantities	D-12
4. Sample Data Sheet	D-14 through D-15
a. Preservice/Baseline Data Sheet	
5. Relief Request (Deleted) Revision 2	D-17

TABLE OF CONTENT

(Continued)

SECTION E VALVES

Introduction	E-2 through E-3
Index	E-4
1. List of Drawings.....	E-5 through E-7
2. List of Valve Categories	E-8 through E-9
3. Sample Data Sheet	
a. Preservice/Baseline Data Sheet	E-11
4. List of Definitions and Valve Tables	
Symbols	E-13 through E-14
5. List of Valves	E-15 through E-44
6. Relief Request (Deleted) Revision 2.....	E-46 through E-75

SECTION F COMPONENT SUPPORTS

Introduction	F-2
Index	F-3
1. Component Supported Reference Index	F-4 through F-23
(Scoped Drawings) (Deleted - Revision 2).....	F-23
2. Sample Data Sheet	F-25

4. Preservice/Baseline Inspection Program

Baseline data to support the PSI program will be compiled in accordance with the 1974 edition of the code through Summer 1975 addenda.

Baseline data/preservice inspections will be performed during the construction and start-up phases of the station, utilizing Westinghouse inspection procedures and SCE&G startup functional and pre-operational test procedures. The specific procedures and example of same are listed in the applicable sections of this plan.

5. Control

This plan, in conjunction with AP-014 (Preservice Inspection Program), has been prepared as the controlling documents governing the preservice/baseline data inspection activities at the V.C. Summer Station.

6. Supporting Programs

All supporting programs and/or documentations referenced herein are maintained at the station.

Should certain ASME Section XI Code requirements be discovered to be impractical due to unforeseen reasons during the process of performing inspections or test,