

CONTAINMENT SYSTEMS

CONTAINMENT LEAKAGE

LIMITING CONDITION FOR OPERATION

3.6.1.2 Containment leakage rates shall be limited to:

a. An overall integrated leakage rate of:

1. $\leq L_a$ (346,000 SCCM), 0.20 percent by weight of the containment air^a per 24 hours at P_a , 50 psig, or
2. $\leq L_t$ (61,600 SCCM), 0.058 percent by weight of the containment air^t per 24 hours at a reduced pressure of P_t , 25 psig.

b. A combined leakage rate of $\leq 0.60 L_c$ (207,600 SCCM), for all penetrations and valves subject to Type B and C tests when pressurized to P_a .

APPLICABILITY: MODES 1, 2, 3 and 4.

ACTION:

With either (a) the measured overall integrated containment leakage rate exceeding $0.75 L_a$ (259,500 SCCM) or $0.75 L_t$ (46,200 SCCM), as applicable, or (b) with the measured combined leakage rate for all penetrations and valves subject to Types B and C tests exceeding $0.60 L_c$, restore the leakage rate(s) to within the limit(s) prior to increasing the Reactor Coolant System temperature above 200°F.

SURVEILLANCE REQUIREMENTS

4.6.1.2 The containment leakage rates shall be demonstrated at the following test schedule and shall be determined in conformance with the criteria specified in Appendix J of 10 CFR Part 50* using the methods and provisions of ANSI N45.4 - 1972:

- a. Three Type A tests (overall Integrated Containment Leakage Rate) shall be conducted at 40 + 10 month intervals during shutdown at either P_a (50 psig) or at P_t (25 psig) during each 10-year service period. The third test of each set shall be conducted during the shutdown for the 10-year plant inservice inspection.*

*The third test of the first 10-year service period shall be conducted during spring 1985 Unit 1 refueling outage.

3/4.6 CONTAINMENT SYSTEMS

3/4.6.1 PRIMARY CONTAINMENT

CONTAINMENT INTEGRITY

LIMITING CONDITION FOR OPERATION

3.6.1.1 Primary CONTAINMENT INTEGRITY shall be maintained.

APPLICABILITY: MODES 1, 2, 3 and 4.

ACTION:

Without primary CONTAINMENT INTEGRITY, restore CONTAINMENT INTEGRITY within one hour or be in at least HOT STANDBY within the next 6 hours and in COLD SHUTDOWN within the following 30 hours.

SURVEILLANCE REQUIREMENTS

4.6.1.1 Primary CONTAINMENT INTEGRITY shall be demonstrated:

- a. At least once per 31 days by verifying that all penetrations* not capable of being closed by OPERABLE containment automatic isolation valves and required to be closed during accident conditions are closed by valves, blind flanges, or deactivated automatic valves secured in their positions, except as provided in Table 3.6-1 of Specification 3.6.4.1.
- b. By verifying that each containment air lock is OPERABLE per Specification 3.6.1.3.
- c. By verifying that the equipment hatch is closed and sealed, prior to entering Mode 4 following a shutdown where the equipment hatch was opened, by conducting a Type B test per Appendix J to 10 CFR Part 50.

*Except valves, blind flanges, and deactivated automatic valves which are located inside the containment and are locked, sealed, or otherwise secured in the closed position. These penetrations shall be verified closed during each COLD SHUTDOWN except that such verification need not be performed more often than once per 92 days.