

MARKUP OF ANO-1 TECHNICAL SPECIFICATION 4.18.5.b

8. Unserviceable describes the condition of a tube if it leaks or contains a defect large enough to affect its structural integrity in the event of an Operating Basis Earthquake, a loss-of-coolant accident, or a steam line or feedwater line break as specified in Specification 4.18.4.c.
  9. Tube Inspection means an inspection of the steam generator tube from the point of entry completely to the point of exit.
- b. The steam generator shall be determined operable after completing the corresponding actions (plug or sleeve all tubes exceeding the plugging limit and all tubes containing through-wall cracks) required by Table 4.18-2, with the following exception:
- Tubes with intergranular attack indications within the upper tube sheet with the potential of through-wall depths greater than the plugging limit may remain in service for the remainder of cycle 14.