


**Detroit
Edison**

2000 Second Avenue
Detroit, Michigan 48226
(313) 237-8000

September 4, 1981
EF2 - 54,625



Mr. L. L. Kintner
U.S. Nuclear Regulatory Commission
Office of Nuclear Reactor Regulation
Division of Licensing
Washington, DC 20555

Reference: Enrico Fermi Atomic Power Plant - Unit 2
NRC Docket No. 50-341

Subject: Seismic Qualification Review Team (SQRT) Audit Response
to Open Items

Dear Mr. Kintner:

As stated in our letter (EF2-54,390) of August 31, 1981, we attach herewith, additional information in connection with Open Item #3a.

We have prepared ground response spectra for 5% and 7% structural (site) damping for 5% and 7% (equipment) damping for N-S direction, and E-W direction reproduced from synthetic time histories - Figures 1 to 4. An overlay of ground response spectra for 5% and 7% structural (site) damping shows an excellent match - See Figures 5 & 6.

We have also prepared overlays of floor response spectra for 5% and 7% structural damping. Both sets of spectra have been developed for 5% equipment damping. These are presented as Attachment I.

An inspection of the overlays shows that the 5% structurally damped spectra pretty well match the 7% structurally damped spectra both in shape and in acceleration magnitudes. The 5% structurally damped curves do show a slightly higher response in the high frequency range. Considering the state of the art developments in this field, the comparison shows no significant differences.

Further, an independent analysis was made to project the response due to 5% structural damping from the 7% structurally damped spectra values as the reference data using a rational analytical approach. The spectra development is presented in Attachment II. This method is somewhat more conservative than the use of the actual floor response spectra. It shows that the 5% structural damped spectra are at most 20% larger than the 7% structural damped spectra, with generally no significant increase over most of the frequency range.

A048
s
1/60

Mr. L. L. Kintner
September 4, 1981 - EF2-54,625
Page 2

The results, as presented in Attachment III, show that no additional requalification of equipment is required. Three items: RPV Top Guide, HVAC Dampers and the Plenum for the multizone unit have calculated stresses in the range of up to 20% over yield. This overstress calculation does not consider the positive effects of higher equipment damping and mobilization of ductility that would accompany such stresses.

Yours very truly,



W. F. Colbert
Technical Director
Enrico Fermi 2

WFC/YNA/jlj
Attachments

cc: B. Little
Dr. Morris Reich
Department of Nuclear Energy
Building 129
Brookhaven National Laboratory
Upton, NY 11973


29 AUG 81
312DL

CALC NO. 500-0000-000
PROJECT FERNI-2
PROJECT NO. 6109-39
DAMPING 0.050 0.070
PAGE

REV

EF2-54625

FIGURE 1



DESIGN SITE SPECTRUM

NOTE

BASE

DIRECTION

NS

ANGLE

SPECTRA NO.

5% SITE DAMP

ELEVATION

540'-0"

LOCATION

REA-RUX BLOC

SARGENT & LUNDY

ENGINEERS

29 AUG 81

312DL

CALC NO. 300-0000-000

PROJECT FERRI-2

PROJECT NO. 6139-30


DAMPING 0.050 0.070

PAGE

REV

EF2-54625

FIGURE 2



DESIGN SITE SPECTRUM

N80E BASE

DIRECTION NO ANGLE

SPECTRA NO. 77 SITE DAMP

ELEVATION 540'-0"

LOCATION REA-RUX BLOS


29 AUG 81
3120L

CALC NO. 500-0203-000
PROJECT FERRI-2
PROJECT NO. 6130-30
DAMPING 0.050 0.070
PAGE

REV

EF2-54625

FIGURE 3



DESIGN SITE SPECTRUM

NODE BASE

DIRECTION EW ANGLE

SPECTRA NO. 5% SITE DAMP

ELEVATION 540'-0"


LOCATION REA-RUX BLOS

29 AUG 81
312DL

CHECK NO. 000-0000-000
PROJECT FERM-2
PROJECT NO. 6139-30
DAMPING 0.000 0.070
PAGE

REV

EF2-5+625
FIGURE 4



DESIGN SITE SPECTRUM

NODE BASE

DIRECTION EW ANGLE

SPECTRA NO. 7% SITE DAMP

ELEVATION 540'-0"

LOCATION REA-AUX BLOC

SARGENT & LUNDY

ENGINEERS

29 AUG 81

3120L

CALC NO. 300-DECB-000

PROJECT FERMI-2

REV


PROJECT NO. 6139-38

DAMPING 0.050 0.070

PAGE

EF2-54625

FIGURE 5



DESIGN SITE SPECTRUM

MODE BASE

DIRECTION NO ANGLE

SPECTER NO. — 5% SITE DAMP

ELEVATION 540'-0"

LOCATION NEA-RUX 2100

--- 7% SITE DAMPING

SARGENT & LUNDY

ENGINEERS

29 AUG 81

3125L

CALC NO. 500-DECO-000

PROJECT FERMI-2

PROJECT NO. 6139-30


DAMPING 0.050 0.070

PROE

REV

EF2-54625

FIGURE 6



DESIGN SITE SPECTRUM

NODE BASE

DIRECTION EW ANGLE

SPECTRA NO. — 5% SITE DAMP

ELEVATION

LOCATION

--- 7% SITE DAMPING

540'-0"

RED-RUX BLOS

SARGENT & LUNDY
ENGINEERS
CHICAGO

ATTACHMENT 1
EF2 - 54,265

SPECTRA COMPARISON FOR 50 EQUIPMENT DAMPING -
REACTOR-AUXILIARY BUILDING COMPLEX

SARGENT & LUNDY

ENGINEERS

28 AUG 81

2240L

CALC NO. 33E/5% & 7% DAMP SITE SPECTRA

PROJECT FERNI-2


REV

PROJECT NO. 6139-38

PEAKS WIDENED BY 10% ON EACH SIDE

DAMPING 0.050

PAGE



RER-AUX 33E/SPECTRA COMPARISON

NODE 1

DIRECTION N3

SPECTRA NO.

B-29

ELEVATION

583'-6"

LOCATION

RER-AUX BLDG. SLAB 1


SARGENT & LUNDY

ENGINEERS

28 AUG '81

224DL

CALC NO. SDE/5% & 7% DAMP SITE SPECTRA
PROJECT FERNI-2 REV
PROJECT NO. 6139-38
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE



RER-AUX SSE/SPECTRA COMPARISON

NODE 1

DIRECTION EW

Page 2

SPECTRA NO.

ELEVATION

LOCATION

B-30

583'-6"

RER-AUX BLDG. SLAB 1


SARGENT & LUNDOY

ENGINEERS

28 AUG 61

2240L

CALC NO. 33E/5% & 7% DAMP SITE SPECTRA
PROJECT FERN1-2 REV
PROJECT NO. 6139-35
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE



REA-AUX 33E/SPECTRA COMPARISON

NODE 2

DIRECTION N5

SPECTRA NO. 8-21

ELEVATION 613'-5"

LOCATION REA-AUX BLOC. BLOC 2


SARGENT & LUNDY

ENGINEERS

28 AUG 81

2240L

CALC NO. 53E/5% & 7% DAMP SITE SPECTRA
PROJECT FERNI-2 REV
PROJECT NO. 6139-38
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE



REA-AUX 53E/SPECTRA COMPARISON

NODE 2

DIRECTION EW

SPECTRA NO.

ELEVATION

LOCATION

B-32

613'-6''

REA-AUX BLDG. SLAB 2

SARGENT & LUNDY

ENGINEERS

28 AUG 81

224DL

CALC NO. 33E/5Z & 7% DAMP SITE SPECTRA

PROJECT FERNI-2


REV

PROJECT NO. 6139-38

PEAKS WIDENED BY 10% ON EACH SIDE

DAMPING 0.050

PAGE



REA-AUX 33E/SPECTRA COMPARISON

N80E 3

DIRECTION NS

SPECTRA NO. C-33

ELEVATION 641'-6"

LOCATION REA-AUX BLDG. SLAB 3


SARGENT & LUNDY

ENGINEERS

28 AUG 81

224DL

CALC NO. 33E/5Z & 7Z DAMP SITE SPECTRA
PROJECT FERM1-2 REV
PROJECT NO. 6139-38
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE



REA-RUX 33E/SPECTRA COMPARISON

NODE 3

DIRECTION EW

Page 6

SPECTRA NO. B-34

ELEVATION 641'-6"

LOCATION

REA-RUX BLOC. SLAC 3


SARGENT & LUNDY

ENGINEERS

28 AUG 81

2240L

CALC NO. 33E/5% & 7% DAMP SITE SPECTRA
PROJECT FERNI-2 REV
PROJECT NO. 6139-30
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE



REA-AUX 33E/SPECTRA COMPARISON

NODE 4

DIRECTION NS

SPECTRA NO. B-35

ELEVATION 659'-0"

LOCATION REA-AUX BLOC. SLAB 4


SARGENT & LUNDY

ENGINEERS

20 AUG 81

224DL

CALC NO. 33E/5% & 7% DAMP SITE SPECTRA
PROJECT FERNI-2 REV
PROJECT NO. 6139-38
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE



REA-AUX 33E/SPECTRA COMPARISON


NODE 4

DIRECTION EW

SPECTRA NO. 8-35


ELEVATION 659'-0"

LOCATION REA-AUX BLOC. SLAB 4



28 AUG 81
2240L

CALC NO. SSE/5% & 7% DAMP SITE SPECTRA
PROJECT FERM-2 REV
PROJECT NO. 6129-58
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE



REA-AUX SSE/SPECTRA COMPARISON
NODE 5
DIRECTION NS


Page 9

SPECTRA NO. B-37
ELEVATION 694'-6''
LOCATION REA-AUX BLDG. SLAB 5

SARGENT & LUNDY
ENGINEERS

28 AUG 81
224DL

CALC NO. SSE/3% & 7% DAMP SITE SPECTRA
PROJECT FERNI-2 REV
PROJECT NO. 6139-38
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE



REA-AUX SSE/SPECTRA COMPARISON

NODE 5

DIRECTION EW

SPECTRA NO. B-38

ELEVATION 684'-6"

LOCATION REA-AUX BLOC. SLAB 5


SARGENT & LUNDY

ENGINEERS

28 AUG 81

224DL

CALC NO. 33E/SZ & 7% DAMP SITE SPECTRA
PROJECT FERNI-2 REV
PROJECT NO. 6139-38
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE



REA-AUX 33E/SPECTRA COMPARISON

NBOE 91

DIRECTION NS

SPECTRA NO. 8-33

ELEVATION

LOCATION

CRANE(ADJ COL 17)


SARGENT & LUNDY

ENGINEERS

28 AUG 81

2240L

CALC NO. 35E/SZ & 7% DAMP SITE SPECTRA
PROJECT FERMI-2 REV
PROJECT NO. 6139-38
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE



KEA-RUX 35E/SPECTRA COMPARISON

SPECTRA NO. B-40

NODE 91

ELEVATION

DIRECTION EW

Page 12

LOCATION

CRANE(ROJ CBL 17)


SARGENT & LUNDY

ENGINEERS

28 AUG 81

224DL

CALC NO. 33E/5% & 7% DAMP SITE SPECTRA
PROJECT PERM-2 REV
PROJECT NO. 6139-38
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE



REA-AUX 33E/SPECTRA COMPARISON

NAOC 13

DIRECTION NS

SPECTRA NO. B-41


ELEVATION DRYWELL CNT

LOCATION 18'-0" BELOW REF INVERT

SARGENT & LUNDY
ENGINEERS

28 AUG 81
224DL

CALC NO. SSC/5% & 7% DAMP SITE SPECTRA
PROJECT FERM1-2 REV
PROJECT NO. 6139-08
PEAKS WIDENED BY 10% ON EACH SIDE
DRAWING 0.050
PAGE



REA-AUX SSE/SPECTRA COMPARISON

NGOE 13

DIRECTION EN

PECTRA NO. B-42

ELEVATION DRYWELL CONT

LOCATION 18'-0" BELOW RPV INVERT

Page 14


SARGENT & LUNDY

ENGINEERS

28 AUG 81

2240L

CALC NO. SSE/5% & 7% DAMP SITE SPECTRA
PROJECT FERNI-2 REV
PROJECT NO. 6139-SB
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE



RCA-AUX SSE/SPECTRA COMPARISON

NODE 14

DIRECTION NS

SPECTRA NO. B-45

ELEVATION DRYWELL CONT

LOCATION 6'-0" BELOW RPV INVERT


SARGENT & LUNDY

ENGINEERS

28 AUG 81

2240L

CALC NO. SSE/SZ & 7% DAMP SITE SPECTRA
PROJECT FERM1-2 REV
PROJECT NO. 6139-S8
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE



REA-AUX SSE/SPECTRA COMPARISON

NODE 14

DIRECTION EW

SPECTRA NO. D-44


ELEVATION DRYWELL CNT

LOCATION 6'-0" BELOW RPY INVERT

SARGENT & LUNDY
ENGINEERS

28 AUG 81
224DL

CALC NO. 33E/5% & 7% DAMP SITE SPECTRA
PROJECT FERM-2 REV
PROJECT NO. 6133-98
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE



REA-AUX 33E/SPECTRA COMPARISON

NODE 28

DIRECTION NS

SPECTRA NO.

B-45

ELEVATION

REACTOR PED.

LOCATION

15'-0" BELOW RPV INVERT


SARGENT & LUNDY

ENGINEERS

28 AUG 81

224DL

CALC NO. 53C/SZ & 7% DAMP SITE SPECTRA
PROJECT FEKNI-2 REV
PROJECT NO. 6139-38
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE



KEA-AUX 53C/SPECTRA COMPARISON

NODE 20

DIRECTION EW

SPECTRA NO. 8-46

ELEVATION REACTOR PED.

LOCATION 19'-0" BELOW REV INVERT


SARGENT & LUNDY

ENGINEERS

28 AUG '81

224DL

CALC NO. 23E/5Z & 7% DAMP SITE SPECTRA
PROJECT FERNI-2 REV
PROJECT NO. 6109-98
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE



REA-AUX 23E/SPECTRA COMPARISON

NODE 29

DIRECTION NS

SPECTRA NO. 8-47

ELEVATION


LOCATION

TOP OF REACTOR PEDESTAL

SARGENT & LUNDY
ENGINEERS

28 AUG 81
2240L

CALC NO. 006/5% & 7% DAMP SITE SPECTRA
PROJECT FERNI-2 REV
PROJECT NO. 6109-30
PEAKS WIDENED BY 10% ON L & R SIDE
DAMPING 0.050
PAGE



REA-AUX SSE/SPECTRA COMPARISON

N80E 29

DIRECTION EW

SPECTRA NO.

ELEVATION

LOCATION

B-48

TOP OF REACTOR PEDESTAL


SARGENT & LUNDY

ENGINEERS

28 AUG 81

2240L

CALC NO. 33E/5% & 7% DAMP SITE SPECTRA
PROJECT FERNI-2 REV
PROJECT NO. 6139-38
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE



RER-AUX 33E/SPECTRA COMPARISON

NODE 73

DIRECTION NS

SPECTRA NO. B-49

ELEVATION RPV

LOCATION 14'-1" ABOVE RPV INVERT

SARGENT & LUNDY


ENGINEERS

28 AUG 81

224DL

CALC NO. 33E/5% & 7% DAMP SITE SPECTRA
PROJECT FERNI-2 REV
PROJECT NO. 6138-58
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.05G
PAGE

FREQUENCY IN CPS



REA-AUX 33E/SPECTRA COMPARISON

NBOE 73

DIRECTION EW

SPECTRA NO. 8-50

ELEVATION RPY

LOCATION 14'-1" ABOVE RPY INVERT


SARGENT & LUNDY

ENGINEERS

28 AUG 81

224DL

CALC NO. 300/02 4 7% DAMP SITE SPECTRA
PROJECT FEARMI-2 REV
PROJECT NO. 0100-00
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE



REA-AUX 300/SPECTRA COMPARISON

NODE 60

DIRECTION NS


SPECTRA NO. 0-51

ELEVATION RTV

LOCATION 52°-11' ABOVE RTV INVERT

28 AUG 81
224DL

CALC NO. 33E/52 & 7% DAMP SITE SPECTRA
PROJECT FERNI-2 REV
PROJECT NO. 5139-38
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE



REA-AUX 33E/SPECTRA COMPARISON
NODE 60
DIRECTION EW

SPECTRA NO. 0-52
ELEVATION RPV
LOCATION 52'-11" ABOVE RPV INVERT


SARGENT & LUNDY

ENGINEERS

28 AUG 81

2240L

CALC NO. 33E/5Z & 7Z DAMP SITE SPECTRA
PROJECT FERNI-2 REV
PROJECT NO. 6139-28
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE



REA-AUX 33E/SPECTRA COMPARISON

NSOE 30

DIRECTION CW

SPECTRA NO. 6-57

ELEVATION 606'-0"

LOCATION SACRIFICIAL SHIELD


SARGENT & LUNDY

ENGINEERS

28 AUG 81

224DL

CALC NO. 99E/02 & 7% DAMP SITE SPECTRA
PROJECT FERMI-2 REV
PROJECT NB. 6139-58
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE



REA-AUX 99E/SPECTRA COMPARISON

NB02 31

DIRECTION EW

SPECTRA NB.

5-50

ELEVATION

627'-11''

LOCATION

SACRIFICIAL SHIELD


SARGENT & LUNDY

ENGINEERS

28 AUG 81

2240L

CALC NO. 33E/5% & 7% DAMP SITE SPECTRA
PROJECT FERM1-2 REV
PROJECT NO. 6139-38
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE



REA-AUX 33E/SPECTRA COMPARISON

N40Z 30

DIRECTION N3

SPECTRA NO. 5-59

ELEVATION 606'-0"

LOCATION SACRIFICIAL SHIELD


SARGENT & LUNDY

ENGINEERS

28 AUG 81

224DL

CALC NO. 99E/57 & 7% DAMP SITE SPECTRA
PROJECT FERMI-2 REV
PROJECT NO. 6139-38
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE



RCA-RUX 99E/SPECTRA COMPARISON

NODE 51

DIRECTION N3

SPECTRA NO.

B-60

ELEVATION

627'-11''

LOCATION


SACRIFICIAL SHIELD

SARGENT & LUNDY
ENGINEERS

28 AUG 81

224DL

CALC NO. 338/5% & 7% DAMP SITE SPECTRA
PROJECT FERNI-2 REV
PROJECT NO. 6139-38
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE



NER-AUX SSE/SPECTRA COMPARISON

NODE 47

DIRECTION NS

SPECTRA NO.

B-61

ELEVATION


SHRUD

LOCATION

33'-5" ABOVE RPY INVERT

23 AUG 81
2240L

CALC NO. 33E/5Z & 7Z DAMP SITE SPECTRA
PROJECT FERRI-2 REV
PROJECT NO. 6139-38
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE




REA-AUX 33E/SPECTRA COMPARISON
NAME 47
DIRECTION EN

SPECTRA NO. B-52
ELEVATION SHRBUD
LOCATION 53'-0" ABOVE RPV INVERT

SARGENT & LUNDY
ENGINEERS

28 AUG 81
224DL

CALC NO. 05E/5% & 7% DAMP SITE SPECTRA
PROJECT FERNI-2 REV
PROJECT NO. 5109-00
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE



REA-HUX 05E/SPECTRA COMPARISON

NODE 79

DIRECTION NS

SPECTRA NO. 6-63

ELEVATION 38000

LOCATION 30'-9" ABOVE RPY INVERT

SARGENT & LUNDY

ENGINEERS

28 AUG 81

224DL

CALC NO. 33E/5% & 7% DAMP SITE SPECTRA

PROJECT FERM-2


REV

PROJECT NO. 6139-30

PEAKS WIDENED BY 10% ON EACH SIDE

DAMPING 0.050

PAGE



REA-AUX 33E/SPECTRA COMPARISON

NBOE 79

DIRECTION EW

SPECTRA NO.


ELEVATION

LOCATION

B-64


SHROUD

50'-9" ABOVE RPY INVERT



28 AUG 81
224DL

CALC NO. 35E/5% & 7% DAMP SITE SPECTRA
PROJECT FERM-2 REV
PROJECT NO. 6130-38
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE



REA-RUX 35E/SPECTRA COMPARISON

NODE 74

DIRECTION NS

SPECTRA NO. B-65

ELEVATION RPV

LOCATION 10'-11" ABOVE RPV INVERT


SARGENT & LUNDY

ENGINEERS

28 AUG 81

224DL

CALC NO. 33E/5Z & 7Z DAMP SITE SPECTRA
PROJECT FERNI-2 REV
PROJECT NO. 0159-98
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE



REA-RUX 33E/SPECTRA COMPARISON

NODE 74

DIRECTION EW

SPECTRA NO.

ELEVATION

LOCATION

B-66

RPV


10'-11" ABOVE RPV INVERT

SARGENT & LUNDY
ENGINEERS

26 AUG 81

2240L

CALC NO. SSE/5% & 7% DAMP SITE SPECTRA
PROJECT PENN-2 REV
PROJECT NO. 5139-38
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING = 0.050
PAGE



REA-AUX SSE/SPECTRA COMPARISON

N80E 72

DIRECTION N3

SPECTRA NB.


6-67

ELEVATION

RPV

LOCATION


15'-11" ABOVE RPV INVERT



28 AUG 81

224DL

CALC NO. 33E/5Z & 7Z DAMP SITE SPECTRA
PROJECT FERNI-2 REV
PROJECT NO. 6139-38
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE



REA-RUX 33E/SPECTRA COMPARISON

NODE 72

DIRECTION EW

SPECTRA NO. 3-58

ELEVATION RPV

LOCATION 15'-11" ABOVE RPV INVERT


SARGENT & LUNDY

ENGINEERS

28 AUG 81

224DL

PILE NO. 39E/5Z & 7% DAMP SITE SPECTRA
PROJECT FERNI-C REV
PROJECT NO. 6139-58
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE



REA-AUX 39E/SPECTRA COMPARISON

NB02 64

DIRECTION NO

SPECTRA NO.

B-09

ELEVATION

RPV

LOCATION


35'-10" ABOVE RPV INVERT

SARGENT & LUNDY

28 AUG 81

2240L

CALC NO. 33E/5% & 7% DAMP SITE SPECTRA
PROJECT FERNI-2 REV
PROJECT NO. 6139-38
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE



RCA-AUX 33E/SPECTRA COMPARISON

NGDE 54

DIRECTION CH

SPECTRA NO. 0-70

ELEVATION RPY

LOCATION 36°-10' ABOVE RPY INVERT


SARGENT & LUNDY

ENGINEERS

28 AUG 31

2240L

CALC NO. SSE/SI & 7% DAMP SITE SPECTRA
PROJECT FERRI-E REV
PROJECT NO. 6139-35
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE



REA-AUX SSE/SPECTRA COMPARISON

MODE 63

DIRECTION NS

SPECTRA NO. B-71

ELEVATION RPV


LOCATION 42'1" ABOVE RPV INVERT

SARGENT & LUNDY

28 AUG 61

224DL

CALC NO. 556/8% & 7% DAMP SITE SPECTRA
PROJECT PERM-2 REV
PROJECT NO. 6100-56
PERKS MODIFIED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE



PER-RUX 556/SPECTRA COMPARISON

NODE 63

DIRECTION EW

SPECTRA NO.

5-72

ELEVATION

RPV


LOCATION

42°1' AGVE RPV INVERT

28 AUG 81

224DL

CALC NO. 33E/5% & 7% DAMP SITE SPECTRA
 PROJECT PERMIT-2 REV
 PROJECT NO. 6139-58
 PEAKS WIDENED BY 10% ON EACH SIDE
 DAMPING 0.050
 PAGE



REP-AUX 33E/SPECTRA COMPARISON

NODE 59

DIRECTION NS

SPECTRA NO. 0-73

ELEVATION RPV

LOCATION 59'-1" ABOVE RPV INVERT


SARGENT & LUNDY

ENGINEERS

28 AUG 81

224DL

CALC NO. 55E/57 & 7% DAMP SITE SPECTRA
PROJECT FERRI-2 REV
PROJECT NO. 6139-28
PEAKS WIDENED BY 10% ON EACH SIDE
DAMPING 0.050
PAGE



RCA-RUX SSE/SPECTRA COMPARISON

NODE 59

DIRECTION EW

SPECTRA NO. 6-74

ELEVATION RPV

LOCATION 59'-1" ABOVE RPV INVERT

Page 42

ATTACHMENT II
EF2 - 54,265

ENRICO FERMI ATOMIC POWER PLANT
UNIT 2

Constructed Equipment Response Spectra
for 5% and 7% Structural Damping and 2%
Equipment Damping

Prepared for: Detroit Edison Company
2000 Second Avenue
Detroit, Michigan 48226

Prepared by: Hopper and Associates
1840 S. Elena Avenue, Suite 208
Redondo Beach, CA 90277

August 27, 1981

HOPPER AND ASSOCIATES
ENGINEERS

1.0 INTRODUCTION

Equipment design spectra exist for the Fermi Design project based on the reassessment earthquake evaluation. These spectra have been generated assuming the structural damping to be 7%. This structural damping was rationally selected based upon anticipated structural response level to the newly postulated earthquake excitation. Subsequently, it was observed that anticipated structural response levels were not achieved and the justification for such high structural damping was questionable.

No concern exists relative to the structural adequacy of the critical Fermi building structures. However, internally housed equipment may experience loading more severe than that indicated by the existing internal equipment spectra generated from 7% structural damping phenomena.

To eliminate such concern, it was considered necessary to determine the influence of 5% structural damping on the existing internal equipment spectra generated for 7% structural damping.

The normal approach to this problem would be to simply reanalyze the existing structure subjected to a given time history with 5% as opposed to 7% damping and generate the attendant internal equipment response spectra. However, basic problems apparently exists in synthesizing one time history that will appropriately envelope both 5% and 7% ground motion input response spectra.

Independent of any time history information we have developed internal equipment response spectra assuming 5% structural damping for comparison with spectra existing for 7% structural damping. This was accomplished by assuming that the response of the building structure could be approximated by a summation of damped sinusoidal acceleration time histories corresponding in frequencies to the primary structural response frequencies of the building structure.

The following sections of this report address the methodology by which comparative spectra were developed, a justification for the synthesization technique employed, a development of response phenomena to decaying sinusoid excitation, details of the technique employed for equipment spectra generation and a summary of results followed by representative equipment response spectra plots for representative building locations.

2.0 METHODOLOGY

2.1 Existing 7% structural damping equipment spectra were reproduced for detailed evaluation purposes. Concurrently, structural response phenomena for the primary Fermi safety related structures were excerpted from references 1 and 2. This information was used to establish the baseline upon which spectral synthesization activities were undertaken.

2.2 The response of internal equipment to decaying sinusoid excitation was established as a function of the sinusoidal decay ratio which is assumed as representative of the extent structural damping mobilized.

2.3 Spectra were synthesized for 7% sinusoidal damping assuming the total response at a given frequency could be represented by a summation of decaying sinusoidal excitations at frequencies equivalent to those associated with the primary structural response modes. Amplification factors for each of the decaying sinusoids were computed in such a way that the 7% excitation response spectra would be equivalent to the synthesized spectra at all predominant building response frequencies. Resulting amplification factors were then used to generate spectral acceleration values intermediate to structural response frequencies.

2.4 Five percent spectra were synthesized with equivalent summation factors and amplification ratios employed for the 7% response situation. Higher basic amplification ratios associated with less severe sinusoidal decay caused amplification to occur in the 5% spectra relative to the 7% spectra in zones in proximity to primary building response frequencies.

2.5 Comparative response spectra were plotted for critical building locations to compare 5% structural damping equipment response spectra with 7% damped structural equipment response spectra. These comparative spectra were then used to establish maximum amplification ratios anticipated at various structural locations for equipment acceptability verification purposes.

3.0 SYNTHESIZATION TECHNIQUE JUSTIFICATION

3.1 The damped sinusoidal response summation approach was selected for internal equipment spectra generations purposes for several reasons. First, consistent and unquestionable basic time history ground motion time histories are unavailable

HOPPER AND ASSOCIATES
ENGINEERS

at this time. Second, we believe this damped sinusoidal model combination approach will yield amplification ratios between the 5% and 7% structural damping spectra that are definitely conservative.

Furthermore, this first approximation simplified approach avoids dangers associated with over sophistication whereby analytical complexities may obscure true structural response characteristics and introduce undetectable unrealistic computational phenomena.

3.2 Our spectral synthesization technique herein basically corresponds to an approach presented by J. M. Biggs and J. M. Rosette entitled "Seismic Analysis of Equipment Mounted on a Massive Structure". This approach was documented in a three day seminar at MIT on Seismic Design for Nuclear Power Plants held in the Spring of 1969. Although the accuracy of this approach is not precise our experience has shown it to yield conservative internal equipment response spectra and the simplicity of the technique seems appropriate for our specific application.

The basic approach is summarized following:

The acceleration for a given spectral frequency may be calculated as

1/2

$$A_{em} = \left[\sum_{n=1}^{n'} (A'_{emn})^2 + \frac{\sum_{n=n'+1}^{n''} \left(I'_{sn} \Phi_{sne} A''_{emn} \right)^2}{\sum_{n=1}^{n''} \left(I'_{sn} \Phi_{sne} \right)^2} \right]$$

The first summation includes those modes for which $\frac{\text{Equipment Period}}{\text{Structural Period}} = \frac{T_{em}}{T_{sn}} < 1.25$; the numerator of the second term includes the remaining modes while the denominator includes all modes.

$$A'_{emn} = \left(\frac{A_{emn}}{A_{sne}} \right) A_{sne}$$

where

$$A_{sne} = \left[\sum_{n=1}^{n''} I'_{sn} \Phi_{sne} \right]$$

and

$$\frac{A_{emn}}{A_{sne}} = \text{Damped sinusoid amplification}$$

$$A'_{emn} = \left(\frac{A_{emn}}{A_{emg}} \right) A_{emg}$$

where

$$A_{emg} = \text{acc due to direct ground motion}$$

and

$$\frac{A_{emn}}{A_{emg}} = \text{Ground motion amplification}$$

also

A_{on} = Ground acceleration at period T_{sn}

I_{sn} = Mode n participation factor

Φ_{sne} = Mode n eigenvector

In our spectra simulation approach we neglect ground motion factors, combine the modal input by direct sum, and compute necessary participation factors to match the baseline spectra.

3.3 The approach taken should also yield conservative spectral amplification ratios between various structural damping input excitation. A major criticism of the technique for general analytical purposes rests upon the argument that modal amplification factors obtained thereby do not account for lengthy earthquake excitations in which total responses may remain at a constant level for several excitation cycles prior to their ultimate damped sinusoidal characteristic response. This phenomena would yield higher amplification ratios for a given piece of equipment but would make the ratio of amplification factors between the various structural damping ratios diminish. This makes results obtained employing this technique conservative.

3.4 The unproven nature of more advanced techniques for internal equipment spectra generation coupled with our ability to check the adequacy of this approach relative to a known 7% response spectrum makes it justifiable to employ the simple approach for spectral synthesization comparative purposes.

4.0 RESPONSE TO DECAYING SINUSOID EXCITATION

4.1 The decaying sinusoid used as a representation of the building modal response was represented by the following acceleration time history.

$$a(t) = \frac{1}{\sqrt{1 - \xi'^2}} \sin \omega_d t \times \exp \left\{ \frac{-\xi'}{\sqrt{1 - \xi'^2}} \omega_d t - \arcsin \sqrt{1 - \xi'^2} \right\}$$

HOPPER AND ASSOCIATES ENGINEERS

where

ξ' = Sinusoidal damping factor

ω_d = Damped frequency of sinusoid

4.2 Response time histories were generated for a simple single degree of freedom system subjected to the aforescribed base excitation. The following equation of motion was solved as a function of time employing the linear acceleration computational sequence described.

$$y + \omega^2 y + 2\omega\xi y = -a(t)$$

where

y = system relative displacement

ω = system natural frequency

ξ = system damping factor

for a given integration time interval h ,

$$\dot{y}_n = \dot{y}_{n-1} + \left\{ \ddot{y}_{n-1} + \ddot{y}_n \right\} \frac{h}{2}$$

$$y_n = y_{n-1} + h\dot{y}_{n-1} + \frac{h^2}{3} \ddot{y}_{n-1} + \frac{h^2}{6} \ddot{y}_n$$

and

$$\begin{aligned} \ddot{y}_n = & - \left(1 + \omega^2 \frac{h^2}{6} + 2\omega \frac{h}{2} \right)^{-1} \times \\ & an + \omega^2 \left(y_{n-1} + h\dot{y}_{n-1} + \frac{h^2}{3} \ddot{y}_{n-1} \right) \\ & + 2\omega\xi \left(\dot{y}_{n-1} + \frac{h}{2} \ddot{y}_{n-1} \right) \end{aligned}$$

The time history output for each frequency is searched for the maximum value of y . The associated absolute acceleration amplification or spectral acceleration amplification is then computed as $\omega^2 y$.

4.3 Spectral amplification summaries associated with the above calculation sequence are shown on the following figure. The maximum ratio between $\xi' = .07$ and $\xi' = .05$ is 1.208. This represents a maximum 21% increase in peak acceleration going from $\xi' = .07$ to $\xi' = .05$.



T_c/T_s
SPECTRA AMPLIFICATION SUMMARY
DAMPED SINUSOID EXCITATION

5.0 EQUIPMENT SPECTRA GENERATION

5.1 It is assumed that a given response spectrum may be constructed from a summation of accelerations associated with the response of damped sinusoids at primary structural response frequencies.

$$[A] (X) = (b)$$

where

$[A]$ = Influence matrix

(X) = Modal amplification vector

(b) = Spectrum accelerations

A_{mn} corresponds to the sinusoidal amplification at frequency n associated with maximum amplification at frequency m .

An expanded influence matrix $[C]$ may similarly be constructed to encompass as many n frequencies as desired with a constant number m frequencies dependent of significant structural response modes.

$$[C] (X) = (d)$$

where (d) would encompass spectrum accelerations at as many frequencies as desired.

In our situation, we have selected (b) to match a given 7% spectrum. (X) was then computed to give the relative amplification for each mode. $[C] (X) = (d)$ a full spectrum matching the existing 7% curve.

$[C]$ is then modified for 5% structural damping and (d) is recomputed yielding a full spectrum simulating the 5% curve to be anticipated from equivalent ground excitation.

5.2 Building analysis data was taken from SL-2682 and SL-3147 and is summarized in the following tabular format:

HOPPER AND ASSOCIATES
ENGINEERS

BUILDING	CRITICAL MODES	PERIODS
N.S. Reactor/Auxiliary Building	7	.2221, .2011, .1994, .1877, .1845, .1548, and .0662
E.W. Reactor/Auxiliary Building	6	.2219, .2011, .1994, .1877, .1845 and .0634
Vert. Reactor/Auxiliary Building	3	.0814, 10656 and .0587
Horizontal RHR Complex	5	.1288, .1034, .0917, .0552 and .0419
Vertical RHR Complex	6	.0655, .0549, .0480, .0440, .0402 and .0321

5.3 Seven 5% structural damping excitation spectra were developed associated with critical locations and directions in each of the category 1 structures delineated in the preceeding section of this report. Based on those results and the consistency of the effect on spectral shape considerations, other representative spectra have been constructed and are included with this report.

6.0 SUMMARY OF RESULTS

Evaluation of comparative equipment response spectra for 7% structural damping and 5% structural damping reveals the maximum amplification the 5% to the 7% curves to be 21%. This maximum amplification varies as a function of building and location and at its minimum range equals 13%.


The observed amplification is apparent only in regions adjacent to significant structural response frequencies and is nonexistent at both the high and low frequency ends of the spectra. Enclosed following are references and an assembly of representative internal equipment response spectra for the Fermi facilities. The 7% building damping excitation spectra correspond identically to those in the reassessment analysis and the 5% building damping excitation spectra correspond to those generated by the synthesization technique described in this report.

HOPPER AND ASSOCIATES
ENGINEERS

REFERENCES

1. Seismic Analysis of the Reactor Auxiliary Building Complex Enrico Fermi Atomic Power Plant Unit 2, Report SL-2682, Sargent and Lundy Engineers, September 27, 1974.
2. Seismic Analysis of RHR Complex Enrico Fermi Atomic Power Plant Unit 2, Report SL-3147, Sargent and Lundy Engineers, July 15, 1980.
3. Seismic Re-Analysis for 7% Damping Site Spectra Reactor - Auxiliary Building, Report SDD-DECO-003, Sargent and Lundy Engineers, April 18, 1981.
4. Seismic Re-analysis of RHR Complex, Report SDD-DECO-001, Sargent and Lundy Engineers, April 18, 1981.

HOPPER AND ASSOCIATES
ENGINEERS




EQUIPMENT RESPONSE SPECTRUM


NS REACTOR/AUXILIARY BUILDING

SLAB 583'6''

HOPPER AND ASSOCIATES
ENGINEERS




EQUIPMENT RESPONSE SPECTRUM
EW REACTOR/AUXILIARY BUILDING
SLAB 583' - 6"




EQUIPMENT RESPONSE SPECTRUM
NS REACTOR/AUXILIARY BUILDING
SLAB 613' - 6"

HOPPER AND ASSOCIATES
ENGINEERS




EQUIPMENT RESPONSE SPECTRUM
EW REACTOR/AUXILIARY BUILDING
SLAB 613' - 5"

HOPPER AND ASSOCIATES
ENGINEERS




PERIOD - SECONDS
EQUIPMENT RESPONSE SPECTRUM
NS REACTOR/AUXILIARY BUILDING
SLAB 641' - 6"

HOPPER AND ASSOCIATES
ENGINEERS



PERIOD - SECONDS
EQUIPMENT RESPONSE SPECTRUM
EW REACTOR/AUXILIARY BUILDING
SLAB 641' - 6"


HOPPER AND ASSOCIATES
ENGINEERS



PERIOD - SECONDS
EQUIPMENT RESPONSE SPECTRUM
NS REACTOR/AUXILIARY BUILDING

SLAB 659' - 0"


HOPPER AND ASSOCIATES
ENGINEERS



EQUIPMENT RESPONSE SPECTRUM
EW REACTOR/AUXILIARY BUILDING


SLAB 659' - 0"

HOPPER AND ASSOCIATES
ENGINEERS




PERIOD - SECONDS
EQUIPMENT RESPONSE SPECTRUM
NS REACTOR/AUXILIARY BUILDING
SLAB 684' - 6"

HOPPER AND ASSOCIATES
ENGINEERS




PERIOD - SECONDS
EQUIPMENT RESPONSE SPECTRUM
EW REACTOR/AUXILIARY BUILDING
SLAB 684' - 6"

HOPPER AND ASSOCIATES
ENGINEERS



PERIOD - SECONDS
EQUIPMENT RESPONSE SPECTRUM
NS REACTOR CONTAINMENT
8' - 0" BELOW INVERT

HOPPER AND ASSOCIATES
ENGINEERS




EQUIPMENT RESPONSE SPECTRUM

EW REACTOR CONTAINMENT


8' - 0" BELOW INVERT

HOPPER AND ASSOCIATES
ENGINEERS



PERIOD - SECONDS
EQUIPMENT RESPONSE SPECTRUM
NS REACTOR BUILDING
TOP OF PEDESTAL

HOPPER AND ASSOCIATES
ENGINEERS




PERIOD - SECONDS

EQUIPMENT RESPONSE SPECTRUM

EW REACTOR BUILDING

TOP OF PEDESTAL

HOPPER AND ASSOCIATES
ENGINEERS




EQUIPMENT RESPONSE SPECTRUM

VERTICAL REACTOR CONTAINMENT


SHIELD 643'-6" , 659'-6" & 689'-6"

HOPPER AND ASSOCIATES
ENGINEERS



PERIOD - SECONDS
EQUIPMENT RESPONSE SPECTRUM
VERTICAL REACTOR BUILDING
SLAB 583'-0", 613'-6"

HOPPER AND ASSOCIATES
ENGINEERS




EQUIPMENT RESPONSE SPECTRUM

VERTICAL REACTOR BUILDING

SLAB 641'-6", 659'-6" & 684'-6"

HOPPER AND ASSOCIATES
ENGINEERS




EQUIPMENT RESPONSE SPECTRUM

VERTICAL AUXILIARY BUILDING


SLAB 583'-6", 613'-6" & 659'-6"

HOPPER AND ASSOCIATES
ENGINEERS



EQUIPMENT RESPONSE SPECTRUM
VERTICAL AUXILIARY BUILDING
SLAB 643'-6" & 677'-6"

HOPPER AND ASSOCIATES
ENGINEERS




EQUIPMENT RESPONSE SPECTRUM

NS RHR COMPLEX


SLAB 590'-0"

HOPPER AND ASSOCIATES
ENGINEERS




EQUIPMENT RESPONSE SPECTRUM
EW RHR COMPLEX
SLAB 590'-0"

HOPPER AND ASSOCIATES
ENGINEERS



PERIOD - SECONDS
EQUIPMENT RESPONSE SPECTRUM
NS RHR COMPLEX
SLAB 617'-0"

HOPPER AND ASSOCIATES
ENGINEERS




EQUIPMENT RESPONSE SPECTRUM

EW RHR COMPLEX


SLAB 617'-0"

HOPPER AND ASSOCIATES
ENGINEERS



EQUIPMENT RESPONSE SPECTRUM
VERTICAL RHR COMPLEX
SLAB 590'-6"

HOPPER AND ASSOCIATES
ENGINEERS



PERIOD - SECONDS
EQUIPMENT RESPONSE SPECTRUM

VERTICAL RHR COMPLEX

SLAB 617' - 6"

HOPPER AND ASSOCIATES
ENGINEERS

ATTACHMENT III
EF2 - 54,625

ENRICO FERMI ATOMIC POWER PLANT
UNIT 2

Re-evaluation of Equipment Qualified to the 7%
Structural Damping Reassessment Earthquake when
Subjected to a 5% Structural Damping Reassess-
ment Earthquake

Prepared for: Detroit Edison Company
2000 Second Avenue
Detroit, Michigan 48226

Prepared by: Hopper and Associates
1840 S. Elena Avenue, Suite 208
Redondo Beach, CA 90277

August 27, 1981

1.0 INTRODUCTION

An exhaustive seismic reassessment evaluation was undertaken by the Detroit Edison Fermi Design Team to evaluate the acceptability of critical equipment relative to a newly postulated earthquake larger than that established as the design basis for the Fermi site. In this reassessment, it was assumed that structural and mechanical items would be experiencing cycles of relatively large stress reversals and appropriate damping values were selected for analytical purposes based upon this assumption. In this regard it was assumed that the primary structures would respond at the 7% damping level.

Upon completion of the seismic reassessment activities and evaluation of the structural analysis results it was observed that anticipated stress levels were not achieved and the structural response was shown to be quite acceptable relative to the reassessment earthquake input excitation.

However, internal equipment design spectra generated from the afore described building analysis response data are not necessarily conservative in nature. If the building responds with a lower effective damping then it would be anticipated that internal equipment response spectra would be greater than those associated with higher values of structural damping. For this reason, equipment response spectra were also generated assuming that the structure would respond at the 5% damping level. These 5% structural damping spectra were plotted along with the 7% structural damping spectra for comparative purposes.

At the completion of the SQRT audit the Nuclear Regulatory Commission requested that Detroit Edison provide to them a summary of the results of the equipment seismic qualification reassessment based on the use of 5% structural damping instead of 7% structural damping. Additional items identified as critical in this evaluation were to be summarized in a table similar to table 5.4-1 existing in the current seismic reassessment report for components requiring requalification or replacement. In addition, Edison was requested to provide the Commission with floor response spectra associated with 5% structural damping.

HOPPER AND ASSOCIATES
ENGINEERS

This report addresses the re-evaluation of equipment previously qualified to a 7% structural damping reassessment earthquake when now subjected to a 5% structural damping reassessment earthquake.

This report is structured to describe the methodology by which this re-evaluation was undertaken and to present a summary of the results obtained from the evaluation. Detailed evaluation information is included as a part of this report.

The detailed evaluation is summarized on the equipment evaluation summary sheets taken from the original supplementary seismic evaluation report EF2-53332 dated July 15, 1981.

2.0 METHODOLOGY

2.1 Five percent structural damping response spectra were generated by an approximate method and are included as part of the reference 1 report. These spectra indicate a maximum amplification in the resonate frequency region of 21% over the 7% values. This maximum resonate amplification changes as a function of building location and ranges to a low peak value of 13%. Amplification is not observed in regions of the spectra away from building resonate frequencies. Both the zero period accelerations and the low frequency accelerations duplicate the 7% curves.

2.2 Existing reassessment results are included as a part of reference 2. This report thus establishes a baseline of equipment adequacy for the 7% structural damping input excitation. As an integral part of the calculation summary tabulation, safety margins existing relative to the 7% excitation have been established for most items. Safety margins existing for other items exist in calculation form in earlier revisions of the reference 2 report.

2.3 The evaluation approach for 5% structural damping input excitation was straight forward. Results of this evaluation have been included on a copy of the 7% damping equipment summary report in existence and are included as a part of this basic report.

All items with a safety margin greater than 21% were immediately considered to be acceptable relative to the 5% earthquake excitation input. The actual safety

margin for these items might be larger in light of the fact that the 21% amplification occurs only in narrow frequency regions on the design spectra but need for further refinement seems unnecessary at this time.

If the safety margin for a given item of equipment was less than 21% than the spectra for the actual equipment location were evaluated to determine if a lower peak amplification value would be in order. If so, the item was considered acceptable. If not, further investigation ensued considering the actual item frequency response and the portion of the total stress assignable to seismic excitation phenomena.

Anticipated maximum stress levels have been determined for all critical equipment items. These stress levels have been compared with yield point stresses for ultimate acceptability justification purposes.

2.4 Ductility was established as allowable in consideration of the evaluation of any Fermi equipment items. The limited pieces of equipment postulated to exceed yield point stress limits have been evaluated relative to an artificial stress bound established 20% above the yield point limit to correspond to an arbitrary but small amount of allowable ductile response in the inelastic region during the reassessment earthquake excitation.

Equipment items that may exhibit ductility phenomena have been specifically delineated on the detailed evaluation sheets with this report.

3.0 SUMMARY OF RESULTS

The detailed evaluation of the Fermi Seismic Reassessment items to 5% rather than 7% structural damping identified no additional items requiring re-evaluation or replacement. With the exception of those items identified as requiring further evaluation for 7% structural excitation and three items identified with a potential inelastic response, all Fermi reassessment equipment items remain below yield point stress levels when subjected to a 5% structural damping excitation.

The three items identified as having a potential for inelastic response due to the higher reassessment earthquake are the RPV top guide, HVAC PD 300 fire damper, and the Plenum for HVAC multi-zone unit.

A reference tabulation and our detailed evaluation summary information are included as the following items in this report.

HOPPER AND ASSOCIATES
ENGINEERS

REFERENCES

1. Enrico Fermi Atomic Power Plant, Unit 2, Constructed Equipment Response Spectra for 5% and 7% Structural Damping and 2% Equipment Damping, Hopper and Associates, Aug. 27, 1981
2. Enrico Fermi Atomic Power Plant, Unit 2, Supplementary Seismic Evaluation Report, EF2-53332 Rev. 0 and Rev. 1, Detroit Edison Company, July 15, 1981.

TABLE 5.3-1

LOADS FOR CERTAIN RPV AND INTERNAL COMPONENTS

	<u>Horizontal</u>	<u>Vertical</u>	<u>Allowable</u>
Top Guide (Shear)	350	31.7	687 kip (1)
Core Plate (Shear)	347	361	687 kip (1)
Stabilizer (Load)	513	0	2,765 kip (2)
RPV Support (Moment)	221,000	N/A	1,152,000 in-kip (1)
RPV Support (Shear)	679	1,191	2,600 kip (1)
CRD Housing (Moment)	507	N/A	18,870 in-kip (2)
CRD Housing (Shear)	14	Negligible	4,400 kip (1)
CRD Restraint Beam (Load)	14	N/A	266 kip (2)
Shroud Support (Moment)	276,000	N/A	347,900 in-kip (2)
<u>Shroud Support (Shear)</u>	<u>1,176</u>	<u>1,031</u>	<u>1,434 kip (2)</u>
Fuel Assembly (Moment)	12,024	See Section 5.3.1	32,200 in-kip
Fuel Assembly (Shear)	250	See Section 5.3.1	687 kip

(1) From Fermi 2 mathematical model 761E774, Revision 4

(2) From equipment design spec. or analysis

Minimum safety margin in shroud support

$$= \frac{1434}{1176} = 1.22 > 1.21 = \text{Maximum}$$
amplification going from 7% structural damping to 5% structural damping.

TABLE 5.3-1 (Continued)

LOADS FOR CERTAIN RPV AND INTERNAL COMPONENTS

	<u>Plant</u>	<u>Load Combination</u>	<u>Vertical Force (kips)</u>	<u>Horizontal Force (kips)</u>
Core Plate	LaSalle 1	E1	423	471
	Fermi 2	New Seismic	361	347
<u>Top Guide</u>	LaSalle 1	B2	40.8	<u>332</u>
	Fermi 2	New Seismic	31.7	<u>350</u>

Load Combinations

$$E1 = NL + (U - \Delta P) + SRV + SSE$$

$$B2 = NL + (A - \Delta P) + Chg. + SRV - 1 + SSE$$

Minimum safety margin in top guide horizontally = $\frac{332}{350} = .95$.

Attached calculations establish RPV system frequency at 6.06 cps. At RPV frequency maximum horizontal amplification from 7% to 5% damping = $\frac{2.68}{2.40} = 1.12$

Potential overstress = $\frac{1.12(.9)^{.95}}{.95} = 1.06 < 1.20$ limit established for ductile response. O.K.

Ductility possible.

• V. H. Inoué decision factor

RPV

Determine system frequency per GE 22A1300BC:
Appendix A

Per the original dynamic analysis 5L-2EE
the pedestal runs between node points
12 and 29 and is designated as member
17 and 18.

$$I_{18} = 27741 \text{ ft}^4, A_{18} = 364 \text{ ft}^2$$

$$I_{17} = 25421 \text{ ft}^4, A_{17} = 315 \text{ ft}^2$$

$$E = 552,000 \text{ Ksf}$$

$$L_{18} = (597' - 11") - (584' - 4") = 13' - 7" = 13.583'$$


$$L_{17} = (584' - 4") - (572' - 1") = 12' - 3" = 12.25'$$

Following G.E.

$$\Delta = \frac{1}{552,000} \left\{ \frac{13.583^3}{3(27741)} + \frac{5}{364} (13.583) + \frac{12.25^3}{3(25421)} + \frac{5}{315} (12.25) \right\}$$

$$= 7.88 \times 10^{-7}$$

$$K = \frac{1}{\Delta} = 1,268,264.$$



From the chart

$$T = .165 \text{ sec}$$

$$f = 6.06 \text{ cps}$$

TABLE 5.3-2

HYDRAULIC CONTROL UNIT

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	% Margin	Analysis Report #	% Margin of Safety	
Hydraulic Control Unit, HPL C11D001	X		DRP 147-C11D001-N*5-5	B5 B6 B29 B30 C6 C16 All dated 4/18/72	C16 dated 4/18/72 Vertical B29 & B30 dated 4/17/81 Horizontal	1300% 500% 500% Vertical cal	DRP 147-C11D001-N*5-5A	1300% Horizontal cal 500% Vertical	<p>The new peak response spectra curves were 1.05 g's horizontal capability of the HCU is 1.1 g's = 1300% margin by test, horizontal</p> <p>Vertical was 2.8 g's peak vs 14 g's capability by test = 500% margin, therefore the HCUs are acceptable.</p>

All safety margins greater than maximum load amplifications.

TAB. 5.3-3

RBR PUMP ANCHORS

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
RBR Pump Anchor Bolts		X	Edison Design Calculation	.15 g horz. .10 g vert.	S & L report SDD-DECo-003 Figures 3 C-11	1415% on yield on yield		N/A	The Anchor bolt stresses were recalculated by applying the new site-specific seismic loads, the equipment nozzle loads from the attached piping, and the equipment dead weight loads. The shear and tension stresses were combined and shown to be less than the new allowable values; therefore, the equipment is requalified to the new site-specific earthquake.

Safety margin greater than maximum load amplification.

TAB. 5.3-3A

RIIR HEAT EXCHANGER AND ANCHORS

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
RIIR Heat Exchanger and anchor bolts	X		See G.E. Letter TDEC-4002 dated 6/22/81	1.5 g horiz. 0.14 g vert.	0.4 G horiz. 0.36 G vert.	5t on yield		N/A	The stresses resulting from the site specific SSE were obtained by multiplying the OBE allowable stresses (based on .75 G horiz, .07 G vertical) by the vertical acceleration ratio and comparing with SSE allowable (yield). The stresses due to nozzle loads and deadweight were also increased even though they didn't change. The calculated stresses are less than the new allowable values; therefore, the equipment is qualified to the site specific SSE.
	<p>Vendor qualified to 1.5g in any direction.</p> <p>As approximations</p> $\sqrt{.44^2 + .42^2 + .36^2} = .67$ $\frac{.67}{.50} = 1.34 > 1.21$ <p>Safety margin greater than maximum load amplification.</p>								

TABLE 5.3-3B

RCIC PUMP ANCHOR BOLTS

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	% Margin	Analysis Report #	% Margin of Safety	
RCIC Pump anchor bolts		X	Edison Design calculation DC-369 Item 2	.15 G horiz. .10 G vert.	S & L report SOD-DECO-003 figures J C-11	609% BASED ON yield		N/A	The anchor bolt stresses were recalculated by applying the new site-specific seismic loads, the equipment nozzle loads from the attached piping, and the equipment dead weight loads. The shear and tension stresses were combined and shown to be less than the new allowable values; therefore, the equipment is requalified to the new site-specific earthquake.

Safety margin greater than maximum load amplification.

TABLE 5.3-4
 RCIC TURBINE ANCHOR BOLTS
 SEISMIC RE-EVALUATION
 SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
RCIC Turbine anchor bolts		X	Edison file No. DC-369 Item 2	1.5 g Horiz .14 g vert.	S & L report SDO-DECo-003 Fig's 3 C-11	25.6%		N/A	The new stresses were conservatively estimated by multiplying the original stresses by the largest acceleration increase comparing all three directions. These new stresses are below the new allowable values; therefore, the equipment is requalified to the new site-specific earthquake.

Safety margin greater than maximum load amplification

TABLE 5.3-5

RCIC PUMP SUCTION STRAINER

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
RCIC Pump suction strainers (Leslie) PIS # E5101D011		X	Edison File No. PI-2416	5 g horz. 3 g vert.	S & L Report SDD-DECO -003 Fig's. 3 C-11	N/A		N/A	The new site-specific earthquake accelerations are less severe than the acceleration loadings that were used in the original seismic qualification; therefore, this equipment is requalified.

Minimum safety margin = 3.8 due to vertical excitation. This margin is greater than the maximum load amplification.

TABLE J.3-6

RHR SERVICE WATER
SEISMIC RE-EVALUATION
SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. 1	Margin	Analysis Report #	Margin of Safety	
RHR Cooling Tower Equip. No. E1156B001A, B, 2A, B Location RHR Elevation 617		X	Marley Co. dated 2-8-74 S & L EMD- 011785				S&L EMD- 029950	111 BASED on tornado loads	Beams were found to be flexible and the resultant acceleration is above ZPA. The piping was found to be close to rigid. Fill stresses are very low. Eliminator stresses are very low. Fill retainers & eliminator retainers are analyzed based on tornado loads (higher loads). Stresses on the following mechanical equipment and parts are: Motor Support Branch Arm Pipe Support Anchor Bolts Embedment Tornado loads are governing loads. Stresses are within allowables.
RHR Service Water Pump and Motor Equip. No. E1151C001A, C & D Location RHR Elevation 596*		X	McDonald Eng. Analysis dated 2-4-74 Goulds Pump Inc. dated 9-23-75 (motor)				S&L EMD- 029950	>100%	Stresses are below yielding limits. Water pump and motor qualified to new response spectra.

Safety margins greater than maximum load amplifications.

* For Flange based on yield.

TABLE 5.3-7

DIESEL GENERATOR COMPONENTS

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion And Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	% Margin	Analysis Report #	% Margin of Safety	
Diesel Generator Skid Assembly Equip. No. R10015001-4 Location BHR Elevation 590' Elevation 590'		X	Colt Ind. Report dated 4-4-75 S&L EMD-001659				S&L EMD-029950	53% *	Stresses are well within allowables. Skid assembly qualifies to new response spectra.
Heat Exchanger Stack Assembly Equip. No. R10015001-4 Location BHR Elevation 590'		X	Colt Ind. Report dated 4-4-75 S&L EMD-001659				S&L EMD-029950	>100% *	The equipment qualifies to new response spectra. Stresses very low.

Safety margins greater than maximum load amplifications.

* Turbocharger mounting bolts based on allowables

** For attachment plate based on allowables

DIESEL GENERATOR COMPONENTS

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure/ Component Description	Method of Original Qualification		Re-Evaluation Results					Conclusion and Remarks	
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin %	Analysis Report #		Margin of Safety
Diesel Generator Skid Piping Equip. No. R10015001-4 Location 101R Elevation 590'	X		Colt Ind. Report dated 4-4-75 S&L EMD-001659		<i>Calculations show acceptability.</i>		S&L EMD-029950	171* 1003***	The equipment qualifies to new response spectra. Stresses are within allowable.
	X		Colt Ind. Report dated 4-4-75 S&L EMD-001659		<i>Safety margins greater than maximum load amplifications.</i>		S&L EMD-029950	531** 1003***	The equipment qualifies to new response spectra. Stresses very low.
	X		Colt Ind. Report dated 4-4-75 S&L EMD-001659				S&L EMD-029950	1003*** 1003***	The equipment qualifies to new response spectra. Stresses very small.
Jacket Water Expansion Tanks Equip. No. R1000A005-8 Location 101R Elevation 604' -2"									
Air Receiver Tank Equip. No. R1000A009-16 Location 101R Elevation 590'									
<p>* In piping based on allowable</p> <p>** For mounting flange based on allowable</p> <p>*** In bolts based on allowable</p>									

* In piping based on allowable

** For mounting flange based on allowable

*** In bolts based on allowable

D.G. Skid Piping

Governing situation - intercooler water - cooler to engine. (Ref: Colt Stress Report)

21.5 cps mode \rightarrow .25 \overline{g} 's input - 3 directions

Maximum stress = 2057 psi

Allowable stress = 27,000 psi

Maximum accelerations from 5% spectra at 21.5 cps

NS = .32 \overline{g} 's

EW = .39 \overline{g} 's

Vert = .80 \overline{g} 's

$$\frac{.86}{.25} (2057) = 7076 \text{ psi} < 27,000 \text{ psi}$$

TABLE 5.3-9

DIESEL GENERATOR FUEL OIL
SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
Fuel Oil Day Tanks Equip. No. R1000A017-20 Location BHR Elevation 590'		X	Colt Ind. Report dated 4-17-74 S&L EMD- 001659		<i>Calculations show acceptability.</i>		S&L EMD- 29950	100*	Stress levels due to re- vised response spectra are within allowable values. This component is requalified.

* For tank holddown bolts
based on allowables.

D.G. Fuel Oil Day Tanks

Governing situation - shell bending stress
(Ref: Colt Stress Report)

Maximum stress = 8856 psi

Direct	Freq	Accel.	New Accel/5% Spectra
Vert	15.5	.27	1.9
EW	12.7	.28	.49
NS	13.9	.3	.45

$$\frac{1 + 1.9}{1 + .27} (8856) = 20 \text{ ksi. Acceptable}$$

TABLE 5.3-10

DIESEL GENERATOR LUBE OIL

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
Lube Oil Strainer Equip. No. R10015001-4 Location 40th Elevation 590'	X		Colt Ind. Report dated 4-4-75				S&L EMD- 079950	1.01*	Stress levels due to revised response spectra are within allowable values. This component is requalified.

Calculations show acceptability.

* For shell based on allowable.

D.G. Lube Oil Strainer

Governing situation - shell stress (Ref. Colt Stress Report)

Maximum stress = 9814 psi

Minimum frequency = 29 cps

Vert. Accel = .09 g's

.36 g's Max g's 5

Lateral Accel = .24 g's

.33 g's Max g's 5

$$\frac{1.36}{1.09} (9814) = 12 \text{ ksi Acceptable}$$

$$\frac{.33}{.24} (9814) = 13 \text{ ksi Acceptable}$$

TABLE 5.-11

DIESEL GENERATOR LUBE OIL

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report	Spectra	Spectra Comparison Fig. 1	Margin	Analysis Report	Margin of Safety	
Lube Oil Filter Equip. n. R10015001-4 Location 101H Elevation 500'		X	Colt Ind. Report dated 4-4-75 S&L EMD- 001659				S&L EMD- 029950	7100%*	Stress levels due to re- vised response spectra are within allowable values. This component is requalified.

*Safety margin greater than
maximum load amplification*

* For shell based on allow-
ables.

TABLE 5.3-12
DIESEL GENERATOR FUEL OIL
SEISMIC RE-EVALUATION
SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	% Margin	Analysis Report #	% Margin of Safety	
Fuel Oil Storage Tanks Equip. No. R300A001-4 Location RHR Elevation 590'		X	Graver Tank & Mfg. Co., dated 6-5-74 S&L EMD- 008913				S&L EMD- 029950	-97% GENERAL	Additional bolts are re- quired at the foundation support. All other cal- culated stresses are be- low allowables. See Section 5.4

Item on existing requalification list.

* For foundation bolts based
on yield.

TABLE 5.1-13

EMERGENCY EQUIPMENT COOLING WATER

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification			Re-Evaluation Results				Conclusion and Remarks
	Test Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
ECM Pump and Motor (Includes Anchors) PIS # P4400C001A	X	Edison File No. 524-116	1.41 horz. .5 vert.	S&L Report SDP-DECO -003 F1 uses B-11 A-12 C-16	93% margin on original allow- ables except for pump outboard bearing See remarks		N/A	For the equipment's critical components the original qualification used the vector sum of the vertical and horizontal accelerations on the equipment's seismic loading. The vector sum of the NS, EW, & vertical accelerations obtained from the new site-specific response spectra was divided by the acceleration value used in the original qualification to determine the "acceleration increase". The new stresses were conservatively estimated by multiplying the original stresses by this "acceleration increase". These new stresses are below the new allowable values; however, the pump outboard bearing radial load (82261) is 40% greater than its original allowable load rating of 62151 at 100 hours of operation. When a bearing is subjected to a constant load greater than its rated load, the bearing life is reduced. For a constant bearing load of 82261, it is estimated that the bearing life would be reduced from 100 hrs. to 10 hrs.
<p>Our S&L calculations show the following capability when evaluated for seismic safety margin considering the actual portion of total stress assignable to earthquake excitation:</p> $\frac{1.35}{1.05} = 1.3 \times 1.021.$ <p>Safety margin greater than minimum load amplification.</p>								

TABLE 3.3-13 (continued)

EMERGENCY EQUIPMENT COOLING WATER

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
EECW Pump and Motor (Includes anchors) PIS IP4400C001A									however, the seismic loading is clearly not constant but occurs for a maximum duration of 10 seconds, therefore, The equipment is requalified to the new site-specific earthquake.

TABLE 2.3-14

EMERGENCY EQUIPMENT COOLING WATER

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
EECW Make-up tank (including anchor bolts) PIS 1P4400A001		X	Edison File No. S20-24	S&L Report SL-2682 Figures B-31 B-32 B-16	S&L Report SDD-DECO -001 Figures B-31 B-32 C-16	1.33 Based on yield		N/A	The original seismic stresses were separated out of the original qualification, increased for the new site-specific earthquake, and then added to the original normal operating and deadweight loads. The new stresses are below the new allowable values; therefore, the equipment is requalified to the new site-specific earthquake.

*Calculations show
acceptability.*

EECW Make Up Tanks

2nd Flr. R.B. location

$$\text{Max Horiz Amp} = 1.13$$

$$\text{Max Vert Amp} = 1.12$$

$$I_{\text{vert}} = 1.2(1.36) + 2.23 + 1 = 3.66$$

$$I_{\text{H}} = 1.15(1.36) + .38 = .67$$

$$I_{\text{H-1}} = 1.13(1.45) + .38 = .92$$

Stress summary

$$\begin{aligned} 3.66(3820) + .67(5044) + .92(6041) \\ + 9650 &= 33.2 < 37.7 \text{ ksi} \end{aligned}$$

Acceptable

TABLE 5.2-15

EMERGENCY EQUIPMENT COOLING WATER

SEISMIC RE-EVALUATION

SUPPLEMENTARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	% Margin	Analysis Report #	% Margin of Safety	
EECW Heat exchanger (including anchor bolts) PIS 1P44000001		X	Edison File No. S21-7	S&L Report SL-2682 Figures B-31 B-32 C-16	S&L report SDD-DECO-003 Figures B-31 B-32 C-16	29.3% factored on yield		N/A	The new stresses were conservatively estimated by multiplying the original stresses by the largest acceleration increase comparing all three directions. These new stresses are below the new allowable values; therefore, the equipment is requalified to the new site specific earthquake.

Safety margin greater than maximum load amplification at this location. (13%)

TABLE 5.3-16

DIESEL GENERATOR SERVICE WATER

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report	Spectra	Spectra Comparison Fig. 1	Margin	Analysis Report	Margin of Safety	
Motor for Diesel Generator Service water pumps and emergency equipment Equip. No. R000C005-B Location RMR Elevation 590'		X	Allis Chalmers dated 5-11-76 S&L EMD- 003791				S&L EMD- 0029950	20%*	Stresses are within the allowable limits. Motor qualifies to new response spectra.
Diesel Generator Service Water Pump *		X							See Section 5.4

Safety margin greater than maximum load amplification at this location. (13%)

** Item on existing requalification list.*

* For anchorage bolts based on allowables.

TABLE 5.3-17

EMERGENCY EQUIPMENT SERVICE WATER

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results			Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Analysis Report #	Margin or Safety	
Emergency Equipment Service Water Pumps Equip. RO. P4500C002A, B Location RHR Elevation 590*	X		McDonald Eng. Rep. ME-229 dated 6-21-75 S&L EMD-001554		<i>Safety margin greater than maximum load amplification.</i>	S&L EMD-029950	43% 20%	Stresses and deflections are below allowable. Pump qualifies to new response spectrum.
Motor for Diesel Generator Service Water pumps and emergency equipment Equip. RO. R100C005-B Location RHR Elevation 590*	X		Allis Chalmers dated 5-13-76 S&L EMD-003791		<i>Safety margin greater than maximum load amplification at this location. (WR)</i>	S&L EMD-029950	20% 43%	Stresses are within the allowable limits. Motor qualifies to new response spectra.

* In shaft deflection based on allowable.

** For anchorage bolts based on allowable.

TABLE 5.3-18

CONTROL AIR

SEISMIC RE-EVALUATIONSUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report	Spectra	Spectra Comparison Fig. 1	% Margin	Analysis Report	% Margin of Safety	
Control air compressor and motor (including anchor bolts) PIS # P50020001		X	Edison File No. B11-179 B11-506	S&L report SL-2682 Figures B-29 B-30 C-16	S&L report SDD-DECO -003 Figures J C-11	189% 115% on yield		N/A	The new stresses were con- servatively estimated by multiplying the original stresses by the largest acceleration increase comparing all three direc- tions. These new stresses are below the new allow- able values; therefore, the equipment is requali- fied to the new site- specific earthquake.

*Safety margin greater than
maximum load amplification.*

TABLE 5.3-19

CONTROL AIR AFTER COOLER

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
Control air after-cooler (including anchors) PIS IP5002B004		X	Edison File No. 011-405	2.4 g horz. 1.9 g vert.	S&L report SDD-DECO -003 Figures B-29 B-30 C-11	N/A		N/A	The new site-specific earthquake accelerations are less severe than the acceleration loadings that were used in the original seismic qualification; therefore, this equipment is requalified.
<p><i>Safety Margins to 8% excitation.</i></p> <p><i>Horiz = $\frac{2.4}{2.02} = 1.18$</i></p> <p><i>Vert = $\frac{1.9}{.78} = 2.44$</i></p> <p><i>Items satisfactorily qualified.</i></p>									

TABLE 5.3-20

CONTROL AIR

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
Control Air Receiver P15P15002A001		X	Edison Pile No.	S&L Report SL-2682 Figures B-5 B-6 B-29 B-30 C-6 C-16	S&L Report SDD-DECo- 003 Figures B-29 B-30 C-11	N/A		N/A	The new site-specific earthquake accelerations are less severe than the acceleration loadings that were used in the original seismic qualification; therefore, this equipment is requalified.
<p><i>Safety margins to 5% excitation.</i></p> <p><i>Horiz = $\frac{2.6}{2.03} = 1.03$</i></p> <p><i>Vert. = $\frac{2.2}{.78} = 2.82$</i></p> <p><i>Items satisfactorily qualified.</i></p>									

HVAC DUCTS

SEISMIC RE-EVALUATIONSUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report	Spectra	Spectra Comparison Fig. 1	Margin	Analysis Report	Margin of Safety	
HVAC Ducts		X							<p>A survey of maximum duct moments due to seismic and dead weight loads indicates that values are within allowable limits. This component is requalified to the site-specific SSE.</p> <p><i>Safety margin in initial reassessment was 3.0 minimum which is greater than maximum load amplification.</i></p>

ESSENTIAL HVAC DAMPERS
SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
PD 300 Fire Damper		X	Edison File No. B9-2175	S&L Report SL-2682 Figures B-37 C-19	S&L Report SDD-DECO-003 Figures B-37 C-19	7% BASED on yield		N/A	The original seismic stresses were separated out of the original qualification, increased for the site-specific SSE, and added to the normal operating loads (in cases where stresses were low, the combined normal operating and seismic stresses were increased by the worst acceleration ratio). Calculated stresses are below the new allowable values; therefore the equipment is requalified to the site-specific SSE.
Backdraft Damper (Pacific Air Products Company)		X	B9-2175	B-37 C-19	B-37 C-19	100% BASED on original allowable		N/A	
Air Damper (Pacific Air Products Company)		X	B9-2175	B-37 C-19	B-37 C-19	10% BASED on original allowable		N/A	
Flexible Hose		X	B9-2175	B-37 C-19	B-37 C-19	large BASED on original allowable		N/A	

* $\frac{1.21}{1.07} = 1.13 < 1.20$ limit established for ductile response. O.K.
Ductility possible.

*** Safety margins greater than maximum load amplifications.

TABLE 5. (Continued)

ESSENTIAL HVAC DAMPERS

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report	Spectra	Spectra Comparison Fig. 1	Margin	Analysis Report	Margin of Safety	
Fire Dampers and Air Control Damper (Air Balance Inc.)	X		B9-2131 or B9-2175 TAB IV	Test input acceleration of 5 g minimum	B-37 C-19	28% *		N/A	The original test response spectra envelope the new site-specific response spectra; therefore, this equipment is requalified.
Damper Motor Mountings for T4100F157A & B (thru F163A & B		X	Edison File No. B9-2174	S&L Report SL-2682 Figures B-37 C-19	S&L Report SDD-DECO-003 Figures B-37 C-19	46% * Based on yield		N/A	The new stresses were conservatively estimated by multiplying the original stresses by the largest acceleration increase comparing all three directions. These new stresses are below the new allowable values; therefore, the equipment is requalified to the new site-specific earthquake.
Damper Motor Mountings for T4100F070 thru F073		X	Edison File No. B9-2150	S&L Report SL-2682 Figures B-37 B-38 C-9	S&L Report SDD-DECO-003 Figures B-37 B-38 C-19	4.1% * Based on yield		N/A	The new stresses were conservatively estimated by multiplying the original stresses by the largest acceleration increase comparing all three directions. These new stresses are below the new allowable values; therefore, the equipment is requalified to the new site-specific earthquake.

* Safety margins greater than maximum load amplification

** At 4.33 cps frequency and 677'-6" location following are accelerations:

EW	Used	5% value
NS	4.16	3.60
Vert	3.64	2.10
		.50

1. A 1.

TABLE 5. 3 (Continued)

ESSENTIAL HVAC DAMPERS

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report	Spectra	Spectra Comparison Fig. 1	Margin	Analysis Report	Margin of Safety	
Fire Dampers T4100F099 & F102 T4100F111 & F112 T4100F086		X	Edison File No. B9-2184	S&L Report SL-2682 Figures B-37 C-9	S&L Report SDD-DECO- 001 Figures B-37 B-38 C-19	5.43 Based on yield		N/A	The new stresses were conservatively estimated by multiplying the original stresses by the largest acceleration increase comparing all three directions. These new stresses are below the new allowable values; therefore, the equipment is requalified to the new site-specific earthquake.
Butterfly Dampers (Valves) Type 4340 Damper Sizes 8", 10", 14", 18", & 48"		X	Edison File No. B9-1119	5 g (N-S) 5 g (E-W) 3 g (Vert)	S&L Report SDD-DECO- 001 Figures B-37 B-38 C-19	13.24 Based on yield		N/A	(as above)
Manual Air Dampers Sizes 32 x 30 26 x 24 48 x 48 36 x 36		X	Edison File No. B9-2176	S&L Report SL 2682 Figures B-37 B-38 C-19	S&L Report SDD-DECO- 001 Figures B-37 B-38 C-19	16.4 Based on yield		N/A	The original seismic stresses were separated out of the original qualification, increased for the new site-specific earthquake, and then added to the original normal operating and deadweight loads. The new stresses are below the new allowable values; therefore, the equipment is requalified to the new site-specific earthquake.

* Safety margins greater than maximum; load amplification.
 ** Computed stress for 5% excitation:
 $25.5(1.21) = 30.9 \text{ KSI} < \text{Yield}$
 Item satisfactory

TABLE 5.-23 (Continued)

ESSENTIAL HVAC DAMPERS

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report	Spectra	Spectra Comparison-Fig. 1	Margin	Analysis Report	Margin of Safety	
Type Coil Dampers 75" x 52" thru 16" x 16"		X	Edison File No. 09-761	S&L Report SL-2682 Figures B-37 B-38 C-19	S&L Report SDD-DECo- 003 Figures B-37 B-38 C-19	45% based on allowa- ble buck- ling load		N/A	The new stresses were conservatively estimated by multiplying the original stresses by the largest acceleration increase comparing all three directions. These new stresses are below the new allowable values; therefore, the equipment is requalified to the new site-specific earthquake.
112" x 11" Control Room Dampers		X	Edison File No. 09-761	1.1 g (N-S) 1.5 g (E-W) 1.5 g (Vert)	S&L Report SDD-DECo- 003 Figures B-37 B-38 C-19	162% based on yield		N/A	(as above)
Fire Dampers FISIT4100F		X	Edison File No. 09-2090	0.6 g (NS) 0.6 g (EW) 0.6 g (Vert)	S&L Report SDD-DECo- 003 Figures B-37 B-38 C-15	N/A		N/A	The new site-specific earthquake accelerations are less severe than the acceleration loadings that were used in the original seismic qualification; therefore, this equipment is requalified.

All safety margins greater than maximum load amplifications.

TABLE J.3-24

HVAC RETURN AIR FANS

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	% Margin	Analysis Report #	% Margin of Safety	
Return Air Fan (Including Anchor Bolts) PISIT4100C011		X	Edison File No. B9-365	S&L Report SL-2682 Figures B-37 B-38 C-19	S&L Report SDD-DECo- 003 Figures B-37 B-38 C-19	weakest compo- nent has a 0% margin based on yield		N/A	The new stresses were conservatively estimated by multiplying the original stresses by the largest acceleration increase comparing all three directions. These new stresses are below the new allowable values; therefore, the equipment is requalified to the new site-specific earthquake.

Calculations show acceptability.

Return Air Fan

5th Flr Air Bl'g. 684'-0"

$$T_{Horiz} = 12 \text{ cps} \quad , \quad T_{Vert} = 21.2 \text{ cps}$$

$$NS = .74 \text{ g's}$$

$$\text{Load} \quad .63$$

$$EW = .92 \text{ g's}$$

$$.62$$

$$Vert = 1.55 \text{ g's}$$

$$1.7$$

$$\frac{.92}{.63} (21.7) = 31.7 \text{ ksi} < \text{Yield}$$

Acceptable

HVAC CENTRIFUGAL CHILLING UNITS

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
Centrifugal Chilling Units (Includes Anchors) PISIT41000008 & 9		X	Edison File No. B9-651	S&L Report SL-2682 Figures B-37 B-38 C-19	S&L Report SDD-DECo- 003 Figures B-37 B-38 C-19	22.13 based on ori- ginal allow- able		N/A	The new stresses were conservatively estimated by multiplying the original stresses by the largest acceleration increase comparing all three directions. The new stresses are below the new allowable values; therefore, the equipment is requalified to the new site-specific earthquake.
Rupture Disc for Centrifugal Chilling Units	X		Edison File No. B9-684	10 g Input	S&L Report SDD-DECo- 003 Figures B-37 B-38 C-19	2100%		N/A	The original qualification indicates that the disc was subjected to a 10 g input. This acceleration is well above the new site-specific response spectra; therefore, the equipment is requalified to the new site-specific earthquake.

All safety margins greater than maximum load amplifications.

HVAC EMERGENCY MAKE-UP MOTORS

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report	Spectra	Spectra Comparison Fig. 1	Margin	Analysis Report	Margin of Safety	
Emergency Make-up Motors for Fans with PIS 1's T41000047 & 16		X	Edison File No. B9-1196	S & L Report SL-2682 Fig's B-37 B-38 C-19	S & L Report SDD-DECO- 003 Fig's B-37 B-38 C-19	N/A		N/A	The new site-specific earthquake accelerations are less severe than the acceleration loadings that were used in the original seismic qualification; therefore, this equipment is requalified.

Existing safety margin (8.8)
greater than maximum load
amplification.

HVAC EMERGENCY MAKE-UP AIR RECIRCULATION AIR FILTERS UNITS

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
Emergency Make-up Fans PIS # T41000047 & 16		X	Edison File No. B9-1387	S & L Report SL-2682 Fig's B-37 B-38 C-19	S & L Report SDD-DECO-003 Fig's B-37 B-38 C-19	214% Based on Yield		N/A	The new stresses were conservatively estimated by multiplying the original stresses by the largest acceleration increase comparing all three directions. These new stresses are below the new allowable values; therefore, the equipment is re-qualified to the new site-specific earthquake.
Emergency Make-up Filters PIS # T41000011		X	Edison File No. B9-762	Fig's B-13 B-14 C-9 of S & L Report SL-2682	Fig's B-37 B-38 C-19 of S & L Report SDD-DECO-003	70.4% Based on Yield		N/A	The new stresses were conservatively estimated by multiplying the original stresses by the largest acceleration increase comparing all three directions. These new stresses are below the new allowable values; therefore, the equipment is re-qualified to the new site-specific earthquake.

All safety margins greater than maximum load amplifications.

HVAC MULTI-ZONE CLIMATE CHANGER

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification			Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety
Multi-Zone Climate Changer PIS # T41001007	X		Edison File No. B9-544 B9-674	S & L Report SL-2682 Fig'a B-37 B-38 C-19	S & L Report SDO-DECO-003 Fig'a B-37 B-38 C-19	Weak-est Component has 0% Margin Based on Yield		N/A
								The new stresses were conservatively estimated by multiplying the original stresses by the largest acceleration increase comparing all three directions. These new stresses are below the new allowable values; therefore, the equipment is requalified to the new site-specific earthquake.
Plenum for HVAC Multi-Zone Unit	X		Edison File No. B9-2203	S & L Report SL-2682 Fig'a B-37 B-38 C-15	S & L Report SDO-DECO-003 Fig'a B-37 B-38 C-15	Weak-est Component has 0% Margin Based on Yield		N/A
								The new stresses were conservatively estimated by multiplying the original stresses by the largest acceleration increase comparing all three directions. These new stresses are below the new allowable values; therefore, the equipment is requalified to the new site-specific earthquake.
Plenum Casing Access Door for HVAC Multi-Zone Unit	X		Edison File No. B9-2202	S & L Report SL-2682 Fig'a B-37 B-38 C-9	S & L Report SDO-DECO-003 Fig'a B-37 B-38 C-19	N/A		N/A
								The new site-specific earthquake accelerations are less severe than the acceleration loadings that were used in the original seismic qualification; therefore, this equipment is requalified.

See attached order slips
it is High frequency item. No amplification anticipated.

Walt - Zone Climate Chamber

4/1

Aux. Bldg. EI 677'-6"

For worst case (18.1 cps max) amplification = 1.09

$$1.09(28.9) = 31.5 \text{ ksi} < \text{Yield}$$

Acceptable

Plenum

EI 684'-6" R.B.

Highest stress = 36.8 ksi

Maximum amplification = 1.18

$$36.8(1.18) = 43.4 \text{ ksi} > \text{Yield}$$

$$\frac{43.4}{30.0} = 1.45$$

Limit of acceptability
Ductility probable

HVAC CHILLED WATER PUMP AND MOTOR

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
Chilled Water Pump and Motor PIS # T4100C040 & 41		X	Edison File No. N9-651 N9-1875	Pumps 1 g N-S 1 g E-W 2 g Vert MPR's 1.6 g N-S 4.25 g E-W 1.6 g Vert	S & L Report SDD-DECO- 003 Fig's B-17 B-38 C-19	N/A		N/A	The new site-specific earthquake accelerations are less severe than the acceleration loadings that were used in the original seismic qualifi- cation; therefore, this equipment is requalified.

*Safety margin (4.54) greater
than maximum load amplification.*

HVAC COOLERS

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report	Spectra	Spectra Comparison Fig. 1	Margin	Analysis Report	Margin of Safety	
Switchgear room Coolers EECW Pump Room Coolers Control Air Compressor Cooler (T41-000001 &) T41-000014 T41-000029 (Respectively)		X	Edison File No. B9-643	B13, B14, C19 SL-2682 (Vertical Times 2.0)	B13, B14, C-19 S & L Report SDD-DECo- 003	20% Based on Yield		N/A	The original seismic stresses were separated out of the original qualification, increased for the site-specific SSE, and added to the normal operating loads. Calculated stresses are below allowable; therefore, the equipment is requalified to the site specific SSE.

Safety margin greater than maximum load amplification at this location.

RHR ROOM COOLERS

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report	Spectra	Spectra Comparison Fig. 1	Margin	Analysis Report	Margin of Safety	
RHR Room Cooler (Including Anchor Bolts) PISIT41000018		X	Edison File No. b9-554	S&L Report SL-2682 Figures B-29 B-30 C-14	S&L Report SDD-DECo-003 Figures B-29 B-30 C-14	N/A		N/A	The new site-specific earthquake accelerations are less severe than the acceleration loadings that were used in the original seismic qualification; therefore, this equipment is requalified.

Safety margin (1.36) greater than maximum load amplification.

HVAC Equipment Room Fan-Coil Unit

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
Equipment Room Fan-Coil Unit PISIT4100B028		X	Edison File No. B9-554	S&L Report SL-2682 Figures B-37 B-38 C-19	S&L Report SDD-DECo- 003 Figures B-37 B-38 C-19	5114 based on yield		N/A	The new stresses were conservatively estimated by multiplying the original stresses by the largest acceleration increase comparing all three directions. These new stresses are below the new allowable values; therefore, the equipment is requalified to the new site-specific earthquake.

Safety margin greater than maximum load amplification.

TABLE 5.3-14

HVAC RCIC PUMP ROOM COOLER

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. 1	Margin	Analysis Report #	Margin of Safety	
RCIC Pump Room Cooler PIS4T4100B021		X	Edison File No. B9-554	S&L Report SL-2682 Exhibit 2 and Fig. C-11	S&L Report SDD-DECo- 003 Figures B-29 B-30 C-11	21.4% BASED on yield		N/A	The new stresses were conservatively estimated by multiplying the original stresses by the largest acceleration increase comparing all three directions. These new stresses are below the new allowable values; therefore, the equipment is requalified to the new site-specific earthquake.

Safety margin greater than maximum load amplification.

TABLE 5.3-35

HVAC CABLE TRAY COOLING PAN

SEISMIC RE-EVALUATIONSUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report	Spectra	Spectra Comparison Fig. 1	Margin	Analysis Report	Margin of Safety	
Cable Tray Cooling Pan PISIT4100C051	<i>Item on existing requalification list.</i>								See Section 5.4

HVAC EQUIPMENT ANCHORS

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
Anchor bolts for the following equipment:			Edison File No.	S&L Report SL-2682 Figures	S&L Report SDD-DECO-003 Figures				
EECW Pump Room Cooler		X	DC-575	B-31 B-32 C-16	B-31 B-32 C-16	257% based on yield		N/A	The anchor bolt stresses were recalculated by applying the new site-specific seismic loads. The resulting shear & tension stresses are below the new allowable stresses; therefore, the anchors will safely sustain the effect of the new site-specific earthquake.
Control Air Compressor Cooler		X	DC-577	B-29 B-30 C-18	B-29 B-30 C-18	376% based on yield		N/A	Same as above
Equipment Room Fan-coil Unit		X	DC-582	B-37 B-38 C-19	B-37 B-38 C-19	524% based on original allowable		N/A	Same as above
Chilled Water Pump and Motor		X	DC-585	B-13 B-14 C-9	B-37 B-38 C-19	119% based on original allowable		N/A	Same as above

All safety margins greater than maximum load amplification

HVAC EQUIPMENT ANCHORS

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report	Spectra	Spectra Comparison Fig. 1	Margin	Analysis Report	Margin of Safety	
Emergency Make-up Filter Unit		X	DC-593 B9-762	B-13 B-14 C-9	B-37 B-38 C-19	95.34 Based on yield		N/A	Same as above
Multi-zone Climate Changer		X	DC-589	B-37 B-38 C-19	B-37 B-38 C-19	23.1 Based on yield		N/A	Same as above
Switchgear Room Coolers		X	DC-572	B-33 B-34 C-19	B-33 B-34 C-19	N/A		N/A	The new site-specific earthquake accelerations are less severe than the acceleration loadings that were used in the original seismic anchor bolt calculations; therefore, the anchors are requalified.
RCIC Pump Room Cooler		X	DC-579	B-29 B-30 C-18	B-29 B-30 C-10	N/A		N/A	Same as above

All safety margins greater than maximum load amplifications.

DRYWELL COOLING SYSTEM

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Flg. #	Margin	Analysis Report #	Margin of Safety	
Drywell Cooling Fans P15FT4700C001 & 2		X	Edison File No. B9-1106 B9-1107	S&L Report SL-2682 Figures B-43 B-44 B-62	S&L Report SDD-DECO- 003 Figures B-59 B-57 B-62	N/A		N/A	The new site-specific earthquake accelerations are less severe than the acceleration loadings that were used in the original seismic qualification; therefore, this equipment is requalified.
Drywell Coolers & Anchors T4700B001 & 2		X	B9-637	B43, B44, B62	B59, B57, B62	-31			The cooler mounting feet show considerable margin with regard to yield stress. The cooling coil frame and anchor bolts are also adequate and are considered requalified.

* Safety margin greater than maximum load amplification at this location.

** Our SART evaluation of this item indicated a safety margin relative to failure of 4.0 which is greater than maximum load amplification.

TABLE 5.3-36

RRR COMPLEX HVAC

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
RRR Complex Pump Room Ventilation, Switchgear exhaust Ventilation A, B, Diesel Generator Ventilation Div. I & II Location RRR Elevations 590' - 617'		X	S&L EMD- 029830				S&L EMD- 029950 & EMD- 029830	20% 7.5 for angle attached to base plate	Reevaluation was based on a dynamic analysis of linear elastic structural model utilizing the method of response spectrum analysis. A continuous, uninterrupted operation and structural integrity of the subject systems during and following an earthquake was demonstrated in the above mentioned analysis. Stresses are within AISC allowables.
Control Dampers, type CD31-PB and OB Isolation Dampers, type CD R2-92 Location RRR		X	Ruskin Mfg. Co. CDR1-92 1/29/79 S&L EMD- 017492 3/20/79 EMD- 017187 2/14/79 2/27/79				S&L EMD- 029950	1.27*	Stresses are within the allowable limits. Control dampers qualify to new response spectra.
<p>* Safety margin greater than maximum load amplification at this location.</p> <p>** This item was assessed to be rigid. No amplification is observed for rigid items going from 7% to 5% damping.</p>									

* For top blade based on allowables

TABLE 5.3-36 (cont.)

RRR COMPLEX HVAC

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
RRR Complex Fans Equip. No. X-41-03-C01, 02, 03, 05, 06, 07, 08 Location RRR Elevation 617*		X	Buffalo Forge Co. 77K-25508-23, 9/78 S&L EMD-016338				S&L EMD-029950	15.8*	Stresses are below yielding on foundation bolts and within allowables on the other sections. This equipment is requalified.
RRR Complex Fans Equip. No. X-41-03-C021, 22, 23, 24 Location RRR Elevation 617*		X	Buffalo Forge Co. 77K-25526-31, 9/78 S&L EMD-016338				S&L EMD-029950	-13.7*	Based on a more sophisticated analysis the fans should qualify. Reanalysis is underway. See Section 5.4
RRR Complex Fans Equip. No. X-41-03-017, 018, 019, 020 Location RRR Elevation 590*		X	Buffalo Forge Co. 77K-25-524-27, 9/78 S&L EMD-016338				S&L EMD-029950	>100**	Based on a very conservative evaluation, the stresses in the same components are higher than allowables. However, when analyzed in detail, the fans may qualify with little or no modification. Reanalysis is underway. See Section 5.4

* For foundation bolts based on yield

** For inlet stand based on yield

*** For shaft over yield

TABLE 5. 36 (cont.)

RRR COMPLEX HVAC

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
RRR Complex Fans Equip. No. X-41-01, C009, 010, 011, 012, 013, 014, 015, 016 Location RRR Elevation 617*		X	Buffalo Forge Co. 77K-25516-23 S&L EMD-016338	<i>safety margin greater than maximum load amplification at this location (13%)</i>			S&L EMD-029950	16.7%	Stresses are below yielding limits

* For inlet stand based on yield

TABLE 5.3-37

INSTRUMENTATION AND CONTROL--PRINCIPAL SYSTEMS

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Plq. #	Margin	Analysis Report #	Margin of Safety	
<u>CONTROL ROOM PANELS</u> *									
H11-P601	X	X						20%	Panel meets seismic requirements by comparison with H11-P602 test
H11-P602	X		SPE Memo 107-78-110					48%	Panel meets seismic requirements based on original test
H11-P603	X	X	SPE MEMO 994-78-130					26%	Panel meets seismic requirements by comparison with H11-P602 test
H11-P612*	X		262A7242					21%	Panel meets seismic requirements based on original test
H11-P613*			SPE Memo 994-78-131					7.5%	Panel meets seismic requirements by comparison with H11-P612 test
H11-P617/P618*								28%	Panel meets seismic requirements by comparison with H11-P612 test
H11-P621*								15%	Panel meets seismic requirements by comparison with H11-P612 test
H11-P622/623*			SPE MEMO 994-78-132					37%	Panel meets seismic requirements based on tests of similar panels for Zimmer and Laguna Verde
H11-P628*								28%	Panel meets seismic requirements by comparison with H11-P612 test

*P-1 Lay Room

* All panels are designed to be rigid so no amplification phenomenon should be observed going from 770 to 570 structural damping.

TABLE 5.3-37 (Continued)

INSTRUMENTATION AND CONTROL--PRINCIPAL SYSTEMS

SEISMIC RE-EVALUATIONSUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
H11-P809			SPE MEMO 994-78- 118					12%	Panel meets seismic requirements based on original test
H11-P807								--	Panel meets seismic requirements by comparison with H11-P809 test
H11-P808								--	Panel meets seismic requirements by comparison with H11-P809 test
H11-P817								49	Panel meets seismic requirements by comparison with original H11-P809 test
Local Racks & Panels									
H21-P004	X						DRF A00794- 22	40%	This equipment is requalified to the new site-specific earthquake
P005	X								
P006	X								
P017	X								
P021	X								
P022	X								
H21-P637							DRF A00794- 22	74%	This equipment is requalified to the new site-specific earthquake
H21-P080	X		OPE-33- 1078				DRF A00794- 22	68%	(as above)
P081	X								
P082	X								
P083	X								
P084	X								
P085	X								
P086	X								
P087	X								

TABLE 5. (Continued)
INSTRUMENTATION AND CONTROL--PRINCIPAL SYSTEMS

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
H21-P296 A & B		X	H21-00 P296A & B						This equipment is requalified to the new site specific earthquake (as above)
H21-P296 E & F		X	H-10-01- S-900-RA- 009						

INSTRUMENTATION AND CONTROL--EECW

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
H11-P857 (relay cab)		X	262A7245				DRF A00794-22	41.3%	his equipment is requalified to the new site specific earthquake
H11-P868 (termination cab)								41.3%	See Section 5.4-1
H11-P891 (termination cab)								41.3%	See Section 5.4-1
H11-P601 (insert B514)								41.3%	See Table 5.3-37
H11-P808 (insert A500)								41.3%	See Table 5.3-37

* Safety margin greater than maximum load amplification
 ** Item on existing requalification list
 *** Rigid items experience no load amplification

INSTRUMENTATION AND CONTROL--CONTROL AIR

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
P50 - North Control Air Compressor Control Panel								*	See Section 5.4
P50-P001 including PSE-P50-N021A and E/V-P50-P000A								*	See Section 5.4
PSE-P50-N020A								*	See Section 5.4
North Dehydration Unit - P50 02D003, 5, 7	X		B11-436					*	See Section 5.4
H11-P214 (relay rm cab.)		X	Nuclear Structures					*	See Section 5.4
H11-P215								4*	The 4% margin is based upon the minimum yield strength. This component is requalified.
H11-P890A (relay rm cab.)								*	See Section 5.4
H11-P601 (B514)								**	See Table 5.3-37
H11-P868 (termination cab.)								*	See Section 5.4

* Items on existing requalification list.

** Rigid items experience no load amplification.

TABLE 5.3-40

INSTRUMENTATION AND CONTROL--ESSENTIAL HVAC

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	% Margin	Analysis Report #	% Margin of Safety	
H21-P296A DIV 1 HVAC control panel with all internal controls: solenoids, relays 5th floor aux. building			York 77113-2					*	Seismic Test Report "Edison File No. B9-1838" submitted to W. Street $q_{reass} < q_{qualif}$ \therefore ok
H21-P296E HVAC control panel with internal controls: solenoids, relays 5th floor aux. building			York 77113-2					*	This equipment is requallified to the new site specific earthquake
H21-P285A chiller compressor control panel			T41-00 B-008-RA-004 Trane B9-1018					*	(as above)
H21-P572 York Seismic Rack			York 77113-2					*	Seismic Test Report "York Final Report 77113-2" submitted to W. Street $q_{reass} < q_{qualif}$ \therefore ok
TSP-T41-N061A, -N062A, N063A, N065A, N066A, N067A (local)								**	See Section 5.4
TSE-T41-N174A, N174C, N174E, N174G, N175A, N175C, N175E, N175G, N177A, N222A								**	See Section 5.4
TE-T41-N119A, N114A								**	See Section 5.4
PDS-T41-N059A, N121A, N124A								**	See Section 5.4

* Rigid items experience no load amplification.
 ** Items on existing requallification list.

all other safety margins greater than maximum load amplification

TABLE 5.3-40 (Continued)
INSTRUMENTATION AND CONTROL- ESSENTIAL HVAC
SEISMIC RE-EVALUATION
SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
PDS-T41-H060A, N325A								* *	See Section 5.4
PSE-T41-N326A									See Section 5.4
Seismic Design Calculations for HVAC Duct mtd. instruments: pressure sw & temp. sensing elements		X	T41-00-G-900-LB-010 B9-1811					431	Fluor Report RICO-8901-2 (DECO file No. 1811). Margin based upon yield stress. This component is requalified.
U1 T41 components Damper Motor Mountings for T-4100 F157A & B thru F163 A & B			Fluor Pioneer Rico 8901-4 B9-2174					891	(Same as Above)
Powers Motor with positioning relay 132-2799 NAMCO Limit Switch EA-700	X		T41-00-0-000-QX-016						This equipment is requalified to the new site specific earthquake
H11-P888 (termination cab.)								* *	See Section 5.4
H11-889 (termination cab.)								* *	See Section 5.4
H11-P808B511								*	See Table 5.3-37

TABLE 5.3-41

INSTRUMENTATION AND CONTROL--DRYWELL COOLING

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
H21-PJ28A Local Panel			EA&T 1001-12-7 B9-1933					*	This equipment is requalified to the new site specific earthquake
H11-P808 Insert A502								*	See Table 5.3-37
H11-P889 (termination cabinet)								**	See Section 5.4
H11-P898A (relay room cab.)								**	See Section 5.4

* Rigid items experience no load amplification.
 ** Items on existing requalification list.

INSTRUMENTATION AND CONTROL--RHR COMPLEX

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report	Spectra	Spectra Comparison Fig. 1	Margin	Analysis Report	Margin of Safety	
<u>COP INSERTS</u>									
H11-P601A501 RHR SW								*	See Table 5.3-37
H11-P601B514 EESW								*	See Table 5.3-37
H11-P807B510 RHR SW								*	See Table 5.3-37
H11-P809A501 Diesel Fuel & Lube								*	See Table 5.3-37
H11-P809A502 Diesel Fuel & Lube								*	See Table 5.3-37
H11-P602B510 EDGSW								*	See Table 5.3-37
<u>TERMINATION CABINETS</u>									
H11-P823 RHR SW									
H11-P868 RHR SW EESW									
H11-P869 Diesel Fuel & Lube								**	See Section 5.4
H21-P350 (Local HVAC Control Panel) - Diesel Generator Ventilation								**	See Section 5.4
H21-P351 (Local HVAC Control Panel) - Diesel Generator Ventilation								**	See Section 5.4
Skid Terminal and Relay Box Equip. No. R30015001-4 Location RHR Elevation 590'	X	ITE Imperial dated 12-19-72					S&L EMD-029950	>100%	Qualifies to the new response spectra. TRS envelopes the new PRS.

* For vertical and horizontal direction.

* Rigid items experience no load amplification
 * Items on existing requalification list
 All other safety margins greater than maximums

9815

TABLE 5. 1 (Continued)

INSTRUMENTATION AND CONTROL--RRR COMPLEX

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	% Margin	Analysis Report #	% Margin of Safety	
Engine Panel Instrumentation Location RRR Elevation 590'	X		Wyle Labs dated 5/1/78 S&L EMD- 013860 EMD- 001659				S&L EMD- 029950	>100%	Instruments qualify to new response spectra. TRS envelopes the new RRS.
Diesel Generator Control Console Equip. No. R300S002, 004, 005, & 007 Location RRR Elevation 617'	X		Colt Ind. R30-Do- S-900- BA-022 (205981) 7/2/75				S&L EMD- 029950	H/A	See Section 5.4
R21-P517 Auto Temp Control Panel - DG Ventilation									See Section 5.4
DG Load Sequencer	X								See Section 5.4
Engine Overspeed Governor Equip. No. R30015001-4 Location RRR Elevation 590'		X	Colt Ind. Report dated 1/24/73 S&L EMD- 001659				S&L EMD- 029950	>100%	Qualifies to the new response spectra.

* For vertical & horizontal direction

INSTRUMENTATION AND CONTROL--BHR COMPLEX

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report	Spectra	Spectra Comparison Fig. 1	Margin	Analysis Report	Margin of Safety	
TEW-X41-N056A (EDG 111) TEW-X41-N056B (EDG 112) Switchgear room HVAC								✱ ✱	See Section 5.4
TEW-X41-N057A TEW-X41-N057C EDG Room HVAC								✱ ✱	See Section 5.4
TEW-X41-N058A Pump Room HVAC								✱ ✱	See Section 5.4
Operators (ITT) For Baskin Dampers								✱ ✱	See Section 5.4

TABLE 5.3-45

480 V AC & 260 V DC MOTOR CONTROL CENTERS (ITE)

SEISMIC RE-EVALUATIONSUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
Supplement Seismic with Standability Test Report MCC-Devices Oct. 8, 1973 R-STS-20 Supplement	X		R1600S-900-RA-003 (E4-468)					*	See Section 5.4
Seismic Withstandability Test Report Oct. 18, 1977 R-STS-16 Wyle Lab Report #43472-1	X		R1600S-900-RA-003 (E5-468)					*	See Section 5.4
Seismic Simulation Test Report to Qualify the Structure Welds, July 31, 1979 R-STS-20 Rev. 1 Wyle Lab. Report #43801-2	X		R1600S-900-RA-010 (E5-594) R1600S-900-RA-012 (E5-607)					*	See Section 5.4
Seismic Mounting for MCC		X	R1600S-900-RA-007	N/A				**	This component is requalified to the new site specific earthquake since reass qualification
Seismic Mounting of Relays in the MCC		X	New	N/A					

* Item on existing requalification list

** Minimum safety margin is $\frac{1.3}{1.5} = 0.87$ which is greater than the maximum load amplification at this location.

TABLE 5.3-46

480 V SWITCHGEAR (ITE)

SEISMIC RE-EVALUATIONSUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report	Spectra	Spectra Comparison Fig. 1	% Margin	Analysis Report	Margin of Safety	
Seismic Certification Report for Class 1E Swgt Electrical Equipment ITE Report R-09122	X		R1400S-900-RA-010 (E5-429)				$\frac{8.0}{2.3} = 2.17$		Ok: TRS envelopes the RRS.
Test Report Seismic Shock - 600 V Metal Enclosed Switchboard and Component A.D. Report No. R-8792	X		R1400S-900-QL-001				$\frac{5.0}{2.3} = 2.17$		Ok: TRS envelopes the RRS.
Seismic Certification Test Report for 750 KVA Voltage Regulators Wyle Lab Report 43169-1	X		R1400S-030-PA-001					*	See Section 5.4
Seismic Simulation Test Report Voltage Regulators Wyle Lab Report No. 42949-1	X		R1400S-900-QL-031 (E5-429)			Min. from TRS/RRS = 3.0			Ok: TRS envelopes the RRS.
Seismic Certification Voltage Regulators ITE	X		R1400S-900-LB-096				$\frac{1}{7} = 1.43$		Seismic certification only. No attachments.
Electrical Equipment Class 1 Seismic Shock Certification - 1500 KVA Transformer Wyle Report No. R-09402	X		R1400S-900-QL-027 (E5-427)			Min. from TRS/RRS = 2.5			Ok: TRS envelopes the RRS.
Addendum to Test Report R-09402			R1400S-900-RA-007 R1400S-000-LB-030						

* Items on existing requalification list.
 All other safety margins greater than maximum load amplifications

TABLE 5.3-46 (Continued)

480 V SWITCHGEAR (ITE)

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
Seismic Certification and Analysis Type VII-9 Dry Type Transform. (ITE)	X		R14003-900-RA-009			Min. from TRA/RAS = 2.05			OK: $\gamma_{reass} < \gamma_{qualif.}$
Switchgear Seismic Mounting by Giffels		X	R14005-900-RA-013	N/A				✱✱	This equipment is requalified to the new site specific earthquake
Switchgear Seismic Mounting by Giffels		X	R14005-900-RA-014	N/A				✱✱	This equipment is requalified to the new site specific earthquake
<p>✱✱ Mounting designed to allowable but may go to yield in this scenario.</p> <p>26-6127 - 2000 - 2170 = 1.87121</p> <p>20</p> <p>Existing margin</p> <p>Mounting will not reach yield.</p>									

TABLE 5...7

4160 V SWITCHGEAR (ITE IMPERIAL)

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	% Margin	Analysis Report #	% Margin of Safety	
Seismic Certification for Class 1E Electrical Equipment (Buses 64B, 64C, 65E, 65F, 64T, 65T, 11 FA, 12 ED, ITE 133-4-196)	X		R14000-000-SC-009-E4-333					*	See Section 5.4
Test Report Seismic Shock 5kV Metal Clad Switchboard and Components, Wyle Lab R-09121	X		R14000-000-RA-003					*	See Section 5.4
Seismic Withstandability Auxiliary Relay GE 12HFA51A42F Report R-09161-BE	X		R1400S-000-RA-011					*	See Section 5.4
Seismic Withstandability Over-Under Voltage Relay GE 12IAV53L1A Report R-0916BF	X							$\frac{5}{2.8} = 1.79$	This equipment is requalified to the new site specific earthquake.
Seismic Withstandability Overcurrent Relay GE 1AC53B104A (Per ITE TD-7629 Procedure) Report R-09161-AT	X							*	See Section 5.4
Seismic Withstandability Overcurrent Relay GE 12PJCH1A1A (Per ITE TD-7629 Procedure) Report R-09161-BK	X		R14000-000-RA-006					*	See Section 5.4

* Items on existing requalification list.
 All other safety margins greater than maximum load amplifications

TABLE 5.3. / (Continued)

4160 V SWITCHGEAR (ITE IMPERIAL)

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
Seismic Withstandability Lockout Relay Elect. Switch Type LOR Cat. 78030 (Per ITE TD-7629 Procedure) Report No. R-09161-BC	X		R14000- 000-RA- 007				$\frac{5}{2.5} = 2$		This equipment is requali- fied to the new site specific earthquake
Seismic Withstandability Overcurrent Relay CE 121AC66C1A (Per ITE TD-7629 Procedure) Report No. R-09161-AV	X		R14000- 000-RA- 008					*	See Section 5.4
Seismic Withstandability J10 & J11 Relay ITE-STD-1-35/36/ 37	X		R14000- 000-BA- 002 (E4- 402)					*	See Section 5.4
Switchgear Mounting Seismic Report by Giffels		X	R1400S- 900-RA- 013		Ratio of yield to allowable $= \frac{36}{20} = 1.8 > 1.21$				This equipment is requali- fied to the new site specific earthquake
Switchgear Seismic Mounting by Giffels		X	R1400S 900-RA- 013						This equipment is requali- fied to the new site specific earthquake

BATTERY MAIN DC FUSE CABINETS VDP NO. EP2-39, 120B

SEISMIC RE-EVALUATIONSUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report	Spectra	Spectra Comparison Fig. 1	Margin	Analysis Report	Margin of Safety	
Main DC Fuse Cabinet Seismic Report		X	R3200S-900-BA-011	N/A	Safety margin greater than maximum load applied			20.9% margin	O.K. A mathematical analysis has been made based on material and fabrication as per Dwg. 68721-2297-2 which indicates that this component is requalified to the revised response spectra.

TABLE 5.3-49

BATTERIES & BATTERY RACKS & THEIR MOUNTING (C&D)

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report	Spectra	Spectra Comparison Fig. 1	% in	Analysis Report	Margin of Safety	
24 V DC Battery--Report of seismic test on 2 (3DCU-9) batteries for C&D. ETL Report 14887 and report for seismic test on two (3-DCU-3) batteries and one ARH 130 AC 3 charger for C&D. ETL Report 15263	X		R3200S-900-RA-008 (E11-84)				$\frac{1.5}{0.665} = 2.26$		$g_{reass} < g_{qualif}$ ok. Most critical slab is slab 15 bldg. aux. 0.665 g 1.5 g.
130 V DC Battery--Seismic simulation test program on two KC-13 battery cells & one ARH 130 HK100 battery charger Wyle Report 142954-1	X		R3200S-900-RA-004 (E11-80)		Min. from TAs/RAS = 1.3				Ok. Test response spectra envelopes the required response spectra (aux. bldg. 643'-6)
Battery racks for 24 V DC batteries--seismic analysis of C&D battery support racks for the C&D No. 3 DCU-7 battery		X	R3200S-900-RA-007 (E11-85)	N/A			$\frac{.593}{.465} = 1.25$		$g_{reass} < g_{qualif}$ ok. (3rd Floor aux. bldg.)
Battery racks for 130 V DC batteries--seismic analysis report of KCU-17 single tier battery rack CCL Report 1A-119-77		X	R3200S-900-PA-003 (E11-81)	N/A			$\left(\frac{Yield}{Alt}\right) \frac{.593}{.553} > 1.21$		$g_{reass} < g_{qualif}$ ok.
Seismic Report of 24/48 V battery rack mounting CA1-001-EP2-159-156 (70-CA1-9364)		X	R32-00S-900-BA-011 R32-00S-900-LC-182	N/A N/A			$\frac{468.61}{(Yield/Alt) \times 1.553} = 17.311$ > 1.21		This equipment is requalified to the new site specific earthquake

All safety margins greater than minimum load amplification.

TABLE 5.3-50

BATTERY CHARGERS AND THEIR MOUNTING (C1D BATTERIES)

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
130 V dc battery charger report of seismic test on two (3-BCH-3) batteries and one APR13AC1 charger and C1D batteries ETL Lab Report 15263	X		R32-00S-900-RA-005 (E11-84)						$q_{reass} < q_{qualif} = \text{ok}$
130 V dc battery charger seismic simulation test program on two KC-13 battery cell and one APR13HK100 battery charger Wyle Lab Report 142954-1	X		R3200S-900RA-006 (E11-80)						This equipment is requalified to the new site specific earthquake
Seismic Class I attachment for 130 V battery charger 24 V battery charger and voltmeter -GA1-0016)	X		R3200S-900RA-013 R3200S 900LC-075 (E11-105)	N/A				481	This equipment is requalified to the new site specific earthquake

$$\frac{1.5}{.665} = 2.26$$

All safety margins greater than maximum load amplification

TABLE 5.3-51

DC FUSED DISTRIBUTION CABINETS (SQUARE D) VDP NO. EF2-30,121C

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
Seismic Qualification for a 250 V DC OMB Panel Board Square D 8998-10-09-L16R	X		R3200S-900-RA-015 (EG-87)					$\frac{1.5}{1.0}$	See Section 5.4
Seismic Class I DC Distribution Panel Installation at the Reactor Building		X	T51000000-RA-001 (E11-128)	N/A			52A	\rightarrow	This equipment is requalified to the new site specific earthquake
Seismic Class I DC Distribution Panel Installation at the R/R Complex		X	R3200S-063	N/A			43A	\rightarrow	This equipment is requalified to the new site specific earthquake

* Item on existing requalification list.

All other safety margins greater than maximum load amplifications.

TABLE 5.3-52

120 V AC MODULAR POWER SUPPLY UNITS (MPUs)
SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
Seismic analysis Report of IAC power supply panel structure #74021-1		X	R3101S-001-00-00	N/A				34.028	This equipment is requalified to the new site specific earthquake
	X		R3101AS-900-RA-002 (E5-443)		0.636 g		$\frac{1.5}{0.636} = 2.36$		
Seismic vibration tests of IAC power supply panel components--ASCO transfer switch isolation voltage regulator & GE fusible disconnect Report 74021-1		X	R1600S-900-RA-009 (E11-30)	N/A				20.12	This equipment is requalified to the new site specific earthquake
Analysis of seismic Class II mountings for modular power units #1 & 2 GAT-001-EF2-193-118 (78-GAT-233)		X	R3101S-001-00-00 (E11-140)	N/A			$\frac{6.75}{0.636} = 10.6$		
Seismic Qualification of the 50M test switch mounting for MPUs 1 & 2. GAT-001-EF2-228-269 (79-GAT-352)		A						20.12	This equipment is requalified to the new site specific earthquake
								20.12	

* High frequency item does not experience amplification
 All other safety margins greater than minimums load amplifications.

DRYWELL, PENETRATIONS (CONAX CORP.) VDP NO. EP2-39, 115C

SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification			Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
Seismic analysis of electrical penetration assemblies & addenda. (Comax Corp.) IPS-88	X	T23-01-X900-BA-009 (E5-335)	N/A			36101-6.0 6FS	6.0	This equipment is requalified to the new site specific earthquake Stress & Qualif ok
Stress analysis nuclear penetration, canister assembly and addenda. (Comax Corp.) IPS-87	X	T2301X-900-BA-008 (E5-284)	N/A					

*Safety margin greater than earlier
load amplification.*

TABLE 5.3-54

TERMINAL BOXES AND TERMINAL BOXES ATTACHED TO DRYCELL PENETRATIONS (HOFFMAN)
SEISMIC RE-EVALUATION

SUMMARY TABLE

System, Structure, Component Description	Method of Original Qualification				Re-Evaluation Results				Conclusion and Remarks
	Test	Analysis	Report #	Spectra #	Spectra Comparison Fig. #	Margin	Analysis Report #	Margin of Safety	
Terminal boxes seismic qualification report Hoffman Type A-1210 CNMF A-1008 CNMF and A-606 CNMF		X	GASI (E11-109)	N/A				73.11	This equipment is requalified to the new site specific earthquake
Terminal box attachment to drycell penetrations, Reactor Bldg.		X	GASI T23 01X 102A RA-001 (E11-136)	N/A				43.41	This equipment is requalified to the new site specific earthquake