



Energy Harbor Nuclear Corp.
Davis-Besse Nuclear Power Station
5501 N. State Route 2
Oak Harbor, OH 43449

Terry J. Brown
Site Vice President, Davis-Besse Nuclear

419-321-7676

January 3, 2022
L-21-187

10 CFR 50.90

ATTN: Document Control Desk
U. S. Nuclear Regulatory Commission
Washington, DC 20555-0001

SUBJECT:

Davis-Besse Nuclear Power Station, Unit No. 1
Docket No. 50-346, License No. NPF-3
Request for an Amendment to Change the Design Basis Methodology for the Shield Building Containment Structure

Pursuant to 10 CFR 50.90, Energy Harbor Nuclear Corp. is submitting a request to amend the Renewed Facility Operating License No. NPF-3 for the Davis-Besse Nuclear Power Station, Unit No. 1.

Energy Harbor Nuclear Corp. proposes a change in the design basis that would accept laminar concrete cracking of a limited width in the outer reinforcement layer of the shield building containment structure as discussed in the updated final safety analysis report.


The enclosure provides a description and assessment of the proposed change. The enclosure includes a report that establishes the technical justification supporting the proposed change and a markup of the updated final safety analysis report.

Energy Harbor Nuclear Corp. requests approval of the proposed amendment by January 31, 2023. Once approved, the amendment shall be implemented within 60 days.

There are no regulatory commitments contained in this submittal. If there are any questions or if additional information is required, please contact Mr. Phil H. Lashley, Manager - Fleet Licensing, at (330) 696-7208.

I declare under penalty of perjury that the foregoing is true and correct. Executed on January 3, 2022.

Sincerely,



Terry J. Brown

Enclosure:
Evaluation of the Proposed Change

cc: NRC Region III Administrator
NRC Resident Inspector
NRC Project Manager
Executive Director, Ohio Emergency Management Agency,
State of Ohio (NRC Liaison)
Utility Radiological Safety Board

Enclosure
L-21-187

Evaluation of the Proposed Change
(1405 pages follow)

Evaluation of the Proposed Change
Page 1 of 9

Subject: Request for an Amendment to Change the Design Basis Methodology for the Shield Building Containment Structure

1.0 SUMMARY DESCRIPTION

2.0 DETAILED DESCRIPTION

- 2.1 System Design and Operation
- 2.2 Current Design Basis Requirement
- 2.3 Reason for the Proposed Change
- 2.4 Description of the Proposed Change

3.0 TECHNICAL EVALUATION

4.0 REGULATORY EVALUATION

- 4.1 Applicable Regulatory Requirements / Criteria
- 4.2 No Significant Hazards Consideration Analysis
- 4.3 Conclusions

5.0 ENVIRONMENTAL CONSIDERATION

6.0 REFERENCES

ATTACHMENTS

1. Bechtel Power Corporation Technical Report, 25884-000-30R-C01R-00002, Revision 0, "Incorporating Laminar Cracks of up to 0.050 Inch in the Design Basis of the Davis-Besse Shield Building."
2. Updated Final Safety Analysis Report Markup.

1.0 SUMMARY DESCRIPTION

In accordance with 10 CFR 50.90, Energy Harbor Nuclear Corp. is providing this evaluation in support of amending Renewed Facility Operating License No. NPF-3 for the Davis-Besse Nuclear Power Station, Unit No. 1 (DBNPS). The proposed change in the design basis would accept laminar concrete cracking of a limited width in the outer reinforcement layer of the shield building containment structure as discussed in the updated final safety analysis report (UFSAR). The proposed changes to the DBNPS UFSAR require prior Nuclear Regulatory Commission (NRC) approval.

2.0 DETAILED DESCRIPTION

2.1 System Design and Operation

As described in Section 1.2.10 of the UFSAR, the containment system consists of two structures: a steel containment vessel and a reinforced concrete shield building, and their associated systems. The containment system provides protection for the public from the radiological consequences of a hypothetical accident discussed in Chapter 15 of the UFSAR.

The containment vessel, including all its penetrations, is a low-leakage steel structure designed to withstand a postulated loss-of-coolant accident and to confine a postulated release of radioactive material. It is a cylindrical pressure vessel with hemispherical dome and ellipsoidal bottom. It houses the reactor vessel, reactor coolant piping, pressurizer, pressurizer quench tank and coolers, reactor coolant pumps, steam generators, core flooding tanks, letdown coolers, and containment air cooling and recirculating systems.

The containment vessel is completely enclosed by a reinforced concrete shield building having a cylindrical shape with a shallow dome roof. An annular space is provided between the wall of the containment vessel and the shield building, and clearance is also provided between the containment vessel and the dome of the shield building. With the exception of the concrete under the containment vessel there are no structural ties between the containment vessel and the shield building above the foundation slab. Above this there is freedom for differential movement between the containment vessel and the shield building

The shield building is designed to provide biological shielding during normal operation and from hypothetical accident conditions. The building provides a means for collection and filtration of fission product leakage from the containment vessel following a hypothetical accident through the emergency ventilation system, an engineered safety feature designed for that purpose. In addition, the building provides environmental protection for the containment vessel from adverse atmospheric conditions and external missiles. The shield building is a nuclear safety-related, seismic Class 1 structure

important to safety and designed to remain functional in the event of a maximum possible earthquake and design basis events.

The reinforced concrete shield building was designed in accordance with American Concrete Institute (ACI) 307-69, "Specification for the Design and Construction of Reinforced Concrete Chimneys," and checked by the ultimate strength design method in accordance with ACI 318-63, "Building Code Requirements for Reinforced Concrete." Load combinations specified in ACI 307-69 provide the design basis of the shield building. Further details of the shield building design and design bases are provided in Section 3.8.2.2 of the UFSAR.

2.2 Current Requirements

As described above, UFSAR Section 3.8.2.2 specifies that the design of the shield building structure conforms to ACI 318-63 and ACI 307-69. In accordance with ACI, the shield building design includes adequate reinforcing in the concrete walls, dome, and foundation to resist design forces and control cracking due to concrete shrinkage and temperature gradients. However, the ACI codes do not specify allowable limits or discuss the acceptability of laminar concrete cracking in regards to structural behavior or capacity of the shield building.

2.3 Reason for the Proposed Change

Laminar concrete cracking in the plane of the outer reinforcement mat of the shield building was observed in 2011 while creating a temporary opening for the reactor pressure vessel head replacement. The Shield Building Monitoring Program described in Section 18.1.43 of the UFSAR supplements the Structures Monitoring Program and monitors for extent and width of concrete cracking, as well as visible change of material properties and loss of material for both concrete and rebar in areas of laminar concrete cracking.

The intent of Energy Harbor is to repair areas of laminar cracking. However, some areas where laminar cracking has been observed have limited access for repair. Laminar cracks in these areas, less than or equal to 0.050 inches, would not be immediately repaired; however, these areas would continue to be part of the monitoring program described above. The proposed change would be to the shield building design basis to specify that cracks less than or equal to 0.050 inches are acceptable and do not affect the structural behavior or capacity of the shield building.

2.4 Description of the Proposed Change

As indicated above, the shield building design includes adequate reinforcing in the concrete walls to resist design forces and control cracking due to concrete shrinkage and temperature gradient. The original structural analysis did not include allowance for laminar concrete cracking. Recent analysis, discussed below, determined a laminar

concrete crack width that has a negligible effect on the overall stiffness, dynamic characteristics and performance of the shield building and is therefore deemed acceptable.

The proposed change will update the UFSAR with a statement that laminar concrete cracks with widths less than or equal to 0.050 inches in the outer reinforcement layer of the shield building are acceptable in the design bases without explicit consideration in the analysis. Laminar concrete cracks with a width greater than 0.050 inches would be repaired.

3.0 TECHNICAL EVALUATION

In order to support the proposed change, conservative experimental tests and analyses have been performed and are presented in Attachment 1, Bechtel Power Corporation Technical Report, 25884-000-30R-C01R-00002. The report concludes that crack widths of up to 0.050 inches have no adverse impact on the capacity of the reinforcing bars to perform their intended function, ensuring shield building structural adequacy. Also, composite action of the shell, overall structural response, and serviceability and durability of the shield building are not adversely impacted with laminar concrete cracking up to 0.050 inches. The monitoring program ensures that any exceedance in cracking is adequately identified and addressed.

The test results show that the outer circumferential reinforcement bars maintain their full design capacity with the presence of laminar concrete cracks with widths up to 0.050 inches. Additionally, review of the load-deflection behavior of the specimens in the test programs does not indicate any significant change in the reloading stiffness of specimens after introduction of the laminar concrete cracks with widths exceeding 0.050 inches.

The shield building is designed for all applicable loads and load combinations in accordance with UFSAR Section 3.8.2.2.4, including dead and live loads, wind and tornado loads, and operating basis and safe shutdown earthquakes. The controlling load combinations for the design of the shield building involve the design basis safe shutdown earthquake, for which the shield building will behave like a cantilever where most of the forces are transferred through in-plane shear and axial membrane forces and very little through out-of-plane bending of the shell. The laminar concrete cracking has no impact on in-plane stiffness of the cylindrical shell, which will resist most of the applicable seismic loads. For thermal and tornado loads that produce hoop tension and moment, the existence of laminar concrete cracking does not change the concrete section behavior since the concrete shell is already assumed to be cracked through-thickness. The applicable tension forces are primarily resisted by the hoop reinforcement, which were demonstrated in testing to maintain their design function with crack widths up to 0.050 inches. Therefore, it is concluded that no changes need to be made to the analytical model in order to account for the effect of the limited laminar concrete cracking on shield building stiffness.

Therefore, the effect of laminar concrete cracking on the overall stiffness, dynamic characteristics, and performance of the shield building is negligible.

Finally, the ability of the shield building to perform its other UFSAR-described design functions of biological shielding and a boundary for the emergency ventilation system are not affected by the laminar concrete cracking. Laminar concrete cracking does not reduce the concrete thickness required for adequate biological shielding. Also, the laminar concrete cracking in the outer reinforcement mat of the shield building will not degrade the shield building pressure boundary since it does not penetrate through-wall.

4.0 REGULATORY EVALUATION

4.1 Applicable Regulatory Requirements / Criteria

The following regulatory requirements and guidance are applicable to this license amendment request.

- As reflected in Section 3 of the UFSAR, the following General Design Criteria are applicable to this proposed change. Appendix A to 10 CFR Part 50 - General Design Criteria for Nuclear Power Plants:

Criterion 1 - Quality Standards and Records. Structures, systems, and components important to safety shall be designed, fabricated, erected, and tested to quality standards commensurate with the importance of the safety functions to be performed. Where generally recognized codes and standards are used, they shall be identified and evaluated to determine their applicability, adequacy, and sufficiency and shall be supplemented or modified as necessary to assure a quality product in keeping with the required safety function. A quality assurance program shall be established and implemented to provide adequate assurance that these structures, systems, and components will satisfactorily perform their safety functions. Appropriate records of the design, fabrication, erection, and testing of structures, systems, and components important to safety shall be maintained by or under the control of the nuclear power unit licensee throughout the life of the unit.

Criterion 2 - Design Bases for Protection Against Natural Phenomena. Structures, systems, and components important to safety shall be designed to withstand the effects of natural phenomena such as earthquakes, tornadoes, hurricanes, floods, tsunamis, and seiches without loss of capability to perform their safety functions. The design bases for these structures, systems, and components shall reflect: (1) appropriate consideration of the most severe of the natural phenomena that have been historically reported for the site and surrounding area, with sufficient margin for the limited accuracy, quantity, and period of time in which the historical data have been accumulated, (2) appropriate combinations of the effects of normal and accident conditions with the effects of the natural phenomena and (3) the importance of the safety functions to be performed.

Criterion 4 - Environmental and Dynamic Effects Design Bases. Structures, systems, and components important to safety shall be designed to accommodate the effects of and to be compatible with the environmental conditions associated with normal operation, maintenance, testing, and postulated accidents, including loss-of-coolant accidents. These structures, systems, and components shall be appropriately protected against dynamic effects, including the effects of missiles, pipe whipping, and discharging fluids, that may result from equipment failures and from events and conditions outside the nuclear power unit. However, dynamic effects associated with postulated pipe ruptures in nuclear power units may be excluded from the design basis when analyses reviewed and approved by the Commission demonstrate that the probability of fluid system piping rupture is extremely low under conditions consistent with the design basis for the piping.

Criterion 16 - Containment Design. Reactor containment and associated systems shall be provided to establish an essentially leak-tight barrier against the uncontrolled release of radioactivity to the environment and to assure that the containment design conditions important to safety are not exceeded for as long as postulated accident conditions require.

Criterion 50 - Containment Design Basis. The reactor containment structure, including access openings, penetrations, and the containment heat removal system shall be designed so that the containment structure and its internal compartments can accommodate, without exceeding the design leakage rate and, with sufficient margin, the calculated pressure and temperature conditions resulting from any loss-of-coolant accident. This margin shall reflect consideration of (1) the effects of potential energy sources which have not been included in the determination of the peak conditions, such as energy in steam generators and energy from metal-water and other chemical reactions that may result from degradation but not total failure of emergency core cooling functioning, (2) the limited experience and experimental data available for defining accident phenomena and containment responses, and (3) the conservatism of the calculational model and input parameters.

- Codes and Standards:

American Concrete Institute (ACI) 307-69, "Specification for the Design and Construction of Reinforced Concrete Chimneys,"

ACI 318-63, "Building Code Requirements for Reinforced Concrete."

The test results in Attachment 1 show that the outer circumferential rebars maintain their full design capacity with the presence of laminar concrete cracks with widths up to 0.050 inches. Therefore, laminar concrete cracking up to this width has no effect on the structural behavior or capacity of the shield building considering reinforcement engagement, composite action of the shell, overall structural response, and serviceability/long term durability of the structure. In conclusion, the effect of laminar

concrete cracking up to this width on the overall stiffness, dynamic characteristics and performance of the shield building is negligible.

The proposed change does not affect compliance with the specified regulations or guidance and will ensure that the lowest functional capabilities or performance levels of equipment required for safe operation are met.

4.2 No Significant Hazards Consideration Analysis

Pursuant to 10 CFR 50.90, Energy Harbor Nuclear Corp. is submitting a request to amend the Renewed Facility Operating License No. NPF-3 for the Davis-Besse Nuclear Power Station, Unit No. 1. The proposed change would accept a limited width of laminar concrete cracking along the outer reinforcement layer in the design basis of the shield building containment structure as discussed in the updated final safety analysis report.

Energy Harbor Nuclear Corp. has evaluated whether or not a significant hazards consideration is involved with the proposed amendment by focusing on the three standards set forth in 10 CFR 50.92, "Issuance of amendment," as discussed below:

1. Does the proposed amendment involve a significant increase in the probability or consequences of an accident previously evaluated?

Response: No

The shield building functions to protect against and mitigate potential accidents. The proposed change of laminar concrete cracking in the outer reinforcement layer up to the width of 0.050 inches has been evaluated with a conclusion that the effect on the overall stiffness, dynamic characteristics, and performance of the shield building is negligible. Based on this, the shield building capability to perform its specified design function is maintained. The proposed change does not involve a significant increase in the probability of an accident previously evaluated.

The effect of the proposed change on the overall shield building integrity and structural capability have been determined to be negligible. Also, the ability of the shield building to perform its other UFSAR-described design functions of biological shielding and a boundary for the emergency ventilation system are not affected. Since the shield building function is maintained, there will not be a significant increase in the consequences of a previously evaluated accident.

Therefore, the proposed amendment does not involve a significant increase in the probability or consequences of an accident previously evaluated.

2. Does the proposed amendment create the possibility of a new or different kind of accident from any accident previously evaluated?

Response: No

The proposed change of laminar concrete cracking in the outer reinforcement layer up to the width of 0.050 inches has been evaluated with a conclusion that the effect on the overall stiffness, dynamic characteristics, and performance of the shield building is negligible. The proposed change does not affect the design function or operation of the shield building or any other plant system, structure or component. Laminar concrete cracks up to 0.050 inches are shown to be negligible with cracks greater than 0.050 inches requiring repair. Based on this, there are no new failure mechanisms or accident initiators created by this proposed change.

Therefore, the proposed amendment does not create the possibility of a new or different kind of accident from any previously evaluated.

3. Does the proposed amendment involve a significant reduction in a margin of safety?

Response: No

The proposed amendment is requesting approval of changes to the UFSAR and shield building design basis to allow a limited width of laminar concrete cracking along the outer concrete reinforcement layer of the shield building. The current licensing and design basis does not provide an explicit acceptance value for laminar concrete cracking, this change specifies a value of 0.050 inches.

Experimental test results have shown that the outer circumferential reinforcement bars maintain their full design capacity with the presence of laminar concrete cracks with widths up to 0.050 inches. Conservatism included in the tests included concrete strength differences between tested and as-built, not including the effect of staggering of spliced reinforcement bars in the tests, and not including the curvature of the shield building in the tests. It is concluded that the effect of laminar concrete cracking up to this width on the shield building design is negligible and the margin of safety is maintained.

Therefore, the proposed amendment does not involve a significant reduction in a margin of safety.

Based on the above, Energy Harbor Nuclear Corp. concludes that the proposed amendment does not involve a significant hazards consideration under the standards set forth in 10 CFR 50.92(c), and, accordingly, a finding of "no significant hazards consideration" is justified.

4.3 Conclusions

In conclusion, based on the considerations discussed above, (1) there is reasonable assurance that the health and safety of the public will not be endangered by operation in the proposed manner, (2) such activities will be conducted in compliance with the Commission's regulations, and (3) the issuance of the amendment will not be inimical to the common defense and security or to the health and safety of the public.

5.0 ENVIRONMENTAL CONSIDERATION

A review has determined that the proposed amendment would change a requirement with respect to installation or use of a facility component located within the restricted area, as defined in 10 CFR 20, or would change an inspection or surveillance requirement. However, the proposed amendment does not involve (i) a significant hazards consideration, (ii) a significant change in the types or significant increase in the amounts of any effluents that may be released offsite, or (iii) a significant increase in individual or cumulative occupational radiation exposure. Accordingly, the proposed amendment meets the eligibility criterion for categorical exclusion set forth in 10 CFR 51.22(c)(9). Therefore, pursuant to 10 CFR 51.22(b), no environmental impact statement or environmental assessment need be prepared in connection with the proposed amendment.

6.0 REFERENCES

1. American Concrete Institute (ACI) Standard 307-69, "Specification for the Design and Construction of Reinforced Concrete Chimneys."
2. American Concrete Institute (ACI) Standard 318-63, "Building Code Requirements for Reinforced Concrete."

Attachment 1

Bechtel Power Corporation Technical Report, 25884-000-30R-C01R-00002,
Revision 0, "Incorporating Laminar Cracks of up to 0.050 Inch in the Design
Basis of the Davis-Besse Shield Building"

(1391 pages follow)

TECHNICAL REPORT
Energy Harbor Nuclear Corporation

**INCORPORATING LAMINAR CRACKS OF UP TO 0.050 INCH IN THE
DESIGN BASIS OF THE DAVIS-BESSE SHIELD BUILDING**

25884-000-30R-C01R-00002, Rev. 000

By

Bechtel Power Corporation

	<small>Digitally signed by: Munshi, Javeed DN: CN = Munshi, Javeed C = US O = Bechtel Global Corporation Date: 2021.02.03 12:19:01 -05'00'</small>	<small>Digitally signed by: Saini, Jaspal DN: CN = Saini, Jaspal C = US O = Bechtel Global Corporation Date: 2021.02.03 12:11:39 -05'00'</small>
PREPARED BY	<u>J Munshi / J. S. Saini</u>	
	<small>Digitally signed by: Saini, Jaspal DN: CN = Saini, Jaspal C = US O = Bechtel Global Corporation Date: 2021.02.03 12:12:19 -05'00'</small>	<small>Digitally signed by: Kline, Steven DN: CN = Kline, Steven C = US O = Bechtel Global Corporation Date: 2021.02.03 12:28:27 -05'00'</small>
CHECKED BY	<u>J. S. Saini / S. Kline</u>	
	<small>Digitally signed by: Rao, Shankar DN: CN = Rao, Shankar C = US O = Bechtel Global Corporation Date: 2021.02.03 15:14:22 -05'00'</small>	
APPROVED BY	<u>S. Rao</u>	

TABLE OF CONTENTS

		Pg. #
1.0	Objective	3
2.0	Background	3
	2.1 Shield Building Description	3
	2.2 History of Laminar Cracking Condition	5
3.0	Rebar Capacity	8
	3.1 Phase I Test Program	9
	3.2 Phase II Test Program	23
	3.3 Phase III Test Program	31
	3.4 Summary of Phase I, II, and III Purdue Test Results	37
	3.5 Quality Assurance	40
4.0	Composite Action of Shell	40
5.0	Overall Structural Response	43
6.0	Serviceability and Long-Term Durability	43
7.0	Conclusions	44
8.0	References	44

LIST OF APPENDICES

- Appendix A: Purdue Phase I Test Report (595 Pages)
- Appendix B: Purdue Phase II Test Report (168 Pages)
- Appendix C: Purdue Phase III Test Report (575 Pages)
- Appendix D: Purdue Memo for Phase II Tests (6 Pages)
- Appendix E: Memo from Dr. Santiago Pujol (2 Pages)

1.0 Objective

The objective of this report is to provide a description of the testing and analysis work performed that establishes the technical justification for including laminar cracks of up to 0.050 inch (unit denoted as " throughout this report) in the design basis of the Davis-Besse Shield Building.

This report addresses the impact of laminar cracking on reinforcement capacity, composite action of the shell, overall structural response, and serviceability and long-term durability to provide the technical justification that laminar cracking up to 0.050" does not adversely impact the structural capacity and performance of the Shield Building.

It should be noted that a repair program has been instituted to completely repair shoulders where laminar cracking exists. This repair program provides general repair to the entire shoulder using ACI codes and guidelines under safety-related work restrictions to eliminate the laminar cracking condition. This repair program restores the Shield Building to the design/licensing basis. However, there are some isolated regions where the cracking is not greater than 0.050" and repair would be difficult due to significant interferences. Thus, this Technical Report supports the repair program by providing the technical justification for incorporation of 0.050" as the acceptance limit for laminar crack width, where cracking less than 0.050" has no effect on the structural capacity and performance and would be incorporated into the design/licensing basis.

General references throughout this report include the USAR as the licensing basis (Ref. 4a), the DCM as the design basis (Ref. 4b), and ACI 318-63 and ACI 307-69 as the design codes of record (Refs. 5a & 5b).

2.0 Background

During the creation of the temporary opening in the cylindrical wall of the Shield Building for the Reactor Pressure Vessel Head (RPVH) replacement at the Davis-Besse nuclear power plant, a laminar crack was observed on October 10, 2011 in the architectural flute shoulder area in the vicinity of the opening. The crack was located in the plane of the main outer reinforcing bar mat. During the original investigation, crack widths were determined using core bore samples. The cracks were established to be tight with crack widths of less than 0.010" in most cases. Since the original investigation, some of these cracks have propagated and/or widened as observed through the Shield Building monitoring program.

2.1 Shield Building Description

The Shield Building at the Davis-Besse nuclear power plant is a safety-related freestanding cylindrical reinforced concrete structure capped with a shallow spherical dome. The structure configuration can be found in References 3a-3c and is shown in Figure 1. The cylindrical wall and dome are 30" and 24" thick, respectively, and the inner radii to the inner surfaces of the wall and dome are 69.5 feet (unit denoted as ' throughout this report) and ~123.3', respectively. There are eight (8) architectural flute areas on the outer periphery of the cylindrical wall, with each area comprised of two built-up or

thickened shoulders. The original Shield Building design considers the flute shoulders as purely architectural features providing no structural capacity beyond that provided by the cylindrical wall.

The Shield Building cylindrical wall is reinforced by meridional (vertical) and circumferential (hoop) reinforcing bars forming a grid near both faces of the wall, with the hoop reinforcement located outside the vertical reinforcement. The reinforcing arrangements for both vertical and hoop rebar varies along the height of the Shield Building. Reinforcing for the shoulders consists of vertical bars and horizontal ties conforming to the profile of the shoulder and intersecting the main reinforcing.




Figure 1: Shield Building Plan and Section

During the original construction of the Shield Building, a temporary opening was provided in the cylindrical wall, which was subsequently closed at the end of construction activities. In 2002, a temporary opening was created and then restored to allow removal and replacement of the RPVH. Subsequently, a temporary opening was created and then restored to allow the removal and replacement of the RPVH in 2011 (a temporary opening with the same profile and location as the 2011 opening was also used for the Steam Generator (SG) replacement in 2014). The arrangement of the original and subsequent temporary openings is depicted in Figure 2.




Figure 2: Shield Building Temporary Openings

2.2 History of Laminar Cracking Condition

During the creation of the 2011 temporary opening for the RPVH replacement, a crack was observed on October 10, 2011 in the architectural flute shoulder area at the edge of the opening (see Figure 3). The crack was found on the left vertical side of the opening (looking from the outside) and identified to be in the plane of the outer main reinforcing bar grid. The crack indication disappeared after some minor manual chipping along the edges of the opening and the crack was established to be a circumferential laminar crack with no indication in the radial (through-thickness) direction.




Figure 3: Cracking in Flute Shoulder Region on Left Edge of Temporary Openings

Further investigations and examinations were carried out, including impulse response (IR) scanning by Construction Technology Laboratories (CTL) of the accessible areas around the circumference of the Shield Building. IR scanning could not be performed on inaccessible areas including the exterior Shield Building wall areas covered by the ladder and vent stack as well as the interior Shield Building wall areas within the Auxiliary Building envelope that were covered by a double wall or equipment. The IR scanning indicated that the laminar cracking was not just limited to the shoulder where the temporary openings were located, but rather was also present in the other shoulders. These scans also revealed that similar cracking was present outside the shoulder areas in the top 20' of the cylindrical wall (approximately between El. 780' and 801') and that local cracking was present near main steam Penetrations 39 and 40. The observations from IR scanning were corroborated by core bores taken from the areas with laminar crack indications. Laminar cracking was not identified in the Shield Building dome.

In general, the observations indicated that the laminar cracking is in line with the outer mat of the main cylindrical reinforcing. The IR maps and core bores in these regions, along-with the chipping conducted on the left edge of the temporary opening, show that in general the cracks terminate when approaching the location where the shoulder reinforcing intercepts the outer mat of the main cylindrical reinforcing.

The widths of the cracks observed in 2011 were measured using a crack comparator from core bores taken at as many locations as possible. These indications of laminar cracking were observed to be tight, with most cracks with widths less than 0.010" (one reading of 0.013").

Since the cracks were tight and there was no evidence of carbonation on the cracked surfaces or of any rebar corrosion, the age of the cracks could not be accurately established. The root cause analysis of the condition concluded that these cracks had been present in the Shield Building for a long time with no adverse impact on its structural integrity and safety function.

During the initial technical acceptance of the Shield Building, industry experts Prof. Mete Sozen of Purdue University and Prof. David Darwin of the University of Kansas were

consulted for an independent assessment of the structural integrity of the Shield Building. As part of their review, they recommended that the potential impact of the laminar crack on the bond capacity of rebar should be investigated at the splice locations by performing additional experimental testing. The details of the testing process and results is outlined in subsequent sections.

Also, as part of initial technical acceptance of the Shield Building, a crack monitoring program was instituted (Ref. 6a). This periodic monitoring program utilizes the combination of IR scanning and core bores to evaluate the condition of the building and to identify any changes in the crack configuration within the building. As committed to in USAR Section 18.1.43, implementation of this monitoring program is per site procedure to identify concrete condition, crack width/extents, and rebar condition (if exposed within the core bores). Inspection is per industry standards and inspectors are qualified as described in Chapter 7 of ACI 349.3R (Ref. 5c). The monitoring program covers the circumference of the Shield Building using a sampling that provides a representative sample for the regions with laminar cracking and incorporates the knowledge gained from previously collected crack data to help track any potential crack growth and/or propagation. The data from the crack monitoring program is documented in References 3d and 3e.

The data from the crack monitoring program in 2013 and 2014 indicated no significant change in crack widths and no indications of any crack propagation from the initial observations.

The data from the crack monitoring program in 2015 indicated that there was an increase in the crack widths at some core bore locations, with the maximum crack width of approximately 0.016" at one location; however, there was no indication of any propagation of cracks beyond the initially identified areas.

The crack monitoring program observations from 2016 indicated that crack widths at most locations were higher than the corresponding 2015 readings, with the maximum crack width exceeding 0.050". The monitoring also observed cracking in previously uncracked bores. Since these observations were significantly different from those in previous monitoring programs, an independent verification of the plant crack measuring procedure was carried out by CTL (Ref. 6b). A comparison of the data collected by plant personnel with that from CTL for the same crack locations and using similar techniques generally produced comparable results, with some exceptions where CTL results indicated higher crack widths at some locations. In summary, the independent review by CTL verified the plant procedure for crack width measurements and confirmed that cracks exceeded 0.050" at some locations. The 2016 monitoring program also indicated the first evidence of rebar corrosion in the areas with laminar cracking.

The crack monitoring program observations from 2017 to current indicate a continued trend of propagation in both crack width and extent of cracking. Each year's findings are documented and evaluated to establish continued operability.

As noted in Section 1.0, a repair program has been instituted to perform bulk concrete repair of the shoulders where laminar cracking exceeds 0.050". In the subsequent

sections, this Technical Report provides the basis for incorporation of the 0.050" acceptance limit into the design/licensing basis.

3.0 Rebar Capacity

The initial technical evaluation identified that the bond strength of the lap splices for the reinforcement in the region of laminar cracking was the main item that needed further investigation. Since the laminar cracking is located along the plane of the reinforcement, the capacity of the reinforcing bars has the greatest potential to be affected by the laminar cracking. The limiting component of this effect was determined to be at the lap splices, where the laminar cracking had the potential to cause slippage and prevent the reinforcing bar from developing its full capacity.

To establish the structural adequacy of the Shield Building with the initially observed laminar cracking with crack widths of up to 0.013", an experimental test program (Phase I) was conducted at Purdue University and the University of Kansas in 2012 with the main objective of investigating the effect of laminar cracks (with widths approaching those observed in the Shield Building) on the bond capacity of the reinforcement at the lap splice locations (Ref. 1a). The observations and conclusions from the Phase I test program were used to perform the initial structural design evaluation of the Shield Building and demonstrate compliance with applicable codes of record and regulatory requirements.

Subsequently, a Phase II test program was conducted at Purdue University in 2016 to establish the maximum width of laminar cracks that will not affect the load carrying capacity of the reinforcement at the lap splice locations (Ref. 1b). The main goal of the Phase II test program was to help establish the structural adequacy of the Shield Building for any crack widths observed during the plant periodic monitoring that may not be covered by the conclusions from the Phase I test program.

As noted earlier, the 2016 crack monitoring program identified significant widening and propagation of the laminar cracks compared to those observed in previous periodic crack monitoring. Some of the laminar crack observations exceeded the bounding crack width limit recommended by the Phase II test program. Therefore, a Phase III test program was designed and conducted at Purdue University in 2017 to investigate the effectiveness of post-installed adhesive anchors on the load carrying capacity of reinforcement at the lap splice locations (Ref. 1c), as a potential repair mechanism for the Shield Building. The experimental setup for the Phase III test program was different from that used in the Phase I and II test programs, but it did include reference specimens without anchors to benchmark the results. Although the use of post-installed anchors was not adopted as the repair mechanism for the Shield Building, the observations from the Phase III reference specimens without anchors provided additional data that can be used to supplement and confirm the conclusions on maximum crack widths from the earlier test programs.

The details of these three test programs are provided below. It is noted that this technical report is based on the Phase I, II and III testing at Purdue University only. Although the results from the Phase I testing at the University of Kansas were utilized in the initial structural adequacy evaluation of the Shield Building and produced similar results as the

testing at Purdue University, they are not included in this report because the testing was not continued at the University of Kansas beyond Phase I (i.e., did not evaluate the effect of laminar cracking on the rebar splices for widths in the range relevant to this technical report).

For all the testing phases, it was not possible to exactly match the concrete properties given the age of the concrete. Therefore, every effort was made in the test programs to test at relatively lower (conservative) compressive strength and tensile strength values to produce conservative bond capacity values. The average 28-day compressive strength from original construction of the Shield Building was 5,836 psi; the average compressive strength of in-place concrete obtained from cores taken during the Shield Building evaluation in 2011 was 7,571 psi, with a corresponding tensile strength of 918 psi. The material properties used for the Phase I, II, and III test programs are described in Sections 3.1.2, 3.2.2, and 3.3.2, respectively. All reinforcing bars used in testing conformed to ASTM A615, which is the same as for the original construction of the Shield Building.

3.1 Phase I Test Program

The objective of the Phase I test program in 2012 was to evaluate the effect of laminar cracking with crack widths on the order of 0.010", on the load carrying capacity of reinforcing bar (Ref. 1a). Based on a review of Shield Building reinforcement details, the 79" lap splices for vertical rebar and hoop rebar below EL 780' and 120" lap splices for hoop rebar above EL 780' were postulated to be within the regions of laminar cracking. The vertical bars are confined by the hoop bars and concrete cover, so the splices for vertical bars are less critical than the splices for the hoop bars. The reinforcement is comprised of both #10 and #11 bars. The #10 reinforcing bar requires less development length and is therefore less critical than the #11 reinforcing bar.

The Phase I test program was established and conducted at Purdue University, testing 12 specimens of 79" and 120" lap splices for #11 bars. The specimen configuration in the Phase I test program used 6" spacing between bars (matching the minimum spacing of rebar for the Shield Building) and was prepared with lap splices placed side by side, as compared to the actual construction of the Shield Building where the splices are staggered. These conservatisms maximized the effect of the rebar/splices on each other. Also, the specimen configuration was conservative in that the splices in the Shield Building conform to the curvature of the building, which would provide an additional confinement effect, but this curvature was not included in the straight beam tests.

The test specimens were large-scale girders with rectangular sections, as typically used for testing splices. The specimens were 4-point girders, simply supported at two points equidistant to the center and loaded at two points, outside the supports, also equidistant to the center. A total of 12 specimens were tested under static loading, with six (Series A) having 120-in splices (nominally 85 bar diameters) and the remaining six (Series B) having 79-in splices (nominally 56 bar diameters). In both Series A and B, loading was applied monotonically in two test girders. In the remaining four test girders, an initial load was applied to or beyond yield to cause initial cracking, then the specimens were unloaded then reloaded.

In addition to load and deflection measurements, crack patterns and widths as well as longitudinal and transverse deformations of the test girders were recorded. The observed behavior of the test girders is described in terms of measured load-deflection relationships, recorded crack-width developments, and calculated reinforcement stresses. Detailed information on those topics is provided in Appendix A.

3.1.1 Experimental Outline

The test setup for the 120" and 79" splices is shown in Figures 4 and 5, respectively. Each girder in Series A had a total length of 39', with the ends of the 120" splice at 3' from the closer support. The cantilevered portions of the girder were 11'-6" long. Loads were applied on each cantilever segment at 10' from the support. Each girder in Series B had a total length of 34'-4", with the ends of the 79" splice at 3' from the closer support. The cantilevered segments of the girder were 10'-10 1/2" long. Loads were applied on each cantilever segment at 9'-8 1/2" from the supports.

The test specimen configuration was based on the following considerations:

- Include more than one lap splice to simulate the interaction of adjacent lap splices (two splices were used).
- Use a minimum cover of 3" that translated to a clear distance of 6" between the two splices and led to a cross-sectional width of (4x3+4x1.41)". The width of the girder section was set at 17 5/8" (Figure 6).
- Produce a splitting crack in the horizontal plane that would intersect both splices. To increase the probability of a splitting crack in the horizontal plane, given that cracking tends to occur in the direction in which cover is smallest, a side cover of 3" was used and a top cover of 5" was used.

The loads were generally applied in increments of 6 kips up to 36 kips, and above 36 kips, load increments were determined by measured displacement. Four of the specimens in Series A were subjected to loading in increments of 6 kips to yield and then to a mid-span deflection of 0.9", unloaded, and reloaded. In Series B, the four specimens were loaded to 36 kips in 6-kip increments, unloaded, and then reloaded.




Figure 6: Cross-Sectional Dimensions of Series A and B Girders (From Appendix A)

Load and deflection measurements were obtained continuously and crack patterns and widths were recorded at different load steps in each test.

3.1.2 Materials

The opening of splitting cracks depends on the relationship between the tensile strength of the concrete and the intensity of bond stress that creates the splitting stresses. Since the compressive strength of the in-place concrete for the Shield Building exceeded 6,000 psi, the tests were conservatively designed to have a concrete strength at time of tests not exceeding 6,000 psi.

Concrete used in the specimens was mixed and delivered to the laboratory by Irving Materials Inc. of West Lafayette, IN. Each girder and its related cylinders were cast using concrete from a single truck. The mix proportions by weight were:

Component	Weight of Component / Weight of Cement
Cement	1
Fine Aggregate	2.4
Coarse Aggregate (max. size = 1¼ in.)	2.6
Water	0.55

Target air entrainment was 5%, similar to the in-situ Shield Building. As concrete was being placed, temperature, air content, and slump of the mix were measured. Air temperature was also recorded. Target moist curing was 7 days but the curing period was reduced for some specimens as a result of early cylinder tests that indicated high strength. Table 1 shows the concrete strength data and detailed information for each casting is included in Appendix A.

All reinforcing bars came from the same heat and the actual material yield and tensile strengths of rebar were 66 ksi and 103 ksi, respectively (Table 2). Stress-strain properties of the bars are included in Appendix A.

Table 1: Concrete for Phase I Test Program

Test Girder Designation	Cast	Tested	Concrete Compressive Strength [psi]	Concrete Splitting Cylinder Strength [psi]	Lap Length [in.]
A1	17 April 2012	4 June 2012	5270	480	120
A2	17 April 2012	1 June 2012	6030	500	120
A3	17 April 2012	30 May 2012	5890	480	120
A4	24 April 2012	8 June 2012	5110	440	120
A5	24 April 2012	7 June 2012	5240	440	120
A6	24 April 2012	5 June 2012	5490	450	120
B1	10 April 2012	10 May 2012	4460	450	79
B2	10 April 2012	23 May 2012	4800	480	79
B3	10 April 2012	21 May 2012	4780	420	79
B4	30 April 2012	14 May 2012	5460	490	79
B5	30 April 2012	17 May 2012	5260	480	79
B6	30 April 2012	25 May 2012	5230	450	79

Table 2: Reinforcement for Phase I Test Program

Bar Designation	#11
Nominal Diameter, in.	1.41
Nominal Area, in ²	1.56
Nominal Perimeter, in.	4.43
Unit Weight, lbf/ft	5.31
Yield Stress*, ksi	66
Strength*, ksi	103
Limiting Strain in 8 in., %	14,18,19

**Note: mean from tests of three coupons*

3.1.3 Load-Deflection Relationships

Figures 7 and 8 contain the measured load-deflection relationships of the Series A and B girders, respectively. The reported deflection is the relative movement (deflection up considered to be positive) of girder mid-span with respect to the supports. The reported load is the averaged load applied near the end of the cantilever section.

All load-deflection curves measured had two common characteristics: (1) Yield moment of the section was developed after appearance of laminar cracks at low loads and at zero load in the case of the reloaded girders, and (2) all girders tested demonstrated a definite capability to maintain strength with increase in deflection beyond the yield.

It is of interest to note that the overall behavior of test girders A1, A4, A5, and A6 that were loaded, unloaded, and reloaded differed very little from those of A2 and A3 that were only loaded once, even though the specimen failures were initiated by the splice bond. In-fact, all the specimens had similar shapes to the envelope curves. All girders in Series A had the same yield deflection (approx. 0.5") and similar maximum mid-span deflections (ranging from 1.4"-1.8"). Similar conclusions can be made for the responses of girders of Series B. For this series, the yield deflection was approximately 0.3" and the maximum deflection ranged from a little below 0.5" (Girder B1) to above 0.6" (Girder B6).

The range in concrete strength from 4460 to 5460 psi did not have a significant influence on the yield deflection. The three test girders with relatively low concrete strengths (Girders B1, B2, and B3) did have slightly lower maximum deflections; but the maximum recorded value for B1 (0.47") with a concrete compressive strength of 4460 psi was not significantly lower than that of B5 (0.55") which had a concrete compressive strength of 5260 psi.

Maximum applied loads ranged from 42.0 kips to 44.1 kips for Series A and from 39.7 kips to 40.6 kips for Series B. Based on the maximum applied load alone, it is hard to differentiate the results for Series B compared to those of Series A. It is also worth noting that results of both Series A and Series B tests showed repeatability and consistency of results as shown in Figure 9 which is reassuring in terms of expected performance.




Figure 7: Force Deflection Behavior of Series A Specimens (From Appendix A)




Figure 8: Force Deflection Behavior of Series B Specimens (From Appendix A)




Figure 9: Consistency of Results for Phase I Test Program

3.1.4 Crack Measurements

Changes in crack patterns and widths were recorded in detail and are reported completely in Appendix A. Observed development of flexural crack patterns and thicknesses were consistent with what is normally expected in reinforced concrete beams responding primarily to flexure. Figure 10 shows a typical pattern of observed cracking. The flexural cracks occurred at a spacing of approximately twice the top cover or ~10". It is also seen that the cracks near mid-span did not reach as far towards the compressed edge of the girder as the ones near the support. This was an indication that the lap splice was effective, and all four bars resisted the load.

Figure 10 also shows the typical pattern of the horizontal crack at or near the level of the reinforcement in the test specimens (highlighted in red and representative of the laminar crack). A descriptive metaphor for their formation is provided by visualizing the bars as thin-walled pressurized tubes embedded in concrete. The internal pressure causes circumferential tensile stresses in the concrete around the tube that decrease with distance. The crack is initiated in the weakest plane which corresponds to the plane resulting in the minimum cover. The crack is initiated in the immediate surface of the tube and progresses out as the pressure in the tube increases. It is also relevant to note that a splitting crack can exist next to the reinforcement but not be visible on the surface of the girder.




Figure 10: Typical Pattern of Cracks – Phase I (From Appendix A)

The projection of this metaphor to the test girders suggests that the splitting crack would occur on a horizontal plane intersecting the reinforcement and that the surface width of the crack is likely to be smaller than its width next to the spliced bars. The force transfer mechanism in the splice is best understood by the following measurements: (1) longitudinal strain distribution at reinforcement level, (2) vertical deformation of the girder surface, and (3) distribution of widths of the splitting cracks. These are presented in detail in Appendix A.

The longitudinal-strain data show that there was a dominant pattern in strain distribution along the splice. In the first loadings, rapid change in strain occurred primarily in the outer 20" segments of the splice, indicating the region where most of the force transfer from bar to bar took place. The test results confirm that the regions of relatively large vertical deformation occurred in the outer 20" of the splices for both the 79" and 120" splices.

The crack-width observations documented that measurable (0.005" or more in thickness) laminar cracks of limited length (6"-12") occurred at low loads on the order of one fourth of the maximum load resisted. Cracks reached levels in excess of 0.100" at loads approaching the maximum load. At such levels of load, laminar cracks meandering along the level of the reinforcement covered virtually the entire test span. In fact, for specimens that were loaded, unloaded, and reloaded, the maximum crack widths reached 0.100" for Series A and 0.030" for Series B specimens during the initial loading.

Figures 11 and 12 show the magnitude of the recorded maximum crack width and vertical deformation along the splice lengths of Series A and B, respectively. The results show good correlation between the crack width and the vertical surface deformation. The results also show that cracks well exceeded the initial crack widths observed in the Shield Building, which were generally less than 0.010", with one crack of 0.013".




Figure 11: Correlation of Vertical Deformation with Crack Width for Series A




Figure 12: Correlation of Vertical Deformation with Crack Width for Series B

3.1.5 Maximum Reinforcement Stresses Attained

As documented in detail in Appendix A, maximum tensile stresses achieved at the ends of the splice were computed based on the moment at the end of the splice and cross-sectional properties of the test girder. The calculated stresses are shown in Table 3. The minimum tensile stress attained in the reinforcement at the end of the splice was 69 ksi (Test Girder B2) and the maximum was 80 ksi (Test Girders A2 and A3).

Table 3: Summary of Results for Phase I

Test Girder Designation	Concrete Splitting Strength (Tensile)	Concrete Compressive Strength	Lap Length	Maximum Applied Load	Maximum Moment at Support	Maximum Moment at Splice End	Calc. Reinf. Stress at Support	Calc. Reinf. Stress at Splice End
	[psi]	[psi]	[in.]	[kip]	[kip*ft]	[kip*ft]	[ksi]	[ksi]
A1	480	5270	120	43.5	481	470	81	79
A2	500	6030	120	44.1	487	476	82	80
A3	480	5890	120	44.1	487	476	82	80
A4	440	5110	120	43.3	479	468	81	79
A5	440	5240	120	43.4	480	469	81	79
A6	450	5490	120	42.0	466	455	78	77
B1	450	4460	79	39.5	425	417	72	71
B2	480	4800	79	38.9	419	419	71	69
B3	420	4780	79	39.7	427	419	72	70
B4	490	5460	79	39.7	427	419	71	70
B5	480	5260	79	40.6	436	428	73	72
B6	450	5230	79	40.6	436	428	73	72

3.1.6 Key Observations

Based on a review of the Phase I test results and the details presented in Appendix A, the following important observations can be made:

- Strain measurements and observed distribution of laminar cracks created during the tests confirmed that most, if not all, of the force transfer from one bar to another occurred in the end of the splice over a length of approximately 20" (~15 bar diameters). In the four specimens that were unloaded and reloaded, the measured maximum widths of these cracks during the initial loading exceeded 0.100" for Series A and 0.030" for Series B, with the maximum widths of the cracks at zero load before reloading being 0.080" for Series A and 0.015" for Series B.
- In both series, laminar cracks formed at a fraction of the yield load in all test girders. The difference between the strength and behavior of the girders loaded monotonically and those unloaded after reaching or exceeding yield and reloaded was negligible.

The existence of laminar cracks at the beginning of loading did not change the strength of the splices. The ratio of the limiting deflection to the yield deflection was approximately 3:1 in Series A with 120" splices and 2 in Series B with 79" splices.

- The yield strength of the rebar was 66 ksi, and for Series A and B test girders, the tensile stresses of 69 ksi to 80 ksi were attained in the reinforcement at the end of the splice (i.e., the rebar achieved more than its yield strength). The maximum reinforcement stresses in the test girders loaded to develop laminar cracks and reloaded differed negligibly from those in girders loaded monotonically. Each test specimen included two splices placed next to each other without stagger and with 6" spacing. This was a conservative test condition compared to that of the Shield building where splices are staggered and typically have a 12" spacing.

The tests indicated that despite the conservative test conditions, the effect of laminar cracking with crack widths larger than 0.015" (conservatively considering the minimum crack widths at zero load before reloading) is inconsequential to the bond or force transfer capacity of both 79" and 120" lap splices, and full yield capacity could be used for design basis calculations.

3.2 Phase II Test Program

A total of 6 specimens were tested as part of the Phase II test program at Purdue University in 2016 to estimate the maximum width of laminar cracks that would not affect the load carrying capacity of the rebar splices (Ref. 1b). Because the first cracks observed in the Shield Building were narrow, Phase I focused on the effects of laminar cracks on the strength of lap splices without specific attention to establishing a plausible limit to the width of those cracks. Therefore, the goal of Phase II testing was to estimate such a bounding maximum crack width that can be used to help establish the structural adequacy of the Shield Building with the crack widths approaching those observed under the plant monitoring program. Based on the results of the Phase I testing, #11 rebar with 79" lap splices were used as the bounding configuration in the Phase II test program (see Appendix B).

3.2.1 Experimental Outline and Loading Protocol

The Phase II test program specimens were labeled as Series C to supplement the Series A and B Phase I specimens at Purdue University. The Series C test girders had the same geometry and configuration as the Series B test girders shown in Figure 5. Similar to the approach used for the Series B tests, the specimens were tested by applying an initial loading and unloading to initiate laminar cracks in the plane of the spliced rebar, and then reloading, with the loads applied in increments during the loading and reloading cycles. However, the loading for Series C girders was applied using a different loading protocol discussed below than that used for Series B girders. Unless noted otherwise, the term "deflection" below refers to the mid-span deflection for Phase II tests.

From the Phase I test results for Series B specimens, it was observed that most of the specimens yielded at a deflection of approximately 0.30" to 0.35". The magnitudes of crack widths are directly correlated to the applied loads and corresponding deflections. The unloading for the Series B girders was initiated before or just at yielding (i.e., at a

deflection less than 0.35” at the maximum applied load during the initial loading and unloading). To develop cracks wider than those observed for Series B girders, the initial loading for Series C girders was applied, in stages, to a total deflection of at least 0.4” before starting to unload the specimen. Four (4) girders (C-1 to C-3 and C-5) were loaded to a deflection of 0.4” during the initial loading and two (2) girders (C-4 and C-6) were loaded to a deflection of 0.5” during the initial loading.

Similar to Phase I tests, load and deflection measurements were obtained continuously and crack patterns and widths were recorded at different load steps in each test.

3.2.2 Materials

The concrete mix design for the Series C tests was kept the same as that used in the Phase I tests at Purdue University. Concrete used in the specimens was mixed and delivered to the laboratory by Irving Materials, Inc. of West Lafayette, IN. Each test girder and its associated cylinders were cast using concrete from a single truck.

Similar to Phase I, target air entrainment for the concrete mix was 5%. As concrete was being placed, air and concrete temperatures, air content, and slump of the mix were measured. The specimens were cured for a week in accordance with the approved Purdue test procedure. The compressive strength of concrete for the Series C specimens is summarized in Table 4 and shows that the mix used for the test girders was of uniform quality and strength. Detailed information and records for each casting are included in Appendix B.

Table 4: Concrete for Phase II Test Program

Test Girder	Cast Date	Test Date	Concrete Compressive Strength* [psi]	Concrete Splitting Cylinder Strength [psi]	Age of Specimen [days]
C1	2/2/2016	3/21/2016	5300	500	48
C2		3/28/2016	5200	450	55
C3		4/4/2016	5900	500	62
C4		4/11/2016	5700	500	69
C5		4/12/2016	5600	500	70
C6		4/14/2016	5300	400	72

**mean of six cylinder tests*

All reinforcing bars came from the same heat. Stress-strain properties of the bars are included in Appendix B. The properties of the reinforcing bars are presented in Table 5. The actual material yield strength of the rebar used for Phase II tests was 65 ksi.

Table 5: Reinforcement for Phase II Test Program

Bar Designation	#11
Nominal Diameter, in	1.41
Nominal Area, in ²	1.56
Nominal Perimeter, in	4.43
Unit Weight, lbf/ft	5.31
Yield Stress*, ksi	65

**mean from tests of three coupons*

3.2.3 Load-Deflection Relationships

Figure 13 depicts the measured load-deflection relationships separately for each of the six (6) test girders and Figure 14 shows the results superimposed in one plot. The reported load is the averaged load applied near the end of the overhang segments and the reported deflection is the mid-span deflection (deflection upward considered to be positive). From Figures 13 and 14, the results of Series C tests showed repeatability and consistency, which provides assurance for the acceptability of the tests (including test results) and expected performance.

The test girders showed yield deflection of approximately 0.28" and maximum deflection ranging from 0.70" to 0.92". The ultimate load ranged from 39.7 kips to 40.9 kips for the Series C girders. All test girders demonstrated a definite capability to maintain strength with increase in deflection beyond yield, irrespective of the point of unloading.




Figure 13: Measured Load-Deflection Relationships for Phase II (Appendix B)




Figure 14: Consistency of Test Results – Phase II

3.2.4 Crack Measurements

Figure 15 shows the vertical deformation plot during the initial loading and unloading for each girder in the middle 80” of the specimen, which approximately corresponds to the length of the splice. The vertical deformation plot for girder C3 contains the data for the South end only, due to a sensor malfunction in the North end.




Figure 15: Vertical Deformations for Series C Test Girders during Initial Loading (from Appendix B)

Consistent with the Series B test girders, the results showed that most of the force transfer occurs at the ends of splice over lengths of approximately 15-bar diameters (i.e., approximately 20"). The calculated crack widths at the surface of specimens and the length of cracks are listed in Table 6.

Table 6: Crack Measurements for Phase II (from Appendix B)

Test Girder	Max. Mid-span deflection at Initial Loading [in]	Max. Crack Width reached during Initial Loading [10 ⁻³ in]	Mid-span Deflection at last reading during reload [in]	Max. Crack Width at last reading during reload [10 ⁻³ in]	Max. Crack Length at South Splice End [in]	Max. Crack Length at North Splice End [in]
C1	0.42	42	0.70	90	27	23
C2	0.40	21	0.41	25	22	27
C3	0.41	39	0.41	42	23	11
C4	0.52	52	0.50	53	28	24
C5	0.43	54	0.42	57	24	18
C6	0.52	30	0.52	33	22	0

3.2.5 Maximum Reinforcement Stresses Achieved

The maximum stresses in reinforcement at the support and splice end were calculated using the same approach as that in the Phase I test program. The stresses correspond to the moments at the respective locations that are primarily due to applied load, but also include contributions from other loads such as self-weight. The rebar stress calculations are reported in Appendix B and are summarized in Table 7. The tensile stresses attained in the reinforcement were well beyond the rebar yield strength, ranging from 73 ksi to 75 ksi.

Table 7: Summary of Test Results for Phase II (from Appendix B)

Test Girder	Concrete Comp. Strength	Concrete Splitting Tensile Strength	Max. Applied Loads	Max. Midspan Deflection	Max. Moment at Support	Max. Moment at Splice End	Calc. Rebar Stress at Support	Calc. Rebar Stress at Splice End
	[psi]	[psi]	[kips]	[in]	[ft-kip]	[ft-kip]	[ksi]	[ksi]
C1	5300	500	39.7	0.70	427	419	74	73
C2	5200	450	40.0	0.85	430	422	75	74
C3	5900	500	40.4	0.79	434	426	76	74
C4	5700	500	40.9	0.83	439	431	76	75
C5	5600	500	40.2	0.82	432	424	75	74
C6	5300	400	40.7	0.92	437	429	76	75

3.2.6 Key Observations

Based on a review of the Phase II test results and the details presented in Appendix B, the following important observations can be made:

- The strength and ductility response of the test girders did not vary significantly with the maximum load applied during the initial loading. This means that the strength and ductility behavior of the test girders are independent of the maximum crack widths generated in the initial loading and unloading. The ductility ratio for the Series C test girders was approximately 3.
- The maximum crack widths at the surface of the specimens at the maximum load applied in the initial loading cycle ranged from 0.021” to 0.054”.
- Laminar cracks parallel to the spliced reinforcing bar opened at low loads. Widths of the laminar cracks varied along the length of the spliced region, with maximum widths typically in regions close to the ends of the splice.
- Most of the force transfer from one rebar to another occurred in the end of the splice over a length of approximately 15-bar diameters (approximately 20”).
- The yield strength of the rebar was 65 ksi, and for all test girders, the tensile stresses of 73 ksi to 75 ksi were attained in the reinforcement at the end of the splice (i.e., the rebar achieved more than its yield strength).

The intent of the Phase II test program was to estimate the maximum crack width that would not have an effect on the load carrying capacity of the lap splices. Table 6 shows that the maximum crack width during initial loading reached 0.054” for Series C test specimens, demonstrating that the load carrying capacity of the lap splices is not impacted for crack widths up to 0.054”.

The repeatability and consistency of the test results shows that the results are reliable. Also, the results are conservative and have a built-in safety margin for the following reasons, similar to those for the Phase I test program:

- The Series C test girders had an conservative configuration, since the pair of spliced rebar was placed closely next to each other and without stagger, specimen concrete compressive strength was lower than the average compressive strength of the in-place concrete in the Shield Building, and confinement effects due to the curvature of Shield Building and the extra concrete thickness of the Shield Building shoulders were neglected. Therefore, the Series C test results are conservative when compared to the behavior of the spliced rebar in the Shield Building.
- For a deformed rebar embedded in concrete and subjected to pullout force, the splitting stresses are highest next to the rebar and decrease away from the rebar. Therefore, the widths of laminar cracks are expected to be higher next to the rebar compared to those at the surface of the specimen. Therefore, the crack widths reported in Table 6 that are measured at the surface of the specimen are conservative.
- The maximum deflection limit of 0.50" during the initial loading was chosen based on considerations of personnel and equipment safety. Irrespective of the maximum load applied during the initial loading prior to unloading, the Series C test girders had similar strength and ductility response. If safety during testing was not a consideration, it is possible that a higher deflection limit could be achievable which would result in larger crack widths and, thus, potentially showing that crack widths larger than those reported in Table 6 may have no adverse impact on the load carrying capacity of the reinforcement.

Phase II tests showed that crack widths of up to 0.054" did not have an adverse impact on the load carrying capacity of the reinforcing bar lap splices. Reference 1b recommended using a safe bounding crack width limit of 0.050" for the purpose of assessing the acceptance of the observed cracking in the Davis-Besse Shield Building. Appendix D includes a technical memo from Purdue University concluding that laminar cracks with widths up to 0.050" have no adverse effect on the load carrying capacity of the rebar lap splices.

3.3 Phase III Test Program

The purpose of the Phase III test program at Purdue University in 2017 was to investigate the effect of post-installed anchors on the load carrying capacity of the rebar lap splices (Ref. 1c). This main intent was to evaluate the adequacy of the anchor system as a potential repair mechanism for the Shield Building at locations where the laminar crack width exceeded the recommended threshold limit of 0.050" based on Phase II test results. Similar to the Phase II test program, the Phase III investigation focused on the #11 rebar with 79" lap splices, which is the critical configuration.

It should be noted that the anchor system tested during Phase III did not ultimately end up being implemented. However, this testing program did utilize reference samples without anchors, which provided additional data to supplement the Phase I and II testing. Also, as will be discussed below, a different test configuration and protocol were utilized

for Phase III; however, the results were similar to Phase I and II, thus providing confirmation of the conclusions reached during Phase I and II.

3.3.1 Experimental Outline and Loading Protocol

Because of the large number of specimens for the Phase III test program and the potential necessity of significantly more tests that would need to be conducted, a simpler test configuration and loading protocol was utilized compared to those used for the Phase I and II test programs at Purdue University. As discussed earlier, Phase I and II test programs used long test girders subjected to 4-point transverse loading that produced constant flexure over the test span and subjected the #11 rebar with lap splice to tensile loading. For the Phase III test program, a simplified test configuration was used, wherein shorter (6'-8" long) specimens were used, but having the same cross-section (17-5/8"x30") as that for the test girders used in the previous test programs (see Figures 16 and 17). The specimen length was dictated by the 79" lap splice length. The test specimens were subjected to tensile loading applied directly to the spliced #11 rebar to produce similar effects as in the test girder specimens used in the previous test programs. The tensile force to the rebar was applied through a "self-reacting" loading frame (see Figures 16 and 17). Refer to Appendix C for details.

Specimens were tested both without any anchors and with different anchor configurations (depth of embedment, spacing, etc.) as transverse reinforcement. Since the use of anchors is not the subject of this Technical Report, only the six (6) specimens without anchors will be discussed.




Figure 16: Series D Test Loading Frame Setup (From Appendix C)



Figure 17: Series D Test Setup and Loading Arrangement (From Ref. 1c)

Table 8: Phase III Test Program Matrix (from Appendix C)

Test Series	Test Specimen	Anchor Details			Bearing Plate
		No. of Anchors	Spacing, s (in)	Embedment depth, d_e (in)	
1	D1	0	N/A	N/A	N/A
	D2				
	D3				
	D9				
	D11				
	D17				

The loading scheme for the tests involved (a) initial loading cycle to create laminar cracks in the specimen, (b) unloading completely, (c) installation of anchors (not covered in this report), and (d) reloading, with loads applied in small increments during the initial loading and reloading cycles. Additionally, during the initial loading cycle, loading was applied to

the specimen to create maximum crack widths exceeding the recommended bounding limit of 0.050” from the Phase II program.

During the test, the forces in reinforcing bar, vertical and horizontal deformations, and crack widths were measured and the crack maps were recorded (see Appendix C).

3.3.2 Materials

The concrete mix design for the Series D tests was kept the same as that used in the Phase I and II tests at Purdue University. Concrete used in the specimens was mixed and delivered to the laboratory by Irving Materials, Inc. of West Lafayette, IN. The first set of specimens was cast on January 11, 2017 and the second set of specimens was cast on April 27, 2017.

Similar to Phases I and II, target air entrainment for the concrete mix was 5%. As concrete was being placed, air and concrete temperatures, air content, and slump of the mix were measured. The specimens were cured for a week. The compressive strength of concrete for the Series D specimens is summarized in Table 9 and shows that the mix used for the test girders was of uniform quality and strength. Detailed information and records for each casting are included in Appendix C.

Table 9: Compressive Strength of Concrete – Phase III Program

Test Specimen	Cast Date	Test Date	Concrete Compressive Strength*	Concrete Splitting Cylinder	Age of Specimen (days)
D1	1/11/2017	2/13/2017	3900	450	33
D2	1/11/2017	2/15/2017	3900	450	35
D3	1/11/2017	2/15/2017	3900	450	35
D9	1/11/2017	3/10/2017	4100	400	58
D11	1/11/2017	3/17/2017	4300	400	65
D17	4/27/2017	7/5/2017	4400	450	69

**mean of three tests*

All reinforcing bars came from the same heat. Stress-strain properties of the bars are included in Appendix C. The nominal properties of the reinforcing bars are presented in Table 10. The actual material yield strength of rebar used for Phase III tests was 67 ksi.

Table 10: Reinforcement Properties – Phase III Program

Bar Designation	#11
Nominal Diameter, in	1.41
Nominal Area, in ²	1.56
Nominal Perimeter, in	4.43
Unit Weight, lbf/ft	5.31
Yield Stress*, ksi	67

**mean from tests of twelve coupons*

3.3.3 Test Results and Key Observations

Figure 18 shows the load vs. crack width plots for the specimens without anchors. Appendix C also provides the plots of variations of vertical and horizontal deformations along the length of specimens and the load vs. specimen elongation plots. Table 11 lists the results, including the maximum crack width and maximum rebar stresses during initial loading cycle and at failure.

In general, Figure 18, along with the test results for the specimens with anchors (Appendix C), shows consistency of results and provides assurance for the acceptability of the tests (including test results) and expected performance. The results for Series D specimens without anchors confirmed that the rebar lap splices can maintain full load carrying capacity with laminar cracks of widths exceeding 0.050”.




Figure 18: Load vs Crack Width for Phase III Specimens without Anchors (from Appendix C)

Table 11: Crack Widths and Rebar Stresses (from Appendix C)

Test Specimen	Max. Rebar Stress at Splice End (ksi)		Max. Laminar Crack Width (in.)	
	Initial Loading	Failure	Initial Loading	Failure
D1	72	73	0.07	0.08
D2	71	71	0.06	0.07
D3	80	81	0.11	0.18
D9	76	76	0.09	0.09
D11	71	71	0.06	0.06
D17	77	77	0.13	0.13

The behavior of the specimens without anchors generally shows predictable response with specimen failure occurring at crack widths exceeding 0.060”.

The conservatisms noted for Phase I and II test programs are also applicable to Phase III. These include the conservative test configuration with lap splices located side by side in a straight specimen and the measurement of cracks at the surface of the specimen instead of at the rebar location.

3.4 Summary of Phase I, II, and III Purdue Test Results

A total of 24 specimens were tested at Purdue University during the Phase I, II, and III test programs (excluding the specimens tested with post-installed anchors). The testing utilized a conservative test configuration to determine the limiting condition.

Phase I was conducted to test lap splices in the presence of existing laminar cracks without specific attention to initial crack width. In Phase II, laminar cracks were observed to have no detrimental effect on splice strength and deformability for cracks widths reaching up to nearly 0.050” during initial loading. In Phase III, the threshold of 0.050” was confirmed by specimens that were able to attain their full strengths after forming splitting cracks with widths ranging from 0.060” to 0.130” during initial loading. Table 12 provides the maximum reinforcement stress at failure and crack widths for the Phase I, II, and III specimens (without anchors) and Figures 19 and 20 shows the maximum reinforcement stress at failure.

Table 12: Compiled Summary of Phase I, II, and III Test Results

Test Program	Test Girder Designation	Concrete Compressive Strength	Lap Length	Max. Crack Width at Initial Loading	Max. Crack Width at last reading during reload	Calculated Reinf. Stress
		[psi]	[in]	[in]	[in]	[ksi]
Phase I	A1	5270	120	(a)	(a)	79
	A2	6030	120			80
	A3	5890	120			80
	A4	5110	120			79
	A5	5240	120			79
	A6	5490	120			77
	B1	4460	79			71
	B2	4800	79			69
	B3	4780	79			70
	B4	5460	79			70
	B5	5260	79			72
	B6	5230	79			72
Phase II	C1	5300	79	0.042	0.090	73
	C2	5300	79	0.021	0.025	74
	C3	5900	79	0.039	0.042	74
	C4	5700	79	0.052	0.053	75
	C5	5600	79	0.054	0.057	74
	C6	5300	79	0.030	0.033	75
Phase III	D1	3900	79	0.070	0.080	73
	D2	3900	79	0.060	0.070	71
	D3	3900	79	0.110	0.180	81
	D9	4100	79	0.090	0.090	76
	D11	4300	79	0.060	0.060	71
	D17	4400	79	0.130	0.130	77

(a) Crack widths not reported because Phase I focused on the effects of laminar cracks on the strength of lap splices without specific attention to establishing a plausible limit to the width of those cracks. See Appendix A.




Figure 19: Maximum Reinforcement Stress at Failure for Phase I




Figure 20: Maximum Reinforcement Stress at Failure for Phases II and III

From the Phase II and III results only, it is evident that the lap splices maintained their full load carrying capacity, with maximum reinforcement stresses ranging from 73 ksi to 81 ksi, with pre-existing crack widths up to 0.130". The average stress in reinforcement at failure was 74.5 ksi with coefficient of variation of 3.6%.

As discussed earlier, the Phase I tests were conducted with smaller widths of pre-existing laminar cracks to establish the structural adequacy of Shield Building with the laminar crack characteristics prevalent at that time. However, the load-deformation relationships of the Phase I specimens are similar to those of the Phase II and III specimens. Additionally, as noted for Phase I tests, the load deformation relationships of the specimens that were loaded, unloaded, and reloaded are almost identical to the response of specimens that were loaded monotonically. Besides demonstrating the repeatability of the test performance, this shows that the response of Phase I test specimens would lead to the same conclusions even if pre-existing cracks with crack widths approaching those in Phase II and III test programs were created. Considering all test results from all Phases, the maximum reinforcement stress ranged from 69 ksi to 81 ksi with an average stress of 73.2 ksi and a coefficient of variation of 4.0%.

Based on the summary of results presented above, it is concluded that the Shield Building rebar lap splices will safely maintain its full load carrying capacity with laminar cracks widths of up to 0.050".

3.5 Quality Assurance

It is noted that the Phase I and II test programs were deemed equivalent to an "augmented quality", with associated QA/QC oversight, the results thereof, are considered appropriate as input to safety-related design. Although the Phase III test program was characterized as "exploratory" and thus, "non-safety", with an intent to establish a suitable anchor system layout, a similar degree of engineering and management oversight was also provided for the Phase III tests. Additionally, as noted above, the results across the three phases are reproducible and consistent. Therefore, the conclusions established in Section 3.4 are considered applicable for safety-related design of the Shield Building.

The QA/QC records from Phase I and II programs are not repeated here, but are available in References 1a and 1b, respectively.

4.0 Composite Action of Shell

The composite action of the section for the out-of-plane bending effects can be evaluated by the magnitude of in-plane shear transfer capacity across cracked concrete.

Shear force can be transmitted across a crack if the crack faces are moving in opposite directions. This shear transfer capacity can come from three mechanisms: 1) aggregate interlock; 2) dowel action; and 3) axial steel force (see Figure 21).




Figure 21: a) Aggregate interlock; b) Dowel action; c) Axial steel force

For a crack without reinforcement across it, shear transfer comes exclusively from the aggregate interlock. The parameters, which affect the aggregate interlock capacity, τ , are identified by different researchers (Walraven, 1980, 1981 (Refs. 7d-7e); Bazant and Gambarova, 1980 (Ref. 7a); Gambarova, 1981 (Ref. 7b); Gambarova and Valente, 1990 (Ref. 7c)) as the crack width, w , the shear displacement, Δ , the concrete crushing strength, f_{cc}' , and the maximum aggregate particle diameter, D_{max} . See Figure 22 for illustration.




Figure 22: Shear transmission across an un-reinforced crack

Walraven (1980) reported numerous experimental results with the range of $D_{max} = 16 \sim 32 \text{ mm}$ (0.63" – 1.25") and $f_{cc}' = 13.4 \sim 59.1 \text{ N/mm}^2$ (1944 psi – 8572 psi), covering different cases of crack width ranging from 0.1 to 1.0 mm (0.004" – 0.039"). Based on theoretical analysis and the aforementioned experimental results, Walraven proposed the following equation for the shear transmission across an un-reinforced crack (Refs. 7d-7e):

$$\tau = -\frac{f_{cc}'}{30} + (1.8 w^{-0.8} + (0.234 w^{-0.707} - 0.20)f_{cc}')\Delta \quad (1)$$

In which:

τ : shear transmission across an un-reinforced crack, N/mm²

f_{cc}' : concrete crushing strength, N/mm²

w : crack width, mm

Δ : shear displacement, mm

Using principles of fracture mechanics, alternative solutions of the shear transfer mechanism across an un-reinforced crack are proposed by Bazant, Gambarova, and Valente (Refs. 7a-7c).

A comparison of various methodologies mentioned above indicate that significant shear capacity can develop across the plane to develop a composite action as shown in Figure 23.




Figure 23: Shear transmission capacity across an un-reinforced crack

Furthermore, in Section 2505 of ACI 318-63, which is used for the ultimate strength design of the Shield Building, the shear transfer along the concrete contact surface without mechanical anchorage (reinforcement) is permitted to be 40 psi for service loads and 76 psi ($1.9 \times 40 = 76$ psi) for ultimate loads. These values are comparable to results discussed above.

Note that per the design calculations, the magnitude of shear across the laminar crack is very small compared to the capacity values discussed above, given the relatively nominal out-of-plane bending effects on the shell due to seismic, wind or tornado effects. It is,

therefore, concluded that laminar cracking of 0.050" (1.25 mm width) in the outer rebar mat will not impact the expected composite behavior of the shell for the design loads.

5.0 Overall Structural Response

The test results show that the outer circumferential rebar maintains its full design capacity with the presence of laminar cracks with widths up to 0.050". Additionally, review of the load-deflection behavior of the specimens in all three test programs does not indicate any significant change in the reloading stiffness of specimens after introduction of the laminar cracks with widths exceeding 0.050".

The Shield Building is designed for all applicable loads and load combinations in accordance with USAR Section 3.8.2.2.4 and DCM Section II.G, including dead and live loads, wind and tornado loads, and operating basis and safe shutdown earthquakes. The controlling load combinations for the design of the Shield Building involve the design basis safe shutdown earthquake, for which the Shield Building will behave like a cantilever where most of the forces are transferred through in-plane shear and axial membrane forces and very little through out-of-plane bending of the shell. The laminar cracking has no impact on in-plane stiffness of the cylindrical shell, which will resist most of the applicable seismic loads. For thermal and tornado loads that produce hoop tension and moment, the existence of laminar cracking does not change the concrete section behavior since the concrete shell is already assumed to be cracked through-thickness. The applicable tension forces are primarily resisted by the hoop reinforcement, which are able to maintain their design function with crack widths up to 0.050" per the testing. Therefore, it is concluded that no changes need to be made to the analytical model in order to account for the effect of laminar cracking on stiffness of the Shield Building.

Based on above discussion, it can be safely concluded that the effect of laminar cracking on the overall stiffness, dynamic characteristics and performance of the Shield Building is negligible.

6.0 Serviceability and Long-Term Durability

Per applicable codes of record for the Shield Building (ACI 318-63 and ACI 307-69) serviceability essentially relates to crack control under service load conditions (not faulted load conditions). Service life of the structure can be affected by the nature, extent and width of cracking present on the surface of the structure that may provide a path for moisture penetration resulting in reinforcement corrosion. For cracking induced by applied loads such as flexure or hoop tension, the primary objective is to limit the crack width (at the surface) to 0.010" per the ACI Standard Building Code, as noted in USAR Section 3.8.2.2.5, in order to limit potential moisture paths that could lead to corrosion of reinforcing steel. The initial detailed condition assessment (supplemented by continued periodic monitoring) did not indicate any unusual surface cracking due to either shrinkage or flexure, with observed surface cracks much tighter than 0.010".

The monitoring program has subsequently indicated rebar corrosion at the locations of maximum laminar crack widths. To address this, a repair program has been implemented and requires removal and replacement of concrete in areas of cracking exceeding 0.050"

with/without any signs of corrosion. The repair program involves chipping of concrete and rebar removal/replacement (as required) to a larger extent than depicted in the latest IR scans. Additionally, a passive cathodic protection program is implemented to mitigate and prevent rebar corrosion after the repair is completed. The periodic monitoring program will continue to verify that the implemented measures are effective in ensuring there is no further rebar corrosion and there are no pathways for moisture infiltration.

Therefore, it is concluded that the long-term durability of the Shield Building is not adversely affected with laminar crack widths of up to 0.050" within the thickness of the cylindrical wall.

7.0 Conclusions

Based on a detailed review of all the relevant technical documents and test reports, it is concluded that crack widths of up to 0.050" have no adverse impact on capacity of reinforcing bars to perform their intended function to ensure the structural adequacy of the Shield Building. Moreover, there are several additional layers of conservatism that add margin to the design capacity. These conservatisms include a higher strength of the in-place concrete versus the strength of test specimens, not including the effect of staggering of spliced rebars in the test specimens, and not including the curvature of the Shield Building in the test specimen.

It is also concluded that the composite action of the shell, overall structural response and serviceability and durability of the Shield Building are not adversely impacted with laminar cracking of 0.050". The monitoring program in place will ensure that any exceedance in cracking or evidence of corrosion are adequately identified and addressed.

Appendix E contains a memorandum from Prof. Santiago Pujol, who was responsible for the experimental testing at Purdue University, supporting these conclusions.

8.0 References


1. Bechtel Technical Reports
 - a. 25593-000-G83-GEG-00016, Rev. 0, Effects of Laminar Cracks on Splice Capacity of No. 11 Bars based on Testing Conducted at Purdue University and University of Kansas for Davis-Besse Shield Building, 2012
 - b. 25884-000-30R-C01G-00001, Rev. 0, Effect of Crack Width on the Load Carrying Capacity of No. 11 Bars with 79-inch Lap Splices based on Phase II Testing Conducted at Purdue University for Davis-Besse Shield Building, 2016
 - c. 25884-000-30R-C01G-00005, Rev. 0, Effect of Post-Installed Anchors on Load Carrying Capacity of No. 11 Bars with 79-inch Lap Splices for Specimens with Pre-existing Laminar Cracks based on Phase III Testing Conducted at Purdue University, 2018
2. NOT USED.
3. Drawings
 - a. C-109, Rev. 6, Shield Building Roof Plan and Details, Sh. 1
 - b. C-110, Rev. 8, Shield Building Roof Plan Wall Section and Details

- c. C-111, Rev. 13, Shield Building Wall Development
- d. C-111A, Rev. 10, Shield Building Exterior Developed Elevation
- e. C-111B, Rev. 6, Shield Building Data for Core Bore Inspections
- 4. Davis Besse Nuclear Power Station Design Basis Documents
 - a. Chapters 3 and 18, Updated Safety Analysis Report, Rev. 33
 - b. Design Criteria Manual, Rev. 45
- 5. Codes and Standards & NRC Regulatory Documents
 - a. ACI 318-63, Building Code Requirements for Reinforced Concrete
 - b. ACI 307-69, Specification for Design and Construction of Reinforced Concrete Chimneys
 - c. ACI 349.3R-02, Evaluation of Existing Nuclear Safety-Related Concrete Structures
- 6. Plant Procedures and Other Plant Documents
 - a. EN-DP-01511, Rev. 11, "Structures Monitoring", FENOC Procedure
 - b. Shield Building Crack Width Validation, CTL Group Report, October 27, 2016
- 7. Technical Publications
 - a. Bazant, Z. P., and Gambarova, P. G., (1980). "Rough Cracks in Reinforced Concrete", J. Struct. Div. ASCE 106, pp. 819-842.
 - b. Gambarova, P. G., (1981). "On Aggregate Interlock Mechanism in Reinforced Concrete Plates with Extensive Cracking", IABSE Colloquium, Delft, pp. 105-134.
 - c. Gambarova, P. G., and Valente, G., (1990). "Smearred Crack Analysis for Fracture and Aggregate Interlock in Concrete", Engineering Fracture Mechanics, Vol. 35, No. 4/5, pp. 651-663.
 - d. Walraven, J. C., (1980). "Aggregate Interlock: A Theoretical and Experimental Analysis", PhD thesis, Delft University.
 - e. Walraven, J. C., (1981). "Behavior of Cracks in Plain and Reinforced Concrete Subjected to Shear", IABSE Colloquium, Delft, pp. 249-266.

25884-000-30R-C01R-00002, Rev. 000

APPENDIX A

“Purdue Phase I Test Report”



AN INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED LAP SPLICES OF #11 REINFORCING BARS

A Report Submitted to

First Energy Nuclear Operating Company
Oak Harbor, Ohio

by
Mete A. Sozen

and
Santiago Pujol

12 July 2012
Bowen Laboratory
West Lafayette, IN

TABLE OF CONTENTS

SUMMARY	6
1. Introductory Remarks	7
2. Object and Scope	7
3. Materials	10
4. Observed Relationship between Applied Load and Deflection	10
5. Crack Development.....	11
6. Maximum Reinforcement Stress Attained.....	14
7. Conclusions	14

TABLES

Table 1. Concrete	16
Table 2. Reinforcement.....	17
Table 3. Summary of Results.....	18

FIGURES

Figure 1 Overall Properties of The Test Girders.....	19
Figure 2 Test Girder, Series A.....	20
Figure 3 Test Girder Series B.....	20
Figure 4 Cross-Sectional Dimensions of Series A and B Girders	21
Figure 5 Photograph of One of The Cantilevered Segments of A Test Girder	21
Figure 6 Flexural Cracks and Bursting Cracks.....	22
Figure 7 West Elevation of Test Girder A4. Initial Loading. Applied Load = 36 kip.....	23
Figure 8 East Elevation of Test Girder A4. Initial Loading. Applied Load = 36 kip	23
Figure 9 West Elevation of Test Girder A4 Reloaded to 36 kip.....	24
Figure 10 East Elevation of Test Girder A4 Reloaded to 36 kip	24
Figure 11 West Elevation of Test Girder A4 Reloaded to 42 kip.....	25
Figure 12 East Elevation of Test Girder A4 Reloaded to 42 kip	25
Figure 13 Load-Deflection Plot for Test Girder A1.....	26
Figure 14 Load-Deflection Plot for Test Girder A2.....	27
Figure 15 Load-Deflection Plot for Test Girder A2.....	28
Figure 16 Load-Deflection Plot for Test Girder A4.....	29
Figure 17 Load-Deflection Plot for Test Girder A5.....	30
Figure 18 Load-Deflection Plot for Test Girder A6.....	31
Figure 19 Load-Deflection Plot for Test Girder B1.....	32
Figure 20 Load-Deflection Plot for test Girder B2.....	33
Figure 21 Load-Deflection Plot for Test Girder B3.....	34
Figure 22 Load-Deflection Plot for Test Girder B4.....	35
Figure 23 Load-Deflection Plot for Test Girder B5.....	36
Figure 24 Load-Deflection Plot for Test Girder B6.....	37
Figure 25 Qualitative Illustration of Internal Stresses Leading to Bursting Cracks.....	38
Figure 26 Optotrak Targets on Series A Girders	39
Figure 27 Optotrak Targets on Series B Girders.....	40
Figure 28 Selected Regions for Maximum Bursting Crack Widths in Series A Girders	41
Figure 29 Selected Regions for Maximum Bursting Crack Widths in Series B Girders	41
Figure 30 Longitudinal Strains at Level of Reinforcement, First Loading of Series A Girders.....	42
Figure 31 Longitudinal Strains at Level of Reinforcement, First Loading of Series B Girders.....	43
Figure 32 Longitudinal Strains at Level of Reinforcement, Reloading of Series A Girders	44

Figure 33 Longitudinal Strains at Level of Reinforcement, Reloading of Series B Girders	45
Figure 34 Transverse Deformations, First Loading of Series A Girders.....	46
Figure 35 Transverse Deformations, First Loading of Series B Girders.....	47
Figure 36 Transverse Deformations, Reloading of Series A Girders	48
Figure 37 Transverse Deformations, Reloading of Series B Girders	49
Figure 38 Representative Cracks, Test Series A.	50
Figure 39 Representative Cracks, Test Series B	51
Figure 40 Recorded Maximum Surface Widths (in thousands of an inch) (in thousands of an inch) of Bursting Cracks at Reinforcement Level, Test Girder A-1.....	52
Figure 41 Recorded Maximum Surface Widths (in thousands of an inch) of Bursting Cracks at Reinforcement Level, Test Girder A-2.....	52
Figure 42 Recorded Maximum Surface Widths (in thousands of an inch) of Bursting Cracks at Reinforcement Level, Test Girder A-3.....	53
Figure 43 Recorded Maximum Surface Widths (in thousands of an inch) of Bursting Cracks at Reinforcement Level, Test Girder A-4.....	53
Figure 44 Recorded Maximum Surface Widths (in thousands of an inch) of Bursting Cracks at Reinforcement Level, Test Girder A-5.....	54
Figure 45 Recorded Maximum Surface Widths (in thousands of an inch) of Bursting Cracks at Reinforcement Level, Test Girder A-6.....	54
Figure 46 Recorded Maximum Surface Widths (in thousands of an inch) of Bursting Cracks at Reinforcement Level, Test Girder B-1.....	55
Figure 47 Recorded Maximum Surface Widths (in thousands of an inch) of Bursting Cracks at Reinforcement Level, Test Girder B-2.....	55
Figure 48 Recorded Maximum Surface Widths (in thousands of an inch) of Bursting Cracks at Reinforcement Level, Test Girder B-3.....	56
Figure 49 Recorded Maximum Surface Widths (in thousands of an inch) of Bursting Cracks at Reinforcement Level, Test Girder B-4.....	56
Figure 50 Recorded Maximum Surface Widths (in thousands of an inch) of Bursting Cracks at Reinforcement Level, Test Girder B-5.....	57
Figure 51 Recorded Maximum Surface Widths (in thousands of an inch) of Bursting Cracks at Reinforcement Level, Test Girder B-6.....	57
Figure 52 Comparison of crack-width measurements and measured vertical deformations, test series A.	58
Figure 53 Comparison of crack-width measurements and measured vertical deformations, test series B.	59
Figure 54 Moment and Shear Diagrams	60
Figure 55 Maximum Unit Stress Reached by Spliced Reinforcement.....	61

APPENDICES

1. Concrete Strength on Test Day
2. Casting Data and As-Built Dimensions
3. Curing
4. Reinforcement Strength
5. Maximum Reinf. Stress Series A
6. Maximum Reinf. Stress Series B
7. Crack Pattern and Width Data
8. Approved Test Procedure
9. Direct Deflection Reads
10. Calibration Certificates
11. Additional Photos
12. Instrumentation Logs

SUMMARY

The object of the experimental investigation reported was to study the effect of laminar cracks on the strength of unconfined lap splices of #11 Grade-60 reinforcing bars embedded in concrete. The study focused on the influence of pre-existing laminar cracks on the strength of lap splices for #11 bars. The planned variables for the study were the length of the splice and the loading program. Twelve girders with lap splices were tested in two series, A and B, of six. Series A had 120-in long splices and series B had 79-in. splices. Concrete strength was not a planned variable. Concrete mixes were selected to produce a concrete strength at 28 days not exceeding 6000 psi. Measured concrete strength at time of test varied from approximately 4500 to 6000 psi. Yield stress of the reinforcing bars was 66 ksi.

In each series, two girders were loaded monotonically to failure. The two series A girders (A-2 and A-3) reached their yield capacities and then failed in flexure to resist a maximum moment of 487 k-ft. The two series B girders also reached their yield capacities and had splice failure at maximum moments of 425 k-ft (Girder B1) and 427 k-ft (Girder B4).

In series A, the remaining four girders were loaded to a deflection beyond yield, unloaded, and then loaded, with pre-existing laminar cracks, to failure. Maximum moments resisted were 481 k-ft (Girder A1), 479 k-ft (Girder A4), 480 k-ft (Girder A5), and 466 k-ft (Girder A6).

In series B, the four were loaded to yield, unloaded, and then loaded, with pre-existing laminar cracks, to failure. Maximum moments resisted were 418 k-ft (Girder B2), 426 k-ft (Girder B3), 435 k-ft (Girder B5), and 435 k-ft (Girder B6).

Load-deflection relationships recorded for the 12 girders are presented in Fig. 13 through 24. Reinforcement stresses developed at splice ends are listed in Table 3. For girders with 120-in splices maximum reinforcement stress attained at ends of splice ranged from 77 to 80 ksi. For girders with 79-in. splices, the range was 69 to 72 ksi.

Differences between the load-deflection responses of initially uncracked and pre-cracked girders were found to be negligible.

Strain measurements and observed distribution of bursting (laminar) cracks confirmed that most, if not all, of the force transfer from one bar to another occurred in the end of the splice over a length of approximately 20 in. (<15 bar diameters). In this region of high bond-stress demand, cracks paralleling the spliced bars opened at as low as one fourth of the maximum load in all girders tested. In the four specimens that were unloaded and reloaded, the measured maximum residual widths of these cracks at zero applied load were 0.08 in for series A and 0.015 for series B.

All load-deflection curves measured had two common characteristics: (1) Yield moment of the section was developed after appearance of laminar bursting cracks at low loads and at zero load in the case of the reloaded girders, and (2) all girders tested demonstrated a definite capability to maintain strength

with increase in deflection beyond yield. The latter characteristic satisfies the traditional demand of professional consensus documents for cases where the loads may be dynamic and/or not known closely.

1. Introductory Remarks

Since the publication of Abrams's monumental study of bond between concrete and steel¹ the engineering profession has been aware of the fact that, in transferring stress to concrete, deformed bars tend to cause bursting stresses in the concrete. The cracks caused by bursting stresses reach the surface of the concrete in which a deformed bar is embedded in a random pattern and tend to parallel the bar causing the stress. Their appearance on the surface of the concrete is a cause for concern.

What if such cracks develop without the influence of bursting stresses related to bond? How much bond stress can a reinforcing bar develop in cracked concrete with the cracks approximating the trajectory of the bar? The experimental investigation described in this report was undertaken to answer this question within a limited domain of variables: "If lap splices of #11 Grade 60 bars with three-in. cover happen to be in concrete having laminar cracks along the plane of the splices, what is the limit to the tensile force that can be transferred from one bar to the other?"

The investigation was carried out at Bowen Laboratory for Large-Scale Civil Engineering Research, West Lafayette, IN. to address this question.

2. Object and Scope

The object of the investigation reported was to study the effect of cracks on the strength of lapped splices of #11 Grade-60 reinforcing bars embedded in concrete. The cracks in question are laminar cracks, or cracks that lie in a plane that coincides with or is parallel and close to the axis of the spliced bars. The fundamental question for the investigation was to determine what level of tensile stress spliced #11 bars could develop if the surrounding concrete already has such cracks.

The test specimens were of a type used usually for testing splices (Fig. 1). They were large-scale girders with rectangular sections. They were simply supported at two points equidistant to the center of the specimen and loaded at two points, outside the reactions, also equidistant to the center of the specimen. A total of 12 specimens were tested under static loading, test durations ranging from three to six hours. Six of these (Series A) had 120-in splices (nominally 85 bar diameters) and the remaining six (Series B) had 79-in splices (nominally 56 bar diameters)..

In each of series A and B, loading was applied continually to failure in two test girders. In the remaining four, loading was first carried to or beyond yielding. Then the load was reduced to zero to be increased again until failure occurred.

¹ Abrams, Duff A., "Tests of Bond between Concrete and Steel," Bulletin #71, Engineering Experiment Station, University of Illinois, Urbana, 1913, 245 pp.

Concrete strength was not a planned variable in the program. For the test girders with the 120-in splices concrete strength, determined using standard 6x12-in. cylinders, varied from approximately 5000 to 6000 psi. For those with 79-in. splices, it varied from approximately 4500 to 5500 psi (Table 1).

Appendix 1 includes details about the tests of concrete samples.

Yield stress and strength of the #11 bars were determined to be 66 ksi and 103 ksi, respectively. Limiting strain, measured over a gage length including the part of the bar that fractured, ranged from 14 to 19 % (Table 2).

In addition to load and deflection measurements, crack patterns and widths as well as longitudinal and transverse deformations of the test girders were recorded. Failure characteristics of the test girders were captured by a high-speed camera operating at 5,000 frames per second.

Following sections contain brief descriptions of the materials, construction and instrumentation of the test girders. Detailed information on those topics is provided in the appendices of this report. The observed behavior of the test girders is described in terms of measured load-deflection relationships, recorded crack-width developments, and calculated reinforcement stresses.

2.1 Experimental Outline

As mentioned in the preceding section, two series of six tests were conducted, one with 120-in. splices and the other with 79-in. splices. Specimens A were cast in groups of three on 17 April 2012 and on 24 April 2012. Specimens B were also cast in groups of three, the first cast being on 10 April 2012 and the second on 30 April.

Because of the concern resulting from early cylinder tests that the concrete strength might surpass 6,000 psi at the intended time of test, specimens of Series B were tested first, during the period 10 through 25 May 2012. Specimens of Series A were tested afterwards during the period 30 May through 8 June 2012. Test dates are listed in Table 1.

The planned variables in the tests were the length of the splice (79 or 120 in.) and the loading program. Two specimens in each series were subjected to increasing applied loads at each loading stage of 6, 12, 18, 24, 30, and 36 kips. Above 36 kips, load increments were determined by measured displacement. Four of the specimens in series A were subjected to loading in increments of 6 kips to yield and then to a mid-span deflection of 0.9 in, unloading, and reloading to failure. In series B, the four specimens were loaded to 36 kip in 6-kip increments, unloaded, and then loaded to failure.

Load and deflection measurements were obtained continuously in each test. Deflections were also measured by dial gages whenever loading was stopped. An Optotrak tracking system was used to measure deformations of the girder after each load increment until there was a threat of failure. Crack patterns and widths were recorded up to a loading stage which was considered to be safe for those making the measurements. This limit, stated in terms of applied load, varied from 30 to 41 kip. Still photographs of the test specimen were taken at all loading stages.

Profile dimensions of the specimen in Series A and B are shown in Fig. 2 and 3

Properties of the girder cross section were based on four considerations.

The first was to have more than one lap splice to simulate the interaction of adjacent lap splices. Two splices were used.

The second was to have a minimum cover of 3 in. that translated to a clear distance of 6 in. between the two splices and led to a cross-sectional width of $(4 \times 3 + 4 \times 1.41)$ in. The width of the girder section was made $17 \frac{5}{8}$ in.

The third was to produce a bursting crack in the horizontal plane that would intersect both splices. To increase the probability of a bursting crack in the horizontal plane and given that cracking tends to occur in the direction in which cover is smaller, the desired minimum side cover of 3 in. was used on the outside bars of the splices and a cover of 5 in. was used on top.

The fourth condition was to make sure that with four #11 bars the section would have a moderate reinforcement ratio not exceeding 1.5 %. An overall depth of 30 in. satisfied that requirement.

The resulting cross-section is shown in Fig.4. Girders of Series A and B had the same-cross sectional dimensions and the same reinforcement. Each girder in series A had a total length of 39 ft .The lap splice length was 120 in. as indicated in Fig. 2. Ends of the splice were each at three ft from the closer support. The cantilevered portions of the girder measured 11 ft 6 in. in length. Loads were applied on each cantilever segment at 10 ft from the support.

Each girder in series B had a total length of 34 ft 4 in. Length of the lap splice was 79 in. and was located as shown in Fig. 3. The ends of the splice were each at three ft from the closer support. The cantilevered segments of the girder were 10 ft $10 \frac{1}{2}$ in. long. Loads were applied on each cantilever segment at 9 ft $8 \frac{1}{2}$ in. from the supports.

To make certain that shear or bond problems did not occur in the cantilevered segments of the girder, they were equipped with post-tensioned external stirrups comprising pairs of 3-in. channels at each end and two $\frac{5}{8}$ in-diameter rods. Figure 4 shows the external stirrups. There were 12 of them on each cantilevered segment placed at equal spacing. Post-tensioning forces in the external stirrups were not measured.

Measured dimensions of test specimens and test setup, obtained before testing, are listed in Appendix 2.

Load was applied through the use of two 60-kip hydraulic center-hole rams near each end of the girder. The rams were supported by a custom-built steel channel. One of the rams on each side was in series with a load cell. A 10x4-in. tube supported the two rams.

3. Materials

(a) Concrete

Concrete used in the specimens was mixed and delivered to the laboratory by Irving Materials Inc. of West Lafayette, IN. Each girder and related cylinders were cast using concrete from a single truck. The mix proportions by weight were

Component	Weight of Component / Weight of Cement
Cement	1
Fine Aggregate	2.4
Coarse Aggregate (max. size = 1¼ in.)	2.6
Water	0.55

Target air entrainment was 5%. As concrete was being placed, temperature, air content, and slump of the mix were measured. Air temperature was recorded. Target moist curing was seven days but the curing period was reduced for some specimens as a result of early cylinder tests that indicated high strength. Detailed information for each casting is included in Appendix 2. Information about curing is given in Appendix 3.

(b) Steel

All #11 reinforcing bars came from the same heat. Stress-strain properties of the bars are included in Appendix 4.

4. Observed Relationships between Applied Load and Deflection

Figures 13 through 24 contain the measured load-deflection relationships of the 12 test girders. The reported deflection is the relative movement (deflection up considered to be positive) of girder mid-span with respect to the supports. The reported load is the load applied near the end of the cantilever section.

It is important to note that a direct comparison of the measured load-deflection curves of girders in series A and B is not justified because of (1) the difference in middle spans (16 ft for girders A and 12 ft 7 in. for girders B), (2) the slight difference in the lever arms of the applied loads (10 ft for girders A and 9 ft 8 ½ in. for girders B) and (3) the difference in the initial selfweight moment (45.8 kip-ft for girders A and 41.7 kip-ft for girders B).

All load-deflection curves measured had two common characteristics: (1) Yield moment of the section was developed after appearance of laminar bursting cracks at low loads and at zero load in the case of the reloaded girders, and (2) all girders tested demonstrated a definite capability to maintain strength with increase in deflection beyond yield. The latter characteristic satisfies the traditional demand of professional consensus documents for cases where the loads may be dynamic and/or not known closely. Considering the Series A girders only, the similar behavior of A2 and A3 is not unexpected. These girders

had similar reinforcement, similar concrete strength (6030 and 5890 psi), similar spans and they were loaded to failure similarly. In both cases failure was initiated by failure of concrete in flexural compression after yielding of reinforcement at the supports. It is of interest to note that the overall behavior of test girders A1, A4, A5, and A6 that were loaded, unloaded, and reloaded to failure differed very little from those of A2 and A3 even though the failures of these four girders were initiated by bond. In fact one could not identify easily the ones that were reloaded by studying the shapes of the envelope curves. Girders in series A all had the same yield deflection (approx. ½ in.) and similar maximum mid-span deflections (ranging from 1.4 to 1.8 in.).

Inspection of Fig. 19 through 24 yields similar conclusions for the responses of girders of series B. For this series, the yield deflection was approximately 1/3 in. and maximum deflection ranged from a little below 0.5 in. (Girder B1) to above 0.6 in. (Girder B6). The range in concrete strength from 4460 to 5460 psi would not be expected to have a perceptible influence on the yield deflection. The three test girders with relatively low concrete strengths (Girders B1, B2, and B3) did have the lower maximum deflections but the maximum recorded value of ~0.47 in. for B1 with a concrete compressive strength of 4460 psi was not that much lower than that of B5 that had a concrete compressive strength of 5260 psi (0.55 in.)

Maximum applied loads for series A ranged from 42 to 44.1 kip. This range was from 39.7 to 40.6 for series B. In fact, on the basis of maximum applied load alone, it is hard to discriminate the results for series B vis-à-vis those of series A.

The narrow ranges of measured peak loads indicate consistency and that the sample size (6 repetitions) was proper.

5. Crack Development

Changes in crack patterns and widths were recorded in detail and are reported completely in Appendix 7. Observed development of flexural crack patterns and thicknesses was consistent with what is normally expected in reinforced concrete beams responding primarily to flexure. As seen in Fig. 6, flexural cracks occurred at a spacing of approximately twice the top cover or ~10 in. It is also seen that the cracks near mid-span did not reach as far towards the compressed edge of the girder as the ones near the support. This was an indication that the lap splice was effective, with most of the force transfer occurring near its ends as discussed later. All four bars were participating in load resistance. In the range of linear response to flexure, the neutral axis depth increases with increase in the reinforcement ratio. Even though the total tensile force in the reinforcement at mid-span was comparable to that at the support, the amount of reinforcement was twice as much. This was reflected in the relative lengths of the flexural cracks at mid-span and at the support.

Examples of crack patterns observed are shown in Fig.7 through 12 and Appendix 11.

Cracks of primary interest in this study are those caused by the bursting stresses related to high bond demand. Appendix 7 contains records of their development in detail for every one of the 12 girders tested.

Figure 6 that shows typical flexural cracks also shows the bursting cracks that traverse the beam surface horizontally at or near the level of the reinforcement. A descriptive metaphor for their formation is provided by visualizing the bars as thin walled pressurized tubes embedded in concrete as illustrated in Fig. 25. The internal pressure causes circumferential tensile stresses in the concrete around the tube that decrease with distance as shown ideally in the figure. The crack is initiated in the weakest plane which corresponds to the plane resulting in the minimum cover. The crack is initiated in the immediate surface of the tube and progresses out as the pressure in the tube increases. It is also relevant to note that a bursting crack can exist next to the reinforcement but not be visible on the surface of the girder.

The projection of this metaphor to the test girders suggests that the bursting crack would occur on a horizontal plane intersecting the reinforcement and that the surface width of the crack is likely to be smaller than its width next to the spliced bars. It also provides an introduction to develop an understanding of the bond phenomena observed in the test girders by combining three sets of measurements: (1) Longitudinal strain distribution at reinforcement level, (2) vertical deformation of the girder, and (3) distribution of widths of the bursting cracks.

The first two sets of data were obtained from movements of targets attached to the test girder and monitored using the Optotrak, an optical system for determining the coordinates of the targets in three dimensions. The locations of the targets in specimens of series A and B are shown in Fig. 26 and 27.

The distributions of measured strain along the splices are shown in Fig. 30 through 33. Figures 30 and 31 contain the data from the initial loadings. Figures 32 and 33 include the data from reloadings of four of the girders in each of series A and B.

Despite the inherent scatter, the longitudinal-strain data show that there was a dominant pattern in strain distribution along the splice. In the first loadings, rapid change in strain occurred primarily in the outer 20-in. segments of the splice as indicated by the slopes of the plotted curves in Fig. 30 and 31. Recognizing that the bars within the splice remain in the linear range of response, the slope of the strain distribution becomes a measure of the rate of stress change. Optotrak measurements identify that the critical segments of the splice where most of the force transfer from bar to bar took place were the outer 20-in. lengths.

Because four girders in each series were unloaded and reloaded, Fig. 32 and 33 contain four plots. These sets of data confirm that, in general, the middle 80 in. of the 120-in. splices and the middle ~40 in. of the 79-in. splices were essentially inert.

Measured vertical deformations of the test girders are shown in Fig. 34 and 35. The results included in these figures confirm that the regions of relatively large vertical deformation occurred in the outer 20 in. of the splices for both the 79 and 120-in. splices. An aspect of these vertical-deformation measurements is of special interest. Normalweight-aggregate concrete is expected to have a short-time tensile-strain

capacity not exceeding 0.0002. The vertical deformation measurements were made over a gage length of 26 in. Any reliable measurement of tensile extension exceeding 0.005 may be interpreted to indicate the presence of cracks. It is plausible to infer from Fig. 34 and 35 that bursting cracks did exist in the outer 20-in. segments of the splices. Most of the tensile force transfer between the spliced bars occurred in splice segments with bursting cracks.

In the following paragraphs, measured widths of bursting cracks are discussed with perspectives provided by the horizontal strain and vertical deformation measurements made.

Lacking a generally accepted index value such as the intensity scale used for earthquake damage to organize and define data susceptible to scatter, the main generalization that can be made about crack-width observations made in this study is that measurable (0.005 in. or more in thickness) bursting cracks of limited length (six to 12 in.) occurred at low loads on the order of one fourth of the maximum load resisted. Bursting cracks reached levels in excess of 0.1 in. at loads approaching the maximum load. At such levels of load, bursting cracks meandering along the level of the reinforcement covered virtually the entire test span. Representative bursting cracks are shown in Fig. 38 and 39.

To organize the observed bursting-crack widths for discussion, it was decided to divide the middle span into six regions A through F as shown in Fig. 28 and 29. The selection of the lengths of the regions was influenced by the arrangement of the Optotrak targets (Fig. 26 & 27). Selected lengths of regions A through F are shown in Fig. 28 for series A and in Fig. 29 for series B.

Maximum widths of the horizontal cracks in the selected regions at selected values of the applied load are shown in Fig. 40 through 51. The horizontal-axis legend shows the distance from mid-span to the center of the region in inches. The legend on the right-hand side of the plot indicates the applied load at which the readings were recorded. The numbers at the peaks of the "cones" indicate the maximum crack width in thousandths of an inch.

Given the randomness of the tensile strength of concrete and the tensile-stress demands set up by bond, one does not expect uniform results in the charts shown in Fig. 40 through 51. Nevertheless, certain trends may be inferred from the charts. Again, the bursting cracks were wider at the splice ends and at the supports. These trends are confirmed by the vertical deformations shown in Fig. 34 and 35. Comparisons of measured vertical deformations and measured cracks widths are shown in Fig. 52 and 53. At the maximum loads shown in Fig. 40 through 51, the maximum crack width reached 0.15 in. (Fig. 40).

Bringing together the observed data from measurements of longitudinal strain, vertical deformation, and crack-width distribution, it becomes clear that most if not all of the force transfer in the splice took place in regions with bursting cracks. With that knowledge, the mean unit bond strength evaluation on the basis of assuming the bond stress to be distributed uniformly along the splice would seem irrelevant. However, to place the results obtained in the realm of common practice, unit bond stresses were calculated. The mean unit bond strength obtained from the tests was $3.1\sqrt{f'_c}$ for the 120-in splices and $4.4\sqrt{f'_c}$ for the 79-in splices. The decrease in mean bond strength with increase in length of splice is

consistent with the observation that most of the stress transfer through bond occurred within approximately 15 bar diameters from each splice end. It is of interest to note that the ratio of the observed mean bond strengths, 0.70, is close to the ratio of the splice lengths, 0.66.

6. Maximum Reinforcement Stresses Attained

As documented in detail in Appendices 5 and 6 maximum tensile stresses achieved at the ends of the splice were computed based on the moment at the end of the splice and cross-sectional properties of the test girder. Fig. 54 shows the distribution of bending moments. The calculated stresses are shown in Table 3.

The minimum tensile stress attained in the reinforcement at the end of the splice was 69 ksi (Test Girder B2) and the maximum was 80 ksi (Test Girders A2 and A3)

7. Conclusions

Two girders in each of Series A and B were loaded monotonically to failure.

Four girders of series A were loaded to a deflection of 0.9 in. (approximately twice the yield deflection) and the unloaded to be reloaded to failure. Four girders of series B were loaded to yield, unloaded and reloaded to failure.

At the start of reloading, lengths of approximately 15 bar diameters at each end of each splice were populated with bursting cracks along the splices. Most of the force transfer between spliced bars occurred within these lengths.

The two series of tests conducted were designed to address the question: what is the limit to the tensile force that can be resisted by lap splices of #11 Grade 60 bars with three-in. cover and in concrete having laminar cracks near the plane of the splices? In both series, laminar bursting cracks formed at a fraction of the yield load in all test girders. The difference between the strength and behavior of the girders loaded directly to failure and those unloaded after reaching or exceeding yield and reloaded was negligible. The existence of laminar cracks at the beginning of loading did not change the strength of the splices. The ratio of the limiting deflection to the yield deflection was approximately three in Series A with 120-in. splices and two in Series B with 79-in. splices.

As listed below and illustrated in Fig. 55, maximum reinforcement stresses in the test girders loaded to failure after having been loaded to develop bursting (laminar) cracks and reloaded differed negligibly from those in girders loaded monotonically to failure.

Test Girder	Type of Loading	Maximum Reinforcement Stress at Splice End
A2	Monotonic	79 ksi
A3	Monotonic	80 ksi
B1	Monotonic	71 ksi
B4	Monotonic	70 ksi
A1	Reloaded after Laminar Cracking	79 ksi
A4	Reloaded after Laminar Cracking	79 ksi
A5	Reloaded after Laminar Cracking	79 ksi
A6	Reloaded after Laminar Cracking	77 ksi
B2	Reloaded after Laminar Cracking	69 ksi
B3	Reloaded after Laminar Cracking	70 ksi
B5	Reloaded after Laminar Cracking	72 ksi
B6	Reloaded after Laminar Cracking	72 ksi

TABLES

Table 1 Concrete

Test Girder Designation	Cast	Tested	Concrete Compressive Strength	Concrete Splitting Cylinder Strength	Lap Length
			psi	psi	in.
A1	17 April 2012	4 June 2012	5270	480	120
A2	17 April 2012	1 June 2012	6030	500	120
A3	17 April 2012	30 May 2012	5890	480	120
A4	24 April 2012	8 June 2012	5110	440	120
A5	24 April 2012	7 June 2012	5240	440	120
A6	24 April 2012	5 June 2012	5490	450	120
B1	10 April 2012	10 May 21012	4460	450	79
B2	10 April 2012	23 May 2012	4800	480	79
B3	10 April 2012	21 May 2012	4780	420	79
B4	30 April 2012	14 May 2012	5460	490	79
B5	30 April 2012	17 May 2012	5260	480	79
B6	30 April 2012	25 May 2012	5230	450	79

Table 2 Reinforcement

Bar Designation	#11
Nominal Diameter, in.	1.41
Nominal Area, in ²	1.56
Nominal Perimeter, in.	4.43
Unit Weight, lbf/ft	5.31
Yield Stress*, ksi	66
Strength*, ksi	103
Limiting Strain in 8 in., %	14,18,19

*Note: means from tests of three coupons

Table 3 Summary of Results

Test Girder Designation	Concrete Splitting Strength (Tensile)	Concrete Compressive Strength	Lap Length	Maximum Applied Load	Maximum Moment at Support	Maximum Moment at Splice End	Calc. Reinf. Stress at Support	Calc. Reinf. Stress at Splice End
	psi	psi	in.	kip	kip*ft	kip*ft	ksi	ksi
A1	480	5270	120	43.5	481	470	81	79
A2	500	6030	120	44.1	487	476	82	80
A3	480	5890	120	44.1	487	476	82	80
A4	440	5110	120	43.3	479	468	81	79
A5	440	5240	120	43.4	480	469	81	79
A6	450	5490	120	42.0	466	455	78	77
B1	450	4460	79	39.5	425	417	72	71
B2	480	4800	79	38.9	419	419	71	69
B3	420	4780	79	39.7	427	419	72	70
B4	490	5460	79	39.7	427	419	71	70
B5	480	5260	79	40.6	436	428	73	72
B6	450	5230	79	40.6	436	428	73	72


FIGURES

Figure 1 Overall Properties of The Test Girders




Figure 2 Test Girder, Series A




Figure 3 Test Girder Series B




Figure 4 Cross-Sectional Dimensions of Series A and B Girders



Figure 5 Photograph of One of The Cantilevered Segments of A Test Girder



Figure 6 Flexural Cracks and Bursting Cracks




Figure 7 West Elevation of Test Girder A4. Initial Loading. Applied Load = 36 kip



Figure 8 East Elevation of Test Girder A4. Initial Loading. Applied Load = 36 kip



Figure 9 West Elevation of Test Girder A4 Reloaded to 36 kip



Figure 10 East Elevation of Test Girder A4 Reloaded to 36 kip




Figure 11 West Elevation of Test Girder A4 Reloaded to 42 kip



Figure 12 East Elevation of Test Girder A4 Reloaded to 42 kip




Figure 13 Load-Deflection Plot for Test Girder A1




Figure 14 Load-Deflection Plot for Test Girder A2




Figure 15 Load-Deflection Plot for Test Girder A3




Figure 16 Load-Deflection Plot for Test Girder A4




Figure 17 Load-Deflection Plot for Test Girder A5




Figure 18 Load-Deflection Plot for Test Girder A6




Figure 19 Load-Deflection Plot for Test Girder B1




Figure 20 Load-Deflection Plot for test Girder B2




Figure 21 Load-Deflection Plot for Test Girder B3




Figure 22 Load-Deflection Plot for Test Girder B4




Figure 23 Load-Deflection Plot for Test Girder B5




Figure 24 Load-Deflection Plot for Test Girder B6




Figure 25 Qualitative Illustration of Internal Stresses Leading to Bursting Cracks




Figure 26 Optotrak Targets on Series A Girders




Figure 27 Optotrak Targets on Series B Girders




Figure 28 Selected Regions for Maximum Bursting Crack Widths in Series A Girders




Figure 29 Selected Regions for Maximum Bursting Crack Widths in Series B Girders




Figure 30 Longitudinal Strains at Level of Reinforcement, First Loading of Series A Girders




Figure 31 Longitudinal Strains at Level of Reinforcement, First Loading of Series B Girders




Figure 32 Longitudinal Strains at Level of Reinforcement, Reloading of Series A Girders




Figure 33 Longitudinal Strains at Level of Reinforcement, Reloading of Series B Girders




Figure 34 Transverse Deformations, First Loading of Series A Girders




Figure 35 Transverse Deformations, First Loading of Series B Girders




Figure 36 Transverse Deformations, Reloading of Series A Girders






Figure 37 Transverse Deformations, Reloading of Series B Girders




Girder A-1, Load = 36 kip (reload).




Girder A-2, Load = 36 kip.



Girder A-3, Load = 36 kip.



Girder A-4, Load = 40 kip (reload).



Girder A-5, Load = 40 kip.



Girder A-6, Load = 46 kip (reload)


Figure 38 Representative Cracks, Test Series A.




Girder B-1, Load = 36 kip.



Girder B-2, Load = 36 kip (reload).




Girder B-3, Load = 36 kip (reload).




Girder B-6, Load = 36 kip (reload).

Figure 39 Representative Cracks, Test Series B




Horizontal axis of chart indicates distances of strip centers from mid-span
 Maximum crack widths measured in each strip at selected applied loads (legend on right) are listed in the chart.
 "0 k - Reload" refers to unloaded state of the girder before reloading.
 Strip widths are 50, 20, and 26 in. on each side of mid-span.
 Value 1 indicates existence of a crack not exceeding 0.004 in. in thickness.

Figure 40 Recorded Maximum Surface Widths (in thousands of an inch) (in thousands of an inch) of Bursting Cracks at Reinforcement Level, Test Girder A-1.




Horizontal axis of chart indicates distances of strip centers from mid-span
 Maximum crack widths measured in each strip at selected applied loads (legend on right) are listed in the chart.
 "0 k - Reload" refers to unloaded state of the girder before reloading.
 Strip widths are 50, 20, and 26 in. on each side of mid-span.
 Value 1 indicates existence of a crack not exceeding 0.004 in. in thickness.

Figure 41 Recorded Maximum Surface Widths (in thousands of an inch) of Bursting Cracks at Reinforcement Level, Test Girder A-2.




Horizontal axis of chart indicates distances of strip centers from mid-span
 Maximum crack widths measured in each strip at selected applied loads (legend on right) are listed in the chart.
 "0 k - Reload" refers to unloaded state of the girder before reloading.
 Strip widths are 50, 20, and 26 in. on each side of mid-span.
 Value 1 indicates existence of a crack not exceeding 0.004 in. in thickness.

Figure 42 Recorded Maximum Surface Widths (in thousands of an inch) of Bursting Cracks at Reinforcement Level, Test Girder A-3.




Horizontal axis of chart indicates distances of strip centers from mid-span
 Maximum crack widths measured in each strip at selected applied loads (legend on right) are listed in the chart.
 "0 k - Reload" refers to unloaded state of the girder before reloading.
 Strip widths are 50, 20, and 26 in. on each side of mid-span.
 Value 1 indicates existence of a crack not exceeding 0.004 in. in thickness.

Figure 43 Recorded Maximum Surface Widths (in thousands of an inch) of Bursting Cracks at Reinforcement Level, Test Girder A-4




Horizontal axis of chart indicates distances of strip centers from mid-span
 Maximum crack widths measured in each strip at selected applied loads (legend on right) are listed in the chart.
 "0 k - Reload" refers to unloaded state of the girder before reloading.
 Strip widths are 50, 20, and 26 in. on each side of mid-span.
 Value 1 indicates existence of a crack not exceeding 0.004 in. in thickness.

Figure 44 Recorded Maximum Surface Widths (in thousands of an inch) of Bursting Cracks at Reinforcement Level, Test Girder A-5.




Horizontal axis of chart indicates distances of strip centers from mid-span
 Maximum crack widths measured in each strip at selected applied loads (legend on right) are listed in the chart.
 "0 k - Reload" refers to unloaded state of the girder before reloading.
 Strip widths are 50, 20, and 26 in. on each side of mid-span.
 Value 1 indicates existence of a crack not exceeding 0.004 in. in thickness.

Figure 45 Recorded Maximum Surface Widths (in thousands of an inch) of Bursting Cracks at Reinforcement Level, Test Girder A-6.




Horizontal axis of chart indicates distances of strip centers from mid-span
 Maximum crack widths measured in each strip at selected applied loads (legend on right) are listed in the chart.
 "0 k - Reload" refers to unloaded state of the girder before reloading.
 Strip widths are 30, 19, and 26.5 in. on each side of mid-span.
 Value 1 indicates existence of a crack not exceeding 0.004 in. in thickness.

Figure 46 Recorded Maximum Surface Widths (in thousands of an inch) of Bursting Cracks at Reinforcement Level, Test Girder B-1.




Horizontal axis of chart indicates distances of strip centers from mid-span
 Maximum crack widths measured in each strip at selected applied loads (legend on right) are listed in the chart.
 "0 k - Reload" refers to unloaded state of the girder before reloading.
 Strip widths are 30, 19, and 26.5 in. on each side of mid-span.
 Value 1 indicates existence of a crack not exceeding 0.004 in. in thickness.

Figure 47 Recorded Maximum Surface Widths (in thousands of an inch) of Bursting Cracks at Reinforcement Level, Test Girder B-2.




Horizontal axis of chart indicates distances of strip centers from mid-span
 Maximum crack widths measured in each strip at selected applied loads (legend on right) are listed in the chart.
 "0 k - Reload" refers to unloaded state of the girder before reloading.
 Strip widths are 30, 19, and 26.5 in. on each side of mid-span.
 Value 1 indicates existence of a crack not exceeding 0.004 in. in thickness.

Figure 48 Recorded Maximum Surface Widths (in thousands of an inch) of Bursting Cracks at Reinforcement Level, Test Girder B-3.




Horizontal axis of chart indicates distances of strip centers from mid-span
 Maximum crack widths measured in each strip at selected applied loads (legend on right) are listed in the chart.
 "0 k - Reload" refers to unloaded state of the girder before reloading.
 Strip widths are 30, 19, and 26.5 in. on each side of mid-span.
 Value 1 indicates existence of a crack not exceeding 0.004 in. in thickness.

Figure 49 Recorded Maximum Surface Widths (in thousands of an inch) of Bursting Cracks at Reinforcement Level, Test Girder B-4.



Horizontal axis of chart indicates distances of strip centers from mid-span
 Maximum crack widths measured in each strip at selected applied loads (legend on right) are listed in the chart.
 "0 k - Reload" refers to unloaded state of the girder before reloading.
 Strip widths are 30, 19, and 26.5 in. on each side of mid-span.
 Value 1 indicates existence of a crack not exceeding 0.004 in. in thickness.

Figure 50 Recorded Maximum Surface Widths (in thousands of an inch) of Bursting Cracks at Reinforcement Level, Test Girder B-5.



Horizontal axis of chart indicates distances of strip centers from mid-span
 Maximum crack widths measured in each strip at selected applied loads (legend on right) are listed in the chart.
 "0 k - Reload" refers to unloaded state of the girder before reloading.
 Strip widths are 30, 19, and 26.5 in. on each side of mid-span.
 Value 1 indicates existence of a crack not exceeding 0.004 in. in thickness.

Figure 51 Recorded Maximum Surface Widths (in thousands of an inch) of Bursting Cracks at Reinforcement Level, Test Girder B-6.




Figure 52 Comparison of crack-width measurements and measured vertical deformations, test series A.




Figure 53 Comparison of crack-width measurements and measured vertical deformations, test series B.




Figure 54 Moment and Shear Diagrams




Figure 55 Maximum Unit Stress Reached by Spliced Reinforcement

TEST GIRDER A1

Cast 17 April 2012
Tested 4 June 2012

A1 := $\left[\begin{array}{l} 5020 \\ 5500 \\ 5190 \\ 5460 \\ 5220 \\ 5210 \end{array} \right]$ psi

$$\text{mean}(A1) = 5.27 \cdot \text{ksi}$$

$$\text{stdev}(A1) = 0.17 \cdot \text{ksi}$$

$$\text{COV1} := \frac{\text{stdev}(A1)}{\text{mean}(A1)} \quad \text{COV1} = 3.1 \cdot \%$$

$$\text{max}(A1) = 5.50 \times 10^3 \cdot \text{psi}$$

$$\text{min}(A1) = 5.02 \times 10^3 \cdot \text{psi}$$

TEST GIRDER A2

Cast 17 April 2012
Tested 4 June 2012

A2 := $\left[\begin{array}{l} 5810 \\ 5620 \\ 5860 \\ 6460 \\ 6330 \\ 6120 \end{array} \right]$ psi

$$\text{mean}(A2) = 6.03 \cdot \text{ksi}$$

$$\text{stdev}(A2) = 0.3 \cdot \text{ksi}$$

$$\text{COV2} := \frac{\text{stdev}(A2)}{\text{mean}(A2)} \quad \text{COV2} = 4.9 \cdot \%$$

$$\text{max}(A2) = 6.46 \times 10^3 \cdot \text{psi}$$

$$\text{min}(A2) = 5.62 \times 10^3 \cdot \text{psi}$$

TEST GIRDER A3**Cast****Tested 30 May 2012**

$$A3 := \begin{array}{l} (\\ 6000 \\ 6010 \\ 5820 \\ 5840 \\ 5830 \\ 5850 \\) \end{array} \text{ psi}$$

$$\text{mean}(A3) = 5.89 \cdot \text{ksi}$$

$$\text{stdev}(A3) = 0.08 \cdot \text{ksi}$$

$$\text{COV3} := \frac{\text{stdev}(A3)}{\text{mean}(A3)} \quad \text{COV3} = 1.4 \cdot \%$$

$$\text{max}(A3) = 6.01 \times 10^3 \cdot \text{psi}$$

$$\text{min}(A3) = 5.82 \times 10^3 \cdot \text{psi}$$

TEST GIRDER A4**Cast 30 April 2012****Tested 22 May 2012**

$$A4 := \begin{array}{l} (\\ 5120 \\ 5240 \\ 5270 \\ 4950 \\ 4870 \\ 5240 \\) \end{array} \text{ psi}$$

$$\text{mean}(A4) = 5.11 \cdot \text{ksi}$$

$$\text{stdev}(A4) = 0.15 \cdot \text{ksi}$$

$$\text{COV4} := \frac{\text{stdev}(A4)}{\text{mean}(A4)} \quad \text{COV4} = 3 \cdot \%$$

$$\text{max}(A4) = 5.27 \times 10^3 \cdot \text{psi}$$

$$\text{min}(A4) = 4.87 \times 10^3 \cdot \text{psi}$$

TEST GIRDER A5

Cast 30 April 2012
Tested 17 May 2012

A5 := $\left[\begin{array}{l} 5320 \\ 5430 \\ 5110 \\ 5360 \\ 4750 \\ 5470 \end{array} \right]$ psi

$$\text{mean}(A5) = 5.24 \cdot \text{ksi}$$

$$\text{stdev}(A5) = 0.25 \cdot \text{ksi}$$

$$\text{COV5} := \frac{\text{stdev}(A5)}{\text{mean}(A5)} \quad \text{COV5} = 4.7 \cdot \%$$

$$\text{max}(A5) = 5.47 \times 10^3 \cdot \text{psi}$$

$$\text{min}(A5) = 4.75 \times 10^3 \cdot \text{psi}$$

TEST GIRDER A6

Cast 24 April 2012
Tested 25 May 2012

A6 := $\left[\begin{array}{l} 5170 \\ 5640 \\ 5370 \\ 5690 \\ 5530 \\ 5570 \end{array} \right]$ psi

$$\text{mean}(A6) = 5.49 \cdot \text{ksi}$$

$$\text{stdev}(A6) = 0.18 \cdot \text{ksi}$$


$$\text{COV6} := \frac{\text{stdev}(A6)}{\text{mean}(A6)} \quad \text{COV6} = 3.2 \cdot \%$$

$$\text{max}(A6) = 5.69 \times 10^3 \cdot \text{psi}$$

$$\text{min}(A6) = 5.17 \times 10^3 \cdot \text{psi}$$

CONCRETE COMPRESSIVE STRENGTH SUMMARY

$$f'_c := \begin{bmatrix} \text{mean}(A1) \\ \text{mean}(A2) \\ \text{mean}(A3) \\ \text{mean}(A4) \\ \text{mean}(A5) \\ \text{mean}(A6) \end{bmatrix} \quad x := \begin{bmatrix} 1 \\ 2 \\ 3 \\ 4 \\ 5 \\ 6 \end{bmatrix} \quad f'_c = \begin{bmatrix} 5267 \\ 6033 \\ 5892 \\ 5115 \\ 5240 \\ 5495 \end{bmatrix} \cdot \text{psi}$$



FENOC PROJECT 2012

SUMMARY
CONCRETE STRENGTH

25 May 2012

TEST GIRDER B1

Cast 10 April 2012

Tested 10 May 2012

$$B1 := \begin{pmatrix} 4250 \\ 4520 \\ 4720 \\ 4400 \\ 4300 \\ 4600 \end{pmatrix} \cdot \text{psi}$$

$$\text{mean}(B1) = 4.46 \cdot \text{ksi}$$

$$\text{stdev}(B1) = 0.17 \cdot \text{ksi}$$

$$\text{COV1} := \frac{\text{stdev}(B1)}{\text{mean}(B1)} \quad \text{COV1} = 0.04$$

$$\text{max}(B1) = 4.72 \times 10^3 \text{ psi}$$

$$\text{min}(B1) = 4.25 \times 10^3 \text{ psi}$$

TEST GIRDER B2

Cast 10 April 2012

Tested 23 May 2012

$$B2 := \begin{pmatrix} 5080 \\ 4730 \\ 4970 \\ 4660 \\ 4710 \\ 4680 \end{pmatrix} \cdot \text{psi}$$

$$\text{mean}(B2) = 4.80 \cdot \text{ksi}$$

$$\text{stdev}(B2) = 0.16 \cdot \text{ksi}$$

$$\text{COV2} := \frac{\text{stdev}(B2)}{\text{mean}(B2)} \quad \text{COV2} = 0.03$$

$$\text{max}(B2) = 5.08 \times 10^3 \text{ psi}$$

$$\text{min}(B2) = 4.66 \times 10^3 \text{ psi}$$

Sheet 1 of 4

FENOC PROJECT 2012

SUMMARY
CONCRETE STRENGTH

25 May 2012

TEST GIRDER B3

Cast 10 April 2012
Tested 21 May 2012

$$B3 := \begin{pmatrix} 4540 \\ 4910 \\ 4760 \\ 4960 \\ 4860 \\ 4670 \end{pmatrix} \cdot \text{psi}$$

$$\text{mean}(B3) = 4.78 \cdot \text{ksi}$$

$$\text{stdev}(B3) = 0.14 \cdot \text{ksi}$$

$$\text{COV3} := \frac{\text{stdev}(B3)}{\text{mean}(B3)} \quad \text{COV3} = 0.03$$

$$\text{max}(B3) = 4.96 \times 10^3 \text{ psi}$$

$$\text{min}(B3) = 4.54 \times 10^3 \text{ psi}$$

TEST GIRDER B5

Cast 30 April 2012
Tested 14 May 2012

$$B4 := \begin{pmatrix} 5470 \\ 5160 \\ 5710 \\ 5540 \\ 5230 \\ 5650 \end{pmatrix} \cdot \text{psi}$$

$$\text{mean}(B4) = 5.46 \cdot \text{ksi}$$

$$\text{stdev}(B4) = 0.20 \cdot \text{ksi}$$

$$\text{COV4} := \frac{\text{stdev}(B4)}{\text{mean}(B4)} \quad \text{COV4} = 0.04$$

$$\text{max}(B4) = 5.71 \times 10^3 \text{ psi}$$

$$\text{min}(B4) = 5.16 \times 10^3 \text{ psi}$$

Sheet 2 of 4

FENOC PROJECT 2012

SUMMARY
CONCRETE STRENGTH

25 May 2012

TEST GIRDER B5

Cast 30 April 2012

Tested 17 May 2012

$$B5 := \begin{pmatrix} 5120 \\ 5340 \\ 5350 \\ 5160 \\ 5370 \\ 5230 \end{pmatrix} \cdot \text{psi}$$

$$\text{mean}(B5) = 5.26 \cdot \text{ksi}$$

$$\text{stdev}(B5) = 0.10 \cdot \text{ksi}$$

$$\text{COV5} := \frac{\text{stdev}(B5)}{\text{mean}(B5)} \quad \text{COV5} = 0.02$$

$$\text{max}(B5) = 5.37 \times 10^3 \text{ psi}$$

$$\text{min}(B5) = 5.12 \times 10^3 \text{ psi}$$

TEST GIRDER B6

Cast 30 April 2012

Tested 25 May 2012

$$B6 := \begin{pmatrix} 5130 \\ 5460 \\ 5130 \\ 5220 \\ 5320 \\ 5120 \end{pmatrix} \cdot \text{psi}$$

$$\text{mean}(B6) = 5.23 \cdot \text{ksi}$$

$$\text{stdev}(B6) = 0.12 \cdot \text{ksi}$$

$$\text{COV6} := \frac{\text{stdev}(B6)}{\text{mean}(B6)} \quad \text{COV6} = 0.02$$

$$\text{max}(B6) = 5.46 \times 10^3 \text{ psi}$$

$$\text{min}(B6) = 5.12 \times 10^3 \text{ psi}$$


FENOC PROJECT 2012

SUMMARY
CONCRETE STRENGTH

25 May 2012

CONCRETE COMPRESSIVE STRENGTH SUMMARY

$$f'_c := \begin{pmatrix} \text{mean}(B1) \\ \text{mean}(B2) \\ \text{mean}(B3) \\ \text{mean}(B4) \\ \text{mean}(B5) \\ \text{mean}(B6) \end{pmatrix} \quad x := \begin{pmatrix} 1 \\ 2 \\ 3 \\ 4 \\ 5 \\ 6 \end{pmatrix} \quad f'_c = \begin{pmatrix} 4.46 \times 10^3 \\ 4.80 \times 10^3 \\ 4.78 \times 10^3 \\ 5.46 \times 10^3 \\ 5.26 \times 10^3 \\ 5.23 \times 10^3 \end{pmatrix} \text{ psi}$$



FENOC PROJECT		CONCRETE TENSILE STRENGTH								30-May-12	Mean	
GIRDER B1	ylind	Date	Diam 1 in.	Diam 2	Diam 3 in.	Mean D in.	Length 1 in.	Length 2 in.	Mean L in.	Measured Max. Force lbf	Tensile Strength psi	Tensile Strength psi
	1	10-May-12	6.03		6.03	6.03	12.10	12.00	12.05	44,320	388	
	2	10-May-12	6.05		6.04	6.05	12.00	12.00	12.00	61,910	543	
	3	10-May-12	6.04		6.04	6.04	12.00	12.00	12.00	45,350	398	
	4	10-May-12	6.05		6.05	6.05	12.00	12.10	12.05	50,500	441	
	5	10-May-12	6.04		6.03	6.04	12.00	12.10	12.05	58,460	512	
	6	10-May-12	6.01		6.01	6.01	12.00	12.10	12.05	44,720	393	
												446
GIRDER B2	1	23-May-12	5.95	5.99	6.04	5.99	12.00	12.00	12.00	49,810	441	
	2	23-May-12	5.97	6.01	6.05	6.01	12.00	11.90	11.95	48,200	427	
	3	23-May-12	5.95	5.98	6.04	5.99	12.00	12.00	12.00	52,890	468	
	4	23-May-12	5.95	5.99	6.05	6.00	12.10	12.10	12.10	60,360	530	
	5	23-May-12	5.96	6.00	6.03	6.00	11.90	12.00	11.95	62,970	559	
	6	23-May-12	5.96	6.00	6.05	6.00	12.00	12.00	12.00	49,490	437	
												477
GIRDER B3	1	21-May-12	6.05	6.00	5.96	6.00	12.00	12.10	12.05	48,840	430	
	2	21-May-12	6.04	6.04	5.96	6.01	12.00	12.00	12.00	42,010	371	
	3	21-May-12	6.05	6.05	5.97	6.02	12.00	12.00	12.00	44,800	395	
	4	21-May-12	6.03	6.03	5.94	6.00	12.00	12.00	12.00	48,410	428	
	5	21-May-12	6.04	6.04	5.96	6.01	12.00	12.00	12.00	49,470	436	
	6	21-May-12	6.05	6.05	5.95	6.02	12.00	12.00	12.00	53,510	472	
												422
GIRDER B4	1	14-May-12	5.93	-	6.04	5.99	12.00	12.00	12.00	52,080	462	
	2	14-May-12	5.94		6.04	5.99	12.00	12.00	12.00	55,050	488	
	3	14-May-12	5.94		6.06	6.00	12.00	12.00	12.00	56,490	499	
	4	14-May-12	5.94		6.06	6.00	12.00	12.00	12.00	52,570	465	
	5	14-May-12	5.94		6.05	6.00	12.00	12.00	12.00	53,690	475	
	6	14-May-12	5.93		6.07	6.00	12.00	12.00	12.00	59,530	526	
												486
GIRDER B5	1	17-May-12	5.96	5.99	6.06	6.00	12.05	12.05	12.05	57,310	504	
	2	17-May-12	5.95	6.00	6.05	6.00	12.05	12.05	12.05	52,820	465	
	3	17-May-12	5.95	5.99	6.06	6.00	12.00	12.00	12.00	51,370	454	
	4	17-May-12	5.96	5.99	6.05	6.00	12.05	12.00	12.03	53,620	473	
	5	17-May-12	5.96	6.00	6.05	6.00	12.00	12.00	12.00	52,730	466	
	6	17-May-12	5.95	6.00	6.06	6.00	12.00	12.05	12.03	54,540	481	
												474
GIRDER B6	1	25-May-12	5.95	5.98	6.04	5.99	12.00	12.00	12.00	49,690	440	
	2	25-May-12	5.96	6.00	6.05	6.00	12.00	11.90	11.95	53,150	472	
	3	25-May-12	5.96	6.01	6.03	6.00	12.00	12.00	12.00	49,780	440	
	4	25-May-12	5.94	5.99	6.04	5.99	12.10	12.00	12.05	45,810	404	
	5	25-May-12	5.95	5.99	6.04	5.99	12.10	12.10	12.10	46,720	410	
	6	25-May-12	5.97	6.00	6.02	6.00	12.00	12.10	12.05	65,270	575	
												457

FENOC PROJECT		CONCRETE TENSILE TEST			30-May-12		
Specimen ID	Cylinder	Date	Diameter, D in	Length, L in	Measured Max Force lbf	Tensile Strength psi	Mean Tensile Strength psi
A-1	1	14-Jun-12	6.00	12	46820	414	480
	2	14-Jun-12	6.00	12	55610	492	
	3	14-Jun-12	6.00	12	65200	576	
	4	14-Jun-12	6.00	12	53470	473	
	5	14-Jun-12	6.00	12	48730	431	
	6	14-Jun-12	6.00	12	57470	508	
A-2	1	1-Jun-12	6.00	12	52370	463	500
	2	1-Jun-12	6.00	12	55870	494	
	3	1-Jun-12	6.00	12	49890	441	
	4	1-Jun-12	6.00	12	51740	457	
	5	1-Jun-12	6.00	12	63970	566	
	6	1-Jun-12	6.00	12	63780	564	
A-3	1	30-May-12	6.00	12	48060	425	480
	2	30-May-12	6.00	12	58190	515	
	3	30-May-12	6.00	12	59030	522	
	4	30-May-12	6.00	12	50900	450	
	5	30-May-12	6.00	12	55200	488	
	6	30-May-12	6.00	12	55630	492	
A-4	1	8-Jun-12	6.00	12	53900	477	440
	2	8-Jun-12	6.00	12	54040	478	
	3	8-Jun-12	6.00	12	47900	424	
	4	8-Jun-12	6.00	12	46800	414	
	5	8-Jun-12	6.00	12	49890	441	
	6	8-Jun-12	6.00	12	48090	425	
A-5	1	7-Jun-12	6.00	12	63340	560	440
	2	7-Jun-12	6.00	12	51980	460	
	3	7-Jun-12	6.00	12	44490	393	
	4	7-Jun-12	6.00	12	41500	367	
	5	7-Jun-12	6.00	12	54360	481	
	6	7-Jun-12	6.00	12	45220	400	
A-6	1	5-Jun-12	6.00	12	57870	512	450
	2	5-Jun-12	6.00	12	50780	449	
	3	5-Jun-12	6.00	12	45610	403	
	4	5-Jun-12	6.00	12	56820	502	
	5	5-Jun-12	6.00	12	45570	403	
	6	5-Jun-12	6.00	12	46860	414	
B-1	1	10-May-12	6.00	12	44320	392	450
	2	10-May-12	6.00	12	61910	547	
	3	10-May-12	6.00	12	45350	401	
	4	10-May-12	6.00	12	50500	447	
	5	10-May-12	6.00	12	58460	517	
	6	10-May-12	6.00	12	44720	395	
B-2	1	23-May-12	6.00	12	49810	440	480
	2	23-May-12	6.00	12	48200	426	
	3	23-May-12	6.00	12	52890	468	
	4	23-May-12	6.00	12	60360	534	
	5	23-May-12	6.00	12	62970	557	
	6	23-May-12	6.00	12	49490	438	
B-3	1	21-May-12	6.00	12	48840	432	420
	2	21-May-12	6.00	12	42010	371	
	3	21-May-12	6.00	12	44800	396	
	4	21-May-12	6.00	12	48410	428	
	5	21-May-12	6.00	12	49470	437	
	6	21-May-12	6.00	12	53510	473	
B-4	1	14-May-12	6.00	12	52080	460	490
	2	14-May-12	6.00	12	55050	487	
	3	14-May-12	6.00	12	56490	499	
	4	14-May-12	6.00	12	52570	465	
	5	14-May-12	6.00	12	53690	475	
	6	14-May-12	6.00	12	59530	526	
B-5	1	17-May-12	6.00	12	57310	507	480
	2	17-May-12	6.00	12	52820	467	
	3	17-May-12	6.00	12	51370	454	
	4	17-May-12	6.00	12	53620	474	
	5	17-May-12	6.00	12	52730	466	
	6	17-May-12	6.00	12	54540	482	
B-6	1	25-May-12	6.00	12	46960	415	450
	2	25-May-12	6.00	12	53150	470	
	3	25-May-12	6.00	12	49780	440	
	4	25-May-12	6.00	12	45810	405	
	5	25-May-12	6.00	12	46720	413	
	6	25-May-12	6.00	12	65270	577	

Project: Tests to Determine the
Behavior of Spliced #11 BarsCasting Documentation v.1
(Rev. 03/30/2012)Specimen: A-1

Sheet 1 of 1

General Information					
Date	Disp Ticket Num	Truck No.	Time on Ticket	Time of Arrival	Temp. in Lab
4/17	1858981	1669	12:29PM	12:45PM	60°F
Measurements made upon arrival of concrete					
Slump (ASTM C143 - 10a)		Air Content (ASTM C231 - 10)			
Time ₁	Result ₁	Time ₁	Result ₁	S/N of Air Meter	
12:51	7 ³ / ₄ "	1:04	5.5%	4130786891	
Time ₂	Result ₂	Time ₂	Result ₂	S/N of Scale	
1:15	7 ³ / ₄	1:20	5.7%	06746056HM	
Unit Weight (ASTM C138 - 10b)					
Time ₁	Wt. of Cont. ₁	Total Wt. ₁	Wt. of Conc. ₁	Result ₁ = Wt. of Conc./Vol. of Cont.	
1:00	8.5#	44.8#	36.3#	145.2 #/cft.	
Time ₂	Wt. of Cont. ₂	Total Wt. ₂	Wt. of Conc. ₂	Result ₂ = Wt. of Conc./Vol. of Cont.	
1:20	8.5#	44.30	35.8#	143.2 #/cft.	
Times of actions during and after casting					
Layer 1 placed	Layer 1 vibration complete	Layer 2 placed	Layer 2 vibration complete	Top surface struck off	Truck Departing Lab
12:50-1PM	✓	1PM-1:10	✓	1:08	1:08PM
Lifting Inserts Placed	Covered with plastic	Plastic removed	Covered with burlap	Burlap doused with water	Covered with plastic
1:45PM	1:50PM	10:30PM	10:35PM	10:40PM	10:45PM
Recorded by	Signature		Date	Time	
S.P.	<i>A. Dujal</i>		4/17/12		
Checked by	Signature		Date	Time	
BPR	<i>Mark</i>		4/17/12	2:00PM	
Checked by	Signature		Date	Time	
<i>SAworth</i>	<i>SAworth</i>		4/17/12	1:11PM	
Comments: Concrete Temp: @ 12:56 PM - 68°F by both digital & analog thermometers Ambient Temp: 60°F					
*The following ASTM standards and specifications will be followed during casting: C172-10, C192-07, C470-09					

Truck 1669	Driver 2140	User user	Disp Ticket Num 1858981	Ticket ID 0	Time Date 12:29 4/17/12
Load Size 6.50	Mix Code CYDS 1008	Returned	Qty	Mix Age	Seq D
					Load ID 1105

Material	Design Qty	Required	Batched	% Var	% Moisture	Actual	Wat
STONE-8	940 lb	6159 lb	6100 lb	-0.96%	0.80%M		6 gl
STONE-4	620 lb	4050 lb	4000 lb	-0.74%			
SAND-Z3	1435 lb	9962 lb	9920 lb	-0.42%	5.80%M		76 gl
CEMENT	588 lb	3822 lb	3815 lb	-0.18%			
WATER	323.2 lb	1417.7 lb	1402.0 lb	-1.10%			168.0 gl
AIR	.80 /C	30.68 oz	30.50 oz	-0.25%			

Actual		Num Batches:	1								
Load	25239 lb	Design W/C:	0.550	Water/Cement:	0.551 T	Design	251.7 gl	Actual	249.5 gl	To Add:	2.3 gl
Slump:	6.00 in	#	Water in Truck:	0.0 lb	Adjust Water:	0.0 lb / Load	Trim Water:	0.0 lb /	CYC		

1

Concrete Delivery Ticket



Plant #	Ticket Number	Truck	Load Size	Mix	Slump	Use	Date	Customer
---------	---------------	-------	-----------	-----	-------	-----	------	----------

18 050001 1669 6.50cy 1000 0.00 EXTERIOR 04/17/12 16091

Sold To	Tax Code	Driver	Project No.	Order No.
---------	----------	--------	-------------	-----------

CHARGE CHSD - BOWEN LAB 3H TREVOR WINDSLEY 2140 5 1811

Delivery Address	P.O. Number
------------------	-------------

BOWEN CIVIL ENGINEERING LAB SCN 2523

Job No. 012525

TRUCK RELEASE BRIAN 012 344 0114

Time Printed 12:22

Load Quantity	Total	Ordered Quantity	Product Code	Product Description	Unit Price	Amount
---------------	-------	------------------	--------------	---------------------	------------	--------

6.50 6.50cy 19.50cy 1000 PURDUE EXPERIMENTAL 89.00 578.50



Environmental Fee

13.00

Water Added At Customer's Request	Total No. Gallons	Slump Meter Reading	Subtotal
-----------------------------------	-------------------	---------------------	----------

0 890

591.50

On Job Time	Finish Pour Time	Auth. #:	Grand Total:	Tax	Total
-------------	------------------	----------	--------------	-----	-------


591.50 591.50

PROPERTY DAMAGE RELEASE / WARNING - Irritating To The Skin and Eyes

Dear Customer - The Seller is not responsible for slumps, strength or quality of concrete to which water or any other material has been added by the purchaser or at his request. The undersigned hereby authorizes Irving Materials, Inc. to use private property for making the delivery shown here on and assumes full responsibility for any damage or injury due to the premises. The undersigned agrees to reimburse said Company for loss of time and equipment by reason of such delivery and also to identify and save harmless said Company from any and all claims, demands and suits for or on account of or in any manner caused by or arising from private property delivery. The undersigned assumes responsibility for a suitable roadway from public highway to point of delivery and is responsible for any needed wrecker service charges as a result. SAFETY WARNING: Keep away from children. Contains Portland Cement. Irritating to the skin and eyes. Wear rubber boots, gloves and eye protection. Prolonged contact may cause burns. In case of contact with skin or eyes, flush thoroughly with water. If irritation persists, get medical attention. For additional information regarding the HAZARDS OF READY MIX CONCRETE, consult the Material Data Safety Sheet (MSDS) available upon request. PRODUCT NOTICE: Seller will not be held responsible for the final appearance of exposed aggregate, integral coloring, stamped and decorative surfacing, and all other forms of architectural and design concrete. DELIVERY NOTICE: Seller assumes no responsibility for deliveries beyond the public right of way. Buyer assumes responsibility for damages including but not limited to curb, sidewalk, driveway, or any property of the contractor or property owner or agents. NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE SAFETY AND HEALTH WARNING NOTICE AND ACCEPTANCE OF THE LOAD.

Release, Load and Terms Accepted By:

X *[Signature]*




Project: Tests to Determine the
Behavior of Spliced #11 Bars

Setup and As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: A-1

Sheet 1 of 2

Section	Concrete As-built Dimensions							
	1	2	3	4	5	6	7	8
Plan	38'-11 ⁷ / ₈ "	38'-11 ⁷ / ₈ "	38'-11 ⁷ / ₈ "	38'-11 ³ / ₄ "				
B-B	17- ³ / ₈ "	30- ¹ / ₄ "	17- ¹¹ / ₁₆ "	30- ³ / ₈ "				
C-C	17- ⁵ / ₈ "	30- ¹ / ₈ "	17- ³ / ₄ "	30- ³ / ₁₆ "				
D-D	17- ⁵ / ₁₆ "	30- ¹ / ₄ "	17- ³ / ₄ "	30- ¹ / ₈ "				
E-E	17- ³ / ₄ "	30- ³ / ₁₆ "	17- ¹¹ / ₁₆ "	30- ¹ / ₁₆ "				
F-F	17- ³ / ₄ "	30- ³ / ₈ "	17- ³ / ₄ "	30- ¹ / ₁₆ "				
Recorded by:			Signature				Date	Time
KAM			MLL				6-2-12	1:00pm
Checked by:			Signature				Date	Time
BPR							6/2/12	1:00PM
Checked by:			Signature				Date	Time
Comments:								
*See concrete as-built drawings for dimension locations								


Project: Tests to Determine the
Behavior of Spliced #11 Bars

Setup and As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: A-1

Sheet 2 of 2

Section	Concrete As-built Dimensions Key - Series A							
	1	2	3	4	5	6	7	8
Plan	39'-0"	39'-0"	39'-0"	39'-0"	N/A	N/A	N/A	N/A
B-B	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
C-C	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
D-D	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
E-E	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
F-F	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
Section	Concrete As-built Dimensions Key - Series B							
	1	2	3	4	5	6	7	8
Plan	34'-4"	34'-4"	34'-4"	34'-4"	N/A	N/A	N/A	N/A
B-B	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
C-C	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
D-D	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
E-E	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
F-F	17-5/8"	30"	17-5/8"	30" ₂₋₅	N/A	N/A	N/A	N/A



Specimen A-1

Behavior of Lap Splices of No. 11 Reinforcing Bars

Sheet:

1

of

4

Drawn by:


KAM

Checked by:

BPR

Date:


6-2-12




*For section B-B through F-F see Sheet 3 of 3



Drawing:	Series A Concrete As-builts	Sheet:	2	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		




Top Plan



Profile


*For section B-B through F-F see Sheet 3 of 3



Bottom Plan



Drawing:	Series B Concrete As-builts	Sheet:	3	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		



Section B-B, C-C, D-D, E-E & F-F
*Facing North





Drawing:	Concrete As-built Sections	Sheet:	4	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

Project: Tests to Determine the Behavior of Spliced #11 Bars

As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: A-1

Sheet 1 of 2

Section	Formwork As-built Dimensions							
	1	2	3	4	5	6	7	8
A-A	173- ³ / ₈	120-0	174-0	174-0	120- ¹ / ₁₆	173- ⁷ / ₈		
B-B	3- ¹ / ₈	8- ³ / ₄	2- ¹⁵ / ₁₆	23- ⁵ / ₈	23- ⁹ / ₁₆	30- ¹ / ₈	30- ¹ / ₈	17- ¹ / ₂
C-C	3- ¹ / ₈	5- ¹³ / ₁₆	3- ¹ / ₁₆	23- ⁵ / ₈	23- ¹¹ / ₁₆	30-0	30- ¹ / ₁₆	17- ¹ / ₂
D-D	3- ¹ / ₈	2- ¹⁵ / ₁₆	5- ⁷ / ₈	23- ³ / ₄	23- ¹³ / ₁₆	30- ¹ / ₈	30- ¹ / ₁₆	17- ⁷ / ₁₆
E-E	3- ¹ / ₈	6- ¹ / ₈	2- ⁷ / ₈	23- ¹¹ / ₁₆	23- ³ / ₄	30-0	30- ¹ / ₁₆	17- ³ / ₈ ⁷ / ₁₆
F-F	4- ¹ / ₂	4- ³ / ₁₆ ↔	6- ³ / ₁₆	23- ⁹ / ₁₆	23- ⁵ / ₈	30- ¹ / ₈	30- ¹ / ₈	17- ⁷ / ₁₆ ¹ / ₂
Recorded by:			Signature			Date	Time	
BPR						4/15	4:40PM	
Checked by:			Signature			Date	Time	
TD						4/15	4:40PM	
Checked by:			Signature			Date	Time	

Comments:
* Section ~~A-A~~ B-B & F-F dimensions 1, 2, & 3 are opposite the key



Project: Tests to Determine the
Behavior of Spliced #11 Bars

As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: A-1

Sheet 2 of 2

Section	Formwork As-built Dimensions Key - Series A							
	1	2	3	4	5	6	7	8
A-A	14'-6"	10'-0"	14'-6"	14'-6"	10'-0"	14'-6"	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
D-D	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
E-E	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
F-F	3"	8-3/4"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
Section	Formwork As-built Dimensions Key - Series B							
	1	2	3	4	5	6	7	8
A-A	13'-10.5"	6'-7"	13'-10.5"	13'-10.5"	6'-7"	13'-10.5"	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
D-D	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
E-E	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
F-F	3"	8-3/4"	3"	23-5/8" ₂₋₁₁	23-5/8"	30"	30"	17-5/8"




*For section B-B through F-F see Sheet 3 of 3


Series A



Drawing:	Series A Formwork As-builts	Sheet:	1	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		



Section A-A




*For section B-B through F-F see Sheet 3 of 3

Series B




Drawing:	Series B Formwork As-builts	Sheet:	2	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		



Section C-C, D-D, & E-E
*Facing North




Section B-B & F-F
*Facing North



Drawing:	Formwork As-built Sections	Sheet:	3	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

Project: Tests to Determine the
Behavior of Spliced #11 BarsCasting Documentation v.1
(Rev. 03/30/2012)Specimen: A-2

Sheet 1 of 1

General Information					
Date	Disp Ticket Num	Truck No.	Time on Ticket	Time of Arrival	Temp. in Lab
4/17/12	1858982	1982	3:25	3:42	62°F
Measurements made upon arrival of concrete					
Slump (ASTM C143 - 10a)		Air Content (ASTM C231 - 10)			
Time ₁	Result ₁	Time ₁	Result ₁	S/N of Air Meter	
3:45	7"	3:52	5.2%	4130786891	
Time ₂	Result ₂	Time ₂	Result ₂	S/N of Scale	
4:10	6½"	4:17	5.0%	06746056HM	
Unit Weight (ASTM C138 - 10b)					
Time ₁	Wt. of Cont. ₁	Total Wt. ₁	Wt. of Conc. ₁	Result ₁ = Wt. of Conc./Vol. of Cont.	
3:50	8.5#	44.8#	36.3#	145.2 #/cft.	
Time ₂	Wt. of Cont. ₂	Total Wt. ₂	Wt. of Conc. ₂	Result ₂ = Wt. of Conc./Vol. of Cont.	
4:15	8.5#	45.0#	36.5#	146.0 #/cft.	
Times of actions during and after casting					
Layer 1 placed	Layer 1 vibration complete	Layer 2 placed	Layer 2 vibration complete	Top surface struck off	Truck Departing Lab
3:45-3:55	✓	3:55-	4:10	4:15	4:18
Lifting Inserts Placed	Covered with plastic	Plastic removed	Covered with burlap	Burlap doused with water	Covered with plastic
✓	5:20PM	10:50PM	10:55PM	11:00PM	11:05PM
Recorded by	Signature		Date	Time	
BPR			4/17/12	5:20PM	
Checked by	Signature		Date	Time	
KAM			4-17-12	5:30PM	
Checked by	Signature		Date	Time	
Shwartz			4/17/12		
Comments: Concrete Temp: 69°					
*The following ASTM standards and specifications will be followed during casting: C172-10, C192-07, C470-09					

Truck 1982 Driver 1076 User user Disp Ticket Num 1858982 Ticket ID 0 Time Date 15:25 4/17/12
 Load Size 6.50 Mix Code CYDS 1008 Returned Qty Mix Age Seq D Load ID 1106

Material	Design Qty	Required	Batched	% Var	% Moisture	Actual	Wet
STONE-8	940 lb	6159 lb	6100 lb	-0.96%	0.80% M		6 gl
STONE-4	620 lb	4030 lb	4000 lb	-0.74%			
SAND-23	1435 lb	9962 lb	9920 lb	-0.42%	6.80% M		76 gl
CEMENT	588 lb	3822 lb	3815 lb	-0.18%			
WATER	323.2 lb	1417.7 lb	1406.0 lb	-0.82%			168.5 gl
AIR	.80 /C	30.58 oz	30.50 oz	-0.25%			

Actual Load 25243 lb Slump: 6.00 in # 5
 Num Batches: 1
 Design W/C: 0.550 Water/Cement: 0.551 T Adjust Water: 0.0 lb / Load
 Design 251.7 gi Actual 250.0 gi To Add: 1.8 gi
 Trial Water: 0.0 lb / CYC Note: Manual feed occurred

2

Concrete Delivery Ticket



Plant #	Ticket Number	Truck	Load Size	Mix	Slump	Use	Date	Customer
1050002	1002	5.3000	1008	5.0M	EXTERIOR		04/17/12	10091
Sold To					Tax Code	Driver	Project No.	Order No.
CHARGE CARD - POWER LAB					TT	DOUG PHENIX	187E	181
Delivery Address							P.O. Number	
SOMER CIVIL ENGINEERING LAB							SON 2525	
TRUCK RELEASE BRIAN 818 344 0114							Job No: CH2523	

Time Printed 15:24

Load Quantity	Total	Ordered Quantity	Product Code	Product Description	Unit Price	Amount
6.50	13.00cy	19.50cy	1008	PURDUE EXPERIMENTAL	89.00	578.50




Water Added At Customer's Request		Total No. Gallons	Slump Meter Reading					Subtotal	591.50
On Job Time	Finish Pour Time	AUTH.#:	Grand Totals:	1,183.00	Tax		Total	591.50	

PROPERTY DAMAGE RELEASE / WARNING - Irritating To The Skin and Eyes

Dear Customer - The Seller is not responsible for slumps, strength or quality of concrete to which water or any other material has been added by the purchaser or at his request. The undersigned hereby authorizes Irving Materials, Inc. to use private property for making the delivery shown here on and assumes full responsibility for any damage or injury due to the premises. The undersigned agrees to reimburse said Company for loss of time and equipment by reason of such delivery and also to identify and save harmless said Company from any and all claims, demands and suits for or on account of or in any manner caused by or arising from private property delivery. The undersigned assumes responsibility for a suitable roadway from public highway to point of delivery and is responsible for any needed wrecker service charges as a result. SAFETY WARNING: Keep away from children. Contains Portland Cement. Irritating to the skin and eyes. Wear rubber boots, gloves and eye protection. Prolonged contact may cause burns. In case of contact with skin or eyes, flush thoroughly with water. If irritation persists, get medical attention. For additional information regarding the HAZARDS OF READY MIX CONCRETE, consult the Material Data Safety Sheet (MSDS) available upon request. PRODUCT NOTICE: Seller will not be held responsible for the final appearance of exposed aggregate, integral coloring, stamped and decorative surfacing, and all other forms of architectural and design concrete. DELIVERY NOTICE: Seller assumes no responsibility for deliveries beyond the public right of way. Buyer assumes responsibility for damages including but not limited to curb, sidewalk, driveway, or any property of the contractor or property owner or agents. NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE SAFETY AND HEALTH WARNING NOTICE AND ACCEPTANCE OF THE LOAD.

Release, Load and Terms Accepted By:

X





Project: Tests to Determine the Behavior of Spliced #11 Bars

Setup and As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: A-2

Sheet 1 of 2

Section	BPR 5/31 Concrete As-built Dimensions								
	1	2	3	4	5	6	7	8	
Plan	38'-11 ⁷ / ₈ "	38'-11 ⁷ / ₈ "	38'-11 ³ / ₄ "	38'-11 ⁷ / ₈ "					
B-B	17-9/16"	30-1/8"	17-11/16"	30-1/8"					
C-C	17-5/8"	30-1/8"	17-11/16"	30-3/16"					
D-D	17-9/16"	30-1/16"	17-3/4"	30-1/16"					
E-E	17-5/8"	30-1/4"	17-5/8"	30-1/8"					
F-F	17-9/16"	30-3/16"	17-5/8"	30-3/16"					
Recorded by:			Signature			Date		Time	
J.N.H.						5.31.12		2:00	
Checked by:			Signature			Date		Time	
BPR						5/31/12		3:45PM	
Checked by:			Signature			Date		Time	

Comments:

*See concrete as-built drawings for dimension locations


Project: Tests to Determine the
Behavior of Spliced #11 Bars

Setup and As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: A-2

Sheet 2 of 2

Section	Concrete As-built Dimensions Key - Series A							
	1	2	3	4	5	6	7	8
Plan	39'-0"	39'-0"	39'-0"	39'-0"	N/A	N/A	N/A	N/A
B-B	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
C-C	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
D-D	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
E-E	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
F-F	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
Section	Concrete As-built Dimensions Key - Series B							
	1	2	3	4	5	6	7	8
Plan	34'-4"	34'-4"	34'-4"	34'-4"	N/A	N/A	N/A	N/A
B-B	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
C-C	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
D-D	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
E-E	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
F-F	17-5/8"	30"	17-5/8"	30" ₂ - 19	N/A	N/A	N/A	N/A




Specimen A-2

Behavior of Lap Splices of No. 11 Reinforcing Bars


Sheet: 1 of 4

Drawn by: KAM Checked by: BPR


Date: 5-31-12



Drawing:	Series A Concrete As-builts	Sheet:	2	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		




Top Plan



Profile


*For section B-B through F-F see Sheet 3 of 3



Bottom Plan



Drawing:	Series B Concrete As-builts	Sheet:	3	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		



Section B-B, C-C, D-D, E-E & F-F
*Facing North





Drawing:	Concrete As-built Sections	Sheet:	4	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

Project: Tests to Determine the
Behavior of Spliced #11 Bars

As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: A-2

Sheet 1 of 2

Section	Formwork As-built Dimensions							
	1	2	3	4	5	6	7	8
A-A	174- $\frac{1}{8}$	120- $\frac{1}{16}$	173- $\frac{15}{16}$	174-0	120-0	174-0		
B-B	2- $\frac{15}{16}$	8- $\frac{7}{8}$	3- $\frac{1}{16}$	23- $\frac{9}{16}$	23- $\frac{9}{16}$	30- $\frac{1}{8}$	30- $\frac{1}{16}$	17- $\frac{1}{2}$
C-C	2- $\frac{15}{16}$	6- $\frac{1}{8}$	3- $\frac{1}{8}$	23- $\frac{11}{16}$	23- $\frac{5}{8}$	30-0	30- $\frac{1}{16}$	17- $\frac{1}{2}$
D-D	2- $\frac{7}{8}$	6- $\frac{1}{8}$	3-0	23- $\frac{7}{8}$	23- $\frac{7}{8}$	30-0	30-0	17- $\frac{7}{16}$ $\frac{1}{2}$
E-E	2- $\frac{15}{16}$	6- $\frac{13}{16}$	3- $\frac{1}{16}$	23- $\frac{5}{8}$	23- $\frac{11}{16}$	30-0	30- $\frac{1}{16}$	17- $\frac{7}{16}$
F-F	4- $\frac{5}{16}$	6- $\frac{1}{8}$	4- $\frac{5}{16}$	23- $\frac{5}{8}$	23- $\frac{5}{8}$	30- $\frac{1}{8}$	30- $\frac{1}{8}$	17 $\frac{1}{2}$
Recorded by:			Signature				Date	Time
BPR							4/15	5:30PM
Checked by:			Signature				Date	Time
TD							4/15	5:30PM
Checked by:			Signature				Date	Time

Comments:

* Section B-B & F-F dimensions 1, 2, & 3 are opposite the key



Project: Tests to Determine the
Behavior of Spliced #11 Bars

As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: A-2

Sheet 2 of 2

Section	Formwork As-built Dimensions Key - Series A							
	1	2	3	4	5	6	7	8
A-A	14'-6"	10'-0"	14'-6"	14'-6"	10'-0"	14'-6"	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
D-D	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
E-E	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
F-F	3"	8-3/4"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
Section	Formwork As-built Dimensions Key - Series B							
	1	2	3	4	5	6	7	8
A-A	13'-10.5"	6'-7"	13'-10.5"	13'-10.5"	6'-7"	13'-10.5"	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
D-D	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
E-E	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
F-F	3"	8-3/4"	3"	23-5/8" 2-25	23-5/8"	30"	30"	17-5/8"




*For section B-B through F-F see Sheet 3 of 3


Series A



Drawing:	Series A Formwork As-builts	Sheet:	1	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		




Section A-A




*For section B-B through F-F see Sheet 3 of 3


Series B




Drawing:	Series B Formwork As-builts	Sheet:	2	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		



Section C-C, D-D, & E-E
*Facing North



Section B-B & F-F
*Facing North



Drawing:	Formwork As-built Sections	Sheet:	3	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

Project: Tests to Determine the
Behavior of Spliced #11 BarsCasting Documentation v.1
(Rev. 03/30/2012)Specimen: A-3

Sheet 1 of 1

General Information					
Date	Disp Ticket Num	Truck No.	Time on Ticket	Time of Arrival	Temp. in Lab
4/17/12	1858983	1839	15:57	4:15PM	62°F
Measurements made upon arrival of concrete					
Slump (ASTM C143 - 10a)		Air Content (ASTM C231 - 10)			
Time ₁	Result ₁	Time ₁	Result ₁	S/N of Air Meter	
4:23	5½"	4:35	4.9%	4130786891	
Time ₂	Result ₂	Time ₂	Result ₂	S/N of Scale	
4:48	6"	4:55	5.1%	06746056HM	
Unit Weight (ASTM C138 - 10b)					
Time ₁	Wt. of Cont. ₁	Total Wt. ₁	Wt. of Conc. ₁	Result ₁ = Wt. of Conc./Vol. of Cont.	
4:32	8.5	45.4	36.9#	147.6#/cft.	
Time ₂	Wt. of Cont. ₂	Total Wt. ₂	Wt. of Conc. ₂	Result ₂ = Wt. of Conc./Vol. of Cont.	
4:52	8.5	44.8	36.3#	145.2#/cft.	
Times of actions during and after casting					
Layer 1 placed	Layer 1 vibration complete	Layer 2 placed	Layer 2 vibration complete	Top surface struck off	Truck Departing Lab
4:25	4:30	✓	✓	✓	✓
Lifting Inserts Placed	Covered with plastic	Plastic removed	Covered with burlap	Burlap doused with water	Covered with plastic
4:30	5:20PM	11:10PM	11:15PM	11:20PM	11:25PM
Recorded by	Signature		Date	Time	
BPR	<i>[Signature]</i>		4/17	4:57PM	
Checked by	Signature		Date	Time	
RAM	<i>[Signature]</i>		4-17-12	5:20PM	
Checked by	Signature		Date	Time	
<i>[Signature]</i>	SA WORTHY		4/17/12		
Comments:					
Concrete Temp 60.2°					
*The following ASTM standards and specifications will be followed during casting: C172-10, C192-07, C470-09					

Truck	Driver	User	Disp Ticket Num	Ticket ID	Time	Date
1839	2463	user	1858983	0	15:57	4/17/12
Load Size	Mix Code	Returned	Qty	Mix Age	Seq	Load ID
6.50 CYDS	1008				D	1107

Material	Design Qty	Required	Batched	% Var	% Moisture	Actual	Wat
STONE-8	940 lb	6159 lb	6100 lb	-0.96%	0.80% M		8 gl
STONE-4	620 lb	4030 lb	4000 lb	-0.74%			
SAND-23	1435 lb	9962 lb	9920 lb	-0.42%	6.80% M		76 gl
CEMENT	588 lb	3822 lb	3875 lb	1.39%			
WATER	323.2 lb	1417.7 lb	1402.0 lb	-1.10%			168.0 gl
AIR	.80 /C	30.58 oz	31.00 oz	1.39%			

Actual	Num Batches: 1								
Load	25299 lb	Design W/C: 0.550	Water/Cement: 0.542 T	Design	251.7 gl	Actual	249.5 gl	To Add:	2.3 gl
Slump:	6.00 In	# Water In Truck:	0.0 lb	Adjust Water:	0.0 lb / Load	Trim Water:	0.0 lb /	CYC	

3

Concrete Delivery Ticket



Plant #	Ticket Number	Truck	Load Size	Mix	Slump	Use	Date	Customer
---------	---------------	-------	-----------	-----	-------	-----	------	----------

250393 - 1839 6.50c - 1000 5.70 EXTERIOR 04/17/18 16891

Sold To	Tax Code	Driver	Project No.	Order No.
---------	----------	--------	-------------	-----------

CHARGE CARD - BOWEN CIV2 011 DANNY SMITH 2482 5 1811

Delivery Address	P.O. Number
------------------	-------------

BOWEN CIVL ENGINEERING LAB SON 8923

TRUCK RELEASE BRIAN 812 344 0114 Job No: 022525

Time Printed 15:55

Load Quantity	Total	Ordered Quantity	Product Code	Product Description	Unit Price	Amount
---------------	-------	------------------	--------------	---------------------	------------	--------

6.50 19.50cy 19.50cy 3008 PURDUE EXPERIMENTAL 89.00 578.50



Environmental Fee

13.00

3

Water Added At Customer's Request	Total No. Gallons	Slump Meter Reading	Subtotal
-----------------------------------	-------------------	---------------------	----------

On Job Time	Finish Pour Time	Grand Total:	Total
-------------	------------------	--------------	-------

PROPERTY DAMAGE RELEASE / WARNING - Irritating To The Skin and Eyes

Dear Customer - The Seller is not responsible for slumps, strength or quality of concrete to which water or any other material has been added by the purchaser or at his request. The undersigned hereby authorizes Irving Materials, Inc. to use private property for making the delivery shown here on and assumes full responsibility for any damage or injury due to the premises. The undersigned agrees to reimburse said Company for loss of time and equipment by reason of such delivery and also to identify and save harmless said Company from any and all claims, demands and suits for or on account of or in any manner caused by or arising from private property delivery. The undersigned assumes responsibility for a suitable roadway from public highway to point of delivery and is responsible for any needed wrecker service charges as a result.


SAFETY WARNING: Keep away from children. Contains Portland Cement. Irritating to the skin and eyes. Wear rubber boots, gloves and eye protection. Prolonged contact may cause burns. In case of contact with skin or eyes, flush thoroughly with water. If irritation persists, get medical attention. For additional information regarding the HAZARDS OF READY MIX CONCRETE, consult the Material Data Safety Sheet (MSDS) available upon request.

PRODUCT NOTICE: Seller will not be held responsible for the final appearance of exposed aggregate, integral coloring, stamped and decorative surfacing, and all other forms of architectural and design concrete.

DELIVERY NOTICE: Seller assumes no responsibility for deliveries beyond the public right of way. Buyer assumes responsibility for damages including but not limited to curb, sidewalk, driveway, or any property of the contractor or property owner or agents.

NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE SAFETY AND HEALTH WARNING NOTICE AND ACCEPTANCE OF THE LOAD.

Release, Load and Terms Accepted By:





Project: Tests to Determine the Behavior of Spliced #11 Bars

Setup and As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: A-3

Sheet 1 of 2

Section	Concrete As-built Dimensions								
	1	2	3	4	5	6	7	8	
Plan	38'-11 ⁷ / ₈ "	38'-11 ⁷ / ₈ "	39'-0"	39'-0"					
B-B	17'- ¹¹ / ₁₆ "	30'- ¹ / ₄ "	17'- ¹¹ / ₁₆ "	30'- ¹ / ₄ "					
C-C	17'- ³ / ₄ "	30'- ¹ / ₁₆ "	17'- ³ / ₄ "	30'- ³ / ₁₆ "					
D-D	17'- ⁵ / ₈ "	30'- ¹ / ₈ "	17'- ³ / ₄ "	30'- ³ / ₁₆ "					
E-E	17'- ³ / ₄ "	30'- ³ / ₁₆ "	17'- ³ / ₄ "	30'- ³ / ₁₆ "					
F-F	17'- ¹¹ / ₁₆ "	30'- ¹ / ₄ "	17'- ³ / ₄ "	30'- ¹ / ₄ "					
Recorded by:			Signature			Date		Time	
J.N.H.						5.29.12		6:40	
Checked by:			Signature			Date		Time	
BPR						5/29/12		7:00PM	
Checked by:			Signature			Date		Time	

Comments:


Project: Tests to Determine the
Behavior of Spliced #11 Bars

Setup and As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: A-3

Sheet 2 of 2

Section	Concrete As-built Dimensions Key - Series A							
	1	2	3	4	5	6	7	8
Plan	39'-0"	39'-0"	39'-0"	39'-0"	N/A	N/A	N/A	N/A
B-B	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
C-C	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
D-D	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
E-E	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
F-F	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
Section	Concrete As-built Dimensions Key - Series B							
	1	2	3	4	5	6	7	8
Plan	34'-4"	34'-4"	34'-4"	34'-4"	N/A	N/A	N/A	N/A
B-B	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
C-C	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
D-D	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
E-E	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
F-F	17-5/8"	30"	17-5/8"	30 $\frac{1}{2}$ - 33	N/A	N/A	N/A	N/A




Specimen A-3

Behavior of Lap Splices of No. 11
Reinforcing Bars

Sheet: 1 of 4


Drawn by: BPR Checked by: VAM

Date: 5/29/12




Top Plan

2 Spa. @




Profile


*For section B-B through F-F see Sheet 3 of 3





Bottom Plan



Drawing:	Series A Concrete As-builts	Sheet:	2	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		




Top Plan



Profile


*For section B-B through F-F see Sheet 3 of 3



Bottom Plan



Drawing:	Series B Concrete As-builts	Sheet:	3	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		



Section B-B, C-C, D-D, E-E & F-F
*Facing North



Drawing:	Concrete As-built Sections	Sheet:	4	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

Project: Tests to Determine the Behavior of Spliced #11 Bars

As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: A-3

Sheet 1 of 2

Section	Formwork As-built Dimensions								
	1	2	3	4	5	6	7	8	
A-A	174-1/8	119-15/16	174-0	174-13/16	119-15/16	173-13/16			
B-B	2-15/16	8-7/8	3-1/16	23-5/8	23-9/16	30-1/8	30-1/8	17-1/2	
C-C	3-0	6-13/16	3-1/16	23-1/16	23-11/16	30-0	30-1/16	17-1/2	
D-D	3-0	6-13/16	3-1/16	23-7/8	23-13/16	30-0	30-1/8	17-1/2	
E-E	2-15/16	6-13/16	3-1/16	23-5/8	23-11/16	30-1/16	30-1/8	17-1/2	
F-F	4-3/8	6-1/8	4-3/8	23-5/8	23-9/16	30-1/8	30-3/16	17-1/2	
Recorded by:			Signature			Date		Time	
BPR			<i>Non Hite</i>			4/15		5:50PM	
Checked by:			Signature			Date		Time	
TD			<i>John P...</i>			4/15		5:50PM	
Checked by:			Signature			Date		Time	

Comments:
 * Section B-B & F-F dimensions are opposite the key
 1, 2, & 3



Project: Tests to Determine the
Behavior of Spliced #11 Bars

As-built Dimensions v.1
(Rev. 04/04/2012)


Specimen: A-3

Sheet 2 of 2


Section	Formwork As-built Dimensions Key - Series A							
	1	2	3	4	5	6	7	8
A-A	14'-6"	10'-0"	14'-6"	14'-6"	10'-0"	14'-6"	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
D-D	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
E-E	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
F-F	3"	8-3/4"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
Section	Formwork As-built Dimensions Key - Series B							
	1	2	3	4	5	6	7	8
A-A	13'-10.5"	6'-7"	13'-10.5"	13'-10.5"	6'-7"	13'-10.5"	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
D-D	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
E-E	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
F-F	3"	8-3/4"	3"	23-5/8" ₂₋₃₉	23-5/8"	30"	30"	17-5/8"



Drawing:	Series A Formwork As-builts	Sheet:	1	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		



Section A-A




*For section B-B through F-F see Sheet 3 of 3


Series B




Drawing:	Series B Formwork As-builts	Sheet:	2	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		



Section C-C, D-D, & E-E
*Facing North



Section B-B & F-F
*Facing North



Drawing:	Formwork As-built Sections	Sheet:	3	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

Project: Tests to Determine the
Behavior of Spliced #11 BarsCasting Documentation v.1
(Rev. 03/30/2012)Specimen: A-4

Sheet 1 of 1

General Information					
Date	Disp Ticket Num	Truck No.	Time on Ticket	Time of Arrival	Temp. in Lab
4/24	1859188	1635	12:26	12:40PM	62°F
Measurements made upon arrival of concrete					
Slump (ASTM C143 - 10a)		Air Content (ASTM C231 - 10)			
Time ₁	Result ₁	Time ₁	Result ₁	S/N of Air Meter	
12:47	7.5"	12:58	4.2%	413078 6891	
Time ₂	Result ₂	Time ₂	Result ₂	S/N of Scale	
13:11	8.5"	13:	3.9%	056HM	
Unit Weight (ASTM C138 - 10b)					
Time ₁	Wt. of Cont. ₁	Total Wt. ₁	Wt. of Conc. ₁	Result ₁ = Wt. of Conc./Vol. of Cont.	
12:55	8.5#	44.7	36.2#	144.8 #/cft.	
Time ₂	Wt. of Cont. ₂	Total Wt. ₂	Wt. of Conc. ₂	Result ₂ = Wt. of Conc./Vol. of Cont.	
13:15	8.5#	44.6	36.1#	144.4 #/cft.	
Times of actions during and after casting					
Layer 1 placed	Layer 1 vibration complete	Layer 2 placed	Layer 2 vibration complete	Top surface struck off	Truck Departing Lab
✓	✓	✓	✓	✓	1:10PM
Lifting Inserts Placed	Covered with plastic	Plastic removed	Covered with burlap	Burlap doused with water	Covered with plastic
2:40PM	2:45PM	8:15PM	8:20PM	8:25PM	8:30PM
Recorded by	Signature		Date	Time	
S.P.	<i>A.D.</i>		4/24	1:20	
Checked by	Signature		Date	Time	
BPR	<i>Worth</i>		4/24	2:34PM	
Checked by	Signature		Date	Time	
<i>SA Worth</i>	<i>SA WORTH</i>		4/24	1:20	
Comments: 3 layers ✓ CONC. TEMP: 66°F (Dig & Cal gages)					

*The following ASTM standards and specifications will be followed during casting: C172-10, C192-07, C470-09

1

Truck 1635 Driver 1867 User user Disp Ticket Num 1859188 Ticket ID 0 Time Date 12:26 4/24/12
 Load Size 6.50 CYDS Mix Code 1008 Returned Qty Mix Age Seq D Load ID 1310

Material	Design Qty	Required	Batched	% Var	% Moisture	Actual	Wat
STONE-8	940 lb	6110 lb	6060 lb	-0.82%	M		
STONE-4	620 lb	4030 lb	4000 lb	-0.74%			
SAND-23	1435 lb	9841 lb	9800 lb	-0.41%	5.50% M	61 gl	
CEMENT	588 lb	3822 lb	3805 lb	-0.44%			
WATER	323.2 lb	1587.8 lb	1578.0 lb	-0.62%		183.1 gl	
AIR	.80 /C	30.58 oz	30.00 oz	-1.88%			

1

Actual Load 25245 lb Slump: 6.00 in # 6.00 in #
 Num Batches: 1
 Design W/C: 0.550 Water/Cement: 0.552 T Adjust Water: 0.0 lb / Load
 Design 251.7 gl Trim Water: 0.0 lb / CYC
 Actual 250.3 gl To Add: 1.4 gl

A-4

Concrete Delivery Ticket



Plant #	Ticket Number	Truck	Load Size	Mix	Slump	Use	Date	Customer
---------	---------------	-------	-----------	-----	-------	-----	------	----------

10 1057108 1635 6.50cy 1000 6.00 BUCKET 01/24/12 10091

Sold To	Tax Code	Driver	Project No.	Order No.
---------	----------	--------	-------------	-----------

YGE CARD LAFAYETTE & WINAMA IN RICK CLOUGH 1867 5 1803

Delivery Address	P.O. Number
------------------	-------------

BOWEN CIVIL ENGINEERING LAB SON2535

TRUCK RELEASE MIKE 559 708-1834 Job No: 2535

Time Printed 12:22

Load Quantity	Total	Ordered Quantity	Product Code	Product Description	Unit Price	Amount
---------------	-------	------------------	--------------	---------------------	------------	--------

6.50 6.50cy 19.50cy 1000 PURDUE EXPERIMENTAL 89.00 578.50



Environmental Fee

13.00

Water Added At Customer's Request	Total No. Gallons	Slump Meter Reading	Subtotal
--------------------------------------	----------------------	------------------------	----------

[Handwritten Signature] 9100

591.50


On Job Time	Finish Pour Time	Grand Total:	Total
-------------	------------------	--------------	-------

AUTH. #: 591.50

PROPERTY DAMAGE RELEASE / WARNING - Irritating To The Skin and Eyes

Dear Customer - The Seller is not responsible for slumps, strength or quality of concrete to which water or any other material has been added by the purchaser or at his request. The undersigned hereby authorizes Irving Materials, Inc. to use private property for making the delivery shown here on and assumes full responsibility for any damage or injury due to the premises. The undersigned agrees to reimburse said Company for loss of time and equipment by reason of such delivery and also to identify and save harmless said Company from any and all claims, demands and suits for or on account of or in any manner caused by or arising from private property delivery. The undersigned assumes responsibility for a suitable roadway from public highway to point of delivery and is responsible for any needed wrecker service charges as a result. SAFETY WARNING: Keep away from children. Contains Portland Cement. Irritating to the skin and eyes. Wear rubber boots, gloves and eye protection. Prolonged contact may cause burns. In case of contact with skin or eyes, flush thoroughly with water. If irritation persists, get medical attention. For additional information regarding the HAZARDS OF READY MIX CONCRETE, consult the Material Data Safety Sheet (MSDS) available upon request. PRODUCT NOTICE: Seller will not be held responsible for the final appearance of exposed aggregate, integral coloring, stamped and decorative surfacing, and all other forms of architectural and design concrete. DELIVERY NOTICE: Seller assumes no responsibility for deliveries beyond the public right of way. Buyer assumes responsibility for damages including but not limited to curb, sidewalk, driveway, or any property of the contractor or property owner or agents. NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE SAFETY AND HEALTH WARNING NOTICE AND ACCEPTANCE OF THE LOAD.

Release, Load and Terms Accepted By: *[Handwritten Signature]*





Project: Tests to Determine the Behavior of Spliced #11 Bars

Setup and As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: A-4

Sheet 1 of 2

Section	Concrete As-built Dimensions							
	1	2	3	4	5	6	7	8
Plan	39' 1/8"	39'	39'	39' 1/8"				
B-B	17-3/8"	30-3/16"	17-1/16"	30-1/8"				
C-C	17-1/2"	30-1/16"	17-3/4"	30-1/16"				
D-D	17-7/16"	30-1/8"	17-5/8"	30-1/8"				
E-E	17-1/16"	30-1/16"	17-1/16"	30-1/8"				
F-F	17-1/16"	30-3/16"	17-1/16"	30-3/16"				
Recorded by:			Signature				Date	Time
J.N.H.							6.7.12	1:20
Checked by:			Signature				Date	Time
BPR							6/7/12	4:30PM
Checked by:			Signature				Date	Time

Comments:

*See concrete as-built drawings for dimension locations


Project: Tests to Determine the
Behavior of Spliced #11 Bars

Setup and As-built Dimensions v.1
(Rev. 04/04/2012)


Specimen: A-4

Sheet 2 of 2



Section	Concrete As-built Dimensions Key - Series A							
	1	2	3	4	5	6	7	8
Plan	39'-0"	39'-0"	39'-0"	39'-0"	N/A	N/A	N/A	N/A
B-B	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
C-C	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
D-D	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
E-E	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
F-F	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
Section	Concrete As-built Dimensions Key - Series B							
	1	2	3	4	5	6	7	8
Plan	34'-4"	34'-4"	34'-4"	34'-4"	N/A	N/A	N/A	N/A
B-B	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
C-C	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
D-D	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
E-E	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
F-F	17-5/8"	30"	17-5/8"	30 ² - 47	N/A	N/A	N/A	N/A



Specimen <i>A-4</i>	Sheet:	1	of	4
Behavior of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	J.N.H.	Checked by:	BPR
	Date:	6.7.12		




Top Plan



Profile


*For section B-B through F-F see Sheet 3 of 3




Bottom Plan



Drawing:	Series A Concrete As-builts	Sheet:	2	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		




Top Plan



Profile


*For section B-B through F-F see Sheet 3 of 3



Bottom Plan



Drawing:	Series B Concrete As-builts	Sheet:	3	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		



Section B-B, C-C, D-D, E-E & F-F
*Facing North



Drawing:	Concrete As-built Sections	Sheet:	4	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

Project: Tests to Determine the Behavior of Spliced #11 Bars

As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: A-4

Sheet 1 of 2

Section	Formwork As-built Dimensions							
	1	2	3	4	5	6	7	8
A-A	173 $\frac{7}{8}$	120 $\frac{1}{16}$	174 $\frac{3}{16}$	174 $\frac{3}{16}$	120-0	173 $\frac{7}{8}$		
B-B	4- $\frac{3}{8}$	6- $\frac{1}{8}$	4- $\frac{3}{16}$	23- $\frac{1}{2}$	23- $\frac{7}{16}$	30- $\frac{1}{16}$	30- $\frac{1}{16}$	17- $\frac{1}{2}$
C-C	3- $\frac{1}{8}$	6- $\frac{1}{16}$	2- $\frac{7}{8}$	23- $\frac{5}{8}$	23- $\frac{1}{2}$	30-0	30- $\frac{1}{16}$	17- $\frac{1}{2}$
D-D	3- $\frac{1}{8}$	6-0	2- $\frac{7}{8}$	23- $\frac{7}{8}$	23- $\frac{7}{8}$	30-0	30- $\frac{1}{8}$	17- $\frac{1}{2}$
E-E	3- $\frac{1}{8}$	5- $\frac{15}{16}$	3- $\frac{1}{16}$	23- $\frac{11}{16}$	23- $\frac{11}{16}$	30-0	30- $\frac{1}{16}$	17- $\frac{1}{2}$
F-F	3- $\frac{1}{16}$	8- $\frac{3}{4}$	3- $\frac{1}{16}$	23- $\frac{9}{16}$	23- $\frac{11}{16}$	30- $\frac{1}{8}$	30- $\frac{3}{16}$	17- $\frac{1}{2}$
Recorded by:			Signature			Date	Time	
BPR			<i>Mr. Winter</i>			4/23	2:40 PM	
Checked by:			Signature			Date	Time	
TD			<i>[Signature]</i>			4/23	2:40	
Checked by:			Signature			Date	Time	

Comments:

*See formwork as-built drawings for dimension locations


Project: Tests to Determine the
Behavior of Spliced #11 Bars

As-built Dimensions v.1
(Rev. 04/04/2012)


Specimen: _____

Sheet 2 of 2

Section	Formwork As-built Dimensions Key - Series A							
	1	2	3	4	5	6	7	8
A-A	14'-6"	10'-0"	14'-6"	14'-6"	10'-0"	14'-6"	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
D-D	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
E-E	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
F-F	3"	8-3/4"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
Section	Formwork As-built Dimensions Key - Series B							
	1	2	3	4	5	6	7	8
A-A	13'-10.5"	6'-7"	13'-10.5"	13'-10.5"	6'-7"	13'-10.5"	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
D-D	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
E-E	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
F-F	3"	8-3/4"	3"	23-5/8" ₂₋₅₃	23-5/8"	30"	30"	17-5/8"



Section A-A





*For section B-B through F-F see Sheet 3 of 3

Series A



Drawing:	Series A Formwork As-builts	Sheet:	1	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		




*For section B-B through F-F see Sheet 3 of 3


Series B



Drawing:	Series B Formwork As-builts	Sheet:	2	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		



Section C-C, D-D, & E-E
*Facing North



Section B-B & F-F
*Facing North



Drawing:	Formwork As-built Sections	Sheet:	3	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

A-5

Project: Tests to Determine the
Behavior of Spliced #11 BarsCasting Documentation v.1
(Rev. 03/30/2012)

Specimen: _____

Sheet 1 of 1

General Information					
Date	Disp Ticket Num	Truck No.	Time on Ticket	Time of Arrival	Temp. in Lab
4/24	1859191	1693	13:01	1:20PM	62°F
Measurements made upon arrival of concrete					
Slump (ASTM C143 - 10a)		Air Content (ASTM C231 - 10)			
Time ₁	Result ₁	Time ₁	Result ₁	S/N of Air Meter	
1:25	8 1/2"	1:33	4.6%	Same as A-4	
Time ₂	Result ₂	Time ₂	Result ₂	S/N of Scale	
1:50	8 1/2"	1:52	4.6%	Same as A-4	
Unit Weight (ASTM C138 - 10b)					
Time ₁	Wt. of Cont. ₁	Total Wt. ₁	Wt. of Conc. ₁	Result ₁ = Wt. of Conc./Vol. of Cont.	
1:31	8.5 #	44.4 #			
Time ₂	Wt. of Cont. ₂	Total Wt. ₂	Wt. of Conc. ₂	Result ₂ = Wt. of Conc./Vol. of Cont.	
1:50	8.5 #	44.2 #			
Times of actions during and after casting					
Layer 1 placed	Layer 1 vibration complete	Layer 2 placed	Layer 2 vibration complete	Top surface struck off	Truck Departing Lab
✓	✓	✓	✓	✓	1:50
Lifting Inserts Placed	Covered with plastic	Plastic removed	Covered with burlap	Burlap doused with water	Covered with plastic
2:40PM	2:45PM	8:20PM	8:25PM	8:30PM	8:35PM
Recorded by	Signature		Date	Time	
S. P.			4/24	1:53	
Checked by	Signature		Date	Time	
BPR			4/24	2:34PM	
Checked by	Signature		Date	Time	
			4/24/12	1:55p	
Comments: CONC. TEMP = 67.5 °F 3 layers					
*The following ASTM standards and specifications will be followed during casting: C172-10, C192-07, C470-09					

Truck 1693 Driver 2774 User user Disp Ticket Num 1859191 Ticket ID 0 Time Date 13:01 4/24/12
 Load Size 6.50 Mix Code CYDS 1008 Returned Qty Mix Age Seq D Load ID 1313

Material	Design Qty	Required	Batched	% Var	% Moisture	Actual	Wat
STONE-8	340 lb	6110 lb	6060 lb	-0.82%	M		
STONE-4	620 lb	4030 lb	4000 lb	-0.74%			
SAND-23	1435 lb	3841 lb	3800 lb	-0.41%	5.50%M	61 gl	
CEMENT	588 lb	3822 lb	3820 lb	-0.05%			
WATER	323.2 lb	1587.8 lb	1580.0 lb	-0.49%		189.3 gl	
AIR	.80 /G	30.58 oz	30.50 oz	-0.25%			

2

Actual Load 25262 lb Slump: 6.00 in # 6.00 in
 Num Batches: 1
 Design W/C: 0.550
 Water/Cement: 0.550 T
 Adjust Water: 0.0 lb
 Design 251.7 gl
 lb / Load
 Trim Water:
 Actual 250.6 gl
 To Add: 1.2 gl
 0.0 lb / CYC

A-5

Concrete Delivery Ticket



Plant #	Ticket Number	Truck	Load Size	Mix	Slump	Use	Date	Customer
10	1859191	1693	6.50cy	1008	6.00	BUCKET	04/24/12	15091
Sold To				Tax Code	Driver	Project No.		Order No.
BOE CRAD - LAFAYETTE & MTNOMA				IN	RON HOWARD	2774 5		1802
Delivery Address							P.O. Number	
ROSEN CIVIL ENGINEERING LAB							SCN2535	
TRUCK RELEASE MIKE 550 708 1934							Job No. 180235	

Load Quantity	Total	Ordered Quantity	Product Code	Product Description	Unit Price	Amount
6.50	13.00cy	19.50cy	1008	PURDUE EXPERIMENTAL	89.00	578.50

2

imi

www.irvmat.com

Environmental Fee

Time Printed 13:00

2

AA5

13.00

Water Added At Driver's Request		Total No. Gallons	Slump Meter Reading					Subtotal	591.50
On Job Time	Finish Pour Time	Auth. #:	Grand Total:	1,183.00				Tax	
								Total	591.50

PROPERTY DAMAGE RELEASE / WARNING - Irritating To The Skin and Eyes

Dear Customer - The Seller is not responsible for slumps, strength or quality of concrete to which water or any other material has been added by the purchaser or at his request. The undersigned hereby authorizes Irving Materials, Inc. to use private property for making the delivery shown here on and assumes full responsibility for any damage or injury due to the premises. The undersigned agrees to reimburse said Company for loss of time and equipment by reason of such delivery and also to identify and save harmless said Company from any and all claims, demands and suits for or on account of or in any manner caused by or arising from private property delivery.

The undersigned assumes responsibility for a suitable roadway from public highway to point of delivery and is responsible for any needed wrecker service charges as a result.

SAFETY WARNING: Keep away from children. Contains Portland Cement. Irritating to the skin and eyes. Wear rubber boots, gloves and eye protection. Prolonged contact may cause burns. In case of contact with skin or eyes, flush thoroughly with water. If irritation persists, get medical attention. For additional information regarding the HAZARDS OF READY MIX CONCRETE, consult the Material Data Safety Sheet (MSDS) available upon request.

PRODUCT NOTICE: Seller will not be held responsible for the final appearance of exposed aggregate, integral coloring, stamped and decorative surfacing, and all other forms of architectural and design concrete.

DELIVERY NOTICE: Seller assumes no responsibility for deliveries beyond the public right of way. Buyer assumes responsibility for damages including but not limited to curb, sidewalk, driveway, or any property of the contractor or property owner or agents.

NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE SAFETY AND HEALTH WARNING NOTICE AND ACCEPTANCE OF THE LOAD.

Release, Load and Terms Accepted By:



Project: Tests to Determine the Behavior of Spliced #11 Bars

Setup and As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: A-5

Sheet 1 of 2

Section	Concrete As-built Dimensions								
	1	2	3	4	5	6	7	8	
Plan	37'-11 3/4"	37'-11 3/4"	37'-11 7/8"	37'-11 7/8"					
B-B	17- 1/2"	30- 1/16"	17- 3/4"	30- 0"					
C-C	17- 1/2"	30- 1/16"	17- 3/4"	30- 1/16"					
D-D	17- 1/2"	30- 3/16"	17- 3/4"	30- 1/4"					
E-E	17- 5/16"	30- 1/8"	17- 5/8"	30- 1/16"					
F-F	17- 9/16"	30- 1/4"	17- 11/16"	30- 1/4"					
Recorded by:			Signature			Date		Time	
KAM			JLL			6-6-12		4:15 pm	
Checked by:			Signature			Date		Time	
BPR			The Nest			6/6/12		4:25 PM	
Checked by:			Signature			Date		Time	

Comments:

*See concrete as-built drawings for dimension locations


Project: Tests to Determine the
Behavior of Spliced #11 Bars

Setup and As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: A-5

Sheet 2 of 2

Section	Concrete As-built Dimensions Key - Series A							
	1	2	3	4	5	6	7	8
Plan	39'-0"	39'-0"	39'-0"	39'-0"	N/A	N/A	N/A	N/A
B-B	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
C-C	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
D-D	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
E-E	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
F-F	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
Section	Concrete As-built Dimensions Key - Series B							
	1	2	3	4	5	6	7	8
Plan	34'-4"	34'-4"	34'-4"	34'-4"	N/A	N/A	N/A	N/A
B-B	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
C-C	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
D-D	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
E-E	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
F-F	17-5/8"	30"	17-5/8"	30 ² - 61	N/A	N/A	N/A	N/A



Specimen *A-5*

Behavior of Lap Splices of No. 11
Reinforcing Bars

Sheet:

1

of

4

Drawn by:


KAM

Checked by:

BPR



Date:

6-6-12




Top Plan

2 Spa. @



Profile


*For section B-B through F-F see Sheet 3 of 3




Bottom Plan



Drawing:	Series A Concrete As-builts	Sheet:	2	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		




Top Plan




Profile


*For section B-B through F-F see Sheet 3 of 3



Bottom Plan



Drawing:	Series B Concrete As-builts	Sheet:	3	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		



Section B-B, C-C, D-D, E-E & F-F
*Facing North





Drawing:	Concrete As-built Sections	Sheet:	4	of	4
	Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:
Date:			04/04/2012		

Project: Tests to Determine the Behavior of Spliced #11 Bars

As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: A-5

Sheet 1 of 2

Section	Formwork As-built Dimensions							
	1	2	3	4	5	6	7	8
A-A	174- $\frac{1}{16}$	119- $\frac{15}{16}$	174-0	174- $\frac{1}{8}$	120-0	173- $\frac{7}{8}$		
B-B	4- $\frac{1}{2}$	5- $\frac{15}{16}$	4- $\frac{3}{8}$	23- $\frac{1}{2}$	23- $\frac{5}{8}$	30- $\frac{1}{8}$	30- $\frac{1}{16}$	17- $\frac{1}{2}$
C-C	3- $\frac{1}{8}$	5- $\frac{7}{8}$	3-0	23- $\frac{5}{8}$	23- $\frac{5}{8}$	30- $\frac{1}{8}$	30- $\frac{1}{8}$	17- $\frac{1}{2}$
D-D	3- $\frac{1}{16}$	5- $\frac{13}{16}$	3- $\frac{1}{16}$	23- $\frac{7}{8}$	23- $\frac{7}{8}$	30- $\frac{1}{8}$	30- $\frac{1}{16}$	17- $\frac{1}{2}$
E-E	3-0	5- $\frac{7}{8}$	3- $\frac{1}{8}$	23- $\frac{5}{8}$	23- $\frac{1}{16}$	30- $\frac{1}{16}$	30- $\frac{1}{16}$	17- $\frac{7}{16}$
F-F	2- $\frac{7}{8}$	8- $\frac{3}{4}$	3- $\frac{1}{8}$	23- $\frac{5}{8}$	23- $\frac{1}{16}$	30- $\frac{1}{8}$	30- $\frac{3}{16}$	17- $\frac{1}{2}$
Recorded by:			Signature			Date	Time	
BPR						4/23	2:50PM	
Checked by:			Signature			Date	Time	
TD						4/23	2:50PM	
Checked by:			Signature			Date	Time	

Comments:

*See formwork as-built drawings for dimension locations



Project: Tests to Determine the
Behavior of Spliced #11 Bars

As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: _____

Sheet 2 of 2



Section	Formwork As-built Dimensions Key - Series A							
	1	2	3	4	5	6	7	8
A-A	14'-6"	10'-0"	14'-6"	14'-6"	10'-0"	14'-6"	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
D-D	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
E-E	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
F-F	3"	8-3/4"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
Section	Formwork As-built Dimensions Key - Series B							
	1	2	3	4	5	6	7	8
A-A	13'-10.5"	6'-7"	13'-10.5"	13'-10.5"	6'-7"	13'-10.5"	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
D-D	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
E-E	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
F-F	3"	8-3/4"	3"	23-5/8" 2-67	23-5/8"	30"	30"	17-5/8"




*For section B-B through F-F see Sheet 3 of 3




Drawing:	Series A Formwork As-builts	Sheet:	1	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		




*For section B-B through F-F see Sheet 3 of 3



Drawing:	Series B Formwork As-builts	Sheet:	2	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		



Section C-C, D-D, & E-E
*Facing North



Section B-B & F-F
*Facing North



Drawing:	Formwork As-built Sections	Sheet:	3	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

Project: Tests to Determine the
Behavior of Spliced #11 BarsCasting Documentation v.1
(Rev. 03/30/2012)Specimen: X-6

Sheet 1 of 1

General Information					
Date	Disp Ticket Num	Truck No.	Time on Ticket	Time of Arrival	Temp. in Lab
4/24/12	1859193	1839	1:51	2:03	62°F
Measurements made upon arrival of concrete					
Slump (ASTM C143 - 10a)		Air Content (ASTM C231 - 10)			
Time ₁	Result ₁	Time ₁	Result ₁	S/N of Air Meter	
2:05	8"	2:15	4.2%	Same as A-5	
Time ₂	Result ₂	Time ₂	Result ₂	S/N of Scale	
2:25	8 1/2"	2:30	4.6%	Same as A-5	
Unit Weight (ASTM C138 - 10b)					
Time ₁	Wt. of Cont. ₁	Total Wt. ₁	Wt. of Conc. ₁	Result ₁ = Wt. of Conc./Vol. of Cont.	
2:12	8.5#	45#			
Time ₂	Wt. of Cont. ₂	Total Wt. ₂	Wt. of Conc. ₂	Result ₂ = Wt. of Conc./Vol. of Cont.	
2:30	8.5	44.6#			
Times of actions during and after casting					
Layer 1 placed	Layer 1 vibration complete	Layer 2 placed	Layer 2 vibration complete	Top surface struck off	Truck Departing Lab
2:15	✓	✓	✓	✓	2:20PM
Lifting Inserts Placed	Covered with plastic	Plastic removed	Covered with burlap	Burlap doused with water	Covered with plastic
2:40PM	2:45PM	8:25PM	8:30PM	8:35PM	8:40PM
Recorded by	Signature		Date	Time	
M.A. Sozen	Met Abram		24 Apr 12	2:31	
Checked by	Signature		Date	Time	
BPR	Newnitz		4/24/12	2:33PM	
Checked by	Signature		Date	Time	
AWORTHY	J Swartz		4/24/12	2:34PM	
Comments: Conc Temp. : 67.5° 3 Lifts					
*The following ASTM standards and specifications will be followed during casting: C172-10, C192-07, C470-09					

Truck 1839 Driver 2463 User user Disp Ticket Num 1859193 Ticket ID 0 Time Date 13:51 4/24/12
 Load Size 6.50 CYDS Mix Code 1008 Returned Qty Mix Age Seq D Load ID 1315

Material	Design Qty	Required	Batched	% Var	% Moisture	Actual	Wat
STONE-8	940 lb	910 lb	6060 lb	-0.82%	M		
STONE-4	620 lb	4030 lb	4000 lb	-0.74%			
SAND-23	1435 lb	9841 lb	9800 lb	-0.41%	5.50%M	61 gl	
CEMENT	588 lb	3822 lb	3860 lb	0.99%			
WATER	323.2 lb	1587.8 lb	1576.0 lb	-0.74%		188.9 gl	
AIR	.80 /C	30.58 oz	30.00 oz	-1.88%			

Actual Load 25298 lb Slump: 6.00 in #
 Num Batches: 1
 Design W/C: 0.550 Water in Truck: 0.0 lb
 Water/Cement: 0.544 Adjust Water: 0.0 lb / Load
 Design 251.7 gl Actual 250.1 gl To Add: 1.7 gl
 Trim Water: 0.0 lb / CYC

3

A-6

Concrete Delivery Ticket



Plant #	Ticket Number	Truck	Load Size	Mix	Slump	Use	Date	Customer
---------	---------------	-------	-----------	-----	-------	-----	------	----------

10 1859195 1839 6.50cy 1000 6.00 RUCKET 07/24/12 16091

Sold To	Tax Code	Driver	Project No.	Order No.
---------	----------	--------	-------------	-----------

ARGE CARD - LAFAYETTE & WINAMA IN DANNY SMITH 2463 5 1803

Delivery Address	P.O. Number
------------------	-------------

BOWEN CIVIL ENGINEERING LAB

30N2535

TRUCK RELEASE MIKE 559 708-1934

Job No. 30N2535

Time Printed 13:46

Load Quantity	Total	Ordered Quantity	Product Code	Product Description	Unit Price	Amount
---------------	-------	------------------	--------------	---------------------	------------	--------

6.50 19.50cy 19.50cy 1000 PURDUE EXPERIMENTAL 89.00 578.50



A-16
13.00

Added At Driver's Request	Total No. Gallons	Slump Meter Reading	Subtotal
------------------------------	----------------------	------------------------	----------


On Job Time	Finish Pour Time	Auth. #	Grand Total:	Tax	Total
-------------	------------------	---------	--------------	-----	-------

PROPERTY DAMAGE RELEASE / WARNING - Irritating To The Skin and Eyes

Dear Customer - The Seller is not responsible for slumps, strength or quality of concrete to which water or any other material has been added by the purchaser or at his request. The undersigned hereby authorizes Irving Materials, Inc. to use private property for making the delivery shown here on and assumes full responsibility for any damage or injury due to the premises. The undersigned agrees to reimburse said Company for loss of time and equipment by reason of such delivery and also to identify and save harmless said Company from any and all claims, demands and suits for or on account of or in any manner caused by or arising from private property delivery. The undersigned assumes responsibility for a suitable roadway from public highway to point of delivery and is responsible for any needed wrecker service charges as a result. SAFETY WARNING: Keep away from children. Contains Portland Cement. Irritating to the skin and eyes. Wear rubber boots, gloves and eye protection. Prolonged contact may cause burns. In case of contact with skin or eyes, flush thoroughly with water. If irritation persists, get medical attention. For additional information regarding the HAZARDS OF READY MIX CONCRETE, consult the Material Data Safety Sheet (MSDS) available upon request. PRODUCT NOTICE: Seller will not be held responsible for the final appearance of exposed aggregate, integral coloring, stamped and decorative surfacing, and all other forms of architectural and design concrete. DELIVERY NOTICE: Seller assumes no responsibility for deliveries beyond the public right of way. Buyer assumes responsibility for damages including but not limited to curb, sidewalk, driveway, or any property of the contractor or property owner or agents. NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE SAFETY AND HEALTH WARNING NOTICE AND ACCEPTANCE OF THE LOAD.

Release, Load and Terms Accepted By:

X



Project: Tests to Determine the Behavior of Spliced #11 Bars

Setup and As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: AG
Sheet 1 of 2

Section	Concrete As-built Dimensions							
	1	2	3	4	5	6	7	8
Plan	39'-0"	38'-11 $\frac{3}{4}$ "	39'-0"	38'-11 $\frac{3}{4}$ "				
B-B	17- $\frac{3}{4}$ "	30- $\frac{1}{16}$ "	17- $\frac{3}{4}$ "	30- $\frac{1}{8}$ "				
C-C	17- $\frac{3}{4}$ "	30- $\frac{1}{16}$ "	17- $\frac{3}{4}$ "	30- $\frac{1}{16}$ "				
D-D	17- $\frac{3}{4}$ "	30- $\frac{1}{16}$ "	17- $\frac{13}{16}$ "	30- $\frac{1}{8}$ "				
E-E	17- $\frac{13}{16}$ "	30- $\frac{1}{16}$ "	17- $\frac{13}{16}$ "	30- $\frac{1}{8}$ "				
F-F	17- $\frac{3}{4}$ "	30- $\frac{1}{8}$ "	17- $\frac{13}{16}$ "	30- $\frac{1}{8}$ "				
Recorded by:			Signature			Date	Time	
KAM			NLL			6-4-12	10:30pm	
Checked by:			Signature			Date	Time	
BPR			M. V. [Signature]			6/4/12	10:30PM	
Checked by:			Signature			Date	Time	

Comments:

*See concrete as-built drawings for dimension locations


Project: Tests to Determine the
Behavior of Spliced #11 Bars

Setup and As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: A-6


Sheet 2 of 2

Section	Concrete As-built Dimensions Key - Series A							
	1	2	3	4	5	6	7	8
Plan	39'-0"	39'-0"	39'-0"	39'-0"	N/A	N/A	N/A	N/A
B-B	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
C-C	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
D-D	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
E-E	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
F-F	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
Section	Concrete As-built Dimensions Key - Series B							
	1	2	3	4	5	6	7	8
Plan	34'-4"	34'-4"	34'-4"	34'-4"	N/A	N/A	N/A	N/A
B-B	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
C-C	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
D-D	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
E-E	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
F-F	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A




Specimen **A-6**
 Behavior of Lap Splices of No. 11
 Reinforcing Bars



Sheet:	1	of	4
Drawn by:	KAN	Checked by:	BPR
Date:	6-4-12		



Drawing:	Series A Concrete As-builts	Sheet:	2	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		




Top Plan



Profile


*For section B-B through F-F see Sheet 3 of 3



Bottom Plan



Drawing:	Series B Concrete As-builts	Sheet:	3	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		



Section B-B, C-C, D-D, E-E & F-F
*Facing North



Drawing:	Concrete As-built Sections	Sheet:	4	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

Project: Tests to Determine the Behavior of Spliced #11 Bars

As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: A-6

Sheet 1 of 2

Section	Formwork As-built Dimensions							
	1	2	3	4	5	6	7	8
A-A	173- $\frac{15}{16}$	120- $\frac{1}{8}$	173- $\frac{7}{8}$	174-0	119- $\frac{15}{16}$	173- $\frac{15}{16}$		
B-B	4- $\frac{3}{8}$	6- $\frac{1}{8}$	4- $\frac{3}{8}$	23- $\frac{1}{2}$	23- $\frac{1}{2}$	30- $\frac{3}{16}$	30- $\frac{1}{8}$	17- $\frac{1}{2}$
C-C	3-0	6- $\frac{1}{8}$	3-0	23- $\frac{5}{8}$	23- $\frac{5}{8}$	30- $\frac{1}{16}$	30- $\frac{1}{16}$	17- $\frac{7}{16}$
D-D	3-0	6- $\frac{1}{8}$	2- $\frac{15}{16}$	23- $\frac{7}{8}$	23- $\frac{7}{8}$	30-0	30- $\frac{1}{16}$	17- $\frac{7}{16}$
E-E	3-0	6- $\frac{1}{8}$	2- $\frac{15}{16}$	23- $\frac{9}{16}$	23- $\frac{1}{16}$	30- $\frac{1}{16}$	30- $\frac{1}{8}$	17- $\frac{1}{2}$
F-F	3- $\frac{1}{8}$	8- $\frac{13}{16}$	2- $\frac{15}{16}$	23- $\frac{9}{16}$	23- $\frac{5}{8}$	30- $\frac{1}{8}$	30- $\frac{1}{8}$	17- $\frac{7}{16}$
Recorded by:			Signature			Date	Time	
BPR			<i>[Signature]</i>			4/23	3:20PM	
Checked by:			Signature			Date	Time	
TD			<i>[Signature]</i>			4/23	3:20PM	
Checked by:			Signature			Date	Time	

Comments:

*See formwork as-built drawings for dimension locations


Project: Tests to Determine the
Behavior of Spliced #11 Bars

As-built Dimensions v.1
(Rev. 04/04/2012)


Specimen: _____

Sheet 2 of 2

Section	Formwork As-built Dimensions Key - Series A							
	1	2	3	4	5	6	7	8
A-A	14'-6"	10'-0"	14'-6"	14'-6"	10'-0"	14'-6"	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
D-D	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
E-E	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
F-F	3"	8-3/4"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
Section	Formwork As-built Dimensions Key - Series B							
	1	2	3	4	5	6	7	8
A-A	13'-10.5"	6'-7"	13'-10.5"	13'-10.5"	6'-7"	13'-10.5"	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
D-D	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
E-E	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
F-F	3"	8-3/4"	3"	23-5/8" ₂₋₈₁	23-5/8"	30"	30"	17-5/8"



Section A-A





*For section B-B through F-F see Sheet 3 of 3

Series A



Drawing:	Series A Formwork As-builts	Sheet:	1	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		




*For section B-B through F-F see Sheet 3 of 3


Series B



Drawing:	Series B Formwork As-builts	Sheet:	2	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		



Section C-C, D-D, & E-E
*Facing North



Section B-B & F-F
*Facing North



Drawing:	Formwork As-built Sections	Sheet:	3	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

B-1

Project: Tests to Determine the
Behavior of Spliced #11 BarsCasting Documentation v.1
(Rev. 03/30/2012)

Specimen: _____

Sheet 1 of 1

General Information					
Date	Disp Ticket Num	Truck No.	Time on Ticket	Time of Arrival	Temp. in Lab
4/10/12	1858848	1982	12:23	1:00 PM	60°F
Measurements made upon arrival of concrete					
Slump (ASTM C143 - 10a)		Air Content (ASTM C231 - 10)			
Time ₁	Result ₁	Time ₁	Result ₁	S/N of Air Meter	
1:05	8.5"	1:17	5.8%	4130786891	
Time ₂	Result ₂	Time ₂	Result ₂	S/N of Scale	
1:46	9.0"	1:56	5.8%	06746056HM	
Unit Weight (ASTM C138 - 10b)					
Time ₁	Wt. of Cont. ₁	Total Wt. ₁	Wt. of Conc. ₁	Result ₁ = Wt. of Conc./Vol. of Cont.	
1:08	8.5#	43.9#			
Time ₂	Wt. of Cont. ₂	Total Wt. ₂	Wt. of Conc. ₂	Result ₂ = Wt. of Conc./Vol. of Cont.	
1:54	8.5#	43.3#			
Times of actions during and after casting					
Layer 1 placed	Layer 1 vibration complete	Layer 2 placed	Layer 2 vibration complete	Top surface struck off	Truck Departing Lab
1:17-1:22	✓	✓	1:45	✓	1:50
Lifting Inserts Placed	Covered with plastic	Plastic removed	Covered with burlap	Burlap doused with water	Covered with plastic
2:48	3:00 PM	8:10	✓	✓	✓
Recorded by	Signature		Date	Time	
S.P.			4/10/12	2:00	
Checked by	Signature		Date	Time	
B.P.			4/10/12	2:00	
Checked by	Signature		Date	Time	
			4/10/12	2:00 PM	
Comments:					
Clump near midspan. → Broken			No leaks.		
Concrete Temperature : 19°C @ 1:33 PM ← Merc. Probe					
63°F @ 1:40 PM			E. Probe / Pankow		
*The following ASTM standards and specifications will be followed during casting: C172-10, C192-07, C470-09					

1

Truck	Driver	User	Disp Ticket Num	Ticket ID	Time	Date
1982	1076	user	1858848	0	12:23	4/10/12
Load Size	Mix Code	Returned	Qty	Mix Age	Seq	Load ID
5.75 CYDS	1008				D	972

Material	Design Qty	Required	Batched	% Var	% Moisture	Actual	Wat
STONE-8	940 lb	5405 lb	5360 lb	-0.83%	M		
STONE-4	620 lb	3565 lb	3800 lb	6.59%			
SAND-23	1425 lb	8864 lb	8640 lb	-0.27%	5.00%M	49 gl	
CEMENT	593 lb	3381 lb	3375 lb	-0.18%			
WATER	323.2 lb	1445.8 lb	1432.0 lb	-0.96%		171.6 gl	
AIR	.80 /C	27.05 oz	26.50 oz	-2.03%			

Actual	Num Batches:		1									
Load	22609 lb	Design W/C:	0.550	Water/Cement:	0.551	T ✓	Design	222.7 gl	Actual	220.9 gl	To Add:	1.8 gl
Slump:	6.00 in	#	Water in Truck:	0.0 lb	Adjust Water:		0.0 lb / Load	Trim Water:	0.0 lb /	CYC		

Concrete Delivery Ticket



Plant #	Ticket Number	Truck	Load Size	Mix	Slump	Use	Date	Customer
---------	---------------	-------	-----------	-----	-------	-----	------	----------

Sold To			Tax Code	Driver	Project No.	Order No.
---------	--	--	----------	--------	-------------	-----------

Delivery Address	P.O. Number
------------------	-------------

BOWEN CIVIL ENGINEERING LAB

Job No. 312-344-0175
 3002513

1

Load Quantity	Total	Ordered Quantity	Product Code	Product Description	Unit Price	Amount
---------------	-------	------------------	--------------	---------------------	------------	--------

5.75	5.7500	17-2500	1000	(MIRQUE EXPERIMENTAL)	85.00	511.75
------	--------	---------	------	-----------------------	-------	--------



Water Added At Customer's Request		Total No. Gallons	Slump Meter Reading	
-----------------------------------	--	-------------------	---------------------	--

Subtotal 565.25
 Tax
 Total 583.25

On Job Time	Finish Pour Time
-------------	------------------

PROPERTY DAMAGE RELEASE / WARNING - Irritating To The Skin and Eyes

Dear Customer - The Seller is not responsible for slumps, strength or quality of concrete to which water or any other material has been added by the purchaser or at his request. The undersigned hereby authorizes Irving Materials, Inc. to use private property for making the delivery shown here on and assumes full responsibility for any damage or injury due to the premises. The undersigned agrees to reimburse said Company for loss of time and equipment by reason of such delivery and also to identify and save harmless said Company from any and all claims, demands and suits for or on account of or in any manner caused by or arising from private property delivery. The undersigned assumes responsibility for a suitable roadway from public highway to point of delivery and is responsible for any needed wrecker service charges as a result.

SAFETY WARNING: Keep away from children. Contains Portland Cement. Irritating to the skin and eyes. Wear rubber boots, gloves and eye protection. Prolonged contact may cause burns. In case of contact with skin or eyes, flush thoroughly with water. If irritation persists, get medical attention. For additional information regarding the HAZARDS OF READY MIX CONCRETE, consult the Material Data Safety Sheet (MSDS) available upon request.

PRODUCT NOTICE: Seller will not be held responsible for the final appearance of exposed aggregate, integral coloring, stamped and decorative surfacing, and all other forms of architectural and design concrete.

DELIVERY NOTICE: Seller assumes no responsibility for deliveries beyond the public right of way. Buyer assumes responsibility for damages including but not limited to curb, sidewalk, driveway, or any property of the contractor or property owner or agents.

NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE SAFETY AND HEALTH WARNING NOTICE AND ACCEPTANCE OF THE LOAD.

Release, Load and Terms Accepted By:



Concrete Delivery Ticket



Plant #	Ticket Number	Truck	Load Size	Mix	Slump	Use	Date	Customer
---------	---------------	-------	-----------	-----	-------	-----	------	----------

18 1858848 1982 5.75cy 1008 5.00 04/10/12 16091

Sold To	Tax Code	Driver	Project No.	Order No.
---------	----------	--------	-------------	-----------

CHARGE CARD - BOWEN LAB IN DOUG PHEBUS 1076 5 1801

Delivery Address	P.O. Number
------------------	-------------

BOWEN CIVIL ENGINEERING LAB 818-344-0114
 TRUCK RELEASE Job No. 572513

Time Printed 12:19

Load Quantity	Total	Ordered Quantity	Product Code	Product Description	Unit Price	Amount
---------------	-------	------------------	--------------	---------------------	------------	--------

5.75 5.75cy 17.25cy 1008 PURDUE EXPERIMENTAL 89.00 511.75



Water Added At Customer's Request		Total No. Gallons	Slump Meter Reading					Subtotal	523.25
On Job Time	Finish Pour Time							Tax	
Grand Totals							523.25	Total	523.25

PROPERTY DAMAGE RELEASE / WARNING - Irritating To The Skin and Eyes

Dear Customer - The Seller is not responsible for slumps, strength or quality of concrete to which water or any other material has been added by the purchaser or at his request. The undersigned hereby authorizes Irving Materials, Inc. to use private property for making the delivery shown here on and assumes full responsibility for any damage or injury due to the premises. The undersigned agrees to reimburse said Company for loss of time and equipment by reason of such delivery and also to identify and save harmless said Company from any and all claims, demands and suits for or on account of or in any manner caused by or arising from private property delivery. The undersigned assumes responsibility for a suitable roadway from public highway to point of delivery and is responsible for any needed wrecker service charges as a result. SAFETY WARNING: Keep away from children. Contains Portland Cement. Irritating to the skin and eyes. Wear rubber boots, gloves and eye protection. Prolonged contact may cause burns. In case of contact with skin or eyes, flush thoroughly with water. If irritation persists, get medical attention. For additional information regarding the HAZARDS OF READY MIX CONCRETE, consult the Material Data Safety Sheet (MSDS) available upon request. PRODUCT NOTICE: Seller will not be held responsible for the final appearance of exposed aggregate, integral coloring, stamped and decorative surfacing, and all other forms of architectural and design concrete. DELIVERY NOTICE: Seller assumes no responsibility for deliveries beyond the public right of way. Buyer assumes responsibility for damages including but not limited to curb, sidewalk, driveway, or any property of the contractor or property owner or agents. NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE SAFETY AND HEALTH WARNING NOTICE AND ACCEPTANCE OF THE LOAD.

Release, Load and Terms Accepted By: **X**





Project: Tests to Determine the Behavior of Spliced #11 Bars

Setup and As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: B-1

Sheet 1 of 2

Section	Concrete As-built Dimensions							
	T 1.	B 2W	B 3	B 4 E	5	6	7	8
Plan	34'-3 $\frac{1}{2}$ "	34'-3 $\frac{1}{2}$ "	34'-3 $\frac{1}{2}$ "	34'-3 $\frac{1}{2}$ "				
B-B	17 $\frac{11}{16}$ "	30 $\frac{11}{16}$ "	17 $\frac{5}{8}$	30 $\frac{11}{16}$ "				
C-C	17 $\frac{5}{8}$	30"	17 $\frac{3}{4}$ "	30"				
D-D	17 $\frac{5}{8}$ "	30 $\frac{1}{16}$ "	17 $\frac{5}{16}$	30"				
E-E	17 $\frac{9}{16}$	30 $\frac{1}{16}$	17 $\frac{5}{8}$	30"				
F-F	17 $\frac{5}{8}$	30 $\frac{1}{16}$	17 $\frac{5}{8}$	30 $\frac{1}{16}$ "				
Recorded by:			Signature			Date	Time	
M. A. Sozen						9 May 2012	10:20 a	
Checked by:			Signature			Date	Time	
S. Pujol						9 May 2012	10:22 am	
Checked by:			Signature			Date	Time	

Comments:

*See concrete as-built drawings for dimension locations

Project: Tests to Determine the
Behavior of Spliced #11 Bars


Setup and As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen:


B-1

Sheet 2 of 2


Section	Concrete As-built Dimensions Key - Series A							
	1	2	3	4	5	6	7	8
Plan	39'-0"	39'-0"	39'-0"	39'-0"	N/A	N/A	N/A	N/A
B-B	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
C-C	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
D-D	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
E-E	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
F-F	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
Section	Concrete As-built Dimensions Key - Series B							
	1	2	3	4	5	6	7	8
Plan	34'-4"	34'-4"	34'-4"	34'-4"	N/A	N/A	N/A	N/A
B-B	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
C-C	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
D-D	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
E-E	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
F-F	17-5/8"	30"	17-5/8"	30" _{2 - 90}	N/A	N/A	N/A	N/A




Specimen B-1	Sheet:	1	of	4
Behavior of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	S. F
	Date:	5/10/12		



Drawing:	Series A Concrete As-builts	Sheet:	2	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		




Top Plan



Profile


*For section B-B through F-F see Sheet 3 of 3



Bottom Plan



Drawing:	Series B Concrete As-builts	Sheet:	3	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		



Section B-B, C-C, D-D, E-E & F-F
*Facing North





Drawing:	Concrete As-built Sections	Sheet:	4	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

Project: Tests to Determine the Behavior of Spliced #11 Bars

As-built Dimensions v.1
(Rev. 04/04/2012)


Specimen: B-1

Sheet 1 of 2


Section	Formwork As-built Dimensions								
	1	2	3	4	5	6	7	8	
A-A	166 ^{5/8}	78 ^{15/16}	166 ^{3/16}	166 ^{1/2}	79	166 ^{3/4}			
B-B	4 ^{3/8}	5 ^{7/8}	4 ^{9/16}	23 ^{5/8}	23 ^{5/8}	30 ^{1/8}	30 ^{1/8}	17 ^{7/16}	
C-C	2 ^{1/8}	5 ^{15/16}	3 ^{1/16}	23 ^{11/16}	23 ^{5/8}	30 ^{1/8}	30 ^{1/8}	17 ^{5/8}	
D-D	3	6	3	23 ^{11/16}	23 ^{5/8}	30 ^{1/8}	30 ^{3/16}	17 ^{7/16}	
E-E	3 ^{1/16}	5 ^{15/16}	3	23 ^{5/8}	23 ^{3/4}	30 ^{1/8}	30 ^{1/8}	17 ^{7/16}	
F-F	3 ^{1/8}	8 ^{5/8}	3 ^{1/16}	23 ^{3/4}	23 ^{5/8}	30 ^{1/8}	30 ^{1/8}	17 ^{9/16}	
Recorded by:			Signature			Date		Time	
KAM						4-8-12		11:15 PM	
Checked by:			Signature			Date		Time	
WHP						4/8/2012		11:30 PM	
Checked by:			Signature			Date		Time	

Comments:

*See formwork as-built drawings for dimension locations



Section A-A





*For section B-B through F-F see Sheet 3 of 3

Series A



Drawing:	Series A Formwork As-builts	Sheet:	1	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		




*For section B-B through F-F see Sheet 3 of 3

Series B




Drawing:	Series B Formwork As-builts	Sheet:	2	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		



Section C-C, D-D, & E-E
*Facing North

Section B-B & F-F
*Facing North



Drawing:	Formwork As-built Sections	Sheet:	3	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

B-2

Project: Tests to Determine the
Behavior of Spliced #11 BarsCasting Documentation v.1
(Rev. 03/30/2012)

Specimen: _____

Sheet 1 of 1

General Information					
Date	Disp Ticket Num	Truck No.	Time on Ticket	Time of Arrival	Temp. in Lab
4/10/12	1858853	1839	1:48	2:08	58°F
Measurements made upon arrival of concrete					
Slump (ASTM C143 - 10a)		Air Content (ASTM C231 - 10)			
Time ₁	Result ₁	Time ₁	Result ₁	S/N of Air Meter	
2:10	8½"	2:16	5.4%	4130786891	
Time ₂	Result ₂	Time ₂	Result ₂	S/N of Scale	
2:36	9"	2:40	5.4%	06746056HM	
Unit Weight (ASTM C138 - 10b)					
Time ₁	Wt. of Cont. ₁	Total Wt. ₁	Wt. of Conc. ₁	Result ₁ = Wt. of Conc./Vol. of Cont.	
2:12	8.5# 8.5#	43.9#			
Time ₂	Wt. of Cont. ₂	Total Wt. ₂	Wt. of Conc. ₂	Result ₂ = Wt. of Conc./Vol. of Cont.	
2:38	8.5#	43.8			
Times of actions during and after casting					
Layer 1 placed	Layer 1 vibration complete	Layer 2 placed	Layer 2 vibration complete	Top surface struck off	Truck Departing Lab
2:16 TO 2:20	✓	2:22-2:24	✓	✓	2:32
Lifting Inserts Placed	Covered with plastic	Plastic removed	Covered with burlap	Burlap doused with water	Covered with plastic
2:22 3:40	3:45	✓	✓	✓	✓
Recorded by	Signature		Date	Time	
	<i>A. Dupl</i>		4/10/12	2:50	
Checked by	Signature		Date	Time	
	Brian Richter		4/10/12	3:00	
Checked by	Signature		Date	Time	
	<i>A. Wood</i>		4/10/12	2:51	
Comments: Spread 14" @ 2:10 , 15" @ 2:36 . No leaks Temp. of concrete: 65°F E Gage. 3 lifts. : 3rd lift 2:25 to 2:30 . vibrated: ✓					
*The following ASTM standards and specifications will be followed during casting: C172-10, C192-07, C470-09					

Truck	Driver	User	Disp Ticket Num	Ticket ID	Time	Date
1839	2463	user	1858853	0	13:48	4/10/12
Load Size	Mix Code	Returned	Qty	Mix Age	Seq	Load ID
5.75 CYDS	1008				D	977

Material	Design Qty	Required	Batched	% Var	% Moisture	Actual	Wat
STONE-8	940 lb	940 lb	936 lb	-0.83%	M		
STONE-4	620 lb	666 lb	640 lb	-0.70%			
SAND-23	1435 lb	964 lb	864 lb	-0.27%	5.00%M	49 gl	
CEMENT	588 lb	3381 lb	3365 lb	-0.47%			
WATER	323.2 lb	1445.8 lb	1442.0 lb	-0.27%		172.8 gl	
AIR	.80 /C	27.05 oz	27.50 oz	1.67%			

2

Actual	Num Batches:		1								
Load	22349 lb	Design W/C:	0.550	Water/Cement:	0.552 ✓ T	Design	222.7 gl	Actual	222.1 gl	To Add:	0.6 gl
Slump:	6.00 in	#	Water In Truck:	0.0 lb	Adjust Water:	0.0 lb / Load	Trim Water:	0.0 lb /	CYC		

Concrete Delivery Ticket



Plant #	Ticket Number	Truck	Load Size	Mix	Slump	Use	Date	Customer
---------	---------------	-------	-----------	-----	-------	-----	------	----------

18	1858452	1839	3.75-4.0	1000	5.00		01/10/12	11091
----	---------	------	----------	------	------	--	----------	-------

Sold To	Tax Code	Driver	Project No.	Order No.
---------	----------	--------	-------------	-----------

(CHARGE CARD) - ROWEN LAB IN DANNY SMITH 5 1001

Delivery Address	P.O. Number
------------------	-------------

BOWEN CIVIL ENGINEERING LAB 312-304-0111

TRUCK RELEASE Job No. 11091

2

Load Quantity	Total	Ordered Quantity	Product Code	Product Description	Unit Price	Amount
---------------	-------	------------------	--------------	---------------------	------------	--------

0.75	11.50	17.25	1000	PURDUE EXPERIMENTAL	34.00	585.00
------	-------	-------	------	---------------------	-------	--------



Water Added At Customer's Request	Total No. Gallons	Slump Meter Reading
-----------------------------------	-------------------	---------------------

On Job Time	Finish Pour Time
-------------	------------------

Subtotal 585.00
 Tax
 Total 585.25

PROPERTY DAMAGE RELEASE / WARNING - Irritating To The Skin and Eyes

Dear Customer - The Seller is not responsible for slumps, strength or quality of concrete to which water or any other material has been added by the purchaser or at his request. The undersigned hereby authorizes Irving Materials, Inc. to use private property for making the delivery shown here on and assumes full responsibility for any damage or injury due to the premises. The undersigned agrees to reimburse said Company for loss of time and equipment by reason of such delivery and also to identify and save harmless said Company from any and all claims, demands and suits for or on account of or in any manner caused by or arising from private property delivery. The undersigned assumes responsibility for a suitable roadway from public highway to point of delivery and is responsible for any needed wrecker service charges as a result. SAFETY WARNING: Keep away from children. Contains Portland Cement. Irritating to the skin and eyes. Wear rubber boots, gloves and eye protection. Prolonged contact may cause burns. In case of contact with skin or eyes, flush thoroughly with water. If irritation persists, get medical attention. For additional information regarding the HAZARDS OF READY MIX CONCRETE, consult the Material Data Safety Sheet (MSDS) available upon request. PRODUCT NOTICE: Seller will not be held responsible for the final appearance of exposed aggregate, integral coloring, stamped and decorative surfacing, and all other forms of architectural and design concrete. DELIVERY NOTICE: Seller assumes no responsibility for deliveries beyond the public right of way. Buyer assumes responsibility for damages including but not limited to curb, sidewalk, driveway, or any property of the contractor or property owner or agents. NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE SAFETY AND HEALTH WARNING NOTICE AND ACCEPTANCE OF THE LOAD.

Release, Load and Terms Accepted By:



Concrete Delivery Ticket



Plant #	Ticket Number	Truck	Load Size	Mix	Slump	Use	Date	Customer
---------	---------------	-------	-----------	-----	-------	-----	------	----------

18 1858853 1839 5.75cy 1008 6.00 04/10/12 16091

Sold To	Tax Code	Driver	Project No.	Order No.
---------	----------	--------	-------------	-----------

CHARGE CARD - BOWEN LAB IN DANNY SMITH 2463 5 1801

Delivery Address	P.O. Number
------------------	-------------

BOWEN CIVIL ENGINEERING LAB

812-344-0119

Job No. 2513

TRUCK RELEASE

2

Time Printed 13:46

Load Quantity	Total	Ordered Quantity	Product Code	Product Description	Unit Price	Amount
---------------	-------	------------------	--------------	---------------------	------------	--------

5.75 11.50cy 17.25cy 1008 PURDUE EXPERIMENTAL 89.00 511.75



Water Added At Customer's Request	Total No. Gallons	Slump Meter Reading
-----------------------------------	-------------------	---------------------

On Job Time	Finish Pour Time
-------------	------------------

RDTH. #:

Grand Total: 1,046.50

Subtotal 523.25
 Tax
 Total 523.25

PROPERTY DAMAGE RELEASE / WARNING - Irritating To The Skin and Eyes

Dear Customer - The Seller is not responsible for slumps, strength or quality of concrete to which water or any other material has been added by the purchaser or at his request. The undersigned hereby authorizes Irving Materials, Inc. to use private property for making the delivery shown here on and assumes full responsibility for any damage or injury due to the premises. The undersigned agrees to reimburse said Company for loss of time and equipment by reason of such delivery and also to identify and save harmless said Company from any and all claims, demands and suits for or on account of or in any manner caused by or arising from private property delivery. The undersigned assumes responsibility for a suitable roadway from public highway to point of delivery and is responsible for any needed wrecker service charges as a result. SAFETY WARNING: Keep away from children. Contains Portland Cement. Irritating to the skin and eyes. Wear rubber boots, gloves and eye protection. Prolonged contact may cause burns. In case of contact with skin or eyes, flush thoroughly with water. If irritation persists, get medical attention. For additional information regarding the HAZARDS OF READY MIX CONCRETE, consult the Material Data Safety Sheet (MSDS) available upon request. PRODUCT NOTICE: Seller will not be held responsible for the final appearance of exposed aggregate, integral coloring, stamped and decorative surfacing, and all other forms of architectural and design concrete. DELIVERY NOTICE: Seller assumes no responsibility for deliveries beyond the public right of way. Buyer assumes responsibility for damages including but not limited to curb, sidewalk, driveway, or any property of the contractor or property owner or agents. NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE SAFETY AND HEALTH WARNING NOTICE AND ACCEPTANCE OF THE LOAD.

Release, Load and Terms Accepted By:

X



Project: Tests to Determine the Behavior of Spliced #11 Bars

Setup and As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: B-2

Sheet 1 of 2

Section	Concrete As-built Dimensions							
	1	2	3	4	5	6	7	8
Plan	34'-4 1/4"	34'-4 3/8"	34'-4 1/4"	34'-4 1/2"				
B-B	17-5/8"	30-1/8"	17-9/16"	30-1/8"				
C-C	17-5/8"	30-1/8"	17-7/16"	30-1/16"				
D-D	17-1/16"	30-1/8"	17-5/8"	30-1/16"				
E-E	17-1/16"	30-1/8"	17-5/8"	30-1/16"				
F-F	17-3/4"	30-1/8"	17-5/8"	30-1/8"				
Recorded by:			Signature				Date	Time
KAM			[Signature]				5-22-12	5:00pm
Checked by:			Signature				Date	Time
BPR			[Signature]				5/22/12	5:10PM
Checked by:			Signature				Date	Time

Comments:


Project: Tests to Determine the
Behavior of Spliced #11 Bars

Setup and As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: B-2

Sheet 2 of 2

Section	Concrete As-built Dimensions Key - Series A							
	1	2	3	4	5	6	7	8
Plan	39'-0"	39'-0"	39'-0"	39'-0"	N/A	N/A	N/A	N/A
B-B	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
C-C	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
D-D	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
E-E	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
F-F	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
Section	Concrete As-built Dimensions Key - Series B							
	1	2	3	4	5	6	7	8
Plan	34'-4"	34'-4"	34'-4"	34'-4"	N/A	N/A	N/A	N/A
B-B	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
C-C	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
D-D	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
E-E	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
F-F	17-5/8"	30"	17-5/8"	30" ₂ - 104	N/A	N/A	N/A	N/A




Specimen **B-2**
Behavior of Lap Splices of No. 11
Reinforcing Bars



Sheet: 1 of 4

Drawn by: **VAM** Checked by: **BPR**

Date: 6-22-12




Top Plan
2 Spa. @



Profile


*For section B-B through F-F see Sheet 3 of 3




Bottom Plan



Drawing:	Series A Concrete As-builts	Sheet:	2	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		




Top Plan



Profile


*For section B-B through F-F see Sheet 3 of 3



Bottom Plan



Drawing:	Series B Concrete As-builts	Sheet:	3	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		



Section B-B, C-C, D-D, E-E & F-F
*Facing North




Drawing:	Concrete As-built Sections	Sheet:	4	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

Project: Tests to Determine the Behavior of Spliced #11 Bars

As-built Dimensions v.1
(Rev. 04/04/2012)


Specimen: B-2

Sheet 1 of 2


Section	Formwork As-built Dimensions							
	1	2	3	4	5	6	7	8
A-A	166 ⁵ / ₈	78 ⁷ / ₈	166 ⁷ / ₈	166 ⁵ / ₈	78 ¹⁵ / ₁₆	166 ³ / ₄		
B-B	4 ³ / ₈	9 ¹ / ₈	4 ³ / ₈	23 ⁵ / ₈	30 ¹/₈ 23 ⁵ / ₈	30 ¹ / ₈	30 ³ / ₁₆	17 ¹ / ₂
C-C	3	6 ¹ / ₁₆	3 ¹ / ₁₆	23 ⁹ / ₁₆	23 ³ / ₄	30 ¹ / ₈	30 ¹ / ₈	17 ⁷ / ₁₆
D-D	3 ¹ / ₁₆	6 ¹ / ₈	3 ¹ / ₁₆	23 ⁵ / ₈	23 ¹³ / ₁₆	30 ¹ / ₈	30 ¹ / ₈	17 ⁷ / ₁₆
E-E	3 ¹ / ₁₆	6	3 ¹ / ₁₆	23 ⁹ / ₁₆	23 ⁵ / ₈	30 ³ / ₁₆	30 ¹ / ₈	17 ⁷ / ₁₆
F-F	3 ¹ / ₁₆	8 ³ / ₄	3 ³ / ₁₆	23 ⁹ / ₁₆	23 ⁹ / ₁₆	30 ³ / ₁₆	30 ³ / ₁₆	17 ⁷ / ₁₆
Recorded by:			Signature				Date	Time
KAM			D L L				4-8-12	11:5 PM
Checked by:			Signature				Date	Time
WHP							4/8/2012	11:30 PM
Checked by:			Signature				Date	Time

Comments:

*See formwork as-built drawings for dimension locations



Section A-A





*For section B-B through F-F see Sheet 3 of 3

Series A



Drawing:	Series A Formwork As-builts	Sheet:	1	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		




*For section B-B through F-F see Sheet 3 of 3

Series B



Drawing:	Series B Formwork As-builts	Sheet:	2	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		



Section C-C, D-D, & E-E
*Facing North

Section B-B & F-F
*Facing North



Drawing:	Formwork As-built Sections	Sheet:	3	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

Project: Tests to Determine the
Behavior of Spliced #11 BarsCasting Documentation v.1
(Rev. 03/30/2012)Specimen: B-23

Sheet 1 of 1

General Information					
Date	Disp Ticket Num	Truck No.	Time on Ticket	Time of Arrival	Temp. in Lab
4/10/12	1858861	1839	2:54	3:05	58°F
Measurements made upon arrival of concrete					
Slump (ASTM C143 - 10a)		Air Content (ASTM C231 - 10)			
Time ₁	Result ₁	Time ₁	Result ₁	S/N of Air Meter	
3:12	8 3/4"	3:18	4.8%	4130786891	
Time ₂	Result ₂	Time ₂	Result ₂	S/N of Scale	
3:39	8"	3:47	4.8%	06746056 HM	
Unit Weight (ASTM C138 - 10b)					
Time ₁	Wt. of Cont. ₁	Total Wt. ₁	Wt. of Conc. ₁	Result ₁ = Wt. of Conc./Vol. of Cont.	
3:16	8.5#	44.3			
Time ₂	Wt. of Cont. ₂	Total Wt. ₂	Wt. of Conc. ₂	Result ₂ = Wt. of Conc./Vol. of Cont.	
	8.5#	44.6			
Times of actions during and after casting					
Layer 1 placed	Layer 1 vibration complete	Layer 2 placed	Layer 2 vibration complete	Top surface struck off	Truck Departing Lab
3:12	✓	✓	✓	✓	3:33
Lifting Inserts Placed	Covered with plastic	Plastic removed	Covered with burlap	Burlap doused with water	Covered with plastic
4:10 PM	4:15 PM	✓	✓	✓	8:35
Recorded by	Signature		Date	Time	
B. R.	<i>[Signature]</i>		4/10/12	3:50 PM	
Checked by	Signature		Date	Time	
S. P.	<i>[Signature]</i>		4/10/12	3:50 PM	
Checked by	Signature		Date	Time	
<i>[Signature]</i>	SAM WORTH		4/10/12	3:47 PM	
Comments: Spread 14" 3 layers + topping Concrete Temp. 60°F Cyl. 1 insertion of vibrator Made from 2nd (Mid) 1/3					
*The following ASTM standards and specifications will be followed during casting: C172-10, C192-07, C470-09					

Truck	Driver	User	Disp Ticket Num	Ticket ID	Time	Date
1839	2463	user	1858861	0	14:54	4/10/12
Load Size	Mix Code	Returned	Qty	Mix Age	Seq	Load ID
5.75 CYDS	1008				D	985

Material	Design Qty	Required	Batched	% Var	% Moisture	Actual	Wat
STONE-8	940 lb ✓	5405 lb	5360 lb	-0.83%	M		
STONE-4	620 lb ✓	3565 lb	3580 lb	0.42%			
SAND-23	1435 lb ✓	8664 lb	8640 lb	-0.27%	5.00%M	49 gl	
CEMENT	588 lb ✓	3391 lb	3380 lb	-0.03%			
WATER	323.2 lb	1445.8 lb	1436.0 lb	-0.68%		172.1 gl	
AIR	.80 fC ✓	27.05 oz	26.50 oz	-2.03%			

3

Actual Load	2238 lb	Design W/C:	0.550	Water/Cement:	0.550 ✓ T	Design	222.7 gl	Actual	221.4 gl	To Add:	1.3 gl
Slump:	6.00 in	#	Water In Truck:	0.0 lb	Adjust Water:	0.0 lb / Load	Trim Water:	0.0 lb /	CYC		

Concrete Delivery Ticket



Plant #	Ticket Number	Truck	Load Size	Mix	Slump	Use	Date	Customer
---------	---------------	-------	-----------	-----	-------	-----	------	----------

15	1858861	1839	3.75cy	1008	E:00		04/10/17	1809
----	---------	------	--------	------	------	--	----------	------

Sold To	Tax Code	Driver	Project No.	Order No.
---------	----------	--------	-------------	-----------

CHARGE CARD - BOWEN LAB IN DANNY SMITH 0003 5 1809

Delivery Address	P.O. Number
------------------	-------------

BOWEN CIVIL ENGINEERING LAB 112-33-0119

TRUCK RELEASE Job No. 1809

3

Load Quantity	Total	Ordered Quantity	Product Code	Product Description	Unit Price	Amount
---------------	-------	------------------	--------------	---------------------	------------	--------

3.75 17.25cy 17.25cy 1008 PURDUE EXPERIMENTAL 80.00 511275



Water Added At Customer's Request	Total No. Gallons	Slump Meter Reading
-----------------------------------	-------------------	---------------------

On Job Time	Finish Pour Time
-------------	------------------

Subtotal 325.25
 Tax 325.25
 Total 650.50

PROPERTY DAMAGE RELEASE / WARNING - Irritating To The Skin and Eyes

Dear Customer - The Seller is not responsible for slumps, strength or quality of concrete to which water or any other material has been added by the purchaser or at his request. The undersigned hereby authorizes Irving Materials, Inc. to use private property for making the delivery shown here on and assumes full responsibility for any damage or injury due to the premises. The undersigned agrees to reimburse said Company for loss of time and equipment by reason of such delivery and also to identify and save harmless said Company from any and all claims, demands and suits for or on account of or in any manner caused by or arising from private property delivery. The undersigned assumes responsibility for a suitable roadway from public highway to point of delivery and is responsible for any needed wrecker service charges as a result. SAFETY WARNING: Keep away from children. Contains Portland Cement. Irritating to the skin and eyes. Wear rubber boots, gloves and eye protection. Prolonged contact may cause burns. In case of contact with skin or eyes, flush thoroughly with water. If irritation persists, get medical attention. For additional information regarding the HAZARDS OF READY MIX CONCRETE, consult the Material Data Safety Sheet (MSDS) available upon request. PRODUCT NOTICE: Seller will not be held responsible for the final appearance of exposed aggregate, integral coloring, stamped and decorative surfacing, and all other forms of architectural and design concrete. DELIVERY NOTICE: Seller assumes no responsibility for deliveries beyond the public right of way. Buyer assumes responsibility for damages including but not limited to curb, sidewalk, driveway, or any property of the contractor or property owner or agents. NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE SAFETY AND HEALTH WARNING NOTICE AND ACCEPTANCE OF THE LOAD.

Release, Load and Terms Accepted By:



Concrete Delivery Ticket



Plant #	Ticket Number	Truck	Load Size	Mix	Slump	Use	Date	Customer
---------	---------------	-------	-----------	-----	-------	-----	------	----------

18	1858861	1839	5.75cy	1008	5.00		04/10/12	16091
Sold To					Tax Code	Driver	Project No.	Order No.
CHARGE CARD - BOWEN LAB					IN	DANNY SMTH	2463 5	1801

Delivery Address	P.O. Number
------------------	-------------

BOWEN CIVIL ENGINEERING LAB
 TRUCK RELEASE
 Job No. 3
 Time Printed 14:54

Load Quantity	Total	Ordered Quantity	Product Code	Product Description	Unit Price	Amount
---------------	-------	------------------	--------------	---------------------	------------	--------

5.75	17.25cy	17.25cy	1008	PURDUE EXPERIMENTAL	89.00	511.75
------	---------	---------	------	---------------------	-------	--------



Water Added At Customer's Request	Total No. Gallons	Slump Meter Reading	Subtotal	523.25
On Job Time	Finish Pour Time	Auth. #:	Grand Total:	1,569.75
			Total	523.25

PROPERTY DAMAGE RELEASE / WARNING - Irritating To The Skin and Eyes

Dear Customer - The Seller is not responsible for slumps, strength or quality of concrete to which water or any other material has been added by the purchaser or at his request. The undersigned hereby authorizes Irving Materials, Inc. to use private property for making the delivery shown here on and assumes full responsibility for any damage or injury due to the premises. The undersigned agrees to reimburse said Company for loss of time and equipment by reason of such delivery and also to identify and save harmless said Company from any and all claims, demands and suits for or on account of or in any manner caused by or arising from private property delivery. The undersigned assumes responsibility for a suitable roadway from public highway to point of delivery and is responsible for any needed wrecker service charges as a result. SAFETY WARNING: Keep away from children. Contains Portland Cement. Irritating to the skin and eyes. Wear rubber boots, gloves and eye protection. Prolonged contact may cause burns. In case of contact with skin or eyes, flush thoroughly with water. If irritation persists, get medical attention. For additional information regarding the HAZARDS OF READY MIX CONCRETE, consult the Material Data Safety Sheet (MSDS) available upon request. PRODUCT NOTICE: Seller will not be held responsible for the final appearance of exposed aggregate, integral coloring, stamped and decorative surfacing, and all other forms of architectural and design concrete. DELIVERY NOTICE: Seller assumes no responsibility for deliveries beyond the public right of way. Buyer assumes responsibility for damages including but not limited to curb, sidewalk, driveway, or any property of the contractor or property owner or agents. NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE SAFETY AND HEALTH WARNING NOTICE AND ACCEPTANCE OF THE LOAD.

Release, Load and Terms Accepted By:



Project: Tests to Determine the Behavior of Spliced #11 Bars

Setup and As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: B-3

Sheet 1 of 2

Section	Concrete As-built Dimensions							
	1	2	3	4	5	6	7	8
Plan	34'-4 1/8"	34'- 4	34'-4 1/4"	34'-4"				
B-B	17-3/4"	30-1/8"	30-1/8"	17-5/8"				
C-C	17-3/4"	30-1/8"	30-1/8"	17-5/8"				
D-D	17-3/4"	30-1/8"	30-1/8"	17-5/8"				
E-E	17-3/4"	30-1/8"	30-3/16"	17-5/8"				
F-F	17-3/4"	30-3/16"	30-3/16"	17-5/8"				
Recorded by:			Signature				Date	Time
KAM			KLL				5-19-12	4:10pm
Checked by:			Signature				Date	Time
BPR			[Signature]				5/19/12	4:10PM
Checked by:			Signature				Date	Time

Comments:

*See concrete as-built drawings for dimension locations


Project: Tests to Determine the
Behavior of Spliced #11 Bars

Setup and As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: B-3

Sheet 2 of 2

Section	Concrete As-built Dimensions Key - Series A							
	1	2	3	4	5	6	7	8
Plan	39'-0"	39'-0"	39'-0"	39'-0"	N/A	N/A	N/A	N/A
B-B	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
C-C	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
D-D	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
E-E	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
F-F	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
Section	Concrete As-built Dimensions Key - Series B							
	1	2	3	4	5	6	7	8
Plan	34'-4"	34'-4"	34'-4"	34'-4"	N/A	N/A	N/A	N/A
B-B	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
C-C	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
D-D	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
E-E	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
F-F	17-5/8"	30"	17-5/8"	30" ₂ - 118	N/A	N/A	N/A	N/A





Specimen B-3

Behavior of Lap Splices of No. 11
Reinforcing Bars


Sheet: 1 of 4

Drawn by: KAM Checked by: BVR



Date: 5-19-12




*For section B-B through F-F see Sheet 3 of 3




Drawing:	Series A Concrete As-builts	Sheet:	2	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		



*For section B-B through F-F see Sheet 3 of 3



Drawing:	Series B Concrete As-builts	Sheet:	3	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		



Section B-B, C-C, D-D, E-E & F-F
*Facing North



Drawing:	Concrete As-built Sections	Sheet:	4	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

Project: Tests to Determine the Behavior of Spliced #11 Bars

As-built Dimensions v.1
(Rev. 04/04/2012)


Specimen: B-3

Sheet 1 of 2


Section	Formwork As-built Dimensions								
	1	2	3	4	5	6	7	8	
A-A	166 ^{3/4}	78 ^{7/8}	166 ^{3/8}	166 ^{1/8}	75 ^{1/16}	166 ^{3/16}			
B-B	4 ^{7/16}	6	4 ^{1/2}	23 ^{3/4}	23 ^{1/2}	30	30 ^{1/16}	17 ^{3/8}	
C-C	3	6 ^{1/16}	3 ^{1/16}	23 ^{3/4}	23 ^{3/16}	30 ^{1/8}	30 ^{1/8}	17 ^{7/16}	
D-D	2 ^{15/16}	6 ^{1/16}	3	23 ^{3/4}	23 ^{5/8}	30 ^{1/16}	30 ^{1/16}	17 ^{7/16}	
E-E	3	5 ^{15/16}	3 ^{1/16}	23 ^{5/8}	23 ^{3/4}	30 ^{1/8}	30 ^{1/8}	17 ^{1/2}	
F-F	2 ^{15/16}	9	3 ^{1/16}	23 ^{1/2}	23 ^{3/4}	30 ^{1/8}	30 ^{1/8}	17 ^{1/2}	
Recorded by:		Signature				Date		Time	
KAM		JLL				4-8-12		11:15 PM	
Checked by:		Signature				Date		Time	
WHP		[Signature]				4/8/2012		11:30 PM	
Checked by:		Signature				Date		Time	

Comments:

*See formwork as-built drawings for dimension locations



Section A-A





*For section B-B through F-F see Sheet 3 of 3

Series A



Drawing:	Series A Formwork As-builts	Sheet:	1	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		




*For section B-B through F-F see Sheet 3 of 3

Series B



Drawing:	Series B Formwork As-builts	Sheet:	2	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		



Section C-C, D-D, & E-E
*Facing North

Section B-B & F-F
*Facing North



Drawing:	Formwork As-built Sections	Sheet:	3	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

Project: Tests to Determine the
Behavior of Spliced #11 BarsCasting Documentation v.1
(Rev. 03/30/2012)Specimen: B-4

Sheet 1 of 1

General Information					
Date	Disp Ticket Num	Truck No.	Time on Ticket	Time of Arrival	Temp. in Lab
4/30	1859311	1982	13:50	2:05PM	70°F
Measurements made upon arrival of concrete					
Slump (ASTM C143 - 10a)		Air Content (ASTM C231 - 10)			
Time ₁	Result ₁	Time ₁	Result ₁	S/N of Air Meter	
2:15 PM	5 1/4"	2:26	4.3	4130786891	
Time ₂	Result ₂	Time ₂	Result ₂	S/N of Scale	
	3 1/4"	2:48	4.0	06746056HM	
Unit Weight (ASTM C138 - 10b)					
Time ₁	Wt. of Cont. ₁	Total Wt. ₁	Wt. of Conc. ₁	Result ₁ = Wt. of Conc./Vol. of Cont.	
2:24	8.5#	45.0	36.5	146 #/cft.	
Time ₂	Wt. of Cont. ₂	Total Wt. ₂	Wt. of Conc. ₂	Result ₂ = Wt. of Conc./Vol. of Cont.	
	8.5#	45.4	36.9	147.6 #/cft.	
Times of actions during and after casting					
Layer 1 placed	Layer 1 vibration complete	Layer 2 placed	Layer 2 vibration complete	Top surface struck off	Truck Departing Lab
2:24	2:30	2:33	2:37	2:40	2:40PM
Lifting Inserts Placed	Covered with plastic	Plastic removed	Covered with burlap	Burlap doused with water	Covered with plastic
2:40	2:45	9:45 PM	9:50 PM	9:55 PM	10:00 PM
Recorded by		Signature		Date	Time
BPR		Mr. White		4/30	4:25PM
Checked by		Signature		Date	Time
Checked by		Signature		Date	Time
SAWORTHY		SAWORTHY		4/30/12	4:10
Comments: 2:25 PM Temp 71.5°					
*The following ASTM standards and specifications will be followed during casting: C172-10, C192-07, C470-09					

Truck	Driver	User	Disp Ticket Num	Ticket ID	Time	Date
1982	1076	user	1859311	0	13:50	4/30/12
Load Size	Mix Code	Returned	Qty	Mix Age	Seq	Load ID
5.75 CYDS	1008				D	1436

Material	Design Qty	Required	Batched	% Var	% Moisture	Actual	Wet
STONE-8	940 lb	5454 lb	5400 lb	-0.98%	0.90% M	6 gl	
STONE-4	620 lb	3586 lb	3560 lb	-0.74%	0.60% M	3 gl	
SAND-23	1435 lb	8804 lb	8780 lb	-0.27%	6.70% M	66 gl	
CEMENT	588 lb	3381 lb	3370 lb	-0.33%			
WATER	323.2 lb	861.8 lb	852.0 lb	-1.13%		102.1 gl	
AIR	.80 /C	27.05 oz	26.50 oz	-2.03%			

Actual	Num Batches: 1								
Load	21964 lb	Design W/C: 0.550	Water/Cement: 0.552 T	Design	222.7 gl	Actual	176.5 gl	To Add:	46.2 gl
Slump:	4.00 in	Water in Truck:	0.0 lb	Adjust Water:	0.0 lb / Load	Trim Water:	-85.0 lb /	CYL	

1 B-4

Concrete Delivery Ticket



Plant #	Ticket Number	Truck	Load Size	Mix	Slump	Use	Date	Customer
---------	---------------	-------	-----------	-----	-------	-----	------	----------

10	1859311	1982	5.75cy	1008	1.00	TEST	04/30/12	18091
----	---------	------	--------	------	------	------	----------	-------

Sold To	Tax Code	Driver	Project No.	Order No.
---------	----------	--------	-------------	-----------

BE CARD - LAFAYETTE & WTNAMA	IN	DOUG PHEBUS	1076	5 1815
------------------------------	----	-------------	------	--------

Delivery Address	P.O. Number
------------------	-------------

DOWEN CIVIL ENGINEERING LAB TRUCK RELEASE SON2548

TRUCK RELEASE BRIAN Job No: SON2548

Time Printed 13:44

Load Quantity	Total	Ordered Quantity	Product Code	Product Description	Unit Price	Amount
---------------	-------	------------------	--------------	---------------------	------------	--------

5.75	5.75cy	17.25cy	1008	PURDUE EXPERIMENTAL	89.00	511.75
------	--------	---------	------	---------------------	-------	--------


 www.irvmat.com
 Environmental Fee
 45.0
 45.0
 1 B-4
 11.50

Water Added At Pumper's Request	Total No. Gallons	Slump Meter Reading	Subtotal
------------------------------------	----------------------	------------------------	----------

On Job Time	Finish Pour Time	YTH. #:	Grand Total	Subtotal	Tax	Total
-------------	------------------	---------	-------------	----------	-----	-------

PROPERTY DAMAGE RELEASE / WARNING - Irritating To The Skin and Eyes

Dear Customer - The Seller is not responsible for slumps, strength or quality of concrete to which water or any other material has been added by the purchaser or at his request. The undersigned hereby authorizes Irving Materials, Inc. to use private property for making the delivery shown here on and assumes full responsibility for any damage or injury due to the premises. The undersigned agrees to reimburse said Company for loss of time and equipment by reason of such delivery and also to identify and save harmless said Company from any and all claims, demands and suits for or on account of or in any manner caused by or arising from private property delivery. The undersigned assumes responsibility for a suitable roadway from public highway to point of delivery and is responsible for any needed wrecker service charges as a result. SAFETY WARNING: Keep away from children. Contains Portland Cement. Irritating to the skin and eyes. Wear rubber boots, gloves and eye protection. Prolonged contact may cause burns. In case of contact with skin or eyes, flush thoroughly with water. If irritation persists, get medical attention. For additional information regarding the HAZARDS OF READY MIX CONCRETE, consult the Material Data Safety Sheet (MSDS) available upon request. PRODUCT NOTICE: Seller will not be held responsible for the final appearance of exposed aggregate, integral coloring, stamped and decorative surfacing, and all other forms of architectural and design concrete. DELIVERY NOTICE: Seller assumes no responsibility for deliveries beyond the public right of way. Buyer assumes responsibility for damages including but not limited to curb, sidewalk, driveway, or any property of the contractor or property owner or agents. NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE SAFETY AND HEALTH WARNING NOTICE AND ACCEPTANCE OF THE LOAD.

Release, Load and Terms Accepted By:
 [Signature]



Project: Tests to Determine the Behavior of Spliced #11 Bars

Setup and As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: B4 Sheet 1 of 2

Section	Concrete As-built Dimensions								
	1	2	3	4	5	6	7	8	
Plan	34'-4"	34'-4"	34'-4"	34'-4"					
B-B	17 ⁹ / ₁₆	30	17 ⁵ / ₈	30' ¹ / ₁₆					
C-C	17 ⁵ / ₈	30 ¹ / ₁₆	17 ⁵ / ₈	30' ¹ / ₁₆					
D-D	17 ⁵ / ₈	30	17 ⁵ / ₈	30' ¹ / ₁₆					
E-E	17 ⁹ / ₁₆	30	17 ⁵ / ₈	30' ¹ / ₁₆					
F-F	17 ⁵ / ₈	30	17 ⁵ / ₈	30' ¹ / ₁₆					
Recorded by:		Signature				Date		Time	
MA Sozen		Nate Aspin				11 May 2012		12:05 PM	
Checked by:		Signature				Date		Time	
S. Pujol		S. Pujol				11 May 12		12:20 PM	
Checked by:		Signature				Date		Time	

Comments: Jacks w. Load Cells: N → 22
S → 11

*See concrete as-built drawings for dimension locations


Project: Tests to Determine the
Behavior of Spliced #11 Bars

Setup and As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: B4

Sheet 2 of 2

Section	Concrete As-built Dimensions Key - Series A							
	1	2	3	4	5	6	7	8
Plan	39'-0"	39'-0"	39'-0"	39'-0"	N/A	N/A	N/A	N/A
B-B	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
C-C	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
D-D	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
E-E	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
F-F	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
Section	Concrete As-built Dimensions Key - Series B							
	1	2	3	4	5	6	7	8
Plan	34'-4"	34'-4"	34'-4"	34'-4"	N/A	N/A	N/A	N/A
B-B	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
C-C	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
D-D	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
E-E	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
F-F	17-5/8"	30"	17-5/8"	30" ² - 131	N/A	N/A	N/A	N/A



Specimen B-4

Behavior of Lap Splices of No. 11 Reinforcing Bars

Sheet:

1

of

4

Drawn by:


BPR

Checked by:

AK


Date:

5/14/12




Top Plan

2 Spa. @



Profile


*For section B-B through F-F see Sheet 3 of 3




Bottom Plan



Drawing:	Series A Concrete As-builts	Sheet:	2	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		




Top Plan



Profile


*For section B-B through F-F see Sheet 3 of 3




Bottom Plan



Drawing:	Series B Concrete As-builts	Sheet:	3	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		



Section B-B, C-C, D-D, E-E & F-F
*Facing North





Drawing:	Concrete As-built Sections	Sheet:	4	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

Project: Tests to Determine the Behavior of Spliced #11 Bars

As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: B-4

Sheet 1 of 2

Section	Formwork As-built Dimensions								
	1	2	3	4	5	6	7	8	
A-A	166 $\frac{3}{8}$	79 $\frac{1}{16}$	166 $\frac{1}{4}$	166 $\frac{1}{4}$	78 $\frac{15}{16}$	166 $\frac{3}{8}$			
B-B	4 $\frac{7}{16}$	6 $\frac{3}{8}$	4 $\frac{3}{16}$	23 $\frac{5}{8}$	23 $\frac{11}{16}$	30 $\frac{1}{8}$	30 $\frac{1}{16}$	17 $\frac{1}{2}$	
C-C	3-0	6 $\frac{3}{16}$	2 $\frac{13}{16}$	23 $\frac{3}{4}$	23 $\frac{3}{4}$	30 $\frac{1}{8}$	30 $\frac{1}{16}$	17 $\frac{9}{16}$	
D-D	3 $\frac{3}{16}$	6-0	2 $\frac{15}{16}$	23 $\frac{7}{8}$	23 $\frac{7}{8}$	30 $\frac{1}{16}$	30 $\frac{1}{16}$	17 $\frac{7}{16}$	
E-E	3 $\frac{3}{16}$	5 $\frac{15}{16}$	3-0	23 $\frac{3}{4}$	23 $\frac{5}{8}$	30 $\frac{1}{16}$	30 $\frac{1}{8}$	17 $\frac{7}{16}$	
F-F	3 $\frac{1}{8}$	8 $\frac{13}{16}$	3 $\frac{1}{16}$	23 $\frac{9}{16}$	23 $\frac{5}{8}$	30 $\frac{1}{16}$	30 $\frac{1}{16}$	17 $\frac{1}{2}$	
Recorded by:			Signature			Date		Time	
TD						5/1 4/30		9:30AM	
Checked by:			Signature			Date		Time	
BPR						4/30		9:30AM	
Checked by:			Signature			Date		Time	

Comments:

*See formwork as-built drawings for dimension locations


Project: Tests to Determine the
Behavior of Spliced #11 Bars

As-built Dimensions v.1
(Rev. 04/04/2012)


Specimen: B-4

Sheet 2 of 2

Section	Formwork As-built Dimensions Key - Series A							
	1	2	3	4	5	6	7	8
A-A	14'-6"	10'-0"	14'-6"	14'-6"	10'-0"	14'-6"	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
D-D	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
E-E	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
F-F	3"	8-3/4"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
Section	Formwork As-built Dimensions Key - Series B							
	1	2	3	4	5	6	7	8
A-A	13'-10.5"	6'-7"	13'-10.5"	13'-10.5"	6'-7"	13'-10.5"	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
D-D	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
E-E	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
F-F	3"	8-3/4"	3"	23-5/8" 2-137	23-5/8"	30"	30"	17-5/8"




Section A-A





*For section B-B through F-F see Sheet 3 of 3

Series A




Drawing:	Series A Formwork As-builts	Sheet:	1	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		




*For section B-B through F-F see Sheet 3 of 3



Drawing:	Series B Formwork As-builts	Sheet:	2	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		



Section C-C, D-D, & E-E
*Facing North



Section B-B & F-F
*Facing North



Drawing:	Formwork As-built Sections	Sheet:	3	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

Project: Tests to Determine the
Behavior of Spliced #11 BarsCasting Documentation v.1
(Rev. 03/30/2012)Specimen: B-5

Sheet 1 of 1

General Information					
Date	Disp Ticket Num	Truck No.	Time on Ticket	Time of Arrival	Temp. in Lab
4/30	1859313	1982	14:54	3:05PM	70°F
Measurements made upon arrival of concrete					
Slump (ASTM C143 - 10a)		Air Content (ASTM C231 - 10)			
Time ₁	Result ₁	Time ₁	Result ₁	S/N of Air Meter	
3:14	6 1/4"	3:20	4.8	4130786891	
Time ₂	Result ₂	Time ₂	Result ₂	S/N of Scale	
3:34 pm	7"	3:41	4.6	06746056 HM	
Unit Weight (ASTM C138 - 10b)					
Time ₁	Wt. of Cont. ₁	Total Wt. ₁	Wt. of Conc. ₁	Result ₁ = Wt. of Conc./Vol. of Cont.	
3:18	8.5#	44.9	36.4#	145.6#/cft.	
Time ₂	Wt. of Cont. ₂	Total Wt. ₂	Wt. of Conc. ₂	Result ₂ = Wt. of Conc./Vol. of Cont.	
3:39	8.5#	44.5	36.0#	144#/cft.	
Times of actions during and after casting					
Layer 1 placed	Layer 1 vibration complete	Layer 2 placed	Layer 2 vibration complete	Top surface struck off	Truck Departing Lab
3:20 pm	3:22 pm	3:26 pm	3:28 pm	✓	✓
Lifting Inserts Placed	Covered with plastic	Plastic removed	Covered with burlap	Burlap doused with water	Covered with plastic
3:24 pm 3:24 pm	3:26	10:00 pm	10:05 pm	10:10 pm	10:15 pm
Recorded by	Signature		Date	Time	
BPR	<i>[Signature]</i>		4/30	4:25 PM	
Checked by	Signature		Date	Time	
Checked by	Signature		Date	Time	
SAWORTHY	<i>[Signature]</i>		4/30/12	4:10	
Comments: 3:18 Temp 69.2%					

*The following ASTM standards and specifications will be followed during casting: C172-10, C192-07, C470-09

Truck	Driver	User	Disp Ticket Num	Ticket ID	Time	Date
1982	1076	user	1859313	1327	14:54	4/30/12
Load Size	Mix Code	Returned	Qty	Mix Age	Seq	Load ID
5.75 CYDS	1008				D	1437
Material	Design Qty	Required	Batched	% Var	% Moisture	Actual Wat
STONE-8	940 lb	5454 lb	5400 lb	-0.98%	0.90% M	6 gl
STONE-4	620 lb	3586 lb	3560 lb	-0.74%	0.60% M	3 gl
SAND-23	1435 lb	8804 lb	8800 lb	-0.05%	6.70% M	66 gl
CEMENT	588 lb	3381 lb	3375 lb	-0.18%		
WATER	323.2 lb	1235.5 lb	1226.0 lb	-0.77%		146.9 gl
AIR	.80 /C	27.05 oz	27.00 oz	* -0.18%		
Actual	Num Batches: 1					
Load Total:	22363 lb	Design 0.550 Water/Cement	0.551 T	Design 222.7 gl	Actual 221.4 gl	To Add: 1.3 gl
Slump:	4.00 in	Water in Truck: 0.0 lb	Adjust Water: 0.0 lb / Load	Trim Water: 0.0 lb/ CYD		

2-B-5

Concrete Delivery Ticket



Plant#	Ticket Number	Truck	Load Size	Mix	Slump	Use	Date	Customer
10	1859313	1982	5.75cy	100B	4.00	TEST	04/30/12	16091
Sold To				Tax Code	Driver		Project No.	Order No.
RBE CARD - LAFAYETTE & WINAMA				IN	DOUG PHEBUS		1076 5	1815
Delivery Address							P.O. Number	

BOWEN CIVIL ENGINEERING LAB TRUCK RELEASE
 TRUCK RELEASE BRIAN

SCN2548
 Job No: CN2548

Time Printed 14:48

Load Quantity	Total	Ordered Quantity	Product Code	Product Description	Unit Price	Amount
3.14	11.50cy	6 1/4"	3.20	7.8		
5.75	11.50cy	17.25cy	100B	PURDUE EXPERIMENTAL	89.00	511.75
3.34		7.0"	3.41	4.62-P-S		
3.18						
3.39			44.5	Environmental Fee		11.50

Water Added At Driver's Request		Total No. Gallons	Slump Meter Reading					Subtotal	523.25
On Job Time	Finish Pour Time	AUTH. #:	Grand Total:	1,046.50	Tax	Total	523.25		


PROPERTY DAMAGE RELEASE / WARNING - Irritating To The Skin and Eyes

Dear Customer - The Seller is not responsible for slumps, strength or quality of concrete to which water or any other material has been added by the purchaser or at his request. The undersigned hereby authorizes Irving Materials, Inc. to use private property for making the delivery shown here on and assumes full responsibility for any damage or injury due to the premises. The undersigned agrees to reimburse said Company for loss of time and equipment by reason of such delivery and also to identify and save harmless said Company from any and all claims, demands and suits for or on account of or in any manner caused by or arising from private property delivery. The undersigned assumes responsibility for a suitable roadway from public highway to point of delivery and is responsible for any needed wrecker service charges as a result. SAFETY WARNING: Keep away from children. Contains Portland Cement. Irritating to the skin and eyes. Wear rubber boots, gloves and eye protection. Prolonged contact may cause burns. In case of contact with skin or eyes, flush thoroughly with water. If irritation persists, get medical attention. For additional information regarding the HAZARDS OF READY MIX CONCRETE, consult the Material Data Safety Sheet (MSDS) available upon request. PRODUCT NOTICE: Seller will not be held responsible for the final appearance of exposed aggregate, integral coloring, stamped and decorative surfacing, and all other forms of architectural and design concrete. DELIVERY NOTICE: Seller assumes no responsibility for deliveries beyond the public right of way. Buyer assumes responsibility for damages including but not limited to curb, sidewalk, driveway, or any property of the contractor or property owner or agents. NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE SAFETY AND HEALTH WARNING NOTICE AND ACCEPTANCE OF THE LOAD.

Release, Load and Terms Accepted By: *[Signature]*



Sawdust
3:18
Temp



Project: Tests to Determine the Behavior of Spliced #11 Bars

Setup and As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: B-5

Sheet 1 of 2

Section	Concrete As-built Dimensions							
	1	2	3	4	5	6	7	8
Plan	34' - 3 ⁵ / ₈ "	34' - 3 ³ / ₄ "	34' - 4"	34' - 3 ⁷ / ₈ "				
B-B	17 - 5 ¹ / ₈ "	30 - 1 ¹ / ₁₆ "	17 - 1 ¹ / ₁₆ "	30 - 1 ¹ / ₈ "				
C-C	17 - 5 ¹ / ₈ "	30 - 1 ¹ / ₈ "	17 - 5 ¹ / ₈ "	30 - 1 ¹ / ₈ "				
D-D	17 - 5 ¹ / ₈ "	30 - 1 ¹ / ₈ "	17 - 5 ¹ / ₈ "	30 - 1 ¹ / ₈ "				
E-E	17 - 9 ¹ / ₁₆ "	30 - 1 ¹ / ₈ "	17 - 5 ¹ / ₈ "	30 - 1 ¹ / ₁₆ "				
F-F	17 - 1 ¹ / ₁₆ "	30 - 1 ¹ / ₈ "	17 - 5 ¹ / ₈ "	30 - 1 ¹ / ₈ "				
Recorded by:			Signature				Date	Time
KAM			[Signature]				5-16-12	
Checked by:			Signature				Date	Time
BPR			[Signature]				5/16/12	11:00AM
Checked by:			Signature				Date	Time

Comments:


Project: Tests to Determine the
Behavior of Spliced #11 Bars

Setup and As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: _____

Sheet 2 of 2

Section	Concrete As-built Dimensions Key - Series A							
	1	2	3	4	5	6	7	8
Plan	39'-0"	39'-0"	39'-0"	39'-0"	N/A	N/A	N/A	N/A
B-B	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
C-C	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
D-D	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
E-E	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
F-F	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
Section	Concrete As-built Dimensions Key - Series B							
	1	2	3	4	5	6	7	8
Plan	34'-4"	34'-4"	34'-4"	34'-4"	N/A	N/A	N/A	N/A
B-B	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
C-C	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
D-D	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
E-E	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
F-F	17-5/8"	30"	17-5/8"	30" ₂ - 145	N/A	N/A	N/A	N/A



Specimen B-5

Behavior of Lap Splices of No. 11
Reinforcing Bars

Sheet:

1

of

4

Drawn by:


WAM

Checked by:


BPR

Date:


5-16-12





*For section B-B through F-F see Sheet 3 of 3



Drawing:	Series A Concrete As-builts	Sheet:	2	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		




Top Plan



Profile


*For section B-B through F-F see Sheet 3 of 3



Bottom Plan



Drawing:	Series B Concrete As-builts	Sheet:	3	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		



Section B-B, C-C, D-D, E-E & F-F
*Facing North



Drawing:	Concrete As-built Sections	Sheet:	4	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

Project: Tests to Determine the Behavior of Spliced #11 Bars

As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: B-5 Sheet 1 of 2

Section	Formwork As-built Dimensions							
	1	2	3	4	5	6	7	8
A-A	$166 - \frac{3}{8}$	$79 - \frac{1}{16}$	$166 - \frac{1}{4}$	$166 - \frac{1}{4}$	$79 - 0$	$166 - \frac{3}{8}$		
B-B	$4 \frac{3}{8}$	$6 \frac{3}{16}$	$4 \frac{3}{8}$	$23 \frac{5}{8}$	$23 \frac{9}{16}$	$30 \frac{1}{8}$	$30 \frac{1}{8}$	$17 \frac{1}{2}$
C-C	$3 - 0$	$6 \frac{3}{16}$	$2 \frac{15}{16}$	$23 \frac{5}{8}$	$23 \frac{5}{8}$	$30 \frac{1}{16}$	$30 \frac{1}{16}$	$17 \frac{1}{2}$
D-D	$3 - \frac{1}{16}$	$6 \frac{3}{16}$	$2 \frac{15}{16}$	$23 \frac{3}{4}$	$23 \frac{3}{4}$	$30 \frac{1}{16}$	$30 \frac{1}{16}$	$17 \frac{7}{16}$
E-E	$3 \frac{1}{8}$	$6 - 0$	$3 - 0$	$23 \frac{11}{16}$	$23 \frac{11}{16}$	$30 \frac{1}{8}$	$30 \frac{1}{8}$	$17 \frac{7}{16}$
F-F	$3 - \frac{1}{8}$	$8 \frac{3}{4}$	$3 - 0$	$23 \frac{5}{8}$	$23 \frac{5}{8}$	$30 \frac{1}{16}$	$30 \frac{1}{8}$	$17 \frac{7}{16}$
Recorded by:			Signature			Date		Time
BPR			<i>Mr. Hite</i>			4/30		9:50AM
Checked by:			Signature			Date		Time
TD			<i>[Signature]</i>			4/30		9:50AM
Checked by:			Signature			Date		Time

Comments:



Project: Tests to Determine the
Behavior of Spliced #11 Bars

As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: B-5

Sheet 2 of 2



Section	Formwork As-built Dimensions Key - Series A							
	1	2	3	4	5	6	7	8
A-A	14'-6"	10'-0"	14'-6"	14'-6"	10'-0"	14'-6"	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
D-D	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
E-E	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
F-F	3"	8-3/4"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
Section	Formwork As-built Dimensions Key - Series B							
	1	2	3	4	5	6	7	8
A-A	13'-10.5"	6'-7"	13'-10.5"	13'-10.5"	6'-7"	13'-10.5"	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
D-D	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
E-E	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
F-F	3"	8-3/4"	3"	23-5/8" ₂₋₁₅₁	23-5/8"	30"	30"	17-5/8"



*For section B-B through F-F see Sheet 3 of 3



Drawing:	Series A Formwork As-builts	Sheet:	1	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		



*For section B-B through F-F see Sheet 3 of 3

Series B



Drawing:	Series B Formwork As-builts	Sheet:	2	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

Project: Tests to Determine the
Behavior of Spliced #11 BarsCasting Documentation v.1
(Rev. 03/30/2012)Specimen: B-6

Sheet 1 of 1

General Information					
Date	Disp Ticket Num	Truck No.	Time on Ticket	Time of Arrival	Temp. in Lab
4/30	1859314	1949	15:30	3:50PM	70°F
Measurements made upon arrival of concrete					
Slump (ASTM C143 - 10a)		Air Content (ASTM C231 - 10)			
Time ₁	Result ₁	Time ₁	Result ₁	S/N of Air Meter	
3:56pm	8 1/4"	4:03	5.3%	4130786891	
Time ₂	Result ₂	Time ₂	Result ₂	S/N of Scale	
4:16pm	7 1/4"	4:2	5.5%	06746056 HM	
Unit Weight (ASTM C138 - 10b)					
Time ₁	Wt. of Cont. ₁	Total Wt. ₁	Wt. of Conc. ₁	Result ₁ = Wt. of Conc./Vol. of Cont.	
4:01pm	8.5#	44.7	36.2#	144.8 #/cft	
Time ₂	Wt. of Cont. ₂	Total Wt. ₂	Wt. of Conc. ₂	Result ₂ = Wt. of Conc./Vol. of Cont.	
4:20	8.5#	44.2	35.7#	142.8 #/cft	
Times of actions during and after casting					
Layer 1 placed	Layer 1 vibration complete	Layer 2 placed	Layer 2 vibration complete	Top surface struck off	Truck Departing Lab
4:05	4:07	4:13	4:15	4:24	✓
Lifting Inserts Placed	Covered with plastic	Plastic removed	Covered with burlap	Burlap doused with water	Covered with plastic
4:30	4:32	10:15PM	10:20PM	10:25PM	10:30PM
Recorded by		Signature		Date	Time
BPR		<i>K. White</i>		4/30	4:25PM
Checked by		Signature		Date	Time
BPR					
Checked by		Signature		Date	Time
SAWORTHY		<i>Staworthy</i>		4/30/12	4:30pm
Comments: 4:04 PM Temp 68.1					
*The following ASTM standards and specifications will be followed during casting: C172-10, C192-07, C470-09					

Truck	Driver	User	Disp Ticket Num	Ticket ID	Time	Date
1949	1395	user	1859314	0	15:30	4/30/12
Load Size	Mix Code	Returned	Qty	Mix Age	Seq	Load ID
5.75	CYDS 1008				D	1438
Material	Design Qty	Required	Batched	% Var	% Moisture	Actual Wat
STONE-8	940 lb	5454 lb	5400 lb	-0.98%	0.90% M	6 gl
STONE-4	620 lb	3586 lb	3560 lb	-0.74%	0.60% M	3 gl
SAND-23	1435 lb	8004 lb	8780 lb	-0.27%	6.70% M	66 gl
CEMENT	588 lb	3381 lb	3380 lb	-0.03%		
WATER	323.2 lb	1235.5 lb	1230.0 lb	-0.45%		147.4 gl
AIR	.80 /C	27.05 oz	27.50 oz	* 1.67%		
Actual	Num Batches:					
Load Total:	22352 lb	Design 0.550	Water/Cement 0.550	T	Design 222.7 gl	Actual 221.8 gl To Add: 0.9 gl
Slump:	4.00 in	Water in Truck: 0.0 lb	Adjust Water: 0.0 lb	/ Load	Trim Water: 0.0 lb/	CYD

3-B-6

Concrete Delivery Ticket



Plant #	Ticket Number	Truck	Load Size	Mix	Slump	Use	Date	Customer
18	1859314	1949	5.75cy	1008	4.00	TEST	04/30/12	15091
Sold To				Tax Code	Driver	Project No.		Order No.
BOWEN CIVIL ENGINEERING LAB TRUCK RELEASE				IN	JOE ZYGAS	1395	5	1815
Delivery Address							P.O. Number	
BOWEN CIVIL ENGINEERING LAB TRUCK RELEASE							SCN2548	
TRUCK RELEASE BRIAN							Job No: SCN2548	

Time Printed 15:29

Load Quantity	Total	Ordered Quantity	Product Code	Product Description	Unit Price	Amount
3.56pm	8 1/4	4.03	403	5.3%		
5.75	17.25cy	17.25cy	1008	PURDUE EXPERIMENTAL	89.00	511.75
4.16	7 1/4	1.2	11-19	2 1/2%		
4.01pm						
4.20						
www.irvmat.com						
Environmental Fee						11.50

Water Added At Pumper's Request		Total No. Gallons	Slump Meter Reading			Subtotal	523.25
On Job Time	Finish Pour Time	AUTH. #:	Grand Total:	1,569.75		Tax	2.11
						Total	523.25

PROPERTY DAMAGE RELEASE / WARNING - Irritating To The Skin and Eyes

Dear Customer - The Seller is not responsible for slumps, strength or quality of concrete to which water or any other material has been added by the purchaser or at his request. The undersigned hereby authorizes Irving Materials, Inc. to use private property for making the delivery shown here on and assumes full responsibility for any damage or injury due to the premises. The undersigned agrees to reimburse said Company for loss of time and equipment by reason of such delivery and also to identify and save harmless said Company from any and all claims, demands and suits for or on account of or in any manner caused by or arising from private property delivery. The undersigned assumes responsibility for a suitable roadway from public highway to point of delivery and is responsible for any needed wrecker service charges as a result.


SAFETY WARNING: Keep away from children. Contains Portland Cement. Irritating to the skin and eyes. Wear rubber boots, gloves and eye protection. Prolonged contact may cause burns. In case of contact with skin or eyes, flush thoroughly with water. If irritation persists, get medical attention. For additional information regarding the HAZARDS OF READY MIX CONCRETE, consult the Material Data Safety Sheet (MSDS) available upon request.

PRODUCT NOTICE: Seller will not be held responsible for the final appearance of exposed aggregate, integral coloring, stamped and decorative surfacing, and all other forms of architectural and design concrete.

DELIVERY NOTICE: Seller assumes no responsibility for deliveries beyond the public right of way. Buyer assumes responsibility for damages including but not limited to curb, sidewalk, driveway, or any property of the contractor or property owner or agents.

NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE SAFETY AND HEALTH WARNING NOTICE AND ACCEPTANCE OF THE LOAD.

Release, Load and Terms Accepted By: *[Signature]*



Went to
4:24 pm
Top AB.





1859314
4/30/12
4:30 pm

Project: Tests to Determine the Behavior of Spliced #11 Bars

Setup and As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: B-26

Sheet 1 of 2

Section	Concrete As-built Dimensions							
	1	2	3	4	5	6	7	8
Plan	34'-3 $\frac{7}{8}$ "	34'-3 $\frac{7}{8}$ "	34'-4"	34'-4"				
B-B	17- $\frac{5}{8}$ "	30- $\frac{3}{16}$ "	17- $\frac{5}{8}$ "	30- $\frac{3}{16}$ "				
C-C	17- $\frac{1}{16}$ "	30- $\frac{1}{8}$ "	17- $\frac{5}{8}$ "	30- $\frac{1}{8}$ "				
D-D	17- $\frac{1}{16}$ "	30- $\frac{1}{4}$ "	17- $\frac{5}{8}$ "	30- $\frac{1}{8}$ "				
E-E	17- $\frac{1}{16}$ "	30"	17- $\frac{5}{8}$ "	30"				
F-F	17- $\frac{1}{16}$ "	30"	17- $\frac{1}{16}$ "	30"				
Recorded by:			Signature				Date	Time
KAM							5-24	3:15pm
Checked by:			Signature				Date	Time
BPR							5/24	3:15PM
Checked by:			Signature				Date	Time

Comments:


Project: Tests to Determine the
Behavior of Spliced #11 Bars

Setup and As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: B-26

Sheet 2 of 2

Section	Concrete As-built Dimensions Key - Series A							
	1	2	3	4	5	6	7	8
Plan	39'-0"	39'-0"	39'-0"	39'-0"	N/A	N/A	N/A	N/A
B-B	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
C-C	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
D-D	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
E-E	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
F-F	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
Section	Concrete As-built Dimensions Key - Series B							
	1	2	3	4	5	6	7	8
Plan	34'-4"	34'-4"	34'-4"	34'-4"	N/A	N/A	N/A	N/A
B-B	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
C-C	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
D-D	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
E-E	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
F-F	17-5/8"	30"	17-5/8"	30" ₂ - 158	N/A	N/A	N/A	N/A





Specimen B-~~2~~6

Behavior of Lap Splices of No. 11
Reinforcing Bars


Sheet: 1 of 4

Drawn by: BPR Checked by: KAM


Date: 5/24/12




*For section B-B through F-F see Sheet 3 of 3



Drawing:	Series A Concrete As-builts	Sheet:	2	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		




Top Plan



Profile


*For section B-B through F-F see Sheet 3 of 3



Bottom Plan



Drawing:	Series B Concrete As-builts	Sheet:	3	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		



Section B-B, C-C, D-D, E-E & F-F
*Facing North



Drawing:	Concrete As-built Sections	Sheet:	4	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

Project: Tests to Determine the Behavior of Spliced #11 Bars

As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: B-6

Sheet 1 of 2

Section	Formwork As-built Dimensions							
	1	2	3	4	5	6	7	8
A-A	166 - $\frac{1}{2}$	79 - 0	166 - $\frac{1}{2}$	166 - $\frac{5}{8}$	78 - $\frac{7}{8}$	166 - $\frac{3}{8}$		
B-B	41 - $\frac{7}{16}$	6 - 0	4 $\frac{1}{2}$	23 - $\frac{9}{16}$	23 $\frac{9}{16}$	30 $\frac{3}{16}$	30 $\frac{1}{8}$	17 $\frac{7}{16}$
C-C	3 - $\frac{1}{16}$	6 $\frac{1}{16}$	3 $\frac{1}{8}$	23 $\frac{5}{8}$	23 $\frac{5}{8}$	30 $\frac{1}{8}$	30 $\frac{1}{8}$	17 $\frac{7}{16}$
D-D	3 $\frac{1}{8}$	6 $\frac{1}{16}$	3 $\frac{1}{16}$	23 $\frac{11}{16}$	23 $\frac{7}{8}$	30 - 0	30 $\frac{1}{8}$	17 $\frac{7}{16}$
E-E	3 $\frac{1}{16}$	6 $\frac{1}{8}$	3 - 0	23 $\frac{1}{2}$	23 $\frac{9}{16}$	30 - 0	30 $\frac{1}{16}$	17 $\frac{7}{16}$
F-F	3 - 0	8 $\frac{3}{16}$	3 $\frac{1}{16}$	23 $\frac{7}{16}$	23 $\frac{7}{16}$	30 - 0	30 $\frac{1}{8}$	17 $\frac{7}{16}$
Recorded by:			Signature				Date	Time
BPR			<i>[Signature]</i>				4/30	10:10AM
Checked by:			Signature				Date	Time
TD			<i>[Signature]</i>				4/30	10:10AM
Checked by:			Signature				Date	Time

Comments:

*See formwork as-built drawings for dimension locations


Project: Tests to Determine the
Behavior of Spliced #11 Bars

As-built Dimensions v.1
(Rev. 04/04/2012)


Specimen: B-6

Sheet 2 of 2

Section	Formwork As-built Dimensions Key - Series A							
	1	2	3	4	5	6	7	8
A-A	14'-6"	10'-0"	14'-6"	14'-6"	10'-0"	14'-6"	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
D-D	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
E-E	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
F-F	3"	8-3/4"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
Section	Formwork As-built Dimensions Key - Series B							
	1	2	3	4	5	6	7	8
A-A	13'-10.5"	6'-7"	13'-10.5"	13'-10.5"	6'-7"	13'-10.5"	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
D-D	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
E-E	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
F-F	3"	8-3/4"	3"	23-5/8" ₂₋₁₆₄	23-5/8"	30"	30"	17-5/8"




Section C-C, D-D, & E-E
*Facing North




Section B-B & F-F
*Facing North



Drawing:	Formwork As-built Sections	Sheet:	3	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		



Section A-A





*For section B-B through F-F see Sheet 3 of 3

Series A



Drawing:	Series A Formwork As-builts	Sheet:	1	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		




*For section B-B through F-F see Sheet 3 of 3


Series B



Drawing:	Series B Formwork As-builts	Sheet:	2	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		



Section C-C, D-D, & E-E
*Facing North



Section B-B & F-F
*Facing North



Drawing:	Formwork As-built Sections	Sheet:	3	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

Project: Tests to Determine the Behavior of Spliced #11 Bars

Curing Documentation v.1 (Rev. 03/30/2012)

Purdue University - Bowen Laboratory Sheet 1 of 1

General Information			
Specimen(s)	Date	Specimen Age	
B-1	4-11-12	1	
	Time Beginning	Time Ending	
	1:30 pm	1:45 pm	
	Temperature inside Lab (deg. F)		
	65		
Description of Work Performed			
Wetted Burlap B-1 & Cylinders			
Recorded by	Signature	Date	Time
KAM	<i>[Signature]</i>	4-11-12	1:45
Checked by	Signature	Date	Time
MAS	<i>[Signature]</i>	4/11/12	1:45 p
Checked by	Signature	Date	Time
Comments:			
*Test specimens and associated cylinders are to be cured under wet burlap for seven days			

Project: Tests to Determine the Behavior of Spliced #11 Bars



Curing Documentation v.1 (Rev. 03/30/2012)

Purdue University - Bowen Laboratory Sheet 1 of 1

General Information			
Specimen(s)	Date	Specimen Age	
B-2	4-11-12	1	
	Time Beginning	Time Ending	
	1:30 pm	1:45 pm	
	Temperature inside Lab (deg. F)		
	65		
Description of Work Performed			
Wetted Burlap B-2 + Cylinders			
Recorded by	Signature	Date	Time
KAM	<i>[Signature]</i>	4-11-12	1:45
Checked by	Signature	Date	Time
MAS	<i>[Signature]</i>	4/11/12	1:45 P
Checked by	Signature	Date	Time
Comments:			
*Test specimens and associated cylinders are to be cured under wet burlap for seven days			

General Information			
Specimen(s)	Date	Specimen Age	
B-3	4-11-12	1	
	Time Beginning	Time Ending	
	1:15 pm	1:30 pm	
	Temperature inside Lab (deg. F)		
	65		
Description of Work Performed			
Wetted Burlap B-3 + cylinders			
Recorded by	Signature	Date	Time
KAM	<i>[Signature]</i>	4-11-12	1:30PM
Checked by	Signature	Date	Time
MAS	<i>[Signature]</i>	4/11/12	1:45P
Checked by	Signature	Date	Time
Comments:			
*Test specimens and associated cylinders are to be cured under wet burlap for seven days			

Project: Tests to Determine the
Behavior of Spliced #11 BarsCuring Documentation v.1
(Rev. 03/30/2012)Purdue University - Bowen Laboratory
Sheet 1 of 1

General Information			
Specimen(s)	Date	Specimen Age	
B-1, 2, 3	4/12/12	2 day	
	Time Beginning	Time Ending	
	11 AM	4 PM	
	Temperature inside Lab (deg. F)		
	60°F		
Description of Work Performed			
<ul style="list-style-type: none"> ✓ Struck Forms, wet beams ✓ Lifted & Moved Specimens + sprayed all w. water ✓ Covered all w. wet burlap + plastic 			
Recorded by	Signature	Date	Time
S.P.		4/12/12	5:00PM
Checked by	Signature	Date	Time
KAM		4-12-12	5:30PM
Checked by	Signature	Date	Time
Comments:			
*Test specimens and associated cylinders are to be cured under wet burlap for seven days			

Project: Tests to Determine the Behavior of Spliced #11 Bars

Curing Documentation v.1
(Rev. 03/30/2012)

Purdue University - Bowen Laboratory
Sheet 1 of 1

General Information		
Specimen(s)	Date	Specimen Age
B-1, 2, 3	4-13-12	3 days
	Time Beginning	Time Ending
	2:30 pm	2:45 pm
	Temperature inside Lab (deg. F)	
	65°	

Description of Work Performed

Wetted Burlap of Specimens + cylinders

Recorded by	Signature	Date	Time
KAM		4-13-12	2:50 pm
Checked by	Signature	Date	Time
 S.P.		4/13/12	5:00 PM
Checked by	Signature	Date	Time

Comments:

*Test specimens and associated cylinders are to be cured under wet burlap for seven days

Project: Tests to Determine the Behavior of Spliced #11 Bars

Curing Documentation v.1 (Rev. 03/30/2012)

Purdue University - Bowen Laboratory Sheet 1 of 1

General Information		
Specimen(s)	Date	Specimen Age
B-1,2,3	4-14	4 days
	Time Beginning	Time Ending
	3:30 pm	3:50 pm
	Temperature inside Lab (deg. F)	
	65°	

Description of Work Performed

Wetted Burlap on specimens B-1,2,3 + cylinders

Recorded by	Signature	Date	Time
KAM	<i>[Signature]</i>	4-14-12	3:50 pm
Checked by	Signature	Date	Time
BPR	<i>[Signature]</i>	4/14/12	4:00 PM
Checked by	Signature	Date	Time

Comments:

*Test specimens and associated cylinders are to be cured under wet burlap for seven days

Project: Tests to Determine the
Behavior of Spliced #11 BarsCuring Documentation v.1
(Rev. 03/30/2012)Purdue University - Bowen Laboratory
Sheet 1 of 1

General Information			
Specimen(s)	Date	Specimen Age	
B-1, B-2, & B-3, + corresponding cylinders	4/15/12	5-days	
	Time Beginning	Time Ending	
	1:30pm	2:00pm	
	Temperature inside Lab (deg. F)		
	65°F		
Description of Work Performed			
Uncovered Doused burlap w/ water Recovered			
Recorded by	Signature	Date	Time
BPR	<i>[Signature]</i>	4/15/12	2:00PM
Checked by	Signature	Date	Time
KAM	<i>[Signature]</i>	4-15	2:00PM
Checked by	Signature	Date	Time
Comments:			
*Test specimens and associated cylinders are to be cured under wet burlap for seven days			

Project: Tests to Determine the Behavior of Spliced #11 Bars

Curing Documentation v.1
(Rev. 03/30/2012)

Purdue University - Bowen Laboratory
Sheet 1 of 1

General Information		
Specimen(s)	Date	Specimen Age
B-1,2,3	4/16/12	6 days
	Time Beginning	Time Ending
	3:00 pm	3:30 pm
	Temperature inside Lab (deg. F)	
	67°	

Description of Work Performed

Dressed burlap and received beams B-1,2,3 + cylinders

Recorded by	Signature	Date	Time
KAM	<i>[Signature]</i>	4-16	4:00pm
Checked by	Signature	Date	Time
BPR	<i>[Signature]</i>	4/16	4:00PM
Checked by	Signature	Date	Time

Comments:

*Test specimens and associated cylinders are to be cured under wet burlap for seven days

Project: Tests to Determine the Behavior of Spliced #11 Bars



Curing Documentation v.1 (Rev. 03/30/2012)

Purdue University - Bowen Laboratory Sheet 1 of 1

General Information		
Specimen(s)	Date	Specimen Age
B-1, B-2, & B-3 & corresponding cylinders	4/17/12	7-day
	Time Beginning	Time Ending
	2:30PM	2:45PM
	Temperature inside Lab (deg. F)	
	62°F	

Description of Work Performed

Doused burlap w/ water
Recovered w/ plastic

Recorded by	Signature	Date	Time
BPR		4/17/12	2:47PM
Checked by	Signature	Date	Time
DPB		4/17/12	2:47PM
Checked by	Signature	Date	Time

Comments:

*Test specimens and associated cylinders are to be cured under wet burlap for seven days

General Information		
Specimen(s)	Date	Specimen Age
B-1, B-2, & B-3 & corresponding cylinders	4/18/12	8-day
	Time Beginning	Time Ending
	4:30 PM	4:45 PM
	Temperature inside Lab (deg. F)	
		65°F

Description of Work Performed

Doused burlap w/ water
 Recovered w/ plastic

Recorded by	Signature	Date	Time
BPR	<i>[Signature]</i>	4/18/12	5:00 PM
Checked by	Signature	Date	Time
TD	<i>[Signature]</i>	4/18/12	5:00 PM
Checked by	Signature	Date	Time

Comments:

*Test specimens and associated cylinders are to be cured under wet burlap for seven days

General Information		
Specimen(s)	Date	Specimen Age
B-1, B-2, & B-3 & cylinders	4/19	9-days
	Time Beginning	Time Ending
	4:00PM	4:15PM
	Temperature inside Lab (deg. F)	
	72°F	

Description of Work Performed

Watered burlap
Covered w/ plastic

Recorded by	Signature	Date	Time
BPR	<i>Am Nite</i>	4/19/12	4:15PM
Checked by	Signature	Date	Time
VAM	<i>MLL</i>	4-19-12	4:30PM
Checked by	Signature	Date	Time

Comments:

*Test specimens and associated cylinders are to be cured under wet burlap for seven days

General Information		
Specimen(s)	Date	Specimen Age
B-1, B-2, & B-3 & Cylinders	4/20/12	10-days
	Time Beginning	Time Ending
	5:30	6:00
	Temperature inside Lab (deg. F)	
	62°F	

Description of Work Performed

Doused burlap w/ water
 Re covered w/ plastic

Recorded by	Signature	Date	Time
KAM	<i>[Signature]</i>	4-20-12	6:00pm
Checked by	Signature	Date	Time
BPR	<i>[Signature]</i>	4/20/12	6:05PM
Checked by	Signature	Date	Time


Comments:

*Test specimens and associated cylinders are to be cured under wet burlap for seven days

General Information		
Specimen(s)	Date	Specimen Age
B-1, 2, 3	4-21-12	11-days
	Time Beginning	Time Ending
	3:30 pm	4:00 pm
	Temperature inside Lab (deg. F)	
	62°F	

Description of Work Performed

Removed burlap on specimens + cylinders, recased with plastic

Recorded by	Signature	Date	Time
KAM		4-21-12	4:15 pm
Checked by	Signature	Date	Time
BPR	Brian Richter	4/21/12	4:20 PM
Checked by	Signature	Date	Time



Comments:

*Test specimens and associated cylinders are to be cured under wet burlap for seven days

General Information		
Specimen(s)	Date	Specimen Age
B-1, B-2, & B-3 + Cylinders	4/23	13-days
	Time Beginning	Time Ending
	2:45PM	3:00PM
	Temperature inside Lab (deg. F)	
		65°F

Description of Work Performed

Watered burlap
Recovered w/ plastic

Recorded by	Signature	Date	Time
BPR		4/23	3:00PM
Checked by	Signature	Date	Time
JNH		4.23.12	3:00PM
Checked by	Signature	Date	Time

Comments:

*Test specimens and associated cylinders are to be cured under wet burlap for seven days

General Information		
Specimen(s)	Date	Specimen Age
B-1, B-2, & B-3 & Cylinders	4/24/12	14-days
	Time Beginning	Time Ending
	11 AM	11:10 AM
	Temperature inside Lab (deg. F)	
	62°F	

Description of Work Performed

Uncovered specimens (stopped curing)

Recorded by	Signature	Date	Time
BPR	<i>[Signature]</i>	4/24	11:15 AM
Checked by	Signature	Date	Time
DPB	<i>[Signature]</i>	4/24	4:10
Checked by	Signature	Date	Time

Comments:

*Test specimens and associated cylinders are to be cured under wet burlap for seven days

Project: Tests to Determine the Behavior of Spliced #11 Bars

Curing Documentation v.1 (Rev. 03/30/2012)

Purdue University - Bowen Laboratory Sheet 1 of 1

General Information		
Specimen(s)	Date	Specimen Age
A-1, A-2, & A-3 + corresponding cylinders	4/18/12	1-day
	Time Beginning	Time Ending
	3:00 PM	3:30 PM
	Temperature inside Lab (deg. F)	
	65°F	

Description of Work Performed

Doused burlap w/ water
Re-covered

Recorded by	Signature	Date	Time
BPR	<i>[Signature]</i>	4/18/12	4:20 PM
Checked by	Signature	Date	Time
TD	<i>[Signature]</i>	4/18/12	4:20 PM
Checked by	Signature	Date	Time

Comments:

*Test specimens and associated cylinders are to be cured under wet burlap for seven days

General Information			
Specimen(s)	Date	Specimen Age	
A-1, A-2, & A-3 & Cylinders	4/19	2-days	
	Time Beginning	Time Ending	
	10:30 AM	5:15 PM	
	Temperature inside Lab (deg. F)		
	72°F		
Description of Work Performed			
<p>Stripped formwork & removed cylinders from molds (10:30AM-2PM) Moved beams off of platforms (2PM-4PM) Covered beams & cyl. w/ wet burlap & plastic (4PM-5:15PM)</p>			
Recorded by	Signature	Date	Time
BPR	<i>[Signature]</i>	4/19/12	5:15 PM
Checked by	Signature	Date	Time
KAM	<i>[Signature]</i>	4-19-12	5:30 PM
Checked by	Signature	Date	Time
Comments:			
*Test specimens and associated cylinders are to be cured under wet burlap for seven days			

General Information		
Specimen(s)	Date	Specimen Age
A-1, A-2, & A-3 & Cylinders	4/20/12	3-days
	Time Beginning	Time Ending
	6:30	6:00
	Temperature inside Lab (deg. F)	
	62°F	

Description of Work Performed

Uncovered specimens & cylinders (stopped curing)

Recorded by	Signature	Date	Time
KAM	<i>[Signature]</i>	4-20-12	6:00 pm
Checked by	Signature	Date	Time
BPR	<i>[Signature]</i>	4/20/12	6:05 PM
Checked by	Signature	Date	Time

Comments:

*Test specimens and associated cylinders are to be cured under wet burlap for seven days

General Information		
Specimen(s)	Date	Specimen Age
A-4, A-5, & A-6 & cylinders	4/25/12	1 # - days
	Time Beginning	Time Ending
	4:00 PM	4:20 PM
	Temperature inside Lab (deg. F)	
		65°F

Description of Work Performed

Doused burlap w/ water
 Recovered w/ plastic

Recorded by	Signature	Date	Time
BPR	<i>[Signature]</i>	4/25	7:10 PM
Checked by	Signature	Date	Time
KAM	<i>[Signature]</i>	4-25-12	7:30 pm
Checked by	Signature	Date	Time

Comments:

*Test specimens and associated cylinders are to be cured under wet burlap for seven days

General Information		
Specimen(s)	Date	Specimen Age
A-4, A-5, & A-6 & corresponding cylinders	4/26/12	2-days
	Time Beginning	Time Ending
	10:30 AM	4:45 PM
	Temperature inside Lab (deg. F)	
	Not Recorded	BPR 6/1/12

Description of Work Performed

Uncovered specimens & cylinders
 Stripped forms & popped cylinders
 Moved specimens
 Covered spec. & cylinders w/ wet burlap
 Covered spec. & cylinders w/ plastic

Recorded by	Signature	Date	Time
BPR	<i>BPR</i>	4/26/12	4:50 PM
Checked by	Signature	Date	Time
KAM	<i>KAM</i>	4-26-12	5:00 PM
Checked by	Signature	Date	Time

Comments:

*Test specimens and associated cylinders are to be cured under wet burlap for seven days

General Information		
Specimen(s)	Date	Specimen Age
A-4, A-5, & A-6 & corresponding cylinders	4/27	3-days
	Time Beginning	Time Ending
	2:30 PM	2:45 PM
	Temperature inside Lab (deg. F)	
		65°F

Description of Work Performed

Doused burlap w/ water
 Recovered w/ plastic

Recorded by	Signature	Date	Time
BPR	<i>[Signature]</i>	4/27/12	3:00 PM
Checked by	Signature	Date	Time
KAM	<i>[Signature]</i>	4-27-12	3:30 pm
Checked by	Signature	Date	Time

Comments:

*Test specimens and associated cylinders are to be cured under wet burlap for seven days

General Information		
Specimen(s)	Date	Specimen Age
A-4, A-5, & A-6	4/28/12	4-days
	Time Beginning	Time Ending
	1:00PM	1:30PM
	Temperature inside Lab (deg. F)	
	65°F	

Description of Work Performed

Doused burlap w/ water
 Recovered w/ plastic

Recorded by	Signature	Date	Time
BPR	<i>BPR</i>	4/28	1:30PM
Checked by	Signature	Date	Time
KAM	<i>KAM</i>	4-28-12	1:30 PM
Checked by	Signature	Date	Time

Comments:

*Test specimens and associated cylinders are to be cured under wet burlap for seven days

General Information		
Specimen(s)	Date	Specimen Age
A-4, A-5, & A-6 & Cylinders	4/30/12	6-days
	Time Beginning	Time Ending
	8:15 AM	8:45 AM
	Temperature inside Lab (deg. F)	
		65°F

Description of Work Performed

Doused burlap w/ water
 Recovered w/ plastic

Recorded by	Signature	Date	Time
BPR	<i>[Signature]</i>	4/30/12	9:15 AM
Checked by	Signature	Date	Time
KAM	<i>[Signature]</i>	4-30-12	9:15 AM
Checked by	Signature	Date	Time

Comments:

*Test specimens and associated cylinders are to be cured under wet burlap for seven days

General Information		
Specimen(s)	Date	Specimen Age
A-4, 5, 6	5-1-12	7 days
	Time Beginning	Time Ending
	1:00 pm	1:15 pm
	Temperature inside Lab (deg. F)	
	65°	

Description of Work Performed

Stopped curing
 Removal plastic from specimens + cylinders

Recorded by	Signature	Date	Time
KAM	<i>[Signature]</i>	5-1-12	1:30
Checked by	Signature	Date	Time
BPR	<i>[Signature]</i>	5/1	4:20 PM
Checked by	Signature	Date	Time

Comments:

*Test specimens and associated cylinders are to be cured under wet burlap for seven days

General Information		
Specimen(s)	Date	Specimen Age
B-4,5,6	5-1-12	1 day
	Time Beginning	Time Ending
	1:15pm	1:30pm
	Temperature inside Lab (deg. F)	
	65°	

Description of Work Performed

Doused Burlap, Recased Specimens + Cylinders

Recorded by	Signature	Date	Time
KAM	<i>[Signature]</i>	5-1-12	1:30pm
Checked by	Signature	Date	Time
BPR	<i>[Signature]</i>	5/1	4:20PM
Checked by	Signature	Date	Time

Comments:

*Test specimens and associated cylinders are to be cured under wet burlap for seven days

General Information		
Specimen(s)	Date	Specimen Age
B-4,5,6	5-3-12	3 days
	Time Beginning	Time Ending
	9:00 am	5:00 pm
	Temperature inside Lab (deg. F)	
	70°	

Description of Work Performed

Removed specimens from forms

Recorded by	Signature	Date	Time
KAM	<i>[Signature]</i>	5-3-12	5:00 pm
Checked by	Signature	Date	Time
BPR	<i>[Signature]</i>	5-3-12	5:00 PM
Checked by	Signature	Date	Time

Comments:

*Test specimens and associated cylinders are to be cured under wet burlap for seven days

Tinius Olsen Testing Machine Company
Displacement Measuring System Verification Report & Certificate
Specifications per ASTM E 2309



Date of Issue May 02, 2011

Certificate Number 9M9AHP05

Issued by:

Tinius Olsen Testing Machine Company
 1065 Easton Road
 P.O. Box 1009
 Horsham, PA 19044-8009, USA
 Tel (215) 675-7100
 Fax (215) 441-0899
 www.TiniusOlsen.com

Page 1 of 3

Authorized Signature

Cheryl Spinico

Owner/Location LABORATORY TESTING INC, 2331 Topaz Drive, Hatfield, Pennsylvania 19440

Calibration Location SAME

Item Description S/N 206051P - POSITION #60013377 Ascending - w/ Computer Display #206051 - As Found/As Left - No Adjustments - Good Condition

Year of Manufacture UNKNOWN

Verification Date April 29, 2011

Verification Recall April 29, 2012

This is to certify that the above testing equipment has been verified by Tinius Olsen Testing Machine Company personnel on Order Number 448750. The listed data is in accordance with the latest practices of ASTM E 2309, and Tinius Olsen Procedure #2600, and have been temperature corrected as necessary. Tinius Olsen's Quality System is maintained in compliance with ANSI / NCSL Z540-1 1994, ISO/IEC 17025 (Complies with ISO 9000 Series for Calibration Activity), ISO 10012-1, and MIL-STD-45662A.

Range in	Class Range in	Class
9.0000	0.1000 TO 9.0000	B
9.0000	0.9000 TO 9.0000	A

LTI
 QA REVIEW
 INT.
 DATE 5/11/11

Services have been performed in accordance with Tinius Olsen Quality Manual, dated 03/13/09__.

These results relate only to the items calibrated. This Report and Certificate shall not be reproduced except in full, without the written approval of Tinius Olsen.

Tinius Olsen Testing Machine Company
Displacement Measuring System Verification Report & Certificate
Specifications per ASTM E 2309

Verification Date April 29, 2011

Certificate Number 9M9AHP05

Page 2 of 3

All verification devices are traceable to the International System of Units (SI) through National Institute of Standards and Technology (NIST) or the National Physical Laboratory (NPL). Serial Number, Manufacturer, Type, Maximum Device Error, Calibration Vendor, and Expiry Date for each standard used during the Certification is listed below.

Serial No.	Manufacturer	Type	Max Device Error	Vendor	Expiry Date
655-4041-J-2	Starrett	INDICATOR	.0007500	Olsen	13-Jul-11

The expanded uncertainties reported are estimates of the measurement uncertainty in the errors determined during the verification. They are expressed as percentages of their respective verification readings. The expanded uncertainties reported are based on combined standard uncertainties, multiplied by a coverage factor of 2, which provide a confidence interval of approximately 95%. The uncertainties reported do not represent the uncertainty of the testing machine or the results of any subsequent tests performed with the testing machine.

Tinius Olsen Testing Machine Company
Displacement Measuring System Verification Report & Certificate
Specifications per ASTM E 2309

Certificate Number 9M9AHP05

Verification Date April 29, 2011

Verification Recall Date April 29, 2012

Page 3 of 3

Owner/Location LABORATORY TESTING INC, 2331 Topaz Drive, Hatfield, Pennsylvania 19440

Calibration Location SAME

Item Description S/N 206051P - POSITION #60013377 Ascending - w/ Computer Display #206051 - As Found/As Left - No Adjustments - Good Condition

Order No. 448750

Customer PO No. PO0002821

Customer ID No.

Year of Mfg. UNKNOWN

Backlash As Found

BackLash As Left

Temp. Start 22.8°C End 22.8°C

Range	Resolution	Ver Read 1	Mach Read1	Ver Read 2	Mach Read 2	Fixed Error	Error	Difference	Uncertainty	Class
in	in	in	in	in	in	in	%	%	%	
9	0.0001	9.0000	8.9733	9.0000	8.9756	-0.0267	-0.30	-0.03	0.38	A
	0.0001	6.7500	6.7252	6.7500	6.7415	-0.0248	-0.37	-0.24	0.38	A
	0.0001	4.5000	4.4929	4.5000	4.5027	-0.0071	-0.16	-0.22	0.38	A
	0.0001	2.2500	2.2440	2.2500	2.2466	-0.0060	-0.27	-0.12	0.39	A
	0.0001	0.9000	0.9020	0.9000	0.8997	0.0020	0.22	0.26	0.35	A
	0.0001	0.6750	0.6767	0.6750	0.6775	0.0025	0.37	-0.12	0.33	B
	0.0001	0.4500	0.4514	0.4500	0.4516	0.0016	0.36	-0.04	0.33	B
	0.0001	0.2250	0.2255	0.2250	0.2258	0.0008	0.36	-0.13	0.54	B
	0.0001	0.1000	0.1004	0.1000	0.1003	0.0004	0.40	0.10	1.14	B

Calibration Technician/Engineer Brian Campbell

1.6.17/1.1.34/32

Witness Kevin Kline

Tinius Olsen Testing Machine Company Certificate



Certificate No. 9M9AHP06

Certificate page 1 of 1

Issued By:

Tinius Olsen Testing Machine Company
1065 Easton Road
Horsham, PA 19044 USA
Telephone: 215-675-7100
Fax: 215-441-0899
Email: service@tiniusolsen.com

Cheryl Spencer
Authorized Signature

Owner/Location: LABORATORY TESTING INC., HATFIELD, PA 19440

Calibration Location: SAME AS ABOVE

Item Description: Crosshead Speed Rate on Machine S/N 206051SR (#6001337) - As Found/As Left - No Adjustments - Good Condition

Verification Date: April 29, 2011

Verification Recall Date: April 29, 2012

This is to certify that the Crosshead Speed Rate on the above testing equipment has been verified by Tinius Olsen Testing Machine Company personnel on Order Number S448750. The listed data is in accordance Tinius Olsen Procedure #2700. Tinius Olsen's Quality System is maintained in compliance with ISO/IEC 17025 (Complies with ISO 9000 Series for Calibration Activity), ANSI / NCSL Z540-1 1994, ISO 10012-1, and MIL-STD-45662A. The estimated expanded uncertainty of the calibration results is: 0.0016 in. The reported expanded uncertainty is based on a standard uncertainty multiplied by a coverage factor of k=2, providing a level of confidence of approximately 95 percent.

Crosshead Speed Rate Certificate

All verification devices are traceable to the International System of Units (SI) through either National Institute of Standards and Technology (NIST) or National Physical Laboratory (NPL) and have been verified within one (1) year or less of the above date. For Verification details, refer to the attached Verification Data and Report Form bearing the same Order or Certificate Number as this Certificate.

Serial No	Manufacturer	Description	Calib Vendor	Expiry Date
DSW-0002	HANHART	STOPWATCH	TINIUS OLSEN	4/28/16
655-4041-J-2	STARRETT	DIAL INDICATOR	TINIUS OLSEN	7/13/11

Services have been performed in accordance with Tinius Olsen Quality Manual, dated March 13, 2009.

These results relate only to the items calibrated. This Certificate shall not be reproduced except in full, without the written approval of Tinius Olsen.

Tinius Olsen Testing Machine Company Rate Verification Datasheet & Report

Tinius Olsen Procedure used 2700
Rev. 10 April 2007
Page 1 of 2

Date 7/29/11 Certificate # 9M9ANP06
 Order No. 448750 Purchase Order No. PO 0002821
 Customer LABORATORY TESTING Machine Mfg. TINIUS OLSEN
 Location HATFIELD, PA Model and Serial # SUPERL 206051
 Machine Display 602 Capacity and Units 400,000 LBS
 Customer ID No. 60013377 Cal. Technician Brian S. G. Cell
 Stopwatch S/N DSL0-0002 Strain Device S/N -
 Dial Indicator S/N 655-4041-J-2 Gauge Length -
 Temperature 73

Condition (Circle One) ~ As Found / As Left / No Adjustments / Limited Calibration / Out of Tolerance

Load Rate (Circle One) Lbf/Min Kgf/Min N/Min Other _____

Control Setting	Load Range	Load Rate Displayed	Change in Load	Time	Actual Load Rate	Error (actual)	Error %
			N/A				

Strain Rate (Circle One) in/in/min mm/mm/min %/min Other _____
 Split Specimen/Broken Specimen* Previously Untested Specimen

Control Setting	Strain Range	Strain Rate Displayed	Change in Strain	Time	Actual Strain Rate	Error (actual)	Error %
			N/A				

* If a Split Specimen or Broken Specimen was used for Strain Rate then the ability of the machine to control was not verified.

Tinius Olsen Testing Machine Company
Testing Machine Verification Report & Certificate
Specifications per ASTM E 4



Date of Issue May 02, 2011

Certificate Number 9M9AHP07

Issued by:

Tinius Olsen Testing Machine Company
 1065 Easton Road
 P.O. Box 1009
 Horsham, PA 19044-8009, USA
 Tel (215) 675-7100
 Fax (215) 441-0899
 www.TiniusOlsen.com

Page 1 of 3

Authorized Signature

Cheryl Spinio

Owner/Location LABORATORY TESTING INC, 2331 Topaz Drive, Hatfield, Pennsylvania 19440
Calibration Location SAME
Item Description S/N 206051 - 400000 lbf HYD SPR L602 #60013377 - w/ Digital Indicator - As Found/As Left - No Adjustments - Good Condition
Serial Numbers: Machine 206051

LC # N/A

Computer # 206051

REC # N/A

Year of Manufacture UNKNOWN

Cal-Check No. 190577

Verification Date April 29, 2011

Verification Recall April 29, 2012

This is to certify that the above testing equipment has been verified by Tinius Olsen Testing Machine Company personnel on Order Number 448750. The listed data is in accordance with ASTM E 4-10, and Tinius Olsen Procedure #1000, and have been temperature corrected as necessary. Tinius Olsen's Quality System is maintained in compliance with ANSI / NCSL Z540-1 1994, ISO/IEC 17025 (Complies with ISO 9000 Series for Calibration Activity), ISO 10012-1, and MIL-STD-45662A.

Capacity Range lbf	Loading Range lbf	Percent Error	Range Pass/Fail
0 to 400000	798.00 TO 401000.00	-0.24	Pass

 ASTM E 4 Allowable Tolerance $\pm 1.0\%$

Services have been performed in accordance with Tinius Olsen Quality Manual, dated 03/13/09 __.

These results relate only to the items calibrated. This Report and Certificate shall not be reproduced except in full, without the written approval of Tinius Olsen.

Tinius Olsen Testing Machine Company
Testing Machine Verification Report & Certificate
Specifications per ASTM E 4

Verification Date April 29, 2011

Certificate Number 9M9AHP07

Page 2 of 3

All verification devices comply with the latest practices of ASTM E 74, and are traceable to the International System of Units (SI) through National Institute of Standards and Technology (NIST) or the National Physical Laboratory (NPL). Serial Number, Manufacturer, Class A Loading Range, Calibration Vendor, Expiry Date, and Certificate Number for each standard used during the Certification is listed below. The class of the verification equipment was equal to or better than the requirements of the classification to which this device has been verified.

Eqp #	S/N	Manufacturer	Class A Loading Range	Calib. Vendor	Calib. Date	Expiry Date
1	104713A (HI)	Tovey	100.00 to 10000.00 lbf	Morehouse	03-Mar-10	03-Mar-12
2	110211A	Tovey	2017.60 to 60000.00 lbf	Tovey	02-Apr-11	02-Apr-12
3	106244A	Tovey	31836.00 to 600000.00 lbf	Tovey	01-Mar-10	01-Mar-12

This Calibration was performed in Compression for increasing forces only. For Universal Testing Machines that have two work areas with a common force application and indicating device, calibration performed in the lower test area in compression is the same for tension in the upper work area and vice versa.

“The constant indicated/constant true force method was used for the verification. Verification by Standard Weights” and/or “Verification by Elastic Calibration Device”

Informative Notes:

The expanded uncertainties reported are estimates of the measurement uncertainty in the errors determined during the verification. They are expressed as percentages of their respective verification readings. The expanded uncertainties reported are based on combined standard uncertainties, multiplied by a coverage factor of 2, which provide a confidence interval of approximately 95%. The uncertainties reported do not represent the uncertainty of the testing machine or the results of any subsequent tests performed with the testing machine. The accuracy of the testing equipment has been found to conform with the tolerance(s) indicated above.

The uncertainties stated refer to the values obtained during verification and make no allowance for factors such as long-term drift, temperature and alignment effects – the influences of such factors should be taken into account by the user of the testing machine.

Tinius Olsen Testing Machine Company
Testing Machine Verification Report & Certificate
Specifications per ASTM E 4

Verification Date April 29, 2011Certificate No. 9M9AHP07

Page 3 of 3

Owner/Location LABORATORY TESTING INC. 2331 Topaz Drive Hatfield, Pennsylvania 19440Calibration Location SAMEItem Description S/N 206051 - 400000 lbf HYD SPR L602 #60013377 - w/ Digital Indicator - As Found/As Left - No Adjustments - Good ConditionCustomer ID No. _____ Year of Mfg. UNKNOWN Cal-Check No. 190577Order No. 448750 Customer PO No. PO0002821 Temperature Start 22.8 °C End 24.4 °CSerial Numbers: TM 206051 LC N/AREC N/A COMP 206051Verification Recall Date April 29, 2012

LOAD RANGE lbf	VERIFIC. * READ #1 lbf	MACHINE READ #1 lbf	VERIFIC. READ #2 lbf	MACHINE READ #2 lbf	FIXED ERROR lbf	ERROR % OF VALUE	DIFFER. % OF VALUE	UNCERTAINTY % OF VALUE	RESOLUTION FOR RANGE(S) lbf	
400000	1	798.2	800.0	802.4	801.4	1.8	0.22	0.35	0.44	4.0
	1	1607.1	1606.9	1606.2	1606.0	-0.3	-0.02	0.01	0.26	4.0
	1	3199.4	3201.6	3201.6	3199.5	2.2	0.07	0.14	0.19	4.0
	2	5600.5	5599.7	5601.1	5600.2	-0.8	-0.02	0.00	0.19	4.0
	2	8003.3	8002.1	8003.4	8002.2	-1.2	-0.01	0.00	0.17	4.0
	2	16010.8	15999.7	16012.0	16000.9	-11.2	-0.07	0.00	0.16	4.0
	2	32028.1	31996.6	32006.7	31999.1	-31.5	-0.10	-0.07	0.16	4.0
	3	56100.9	56004.5	56080.4	55998.6	-96.4	-0.17	-0.03	0.20	4.0
	3	80174.9	79994.9	80165.3	79998.7	-179.9	-0.22	-0.02	0.18	4.0
	3	160383.5	159997.2	160380.8	159995.4	-386.3	-0.24	0.00	0.17	4.0
	3	240465.1	239976.9	240469.2	239982.8	-488.2	-0.20	0.00	0.16	4.0
	3	320610.9	319905.7	320560.3	319989.5	-705.2	-0.22	-0.04	0.16	4.0
	3	401079.8	400352.4	401127.7	400670.5	-727.4	-0.18	-0.07	0.16	4.0
		0.0	0.0	0.0	0.0	0	0.00	0.00	N/A	0.0

Calibration Technician/Engineer Brian CampbellWitness Kevin Kline

Tinius Olsen Testing Machine Company Certificate



Certificate No. 9M9AHP08

Certificate page 1 of 1

Issued By:

Tinius Olsen Testing Machine Company
1065 Easton Road
Horsham, PA 19044 USA
Telephone: 215-675-7100
Fax: 215-441-0899
Email: service@tiniusolsen.com

Cherise Spence
Authorized Signature

Owner/Location: LABORATORY TESTING INC., HATFIELD, PA 19440

Calibration Location: SAME AS ABOVE

Item Description: Strain Rate on Machine S/N 206051STR (#60013377) - As Found/As Left -
No Adjustments - Good Condition

Verification Date: April 29, 2011

Verification Recall Date: April 29, 2012

This is to certify that the Strain Rate on the above testing equipment has been verified by Tinius Olsen Testing Machine Company personnel on Order Number S448750. The listed data is in accordance Tinius Olsen Procedure #2700. Tinius Olsen's Quality System is maintained in compliance with ISO/IEC 17025 (Complies with ISO 9000 Series for Calibration Activity), ANSI / NCSL Z540-1 1994, ISO 10012-1, and MIL-STD-45662A. The estimated expanded uncertainty of the calibration results is: 0.12% of reading. The reported expanded uncertainty is based on a standard uncertainty multiplied by a coverage factor of k=2, providing a level of confidence of approximately 95 percent.

Strain Rate Certificate

All verification devices are traceable to the International System of Units (SI) through either National Institute of Standards and Technology (NIST) or National Physical Laboratory (NPL) and have been verified within one (1) year or less of the above date. For Verification details, refer to the attached Verification Data and Report Form bearing the same Order or Certificate Number as this Certificate.

Serial No	Manufacturer	Description	Calib Vendor	Expiry Date
DSW-0002	HANHART	STOPWATCH	TINIUS OLSEN	4/28/16

Services have been performed in accordance with Tinius Olsen Quality Manual, dated March 13, 2009.

These results relate only to the items calibrated. This Certificate shall not be reproduced except in full, without the written approval of Tinius Olsen.

Tinius Olsen Testing Machine Company Rate Verification Datasheet & Report

Tinius Olsen Procedure used 2700
Rev. 10 April 2007
Page 1 of 2

Date 4/29/11 Certificate # 9M9AHP08
 Order No. 448750 Purchase Order No. PO 0002821
 Customer LABORATORY TESTING Machine Mfg. TINIUS OLSEN
 Location HATFIELD, PA Model and Serial # SUPER L 2060S1
 Machine Display 602 Capacity and Units 400,000 LBF
 Customer ID No. 60613377 Cal. Technician Bruce H. Campbell
 Stopwatch S/N DSW-0002 Strain Device S/N 207344
 Dial Indicator S/N - Gauge Length 2 INCHES
 Temperature 73

Condition (Circle One) ~ As Found / As Left / No Adjustments / Limited Calibration / Out of Tolerance

Load Rate (Circle One) Lbf/Min Kgf/Min N/Min Other _____

Control Setting	Load Range	Load Rate Displayed	Change in Load	Time	Actual Load Rate	Error (actual)	Error %
			N/A				

Strain Rate (Circle One) in/in/min mm/mm/min %/min Other _____
 Split Specimen/Broken Specimen* Previously Untested Specimen

Control Setting	Strain Range	Strain Rate Displayed	Change in Strain	Time	Actual Strain Rate	Error (actual)	Error %
<u>.005</u>	<u>N/A</u>	<u>.005</u>	<u>.005</u>	<u>60.10</u>	<u>.005008</u>	<u>.000008</u>	<u>.16</u>

* If a Split Specimen or Broken Specimen was used for Strain Rate then the ability of the machine to control was not verified.

**Tinius Olsen Testing Machine Company
Instrument Verification Report & Certificate
Specifications per ASTM E 83**



Date of Issue May 03, 2011

Certificate Number 9M9AHP01

Issued by:

Tinius Olsen Testing Machine Company
1065 Easton Road
P.O. Box 1009
Horsham, PA 19044-8009, USA
Tel (215) 675-7100
Fax (215) 441-0899
www.TiniusOlsen.com

Page 1 of 3

Authorized Signature

Cheryl Spinico

Owner/Location LABORATORY TESTING INC, 2331 Topaz Drive, Hatfield, Pennsylvania 19440**Calibration Location** SAME**Item Description** S/N 207344 - LS-4%-2 EXTENS #60013378 - w/ Digital Indicator #206051 - As Found - Out of Tolerance Condition**Year of Mfr.** UNKNOWN **Mfr.** Tinius Olsen **Cal-Check No.** N/A **Cal Factor** N/A**Verification Date** April 29, 2011 **Verification Recall** April 29, 2012

This is to certify that the above testing equipment has been verified by Tinius Olsen Testing Machine Company personnel on Order Number 448750. The listed data is in accordance with the latest practices of ASTM E 83, and Tinius Olsen Procedure #2000, and have been temperature corrected as necessary. Tinius Olsen's Quality System is maintained in compliance with ANSI / NCSL Z540-1 1994, ISO/IEC 17025 (Complies with ISO 9000 Series for Calibration Activity), ISO 10012-1, and MIL-STD-45662A.

Range in/in	Calibration Factor	Class Range in/in	Class
0.0400	0.004	0.0010 TO 0.0400	D

NOT USED FOR
complete range
see page 3
5/9/11

LTI
QA REVIEW
INIT.
DATE 5/11/11

Services have been performed in accordance with Tinius Olsen Quality Manual, dated March 13, 2009.

These results relate only to the items calibrated. This Report and Certificate shall not be reproduced except in full, without the written approval of Tinius Olsen.

Tinius Olsen Testing Machine Company
Instrument Verification Report & Certificate
Specifications per ASTM E 83

Verification Date April 29, 2011

Certificate Number 9M9AHP01

Page 2 of 3

All verification devices comply with the latest practices of ASTM E 83, and are traceable to the International System of Units (SI) through National Institute of Standards and Technology (NIST) or the National Physical Laboratory (NPL). Serial Number, Manufacturer, Type, Calibration Vendor, Expiry Date, and Max Device Error for each standard used during the Certification is listed below. The class of the verification equipment was equal to or better than the requirements of the classification to which this device has been verified.

Serial No.	Manufacturer	Type	Max Device Error	Vendor	Expiry Date
174409-1	Olsen	CALIBRATOR	.00002000	Olsen	15-Jul-11

Informative Notes:

The expanded uncertainties reported are estimates of the measurement uncertainty in the errors determined during the verification. They are expressed as percentages of their respective verification readings. The expanded uncertainties reported are based on combined standard uncertainties, multiplied by a coverage factor of 2, which provide a confidence interval of approximately 95%. The uncertainties reported do not represent the uncertainty of the instrument or the results of any subsequent tests performed with the testing machine. The accuracy of the testing equipment has been found to conform with the tolerance(s) indicated above.

The uncertainties stated refer to the values obtained during verification and make no allowance for factors such as long-term drift, temperature and alignment effects – the influences of such factors should be taken into account by the user of the testing machine.

The expanded uncertainties reported have been calculated in accordance with the latest revision of ASTM E83 - Appendix X4.

Tinius Olsen Testing Machine Company
Instrument Verification Report & Certificate
Specifications per ASTM E 83

Verification Date April 29, 2011Certificate No. 9M9AHP01

Page 3 of 3

Owner/Location LABORATORY TESTING INC, 2331 Topaz Drive Hatfield, Pennsylvania 19440Calibration Location SAMEItem Description S/N 207344 - LS-4%-2 EXTENS #60013378 - w/ Digital Indicator #206051 - As Found - Out of Tolerance ConditionOrder No. 448750 Customer PO No. PO0002821 Customer ID No. _____Year of Mfg. UNKNOWN Temperature Start 21.7 °C Mid N/A °C End 21.7 °CGauge Length: Design 2.00in Measured 1 2.0011in Error 0.0011in 0.055%Measured 2 2.0011 in Error 0.0011 in 0.055%Uncertainty 0.002in Verification Method DirectAttachment Method AS PER INSTRUCTIONS Calibration Position Vertical Readout Method DigitalCal-Check No. N/A Cal Factor N/AVerification Recall Date April 29, 2012

STRAIN RANGE	VERIFIC. READ #1	MACHINE READ #1	VERIFIC. READ #2	MACHINE READ #2	FIXED ERROR	ERROR % OF VALUE	DIFFER. % OF VALUE	UNCERTAINTY % OF VALUE	RESOLUTION FOR RANGE(S)	CLASS FOR READING
in/in	in/in	in/in	in/in	in/in	in/in				in/in	
0.0400	.0010000	.0009728	.0010000	.0000000	-.0000272	-2.72	-2.72	2.40	0.0000010	B-1
	.0020000	.0016575	.0020000	.0000000	-.0003425	-17.12	-17.12	1.20	0.0000010	C
	.0040000	.0026340	.0040000	.0000000	-.0013660	-34.10	-34.10	0.60	0.0000010	D
	.0070000	.0041731	.0070000	.0000000	-.0028269	-40.40	-40.40	0.34	0.0000010	D
	.0100000	.0072402	.0100000	.0000000	-.0027598	-27.60	-27.60	0.24	0.0000010	D
	.0200000	.0167961	.0200000	.0000000	-.0032039	-16.02	-16.02	0.12	0.0000010	D
	.0400000	.0375147	.0400000	.0000000	-.0024853	-6.21	-6.21	0.12	0.0000010	D

* NOT USED IN THIS RANGE
[Signature] 5/9/11

Calibration Technician Brian CampbellWitness Kevin Kline

Tinius Olsen Testing Machine Company
Instrument Verification Report & Certificate
Specifications per ASTM E 83



Date of Issue May 03, 2011

Certificate Number 9M9AHP02

Issued by:

Tinius Olsen Testing Machine Company
 1065 Easton Road
 P.O. Box 1009
 Horsham, PA 19044-8009, USA
 Tel (215) 675-7100
 Fax (215) 441-0899
 www.TiniusOlsen.com

Page 1 of 3

Authorized Signature

Cheryl Spinico

Owner/Location LABORATORY TESTING INC, 2331 Topaz Drive, Hatfield, Pennsylvania 19440
Calibration Location SAME**Item Description** S/N 207344 - LS-4%-2 EXTENS #60013378 - w/ Digital Indicator #206051 - As Left - Good Condition**Year of Mfr.** UNKNOWN **Mfr.** Tinius Olsen **Cal-Check No.** N/A **Cal Factor** N/A**Verification Date** April 29, 2011 **Verification Recall** April 29, 2012

This is to certify that the above testing equipment has been verified by Tinius Olsen Testing Machine Company personnel on Order Number 448750. The listed data is in accordance with the latest practices of ASTM E 83, and Tinius Olsen Procedure #2000, and have been temperature corrected as necessary. Tinius Olsen's Quality System is maintained in compliance with ANSI / NCSL Z540-1 1994, ISO/IEC 17025 (Complies with ISO 9000 Series for Calibration Activity), ISO 10012-1, and MIL-STD-45662A.

Range in/in	Calibration Factor	Class Range in/in	Class
0.0400	0.004	0.0010 TO 0.0400	B-1

Services have been performed in accordance with Tinius Olsen Quality Manual, dated March 13, 2009.

These results relate only to the items calibrated. This Report and Certificate shall not be reproduced except in full, without the written approval of Tinius Olsen.

Tinius Olsen Testing Machine Company
Instrument Verification Report & Certificate
Specifications per ASTM E 83

Verification Date April 29, 2011

Certificate Number 9M9AHP02

Page 2 of 3

All verification devices comply with the latest practices of ASTM E 83, and are traceable to the International System of Units (SI) through National Institute of Standards and Technology (NIST) or the National Physical Laboratory (NPL). Serial Number, Manufacturer, Type, Calibration Vendor, Expiry Date, and Max Device Error for each standard used during the Certification is listed below. The class of the verification equipment was equal to or better than the requirements of the classification to which this device has been verified.

Serial No.	Manufacturer	Type	Max Device Error	Vendor	Expiry Date
174409-1	Olsen	CALIBRATOR	.00002000	Olsen	15-Jul-11

Informative Notes:

The expanded uncertainties reported are estimates of the measurement uncertainty in the errors determined during the verification. They are expressed as percentages of their respective verification readings. The expanded uncertainties reported are based on combined standard uncertainties, multiplied by a coverage factor of 2, which provide a confidence interval of approximately 95%. The uncertainties reported do not represent the uncertainty of the instrument or the results of any subsequent tests performed with the testing machine. The accuracy of the testing equipment has been found to conform with the tolerance(s) indicated above.

The uncertainties stated refer to the values obtained during verification and make no allowance for factors such as long-term drift, temperature and alignment effects – the influences of such factors should be taken into account by the user of the testing machine.

The expanded uncertainties reported have been calculated in accordance with the latest revision of ASTM E83 - Appendix X4.

Tinius Olsen Testing Machine Company
Instrument Verification Report & Certificate
Specifications per ASTM E 83

Verification Date April 29, 2011Certificate No. 9M9AHP02

Page 3 of 3

Owner/Location LABORATORY TESTING INC, 2331 Topaz Drive Hatfield, Pennsylvania 19440Calibration Location SAMEItem Description S/N 207344 - LS-4%-2 EXTENS #60013378 - w/ Digital Indicator #206051 - As Left - Good ConditionOrder No. 448750 Customer PO No. PO0002821 Customer ID No. _____Year of Mfg. UNKNOWN Temperature Start 21.7 °C Mid 22.8 °C End 22.8 °CGauge Length: Design 2.00in Measured 1 2.0011in Error 0.0011in 0.055%Measured 2 2.0011 in Error 0.0011 in 0.055%Uncertainty 0.002in Verification Method DirectAttachment Method AS PER INSTRUCTIONS Calibration Position Vertical Readout Method DigitalCal-Check No. N/A Cal Factor N/AVerification Recall Date April 29, 2012

STRAIN RANGE	VERIFIC. READ #1	MACHINE READ #1	VERIFIC. READ #2	MACHINE READ #2	FIXED ERROR	ERROR % OF VALUE	DIFFER. % OF VALUE	UNCERTAINTY % OF VALUE	RESOLUTION FOR RANGE(S)	CLASS FOR READING
in/in	in/in	in/in	in/in	in/in	in/in				in/in	
0.0400	.0010000	.0010014	.0010000	.0010015	.0000015	0.15	-0.01	2.40	0.0000010	B-1
	.0020000	.0019952	.0020000	.0020057	.0000057	0.29	-0.53	1.20	0.0000010	B-1
	.0040000	.0039754	.0040000	.0039928	-.0000246	-0.61	-0.43	0.60	0.0000010	B-1
	.0070000	.0069742	.0070000	.0069895	-.0000258	-0.37	-0.22	0.34	0.0000010	B-1
	.0100000	.0099552	.0100000	.0099872	-.0000448	-0.45	-0.32	0.24	0.0000010	B-1
	.0200000	.0199417	.0200000	.0199958	-.0000583	-0.29	-0.27	0.12	0.0000010	B-1
	.0400000	.0399920	.0400000	.0400414	.0000414	0.10	-0.12	0.12	0.0000010	B-1

Calibration Technician Brian CampbellWitness Kevin Kline



Tinius Olsen Testing Machine Co.
Corporate Headquarters
1065 Easton Road
Horsham, PA 19044-8009, USA
Tel (215) 675-7100
Fax (215) 441-0899
www.TiniusOlsen.com

May 3, 2011

LABORATORY TESTING INC
2331 Topaz Drive
Hatfield, Pennsylvania 19440

Attn: Frank Peszka

Re: Service Visit S448750

Ladies/Gentlemen:

Enclosed please find your Report and Certificate(s) of Verification covering the following equipment:

S/N 207344 - LS-4%-2 EXTENS #60013378 - w/ Digital Indicator #206051 - As Found - Out of Tolerance Condition
S/N 207344 - LS-4%-2 EXTENS #60013378 - w/ Digital Indicator #206051 - As Left - Good Condition
S/N 64167 - S-1 EXTENS - w/ Digital Indicator #206051 - As Found - Out of Tolerance Condition
S/N 64167 - S-1 EXTENS - w/ Digital Indicator #206051 - As Left - Good Condition
S/N 206051P - POSITION #60013377 Ascending - w/ Computer Display #206051 - No Adjustments - Good Condition
S/N 206051SR - SPEED RATE #60013377 - No Adjustments - Good Condition
S/N 206051 - 400000 lbf HYD SPR L602 #60013377 - w/ Digital Indicator - No Adjustments - Good Condition
S/N 206051-STR - STRAIN RATE #60013377 - No Adjustments - Good Condition

We trust these certificates complete your files.

Very truly yours,

Tinius Olsen Testing Machine Company

A handwritten signature in cursive script that reads "Cheryl Spinico".

Cheryl Spinico
Authorized Signature

Encl.

Since 1880 . . . a tradition of leadership in materials testing

Tinius Olsen

Corporate Headquarters

1065 Easton Road

Horsham, PA USA 19044-8009

(215) 675-7100; Fax (215) 441-0899

Service@TiniusOlsen.com

www.TiniusOlsen.com



Field Service Report

Date: 29-Apr-2011 **Service Order Number:** 448750
Customer: Frank Peszka **Purchase Order Number:** PO0002821
 LABORATORY TESTING INC
 2331 Topaz Drive
 Hatfield, Pennsylvania 19440
Account Number: 304995

Scheduled Work Completed

Date	Serial Number	Capacity	Name
29-Apr-2011	207344		LS-4%-2 EXTENS #60013378
	Calibration: 1	w/ Digital Indicator #206051 - As Found - Out of Tolerance Condition, Witnessed By: Kevin Kline	Notes: I found the pivot screws very loose.
	Calibration: 2	w/ Digital Indicator #206051 - As Left - Good Condition, Witnessed By: Kevin Kline	
29-Apr-2011	64167		S-1 EXTENS
	Calibration: 1	w/ Digital Indicator #206051 - As Found - Out of Tolerance Condition, Witnessed By: Kevin Kline	Notes: I found the readings out over 1%.
	Calibration: 2	w/ Digital Indicator #206051 - As Left - Good Condition, Witnessed By: Kevin Kline	
29-Apr-2011	206051P		POSITION #60013377
	Calibration: 1	Ascending - w/ Computer Display #206051 - No Adjustments - Good Condition, Witnessed By: Kevin Kline	
29-Apr-2011	206051SR		SPEED RATE #60013377
	Calibration: 1	No Adjustments - Good Condition, Witnessed By: Kevin Kline	Notes: THE EQUIPMENT USED FOR THIS CALIBRATION WAS THE MACHINES CALIBRATED POSITION DISPLAY ALONG WITH A CERTIFIED STOP WATCH.
29-Apr-2011	206051	400000 LBF	HYD SPR L602 #60013377
	Calibration: 1	- w/ Digital Indicator - No Adjustments - Good Condition, Witnessed By: Kevin Kline	
29-Apr-2011	206051-STR		STRAIN RATE #60013377
	Calibration: 1	No Adjustments - Good Condition, Witnessed By: Kevin Kline	Notes: THE EQUIPMENT USED FOR THIS CALIBRATION WAS A CALIBRATED EXTENSOMETER AND A DUMMY SPECIMEN.

Service Technician Notes

The above machine calibrated to within 1% no adjustments were made. Position speed and strain were also performed. As Found and As Left was performed on both extensometers.

Parts Used

Item Number	Description	Qty
90001429	PIVOT SCREW with Hex Nut, Standard 5-44 THDS	2

Work performed by: Campbell, Brian

Page No. 1

Arrive: 29-Apr-2011 08:30 AM

Depart: 29-Apr-2011 01:00 PM

SOLD TO: HARRIS SUPPLY SOLUTIONS INC
318 ARVIN AVE
STONE CREEK ON L8E 2M2
CANADA



CERTIFIED MILL TEST REPORT

Page: 1

SHIP TO: HARRIS SUPPLY SOLUTIONS INC
C/O KINDER MORGAN CHICAGO IL
162 EAST 26TH STREET
CHICAGO HEIGHTS, IL 60411-

Ship from:
Nucor Steel Kankakee, Inc.
One Nucor Way
Bourbonnais, IL 60914
845-937-3131

Date: 24-May-2011
B.L. Number: 424276
Load Number: 211049

Material Safety Data Sheets are available at www.nucorbar.com or by contacting your inside sales representative.

NSMG-08 March 9, 2011

HEAT NUM. *	DESCRIPTION	PHYSICAL TESTS					CHEMICAL TESTS												
		YIELD P.S.I.	TENSILE P.S.I.	ELONG % IN 8"	BEND	WT% DEF	C	Ni	Mn	Cr	P	Mo	S	V	Si	Cb	Cu	Sn	C.E.
PO# => KN1110050601	P109963-CYCLE 3 Nucor Steel - Kankakee Inc 36/#11 Rebar 60' A615M Gr 420 (Gr60) ASTM A615/A615M-09b GR 60[420] AASHTO M31-07 Melted 01/31/11 Rolled 02/10/11	69,560 480MPa	99,605 687MPa	10.0%	OK	-3.5% .085	.39 .23	1.21 .16	.013 .069	.041 .007	.21 .002	.38	.63						
PO# => KN1110054001	P109963-CYCLE 3 Nucor Steel - Kankakee Inc 36/#11 Rebar 60' A615M Gr 420 (Gr60) ASTM A615/A615M-09b GR 60[420] AASHTO M31-07 Melted 02/07/11 Rolled 02/10/11	66,054 455MPa	98,737 681MPa	16.0%	OK	-3.2% .084	.40 .20	1.04 .09	.013 .063	.047 .019	.23 .002	.35	.60						

*Call Circ City
from which heat
did we get*

I hereby certify that the material described herein has been manufactured in accordance with the specifications and standards listed above and that it satisfies those requirements.
1.) Weld repair was not performed on this material.
2.) Melted and Manufactured in the United States.
3.) Mercury, Radium, or Alpha source materials in any form have not been used in the production of this material.

SOLD TO: HARRIS SUPPLY SOLUTIONS INC
318 ARVIN AVE
STONEY CREEK ON L8E 2M2
CANADA



CERTIFIED MILL TEST REPORT

Page: 1

SHIP TO: HARRIS SUPPLY SOLUTIONS INC
C/O KINDER MORGAN CHICAGO IL
162 EAST 26TH STREET
CHICAGO HEIGHTS, IL 60411-

Ship from:
Nucor Steel Kankakee, Inc.
One Nucor Way
Bourbonnais, IL 60914
815-937-3131

Date: 25-Aug-2011
B.L. Number: 429448
Load Number: 214504


Material Safety Data Sheets are available at www.nucorbar.com or by contacting your inside sales representative.

NBMG-08 March 5, 2011

HEAT NUM.*	DESCRIPTION	PHYSICAL TESTS					CHEMICAL TESTS												
		YIELD P.S.I.	TENSILE P.S.I.	ELONG % IN 8"	BEND	WT% DEF	C	Ni	Mn	Cr	P	Mo	S	V	Si	Cb	Cu	Sn	C.E.
PO# => KN1110329601	p111330 Nucor Steel - Kankakee Inc 13/#4 Rebar 60' A615M Gr 420 (Gr60) ASTM A615/A615M-09b GR 60[420] AASHTO M31-07 Melted 08/02/11 Rolled 08/10/11	68,748 474MPa	104,388 720MPa	14.8%	OK	-0.8% .030	.38 .26	.99 .11	.015 .076	.047 .011	.22 .002	.35	.58						
PO# => KN1110329701	p111330 Nucor Steel - Kankakee Inc 13/#4 Rebar 60' A615M Gr 420 (Gr60) ASTM A615/A615M-09b GR 60[420] AASHTO M31-07 Melted 08/02/11 Rolled 08/10/11	64,499 445MPa	97,943 675MPa	17.5%	OK	-2.7% .030	.36 .25	.99 .12	.015 .069	.050 .011	.20 .002	.38	.56						

I hereby certify that the material described herein has been manufactured in accordance with the specifications and standards listed above and that it satisfies those requirements.
1.) Weld repair was not performed on this material.
2.) Melted and Manufactured in the United States.
3.) Mercury, Radium, or Alpha source materials in any form have not been used in the production of this material.

QUALITY ASSURANCE: Curtis Glenn



Laboratory Testing Inc.
 2331 Topaz Drive
 Hatfield, PA 19440

Rebar @ .2% Offset

Customer	Purdue University
Traveler #	12-13151
Machine #	400K (60013377)
Extensometer #	2" (60013378)
Caliper #	(60012882)
Micrometer#	N/A
Operator	PLS

Test Setting	Rebar .2% Offset
	Yield


-----:
 Sample No.: 1
 Heat No.: *****
 -----:

Diameter, in:	1.4100
Area, in ² :	1.5600
Modulus, Mpsi:	31.2

-----:
 Ultimate, lbf: 160911
 Yield Pt., lbf: 102674
 OS @ .2, lbf: 102558
 -----:

Ultimate, ksi:	103
Yield Pt., ksi:	66
OS @ .2, ksi:	65.5

TE, %:	19
Frac. Location:	Within 2/3




Laboratory Testing Inc.
 2331 Topaz Drive
 Hatfield, PA 19440

Rebar @ .2% Offset

Customer	Purdue University
Traveler #	12-13151
Machine #	400K (60013377)
Extensometer #	2" (60013378)
Caliper #	(60012882)
Micrometer#	N/A
Operator	PLS

Test Setting	Rebar .2% Offset
	Yield

-----:	
Sample No.:	2
Heat No.:	*****
-----:	
Diameter, in:	1.4100
Area, in ² :	1.5600
Modulus, Mpsi:	28.5
-----:	
Ultimate, lbf:	160609
Yield Pt., lbf:	102397
OS @ .2, lbf:	102583
-----:	
Ultimate, ksi:	103
Yield Pt., ksi:	65.5
OS @ .2, ksi:	66
TE, %:	14
Frac. Location:	Outside 2/3



Laboratory Testing Inc.
 2331 Topaz Drive
 Hatfield, PA 19440

Rebar @ .2% Offset

Customer	Purdue University
Traveler #	12-13151
Machine #	400K (60013377)
Extensometer #	2" (60013378)
Caliper #	(60012882)
Micrometer#	N/A
Operator	PLS

Test Setting	Rebar .2% Offset
	Yield


-----:	
Sample No.:	3
Heat No.:	*****
-----:	
Diameter, in:	1.4100
Area, in ² :	1.5600
Modulus, Mpsi:	30.9
-----:	
Ultimate, lbf:	160453
Yield Pt., lbf:	102794
OS @ .2, lbf:	102589
-----:	
Ultimate, ksi:	103
Yield Pt., ksi:	66
OS @ .2, ksi:	66
TE, %:	18
Frac. Location:	Within 2/3

**SERIES A
A1**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/17/2012**

TEST GIRDER A1



X-Sect. Area for a #11 Bar

$$A_{sb} := 1.56 \text{ in}^2$$

Diameter, # 11 Bar

$$d_b := 1.41 \text{ in}$$

Nominal width of Section

$$b := \left(17 + \frac{5}{8} \right) \cdot \text{in}$$

Nominal height of Section

$$h := 30 \text{ in}$$

Top cover

$$c_t := 5 \text{ in}$$

Effective depth

$$d := 30 \text{ in} - c_t - \frac{d_b}{2}$$

$$d = 24 \cdot \text{in}$$

Yield Stress

$$f_y := 66 \text{ ksi}$$

Concrete Strength

$$f'_c := 5270 \text{ psi}$$

Total Length

$$L_t := 39 \text{ ft}$$

Cantilevered Span

$$a := 11 \text{ ft} + 6 \text{ in}$$

$$a = 11.5 \text{ ft}$$

Interior Span

$$L_m := 16 \text{ ft}$$

$$L_m = 16 \text{ ft}$$

Reinforcement Ratio

$$\rho := 2 \cdot \frac{A_{sb}}{b \cdot d}$$

$$\rho = 0.73 \cdot \%$$

Initial moment at support

$$M_{\text{supinit}} := 45.8 \text{ kip} \cdot \text{ft}$$

**SERIES A
A1**

Reinforcement Stress

Formatted 27 May 12

Printed 6/17/2012

EVALUATION AFTER TEST TO FAILURE

REINFORCEMENT STRESS AT MEASURED MAXIMUM LOAD

Note : Following calculations are made considering the supports not to have width in the direction of the span.

$$\text{Unit selfweight} \quad w_s := b \cdot h \cdot 150 \frac{\text{lb}}{\text{ft}^3} \quad w_s = 0.55 \cdot \frac{\text{kip}}{\text{ft}}$$

$$\text{Measured Maximum Applied Load} \quad P_{\max} := 43.5 \text{kip}$$

Moment at support related to selfweight and loading gear

$$M_{\text{supinit}} = 46 \cdot \text{kip} \cdot \text{ft}$$

Maximum moment at support

$$M_{\text{supmax}} := P_{\max} \cdot (a - 18 \text{in}) + M_{\text{supinit}}$$

Moment at 3 ft toward mid-span from support

$$M_{3\text{ft}} := -M_{\text{supmax}} + \frac{w_s \cdot L_m}{2} \cdot 3\text{ft} - w_s \cdot \frac{(3\text{ft})^2}{2}$$

$$M_{3\text{ft}} = -470 \cdot \text{kip} \cdot \text{ft}$$

NOTE : Strain distributions over the depth of the section at the supports and at ends of the spliced bars are not linear once cracking is initiated. To assume a linear strain distribution and then to use an "exact" stress-strain relationship for the concrete is not correct. In the following, stresses in the reinforcement will be calculated assuming both linear and nonlinear response in the compressed concrete, and the lower value determined will be taken as the stress achieved. In both sets of calculations, contribution of the tensile strength of the concrete will be considered negligible.

**SERIES A
A1****Reinforcement Stress****Formatted 27 May 12
Printed 6/17/2012**

**MAXIMUM REINFORCEMENT STRESS AT SUPPORT
ASSUMING FULLY NONLINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$f_{\text{supmaxnon}} := \frac{M_{\text{supmax}}}{2 \cdot A_{\text{sb}} \cdot d \cdot \left(1 - 0.4 \cdot \frac{\rho \cdot 81 \text{ ksi}}{0.7 \cdot f'_c} \right)} = 81 \cdot \text{ksi}$$

**MAXIMUM REINFORCEMENT STRESS AT SUPPORT
ASSUMING FULLY LINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$\text{Conc. modulus} \quad E_c := 57000 \cdot \sqrt{f'_c \cdot \text{psi}} \quad E_c = 4.1 \times 10^6 \text{ psi}$$

Steel modulus

$$E_s := 29000 \text{ ksi}$$

Modular ratio

$$n := \frac{E_s}{E_c} \quad n = 7$$

Depth to neutral axis from extreme fiber in compression

$$k := \sqrt{(\rho \cdot n)^2 + 2 \cdot \rho \cdot n} - \rho \cdot n \quad k = 0.27$$

$$f_{\text{supmaxlin}} := \frac{M_{\text{supmax}}}{2 \cdot A_{\text{sb}} \cdot d \cdot \left(1 - \frac{k}{3} \right)} = 84 \cdot \text{ksi}$$

Check related maximum compressive stress in concrete

$$f_{\text{clin1}} := \frac{M_{\text{supmax}}}{\left(\frac{k \cdot b \cdot d^2}{2} \right) \cdot \left(1 - \frac{k}{3} \right)} = 4.5 \times 10^3 \cdot \text{psi} \quad (\text{Compression})$$

**SERIES A
A1**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/17/2012**

**MAXIMUM REINFORCEMENT STRESS IN CONTINUOUS
BAR AT END OF SPLICE ASSUMING FULLY NONLINEAR
DISTRIBUTION OF COMPRESSIVE STRESS IN THE
CONCRETE**

$$f_{snon3} := \frac{-M_{3ft}}{2 \cdot A_{sb} \cdot d \cdot \left(1 - 0.4 \cdot \frac{\rho \cdot 79 \text{ksi}}{0.7 \cdot f'_c}\right)} = 79 \cdot \text{ksi}$$

**MAXIMUM REINFORCEMENT STRESS IN CONTINUOUS BAR
AT END OF SPLICE ASSUMING LINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$f_{slin3} := \frac{-M_{3ft}}{2 \cdot A_{sb} \cdot d \cdot \left(1 - \frac{k}{3}\right)} = 82 \cdot \text{ksi}$$

Check related maximum concrete stress

$$f_{clin3} := \frac{-M_{3ft}}{\left(\frac{k \cdot b \cdot d^2}{2}\right) \cdot \left(1 - \frac{k}{3}\right)} = 4.4 \times 10^3 \text{ psi} \quad (\text{Compression})$$

**SERIES A
A1**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/17/2012**

SUMMARY

Reinforcement stress based on observed maximum load

At support

NONLINEAR

LINEAR

$$f_{\text{supmaxnon}} = 81 \cdot \text{ksi}$$

$$f_{\text{supmaxlin}} = 84 \cdot \text{ksi}$$

At splice end

$$f_{\text{snon3}} = 79 \cdot \text{ksi}$$

$$f_{\text{slin3}} = 82 \cdot \text{ksi}$$

NOMINAL UNIT BOND STRESS

Length of splice

$$L_d := 120 \text{in}$$

Bar diameter

$$d_b = 1.41 \cdot \text{in}$$

Average bond stress at maximum load

$$\mu_{\text{avg}} := \frac{f_{\text{snon3}} \cdot d_b}{4 \cdot L_d}$$

$$\text{round}\left(\frac{\mu_{\text{avg}}}{\text{psi}}, -1\right) \cdot \text{psi} = 230 \text{psi}$$

The number listed above for bond stress has relevance to design but is irrelevant to the actual bond stress at maximum load.

The hard information from the test is that the 120-in splice for No. 11 bars has developed a maximum bar stress of at least


$$f_{\text{snon3}} = 79 \cdot \text{ksi}$$

**SERIES A
A2**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/17/2012**

TEST GIRDER A2



X-Sect. Area for a #11 Bar

$$A_{sb} := 1.56 \text{ in}^2$$

Diameter, # 11 Bar

$$d_b := 1.41 \text{ in}$$

Nominal width of Section

$$b := \left(17 + \frac{5}{8} \right) \cdot \text{in}$$

Nominal height of Section

$$h := 30 \text{ in}$$

Top cover

$$c_t := 5 \text{ in}$$

Effective depth

$$d := 30 \text{ in} - c_t - \frac{d_b}{2}$$

$$d = 24 \cdot \text{in}$$

Yield Stress

$$f_y := 66 \text{ ksi}$$

Concrete Strength

$$f'_c := 6030 \text{ psi}$$

Total Length

$$L_t := 39 \text{ ft}$$

Cantilevered Span

$$a := 11 \text{ ft} + 6 \text{ in}$$

$$a = 11.5 \text{ ft}$$

Interior Span

$$L_m := 16 \text{ ft}$$

$$L_m = 16 \text{ ft}$$

Reinforcement Ratio

$$\rho := 2 \cdot \frac{A_{sb}}{b \cdot d}$$

$$\rho = 0.73 \cdot \%$$

Initial moment at support

$$M_{\text{supinit}} := 45.8 \text{ kip} \cdot \text{ft}$$

**SERIES A
A2**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/17/2012**

EVALUATION AFTER TEST TO FAILURE

REINFORCEMENT STRESS AT MEASURED MAXIMUM LOAD

Note : Following calculations are made considering the supports not to have width in the direction of the span.

$$\text{Unit selfweight} \quad w_s := b \cdot h \cdot 150 \frac{\text{lb}}{\text{ft}^3} \quad w_s = 0.55 \cdot \frac{\text{kip}}{\text{ft}}$$

$$\text{Measured Maximum Applied Load} \quad P_{\max} := 44.1 \text{ kip}$$

Moment at support related to selfweight and loading gear

$$M_{\text{supinit}} = 46 \cdot \text{kip} \cdot \text{ft}$$

Maximum moment at support

$$M_{\text{supmax}} := P_{\max} \cdot (a - 18 \text{ in}) + M_{\text{supinit}}$$

Moment at 3 ft toward mid-span from support

$$M_{3\text{ft}} := -M_{\text{supmax}} + \frac{w_s \cdot L_m}{2} \cdot 3\text{ft} - w_s \cdot \frac{(3\text{ft})^2}{2}$$

$$M_{3\text{ft}} = -476 \cdot \text{kip} \cdot \text{ft}$$

NOTE : Strain distributions over the depth of the section at the supports and at ends of the spliced bars are not linear once cracking is initiated. To assume a linear strain distribution and then to use an "exact" stress-strain relationship for the concrete is not correct. In the following, stresses in the reinforcement will be calculated assuming both linear and nonlinear response in the compressed concrete, and the lower value determined will be taken as the stress achieved. In both sets of calculations, contribution of the tensile strength of the concrete will be considered negligible.

**SERIES A
A2****Reinforcement Stress****Formatted 27 May 12
Printed 6/17/2012**

**MAXIMUM REINFORCEMENT STRESS AT SUPPORT
ASSUMING FULLY NONLINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$f_{\text{supmaxnon}} := \frac{M_{\text{supmax}}}{2 \cdot A_{\text{sb}} \cdot d \cdot \left(1 - 0.4 \cdot \frac{\rho \cdot 82 \text{ksi}}{0.7 \cdot f'_c} \right)} = 82 \cdot \text{ksi}$$

**MAXIMUM REINFORCEMENT STRESS AT SUPPORT
ASSUMING FULLY LINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$\text{Conc. modulus} \quad E_c := 57000 \cdot \sqrt{f'_c \cdot \text{psi}} \quad E_c = 4.4 \times 10^6 \text{ psi}$$

Steel modulus

$$E_s := 29000 \text{ksi}$$

Modular ratio

$$n := \frac{E_s}{E_c} \quad n = 7$$

Depth to neutral axis from extreme fiber in compression

$$k := \sqrt{(\rho \cdot n)^2 + 2 \cdot \rho \cdot n} - \rho \cdot n \quad k = 0.26$$

$$f_{\text{supmaxlin}} := \frac{M_{\text{supmax}}}{2 \cdot A_{\text{sb}} \cdot d \cdot \left(1 - \frac{k}{3} \right)} = 85 \cdot \text{ksi}$$

Check related maximum compressive stress in concrete

$$f_{\text{clin1}} := \frac{M_{\text{supmax}}}{\left(\frac{k \cdot b \cdot d^2}{2} \right) \cdot \left(1 - \frac{k}{3} \right)} = 4.6 \times 10^3 \cdot \text{psi} \quad (\text{Compression})$$

**SERIES A
A2**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/17/2012**

**MAXIMUM REINFORCEMENT STRESS IN CONTINUOUS
BAR AT END OF SPLICE ASSUMING FULLY NONLINEAR
DISTRIBUTION OF COMPRESSIVE STRESS IN THE
CONCRETE**

$$f_{snon3} := \frac{-M_{3ft}}{2 \cdot A_{sb} \cdot d \cdot \left(1 - 0.4 \cdot \frac{\rho \cdot 80\text{ksi}}{0.7 \cdot f'_c}\right)} = 80 \cdot \text{ksi}$$

**MAXIMUM REINFORCEMENT STRESS IN CONTINUOUS BAR
AT END OF SPLICE ASSUMING LINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$f_{slin3} := \frac{-M_{3ft}}{2 \cdot A_{sb} \cdot d \cdot \left(1 - \frac{k}{3}\right)} = 83 \cdot \text{ksi}$$

Check related maximum concrete stress

$$f_{clin3} := \frac{-M_{3ft}}{\left(\frac{k \cdot b \cdot d^2}{2}\right) \cdot \left(1 - \frac{k}{3}\right)} = 4.5 \times 10^3 \text{ psi} \quad (\text{Compression})$$

**SERIES A
A2**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/17/2012**

SUMMARY

Reinforcement stress based on observed maximum load

At support

NONLINEAR

LINEAR

$$f_{\text{supmaxnon}} = 82 \cdot \text{ksi}$$

$$f_{\text{supmaxlin}} = 85 \cdot \text{ksi}$$

At splice end

$$f_{\text{snon3}} = 80 \cdot \text{ksi}$$

$$f_{\text{slin3}} = 83 \cdot \text{ksi}$$

NOMINAL UNIT BOND STRESS

Length of splice

$$L_d := 120 \text{in}$$

Bar diameter

$$d_b = 1.41 \cdot \text{in}$$

Average bond stress at maximum load

$$\mu_{\text{avg}} := \frac{f_{\text{snon3}} \cdot d_b}{4 \cdot L_d}$$

$$\text{round}\left(\frac{\mu_{\text{avg}}}{\text{psi}}, -1\right) \cdot \text{psi} = 230 \text{psi}$$

The number listed above for bond stress has relevance to design but is irrelevant to the actual bond stress at maximum load.

The hard information from the test is that the 120-in splice for No. 11 bars has developed a maximum bar stress of at least


$$f_{\text{snon3}} = 80 \cdot \text{ksi}$$

**SERIES A
A3**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/17/2012**

TEST GIRDER A3



X-Sect. Area for a #11 Bar

$$A_{sb} := 1.56 \text{ in}^2$$

Diameter, # 11 Bar

$$d_b := 1.41 \text{ in}$$

Nominal width of Section

$$b := \left(17 + \frac{5}{8} \right) \cdot \text{in}$$

Nominal height of Section

$$h := 30 \text{ in}$$

Top cover

$$c_t := 5 \text{ in}$$

Effective depth

$$d := 30 \text{ in} - c_t - \frac{d_b}{2}$$

$$d = 24 \cdot \text{in}$$

Yield Stress

$$f_y := 66 \text{ ksi}$$

Concrete Strength

$$f'_c := 5890 \text{ psi}$$

Total Length

$$L_t := 39 \text{ ft}$$

Cantilevered Span

$$a := 11 \text{ ft} + 6 \text{ in}$$

$$a = 11.5 \text{ ft}$$

Interior Span

$$L_m := 16 \text{ ft}$$

$$L_m = 16 \text{ ft}$$

Reinforcement Ratio

$$\rho := 2 \cdot \frac{A_{sb}}{b \cdot d}$$

$$\rho = 0.73 \cdot \%$$

**SERIES A
A3**

Reinforcement Stress

Formatted 27 May 12

Printed 6/17/2012

Initial moment at support

$$M_{\text{supinit}} := 45.8 \text{ kip} \cdot \text{ft}$$

EVALUATION AFTER TEST TO FAILURE

REINFORCEMENT STRESS AT MEASURED MAXIMUM LOAD

Note : Following calculations are made considering the supports not to have width in the direction of the span.

$$\text{Unit selfweight} \quad w_s := b \cdot h \cdot 150 \frac{\text{lb}}{\text{ft}^3} \quad w_s = 0.55 \cdot \frac{\text{kip}}{\text{ft}}$$

$$\text{Measured Maximum Applied Load} \quad P_{\text{max}} := 44.1 \text{ kip}$$

Moment at support related to selfweight and loading gear

$$M_{\text{supinit}} = 46 \cdot \text{kip} \cdot \text{ft}$$

Maximum moment at support

$$M_{\text{supmax}} := P_{\text{max}} \cdot (a - 18 \text{ in}) + M_{\text{supinit}}$$

Moment at 3 ft toward mid-span from support

$$M_{3\text{ft}} := -M_{\text{supmax}} + \frac{w_s \cdot L_m}{2} \cdot 3\text{ft} - w_s \cdot \frac{(3\text{ft})^2}{2}$$

$$M_{3\text{ft}} = -476 \cdot \text{kip} \cdot \text{ft}$$

NOTE : Strain distributions over the depth of the section at the supports and at ends of the spliced bars are not linear once cracking is initiated. To assume a linear strain distribution and then to use an "exact" stress-strain relationship for the concrete is not correct. In the following, stresses in the reinforcement will be calculated assuming both linear and nonlinear response in the compressed concrete, and the lower value determined will be taken as the stress achieved. In both sets of calculations, contribution of the tensile strength of the concrete will be considered negligible.

**SERIES A
A3****Reinforcement Stress****Formatted 27 May 12
Printed 6/17/2012**

**MAXIMUM REINFORCEMENT STRESS AT SUPPORT
ASSUMING FULLY NONLINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$f_{\text{supmaxnon}} := \frac{M_{\text{supmax}}}{2 \cdot A_{\text{sb}} \cdot d \cdot \left(1 - 0.4 \cdot \frac{\rho \cdot 82 \text{ksi}}{0.7 \cdot f'_c} \right)} = 82 \cdot \text{ksi}$$

**MAXIMUM REINFORCEMENT STRESS AT SUPPORT
ASSUMING FULLY LINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$\text{Conc. modulus} \quad E_c := 57000 \cdot \sqrt{f'_c \cdot \text{psi}} \quad E_c = 4.4 \times 10^6 \text{ psi}$$

Steel modulus

$$E_s := 29000 \text{ ksi}$$

Modular ratio

$$n := \frac{E_s}{E_c} \quad n = 7$$

Depth to neutral axis from extreme fiber in compression

$$k := \sqrt{(\rho \cdot n)^2 + 2 \cdot \rho \cdot n} - \rho \cdot n \quad k = 0.27$$

$$f_{\text{supmaxlin}} := \frac{M_{\text{supmax}}}{2 \cdot A_{\text{sb}} \cdot d \cdot \left(1 - \frac{k}{3} \right)} = 85 \cdot \text{ksi}$$

Check related maximum compressive stress in concrete

$$f_{\text{clin1}} := \frac{M_{\text{supmax}}}{\left(\frac{k \cdot b \cdot d^2}{2} \right) \cdot \left(1 - \frac{k}{3} \right)} = 4.6 \times 10^3 \cdot \text{psi} \quad (\text{Compression})$$

**SERIES A
A3**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/17/2012**

**MAXIMUM REINFORCEMENT STRESS IN CONTINUOUS
BAR AT END OF SPLICE ASSUMING FULLY NONLINEAR
DISTRIBUTION OF COMPRESSIVE STRESS IN THE
CONCRETE**

$$f_{snon3} := \frac{-M_{3ft}}{2 \cdot A_{sb} \cdot d \cdot \left(1 - 0.4 \cdot \frac{\rho \cdot 80\text{ksi}}{0.7 \cdot f'_c}\right)} = 80 \cdot \text{ksi}$$

**MAXIMUM REINFORCEMENT STRESS IN CONTINUOUS BAR
AT END OF SPLICE ASSUMING LINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$f_{slin3} := \frac{-M_{3ft}}{2 \cdot A_{sb} \cdot d \cdot \left(1 - \frac{k}{3}\right)} = 83 \cdot \text{ksi}$$

Check related maximum concrete stress

$$f_{clin3} := \frac{-M_{3ft}}{\left(\frac{k \cdot b \cdot d^2}{2}\right) \cdot \left(1 - \frac{k}{3}\right)} = 4.5 \times 10^3 \text{ psi} \quad (\text{Compression})$$

**SERIES A
A3**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/17/2012**

SUMMARY

Reinforcement stress based on observed maximum load

At support

NONLINEAR

LINEAR

$$f_{\text{supmaxnon}} = 82 \cdot \text{ksi}$$

$$f_{\text{supmaxlin}} = 85 \cdot \text{ksi}$$

At splice end

$$f_{\text{snon3}} = 80 \cdot \text{ksi}$$

$$f_{\text{slin3}} = 83 \cdot \text{ksi}$$

NOMINAL UNIT BOND STRESS

Length of splice

$$L_d := 120 \text{in}$$

Bar diameter

$$d_b = 1.41 \cdot \text{in}$$

Average bond stress at maximum load

$$\mu_{\text{avg}} := \frac{f_{\text{snon3}} \cdot d_b}{4 \cdot L_d}$$

$$\text{round}\left(\frac{\mu_{\text{avg}}}{\text{psi}}, -1\right) \cdot \text{psi} = 230 \text{psi}$$

The number listed above for bond stress has relevance to design but is irrelevant to the actual bond stress at maximum load.

The hard information from the test is that the 120-in splice for No. 11 bars has developed a maximum bar stress of at least


$$f_{\text{snon3}} = 80 \cdot \text{ksi}$$

**SERIES A
A4**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/18/2012**

TEST GIRDER A4



X-Sect. Area for a #11 Bar

$$A_{sb} := 1.56 \text{ in}^2$$

Diameter, # 11 Bar

$$d_b := 1.41 \text{ in}$$

Nominal width of Section

$$b := \left(17 + \frac{5}{8} \right) \cdot \text{in}$$

Nominal height of Section

$$h := 30 \text{ in}$$

Top cover

$$c_t := 5 \text{ in}$$

Effective depth

$$d := 30 \text{ in} - c_t - \frac{d_b}{2}$$

$$d = 24 \cdot \text{in}$$

Yield Stress

$$f_y := 66 \text{ ksi}$$

Concrete Strength

$$f'_c := 5110 \text{ psi}$$

Total Length

$$L_t := 39 \text{ ft}$$

Cantilevered Span

$$a := 11 \text{ ft} + 6 \text{ in}$$

$$a = 11.5 \text{ ft}$$

Interior Span

$$L_m := 16 \text{ ft}$$

$$L_m = 16 \text{ ft}$$

Reinforcement Ratio

$$\rho := 2 \cdot \frac{A_{sb}}{b \cdot d}$$

$$\rho = 0.73 \cdot \%$$

Initial moment at support

$$M_{\text{supinit}} := 45.8 \text{ kip} \cdot \text{ft}$$

**SERIES A
A4**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/18/2012**

EVALUATION AFTER TEST TO FAILURE

REINFORCEMENT STRESS AT MEASURED MAXIMUM LOAD

Note : Following calculations are made considering the supports not to have width in the direction of the span.

$$\text{Unit selfweight} \quad w_s := b \cdot h \cdot 150 \frac{\text{lb}}{\text{ft}^3} \quad w_s = 0.55 \cdot \frac{\text{kip}}{\text{ft}}$$

$$\text{Measured Maximum Applied Load} \quad P_{\max} := 43.3 \text{kip}$$

Moment at support related to selfweight and loading gear

$$M_{\text{supinit}} = 46 \cdot \text{kip} \cdot \text{ft}$$

Maximum moment at support

$$M_{\text{supmax}} := P_{\max} \cdot (a - 18\text{in}) + M_{\text{supinit}}$$

Moment at 3 ft toward mid-span from support

$$M_{3\text{ft}} := M_{\text{supmax}} - \frac{w_s \cdot L_m}{2} \cdot 3\text{ft} + w_s \cdot \frac{(3\text{ft})^2}{2} = 468 \cdot \text{kip} \cdot \text{ft}$$

$$M_{3\text{ft}} = 468 \cdot \text{kip} \cdot \text{ft}$$

NOTE : Strain distributions over the depth of the section at the supports and at ends of the spliced bars are not linear once cracking is initiated. To assume a linear strain distribution and then to use an "exact" stress-strain relationship for the concrete is not correct. In the following, stresses in the reinforcement will be calculated assuming both linear and nonlinear response in the compressed concrete, and the lower value determined will be taken as the stress achieved. In both sets of calculations, contribution of the tensile strength of the concrete will be considered negligible.

**SERIES A
A4****Reinforcement Stress****Formatted 27 May 12
Printed 6/18/2012**

**MAXIMUM REINFORCEMENT STRESS AT SUPPORT
ASSUMING FULLY NONLINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$f_{\text{supmaxnon}} := \frac{M_{\text{supmax}}}{2 \cdot A_{\text{sb}} \cdot d \cdot \left(1 - 0.4 \cdot \frac{\rho \cdot 82 \text{ksi}}{0.7 \cdot f'_c} \right)} = 81 \cdot \text{ksi}$$

**MAXIMUM REINFORCEMENT STRESS AT SUPPORT
ASSUMING FULLY LINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$\text{Conc. modulus} \quad E_c := 57000 \cdot \sqrt{f'_c \cdot \text{psi}} \quad E_c = 4.1 \times 10^6 \text{ psi}$$

Steel modulus

$$E_s := 29000 \text{ksi}$$

Modular ratio

$$n := \frac{E_s}{E_c} \quad n = 7$$

Depth to neutral axis from extreme fiber in compression

$$k := \sqrt{(\rho \cdot n)^2 + 2 \cdot \rho \cdot n} - \rho \cdot n \quad k = 0.27$$

$$f_{\text{supmaxlin}} := \frac{M_{\text{supmax}}}{2 \cdot A_{\text{sb}} \cdot d \cdot \left(1 - \frac{k}{3} \right)} = 83 \cdot \text{ksi}$$

Check related maximum compressive stress in concrete

$$f_{\text{clin1}} := \frac{M_{\text{supmax}}}{\left(\frac{k \cdot b \cdot d^2}{2} \right) \cdot \left(1 - \frac{k}{3} \right)} = 4.4 \times 10^3 \cdot \text{psi} \quad (\text{Compression})$$

**SERIES A
A4**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/18/2012**

**MAXIMUM REINFORCEMENT STRESS IN CONTINUOUS
BAR AT END OF SPLICE ASSUMING FULLY NONLINEAR
DISTRIBUTION OF COMPRESSIVE STRESS IN THE
CONCRETE**

$$f_{snon3} := \frac{M_{3ft}}{2 \cdot A_{sb} \cdot d \cdot \left(1 - 0.4 \cdot \frac{\rho \cdot 80\text{ksi}}{0.7 \cdot f'_c}\right)} = 79 \cdot \text{ksi}$$

**MAXIMUM REINFORCEMENT STRESS IN CONTINUOUS BAR
AT END OF SPLICE ASSUMING LINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$f_{slin3} := \frac{M_{3ft}}{2 \cdot A_{sb} \cdot d \cdot \left(1 - \frac{k}{3}\right)} = 82 \cdot \text{ksi}$$

Check related maximum concrete stress

$$f_{clin3} := \frac{M_{3ft}}{\left(\frac{k \cdot b \cdot d^2}{2}\right) \cdot \left(1 - \frac{k}{3}\right)} = 4.3 \times 10^3 \text{ psi} \quad (\text{Compression})$$

**SERIES A
A4**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/18/2012**

SUMMARY

Reinforcement stress based on observed maximum load

At support

NONLINEAR

LINEAR

$$f_{\text{supmaxnon}} = 81 \cdot \text{ksi}$$

$$f_{\text{supmaxlin}} = 83 \cdot \text{ksi}$$

At splice end

$$f_{\text{snon3}} = 79 \cdot \text{ksi}$$

$$f_{\text{slin3}} = 82 \cdot \text{ksi}$$

NOMINAL UNIT BOND STRESS

Length of splice

$$L_d := 120 \text{in}$$

Bar diameter

$$d_b = 1.41 \cdot \text{in}$$

Average bond stress at maximum load

$$\mu_{\text{avg}} := \frac{f_{\text{snon3}} \cdot d_b}{4 \cdot L_d}$$

$$\text{round}\left(\frac{\mu_{\text{avg}}}{\text{psi}}, -1\right) \cdot \text{psi} = 230 \text{psi}$$

The number listed above for bond stress has relevance to design but is irrelevant to the actual bond stress at maximum load.

The hard information from the test is that the 120-in splice for No. 11 bars has developed a maximum bar stress of at least


$$f_{\text{snon3}} = 79 \cdot \text{ksi}$$

**SERIES A
A5**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/18/2012**

TEST GIRDER A5



X-Sect. Area for a #11 Bar

$$A_{sb} := 1.56 \text{ in}^2$$

Diameter, # 11 Bar

$$d_b := 1.41 \text{ in}$$

Nominal width of Section

$$b := \left(17 + \frac{5}{8} \right) \cdot \text{in}$$

Nominal height of Section

$$h := 30 \text{ in}$$

Top cover

$$c_t := 5 \text{ in}$$

Effective depth

$$d := 30 \text{ in} - c_t - \frac{d_b}{2}$$

$$d = 24 \cdot \text{in}$$

Yield Stress

$$f_y := 66 \text{ ksi}$$

Concrete Strength

$$f'_c := 5240 \text{ psi}$$

Total Length

$$L_t := 39 \text{ ft}$$

Cantilevered Span

$$a := 11 \text{ ft} + 6 \text{ in}$$

$$a = 11.5 \text{ ft}$$

Interior Span

$$L_m := 16 \text{ ft}$$

$$L_m = 16 \text{ ft}$$

Reinforcement Ratio

$$\rho := 2 \cdot \frac{A_{sb}}{b \cdot d}$$

$$\rho = 0.73 \cdot \%$$

Initial moment at support

$$M_{\text{supinit}} := 45.8 \text{ kip} \cdot \text{ft}$$

**SERIES A
A5**

Reinforcement Stress

Formatted 27 May 12

Printed 6/18/2012

EVALUATION AFTER TEST TO FAILURE

REINFORCEMENT STRESS AT MEASURED MAXIMUM LOAD

Note : Following calculations are made considering the supports not to have width in the direction of the span.

$$\text{Unit selfweight} \quad w_s := b \cdot h \cdot 150 \frac{\text{lb}}{\text{ft}^3} \quad w_s = 0.55 \cdot \frac{\text{kip}}{\text{ft}}$$

$$\text{Measured Maximum Applied Load} \quad P_{\max} := 43.4 \text{ kip}$$

Moment at support related to selfweight and loading gear

$$M_{\text{supinit}} = 46 \cdot \text{kip} \cdot \text{ft}$$

Maximum moment at support

$$M_{\text{supmax}} := P_{\max} \cdot (a - 18 \text{ in}) + M_{\text{supinit}}$$

Moment at 3 ft toward mid-span from support

$$M_{3\text{ft}} := M_{\text{supmax}} - \frac{w_s \cdot L_m}{2} \cdot 3\text{ft} + w_s \cdot \frac{(3\text{ft})^2}{2}$$

$$M_{3\text{ft}} = 469 \cdot \text{kip} \cdot \text{ft}$$

NOTE : Strain distributions over the depth of the section at the supports and at ends of the spliced bars are not linear once cracking is initiated. To assume a linear strain distribution and then to use an "exact" stress-strain relationship for the concrete is not correct. In the following, stresses in the reinforcement will be calculated assuming both linear and nonlinear response in the compressed concrete, and the lower value determined will be taken as the stress achieved. In both sets of calculations, contribution of the tensile strength of the concrete will be considered negligible.

**SERIES A
A5****Reinforcement Stress****Formatted 27 May 12
Printed 6/18/2012**

**MAXIMUM REINFORCEMENT STRESS AT SUPPORT
ASSUMING FULLY NONLINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$f_{\text{supmaxnon}} := \frac{M_{\text{supmax}}}{2 \cdot A_{\text{sb}} \cdot d \cdot \left(1 - 0.4 \cdot \frac{\rho \cdot 81 \text{ ksi}}{0.7 \cdot f'_c} \right)} = 81 \cdot \text{ksi}$$

**MAXIMUM REINFORCEMENT STRESS AT SUPPORT
ASSUMING FULLY LINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$\text{Conc. modulus} \quad E_c := 57000 \cdot \sqrt{f'_c \cdot \text{psi}} \quad E_c = 4.1 \times 10^6 \text{ psi}$$

Steel modulus

$$E_s := 29000 \text{ ksi}$$

Modular ratio

$$n := \frac{E_s}{E_c} \quad n = 7$$

Depth to neutral axis from extreme fiber in compression

$$k := \sqrt{(\rho \cdot n)^2 + 2 \cdot \rho \cdot n} - \rho \cdot n \quad k = 0.27$$

$$f_{\text{supmaxlin}} := \frac{M_{\text{supmax}}}{2 \cdot A_{\text{sb}} \cdot d \cdot \left(1 - \frac{k}{3} \right)} = 84 \cdot \text{ksi}$$

Check related maximum compressive stress in concrete

$$f_{\text{clin1}} := \frac{M_{\text{supmax}}}{\left(\frac{k \cdot b \cdot d^2}{2} \right) \cdot \left(1 - \frac{k}{3} \right)} = 4.5 \times 10^3 \cdot \text{psi} \quad (\text{Compression})$$

**SERIES A
A5**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/18/2012**

**MAXIMUM REINFORCEMENT STRESS IN CONTINUOUS
BAR AT END OF SPLICE ASSUMING FULLY NONLINEAR
DISTRIBUTION OF COMPRESSIVE STRESS IN THE
CONCRETE**

$$f_{snon3} := \frac{M_{3ft}}{2 \cdot A_{sb} \cdot d \cdot \left(1 - 0.4 \cdot \frac{\rho \cdot 79 \text{ksi}}{0.7 \cdot f'_c}\right)} = 79 \cdot \text{ksi}$$

**MAXIMUM REINFORCEMENT STRESS IN CONTINUOUS BAR
AT END OF SPLICE ASSUMING LINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$f_{slin3} := \frac{M_{3ft}}{2 \cdot A_{sb} \cdot d \cdot \left(1 - \frac{k}{3}\right)} = 82 \cdot \text{ksi}$$

Check related maximum concrete stress

$$f_{clin3} := \frac{M_{3ft}}{\left(\frac{k \cdot b \cdot d^2}{2}\right) \cdot \left(1 - \frac{k}{3}\right)} = 4.4 \times 10^3 \text{ psi} \quad (\text{Compression})$$

**SERIES A
A5**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/18/2012**

SUMMARY

Reinforcement stress based on observed maximum load

At support

NONLINEAR

LINEAR

$$f_{\text{supmaxnon}} = 81 \cdot \text{ksi}$$

$$f_{\text{supmaxlin}} = 84 \cdot \text{ksi}$$

At splice end

$$f_{\text{snon3}} = 79 \cdot \text{ksi}$$

$$f_{\text{slin3}} = 82 \cdot \text{ksi}$$

NOMINAL UNIT BOND STRESS

Length of splice

$$L_d := 120 \text{in}$$

Bar diameter

$$d_b = 1.41 \cdot \text{in}$$

Average bond stress at maximum load

$$\mu_{\text{avg}} := \frac{f_{\text{snon3}} \cdot d_b}{4 \cdot L_d}$$

$$\text{round}\left(\frac{\mu_{\text{avg}}}{\text{psi}}, -1\right) \cdot \text{psi} = 230 \text{psi}$$

The number listed above for bond stress has relevance to design but is irrelevant to the actual bond stress at maximum load.

The hard information from the test is that the 120-in splice for No. 11 bars has developed a maximum bar stress of at least


$$f_{\text{snon3}} = 79 \cdot \text{ksi}$$

**SERIES A
A6**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/18/2012**

TEST GIRDER A6



X-Sect. Area for a #11 Bar

$$A_{sb} := 1.56 \text{ in}^2$$

Diameter, # 11 Bar

$$d_b := 1.41 \text{ in}$$

Nominal width of Section

$$b := \left(17 + \frac{5}{8} \right) \cdot \text{in}$$

Nominal height of Section

$$h := 30 \text{ in}$$

Top cover

$$c_t := 5 \text{ in}$$

Effective depth

$$d := 30 \text{ in} - c_t - \frac{d_b}{2}$$

$$d = 24 \cdot \text{in}$$

Yield Stress

$$f_y := 66 \text{ ksi}$$

Concrete Strength

$$f'_c := 5490 \text{ psi}$$

Total Length

$$L_t := 39 \text{ ft}$$

Cantilevered Span

$$a := 11 \text{ ft} + 6 \text{ in}$$

$$a = 11.5 \text{ ft}$$

Interior Span

$$L_m := 16 \text{ ft}$$

$$L_m = 16 \text{ ft}$$

Reinforcement Ratio

$$\rho := 2 \cdot \frac{A_{sb}}{b \cdot d}$$

$$\rho = 0.73 \cdot \%$$

Initial moment at support

$$M_{\text{supinit}} := 45.8 \text{ kip} \cdot \text{ft}$$

**SERIES A
A6**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/18/2012**

EVALUATION AFTER TEST TO FAILURE

REINFORCEMENT STRESS AT MEASURED MAXIMUM LOAD

Note : Following calculations are made considering the supports not to have width in the direction of the span.

$$\text{Unit selfweight} \quad w_s := b \cdot h \cdot 150 \frac{\text{lb}}{\text{ft}^3} \quad w_s = 0.55 \cdot \frac{\text{kip}}{\text{ft}}$$

$$\text{Measured Maximum Applied Load} \quad P_{\max} := 42.0 \text{kip}$$

Moment at support related to selfweight and loading gear

$$M_{\text{supinit}} = 46 \cdot \text{kip} \cdot \text{ft}$$

Maximum moment at support

$$M_{\text{supmax}} := P_{\max} \cdot (a - 18 \text{in}) + M_{\text{supinit}} = 466 \text{kip} \cdot \text{ft}$$

Moment at 3 ft toward mid-span from support

$$M_{3\text{ft}} := M_{\text{supmax}} - \frac{w_s \cdot L_m}{2} \cdot 3\text{ft} + w_s \cdot \frac{(3\text{ft})^2}{2}$$

$$M_{3\text{ft}} = 455 \cdot \text{kip} \cdot \text{ft}$$

NOTE : Strain distributions over the depth of the section at the supports and at ends of the spliced bars are not linear once cracking is initiated. To assume a linear strain distribution and then to use an "exact" stress-strain relationship for the concrete is not correct. In the following, stresses in the reinforcement will be calculated assuming both linear and nonlinear response in the compressed concrete, and the lower value determined will be taken as the stress achieved. In both sets of calculations, contribution of the tensile strength of the concrete will be considered negligible.

**SERIES A
A6****Reinforcement Stress****Formatted 27 May 12
Printed 6/18/2012**

**MAXIMUM REINFORCEMENT STRESS AT SUPPORT
ASSUMING FULLY NONLINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$f_{\text{supmaxnon}} := \frac{M_{\text{supmax}}}{2 \cdot A_{\text{sb}} \cdot d \cdot \left(1 - 0.4 \cdot \frac{\rho \cdot 78 \text{ksi}}{0.7 \cdot f'_c} \right)} = 78 \cdot \text{ksi}$$

**MAXIMUM REINFORCEMENT STRESS AT SUPPORT
ASSUMING FULLY LINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$\text{Conc. modulus} \quad E_c := 57000 \cdot \sqrt{f'_c \cdot \text{psi}} \quad E_c = 4.2 \times 10^6 \text{ psi}$$

Steel modulus

$$E_s := 29000 \text{ksi}$$

Modular ratio

$$n := \frac{E_s}{E_c} \quad n = 7$$

Depth to neutral axis from extreme fiber in compression

$$k := \sqrt{(\rho \cdot n)^2 + 2 \cdot \rho \cdot n} - \rho \cdot n \quad k = 0.27$$

$$f_{\text{supmaxlin}} := \frac{M_{\text{supmax}}}{2 \cdot A_{\text{sb}} \cdot d \cdot \left(1 - \frac{k}{3} \right)} = 81 \cdot \text{ksi}$$

Check related maximum compressive stress in concrete

$$f_{\text{clin1}} := \frac{M_{\text{supmax}}}{\left(\frac{k \cdot b \cdot d^2}{2} \right) \cdot \left(1 - \frac{k}{3} \right)} = 4.4 \times 10^3 \cdot \text{psi} \quad (\text{Compression})$$

**SERIES A
A6**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/18/2012**

**MAXIMUM REINFORCEMENT STRESS IN CONTINUOUS
BAR AT END OF SPLICE ASSUMING FULLY NONLINEAR
DISTRIBUTION OF COMPRESSIVE STRESS IN THE
CONCRETE**

$$f_{snon3} := \frac{M_{3ft}}{2 \cdot A_{sb} \cdot d \cdot \left(1 - 0.4 \cdot \frac{\rho \cdot 77 \text{ksi}}{0.7 \cdot f'_c}\right)} = 77 \cdot \text{ksi}$$

**MAXIMUM REINFORCEMENT STRESS IN CONTINUOUS BAR
AT END OF SPLICE ASSUMING LINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$f_{slin3} := \frac{M_{3ft}}{2 \cdot A_{sb} \cdot d \cdot \left(1 - \frac{k}{3}\right)} = 79 \cdot \text{ksi}$$

Check related maximum concrete stress

$$f_{clin3} := \frac{M_{3ft}}{\left(\frac{k \cdot b \cdot d^2}{2}\right) \cdot \left(1 - \frac{k}{3}\right)} = 4.3 \times 10^3 \text{ psi} \quad (\text{Compression})$$

**SERIES A
A6**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/18/2012**

SUMMARY

Reinforcement stress based on observed maximum load

At support

NONLINEAR

LINEAR

$$f_{\text{supmaxnon}} = 78 \cdot \text{ksi}$$

$$f_{\text{supmaxlin}} = 81 \cdot \text{ksi}$$

At splice end

$$f_{\text{snon3}} = 77 \cdot \text{ksi}$$

$$f_{\text{slin3}} = 79 \cdot \text{ksi}$$

NOMINAL UNIT BOND STRESS

Length of splice

$$L_d := 120 \text{in}$$

Bar diameter

$$d_b = 1.41 \cdot \text{in}$$

Average bond stress at maximum load

$$\mu_{\text{avg}} := \frac{f_{\text{snon3}} \cdot d_b}{4 \cdot L_d}$$

$$\text{round}\left(\frac{\mu_{\text{avg}}}{\text{psi}}, -1\right) \cdot \text{psi} = 220 \text{psi}$$

The number listed above for bond stress has relevance to design but is irrelevant to the actual bond stress at maximum load.

The hard information from the test is that the 120-in splice for No. 11 bars has developed a maximum bar stress of at least


$$f_{\text{snon3}} = 77 \cdot \text{ksi}$$

**SERIES B
B1**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/18/2012**

TEST GIRDER B1



X-Sect. Area for a #11 Bar

Diameter, # 11 Bar

Nominal width of Section

Nominal height of Section

Top cover

Effective depth $d := 30\text{in} - c_t - \frac{d_b}{2}$

Yield Stress

Concrete Strength

Total Length

$L_t := 2 \cdot 14\text{in} + 2 \cdot 9\text{ft} + 2 \cdot 8.5\text{in} + 2 \cdot 3\text{ft} + 6\text{ft} + 7\text{in}$

Cantilevered Span $a := 10\text{ft} + 10.5\text{in}$

Interior Span $L_m := 12\text{ft} + 7\text{in}$

Reinforcement Ratio $\rho := 2 \cdot \frac{A_{sb}}{b \cdot d}$

Initial moment at support

$$A_{sb} := 1.56\text{in}^2$$

$$d_b := 1.41\text{in}$$

$$b := \left(17 + \frac{5}{8}\right) \cdot \text{in}$$

$$h := 30\text{in}$$

$$c_t := 5\text{in}$$

$$d = 24 \cdot \text{in}$$

$$f_y := 66\text{ksi}$$

$$f'_c := 4460\text{psi}$$

$$L_t = 34.3 \text{ ft}$$

$$a = 10.9 \text{ ft}$$

$$L_m = 13 \text{ ft}$$

$$\rho = 0.73 \cdot \%$$

$$M_{\text{supinit}} := 40.5\text{kip} \cdot \text{ft}$$

**SERIES B
B1**

Reinforcement Stress

Formatted 27 May 12

Printed 6/18/2012

EVALUATION AFTER TEST TO FAILURE

REINFORCEMENT STRESS AT MEASURED MAXIMUM LOAD

Note : Following calculations are made considering the supports not to have width in the direction of the span.

$$\text{Unit selfweight} \quad w_s := b \cdot h \cdot 150 \frac{\text{lb}}{\text{ft}^3} \quad w_s = 0.55 \cdot \frac{\text{kip}}{\text{ft}}$$

$$\text{Measured Maximum Applied Load} \quad P_{\max} := 39.5 \text{kip}$$

Moment at support related to selfweight and loading gear

Maximum moment at support

$$M_{\text{supmax}} := P_{\max} \cdot (a - 14 \text{in}) + M_{\text{supinit}}$$

Moment at 3 ft toward mid-span from support

$$M_{3\text{ft}} := M_{\text{supmax}} - \frac{w_s \cdot L_m}{2} \cdot 3\text{ft} + w_s \cdot \frac{(3\text{ft})^2}{2}$$

$$M_{3\text{ft}} = 416 \cdot \text{kip} \cdot \text{ft}$$

NOTE : Strain distributions over the depth of the section at the supports and at ends of the spliced bars are not linear once cracking is initiated. To assume a linear strain distribution and then to use an "exact" stress-strain relationship for the concrete is not correct. In the following, stresses in the reinforcement will be calculated assuming both linear and nonlinear response in the compressed concrete, and the lower value determined will be taken as the stress achieved. In both sets of calculations, contribution of the tensile strength of the concrete will be considered negligible.

**SERIES B
B1****Reinforcement Stress****Formatted 27 May 12
Printed 6/18/2012****MAXIMUM REINFORCEMENT STRESS AT SUPPORT
ASSUMING FULLY NONLINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$f_{\text{supmaxnon}} := \frac{M_{\text{supmax}}}{2 \cdot A_{\text{sb}} \cdot d \cdot \left(1 - 0.4 \cdot \frac{\rho \cdot 72 \text{ksi}}{0.7 \cdot f'_c} \right)} = 72 \cdot \text{ksi}$$

**MAXIMUM REINFORCEMENT STRESS AT SUPPORT
ASSUMING FULLY LINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$\text{Conc. modulus } E_c := 57000 \cdot \sqrt{f'_c} \cdot \text{psi} \quad E_c = 3.8 \times 10^6 \text{ psi}$$

Steel modulus

$$E_s := 29000 \text{ ksi}$$

Modular ratio

$$n := \frac{E_s}{E_c} \quad n = 8$$

Depth to neutral axis from extreme fiber in compression

$$k := \sqrt{(\rho \cdot n)^2 + 2 \cdot \rho \cdot n} - \rho \cdot n \quad k = 0.28$$

$$f_{\text{supmaxlin}} := \frac{M_{\text{supmax}}}{2 \cdot A_{\text{sb}} \cdot d \cdot \left(1 - \frac{k}{3} \right)} = 74 \cdot \text{ksi}$$

Check related maximum compressive stress in concrete

$$f_{\text{clin1}} := \frac{M_{\text{supmax}}}{\left(\frac{k \cdot b \cdot d^2}{2} \right) \cdot \left(1 - \frac{k}{3} \right)} = 3.8 \times 10^3 \cdot \text{psi} \quad (\text{Compression})$$

**SERIES B
B1**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/18/2012**

**MAXIMUM REINFORCEMENT STRESS IN CONTINUOUS
BAR AT END OF SPLICE ASSUMING FULLY NONLINEAR
DISTRIBUTION OF COMPRESSIVE STRESS IN THE
CONCRETE**

$$f_{snon3} := \frac{M_{3ft}}{2 \cdot A_{sb} \cdot d \cdot \left(1 - 0.4 \cdot \frac{\rho \cdot 71 \text{ ksi}}{0.7 \cdot f'_c}\right)} = 71 \cdot \text{ksi}$$

**MAXIMUM REINFORCEMENT STRESS IN CONTINUOUS BAR
AT END OF SPLICE ASSUMING LINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$f_{slin3} := \frac{M_{3ft}}{2 \cdot A_{sb} \cdot d \cdot \left(1 - \frac{k}{3}\right)} = 73 \cdot \text{ksi}$$

Check related maximum concrete stress

$$f_{clin3} := \frac{M_{3ft}}{\left(\frac{k \cdot b \cdot d^2}{2}\right) \cdot \left(1 - \frac{k}{3}\right)} = 3.8 \times 10^3 \text{ psi} \quad (\text{Compression})$$

**SERIES B
B1**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/18/2012**

SUMMARY

Reinforcement stress based on observed maximum load

At support

NONLINEAR

LINEAR

$$f_{\text{supmaxnon}} = 72 \cdot \text{ksi}$$

$$f_{\text{supmaxlin}} = 74 \cdot \text{ksi}$$

At splice end

$$f_{\text{snon3}} = 71 \cdot \text{ksi}$$

$$f_{\text{slin3}} = 73 \cdot \text{ksi}$$

NOMINAL UNIT BOND STRESS

Length of splice

$$L_d := 79 \text{ in}$$

Bar diameter

$$d_b = 1.41 \cdot \text{in}$$

Average bond stress at maximum load

$$\mu_{\text{avg}} := \frac{f_{\text{snon3}} \cdot d_b}{4 \cdot L_d}$$

$$\text{round}\left(\frac{\mu_{\text{avg}}}{\text{psi}}, -1\right) \cdot \text{psi} = 310 \text{ psi}$$

The number listed above for bond stress has relevance to design but is irrelevant to the actual bond stress at maximum load.

The hard information from the test is that the 79-in splice for No. 11 bars has developed a maximum bar stress of at least


$$f_{\text{snon3}} = 71 \cdot \text{ksi}$$

**SERIES B
B2**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/18/2012**

TEST GIRDER B2



X-Sect. Area for a #11 Bar

Diameter, # 11 Bar

Nominal width of Section

Nominal height of Section

Top cover

Effective depth $d := 30\text{in} - c_t - \frac{d_b}{2}$

Yield Stress

Concrete Strength

Total Length

$L_t := 2 \cdot 14\text{in} + 2 \cdot 9\text{ft} + 2 \cdot 8.5\text{in} + 2 \cdot 3\text{ft} + 6\text{ft} + 7\text{in}$

Cantilevered Span $a := 10\text{ft} + 10.5\text{in}$

Interior Span $L_m := 12\text{ft} + 7\text{in}$

Reinforcement Ratio $\rho := 2 \cdot \frac{A_{sb}}{b \cdot d}$

Initial moment at support

$$A_{sb} := 1.56\text{in}^2$$

$$d_b := 1.41\text{in}$$

$$b := \left(17 + \frac{5}{8}\right) \cdot \text{in}$$

$$h := 30\text{in}$$

$$c_t := 5\text{in}$$

$$d = 24 \cdot \text{in}$$

$$f_y := 66\text{ksi}$$

$$f'_c := 4800\text{psi}$$

$$L_t = 34.3 \text{ ft}$$

$$a = 10.9 \text{ ft}$$

$$L_m = 13 \text{ ft}$$

$$\rho = 0.73 \cdot \%$$

$$M_{\text{supinit}} := 40.5\text{kip} \cdot \text{ft}$$

**SERIES B
B2**

Reinforcement Stress

Formatted 27 May 12

Printed 6/18/2012

EVALUATION AFTER TEST TO FAILURE

REINFORCEMENT STRESS AT MEASURED MAXIMUM LOAD

Note : Following calculations are made considering the supports not to have width in the direction of the span.

$$\text{Unit selfweight} \quad w_s := b \cdot h \cdot 150 \frac{\text{lb}}{\text{ft}^3} \quad w_s = 0.55 \cdot \frac{\text{kip}}{\text{ft}}$$

$$\text{Measured Maximum Applied Load} \quad P_{\max} := 38.9 \text{kip}$$

Moment at support related to selfweight and loading gear

Maximum moment at support

$$M_{\text{supmax}} := P_{\max} \cdot (a - 14 \text{in}) + M_{\text{supinit}}$$

Moment at 3 ft toward mid-span from support

$$M_{3\text{ft}} := M_{\text{supmax}} - \frac{w_s \cdot L_m}{2} \cdot 3\text{ft} + w_s \cdot \frac{(3\text{ft})^2}{2}$$

$$M_{3\text{ft}} = 410 \cdot \text{kip} \cdot \text{ft}$$

NOTE : Strain distributions over the depth of the section at the supports and at ends of the spliced bars are not linear once cracking is initiated. To assume a linear strain distribution and then to use an "exact" stress-strain relationship for the concrete is not correct. In the following, stresses in the reinforcement will be calculated assuming both linear and nonlinear response in the compressed concrete, and the lower value determined will be taken as the stress achieved. In both sets of calculations, contribution of the tensile strength of the concrete will be considered negligible.

**SERIES B
B2****Reinforcement Stress****Formatted 27 May 12
Printed 6/18/2012****MAXIMUM REINFORCEMENT STRESS AT SUPPORT
ASSUMING FULLY NONLINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$f_{\text{supmaxnon}} := \frac{M_{\text{supmax}}}{2 \cdot A_{\text{sb}} \cdot d \cdot \left(1 - 0.4 \cdot \frac{\rho \cdot 72 \text{ksi}}{0.7 \cdot f'_c} \right)} = 71 \cdot \text{ksi}$$

**MAXIMUM REINFORCEMENT STRESS AT SUPPORT
ASSUMING FULLY LINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$\text{Conc. modulus } E_c := 57000 \cdot \sqrt{f'_c} \cdot \text{psi} \quad E_c = 3.9 \times 10^6 \text{ psi}$$

Steel modulus

$$E_s := 29000 \text{ ksi}$$

Modular ratio

$$n := \frac{E_s}{E_c} \quad n = 7$$

Depth to neutral axis from extreme fiber in compression

$$k := \sqrt{(\rho \cdot n)^2 + 2 \cdot \rho \cdot n} - \rho \cdot n \quad k = 0.28$$

$$f_{\text{supmaxlin}} := \frac{M_{\text{supmax}}}{2 \cdot A_{\text{sb}} \cdot d \cdot \left(1 - \frac{k}{3} \right)} = 73 \cdot \text{ksi}$$

Check related maximum compressive stress in concrete

$$f_{\text{clin1}} := \frac{M_{\text{supmax}}}{\left(\frac{k \cdot b \cdot d^2}{2} \right) \cdot \left(1 - \frac{k}{3} \right)} = 3.8 \times 10^3 \cdot \text{psi} \quad (\text{Compression})$$

**SERIES B
B2**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/18/2012**

**MAXIMUM REINFORCEMENT STRESS IN CONTINUOUS
BAR AT END OF SPLICE ASSUMING FULLY NONLINEAR
DISTRIBUTION OF COMPRESSIVE STRESS IN THE
CONCRETE**

$$f_{snon3} := \frac{M_{3ft}}{2 \cdot A_{sb} \cdot d \cdot \left(1 - 0.4 \cdot \frac{\rho \cdot 69 \text{ksi}}{0.7 \cdot f'_c}\right)} = 69 \cdot \text{ksi}$$

**MAXIMUM REINFORCEMENT STRESS IN CONTINUOUS BAR
AT END OF SPLICE ASSUMING LINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$f_{slin3} := \frac{M_{3ft}}{2 \cdot A_{sb} \cdot d \cdot \left(1 - \frac{k}{3}\right)} = 72 \cdot \text{ksi}$$

Check related maximum concrete stress

$$f_{clin3} := \frac{M_{3ft}}{\left(\frac{k \cdot b \cdot d^2}{2}\right) \cdot \left(1 - \frac{k}{3}\right)} = 3.8 \times 10^3 \text{ psi} \quad (\text{Compression})$$

**SERIES B
B2**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/18/2012**

SUMMARY

Reinforcement stress based on observed maximum load

At support

NONLINEAR

LINEAR

$$f_{\text{supmaxnon}} = 71 \cdot \text{ksi}$$

$$f_{\text{supmaxlin}} = 73 \cdot \text{ksi}$$

At splice end

$$f_{\text{snon3}} = 69 \cdot \text{ksi}$$

$$f_{\text{slin3}} = 72 \cdot \text{ksi}$$

NOMINAL UNIT BOND STRESS

Length of splice

$$L_d := 79 \text{in}$$

Bar diameter

$$d_b = 1.41 \cdot \text{in}$$

Average bond stress at maximum load

$$\mu_{\text{avg}} := \frac{f_{\text{snon3}} \cdot d_b}{4 \cdot L_d}$$

$$\text{round}\left(\frac{\mu_{\text{avg}}}{\text{psi}}, -1\right) \cdot \text{psi} = 310 \text{psi}$$

The number listed above for bond stress has relevance to design but is irrelevant to the actual bond stress at maximum load.

The hard information from the test is that the 79-in splice for No. 11 bars has developed a maximum bar stress of at least


$$f_{\text{snon3}} = 69 \cdot \text{ksi}$$

**SERIES B
B3**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/18/2012**

TEST GIRDER B3



X-Sect. Area for a #11 Bar

Diameter, # 11 Bar

Nominal width of Section

Nominal height of Section

Top cover

Effective depth $d := 30\text{in} - c_t - \frac{d_b}{2}$

Yield Stress

Concrete Strength

Total Length

$L_t := 2 \cdot 14\text{in} + 2 \cdot 9\text{ft} + 2 \cdot 8.5\text{in} + 2 \cdot 3\text{ft} + 6\text{ft} + 7\text{in}$

Cantilevered Span $a := 10\text{ft} + 10.5\text{in}$

Interior Span $L_m := 12\text{ft} + 7\text{in}$

Reinforcement Ratio $\rho := 2 \cdot \frac{A_{sb}}{b \cdot d}$

Initial moment at support

$$A_{sb} := 1.56\text{in}^2$$

$$d_b := 1.41\text{in}$$

$$b := \left(17 + \frac{5}{8}\right) \cdot \text{in}$$

$$h := 30\text{in}$$

$$c_t := 5\text{in}$$

$$d = 24 \cdot \text{in}$$

$$f_y := 66\text{ksi}$$

$$f'_c := 4780\text{psi}$$

$$L_t = 34.3 \text{ ft}$$

$$a = 10.9 \text{ ft}$$

$$L_m = 13 \text{ ft}$$

$$\rho = 0.73 \cdot \%$$

$$M_{\text{supinit}} := 40.5\text{kip} \cdot \text{ft}$$

**SERIES B
B3**

Reinforcement Stress

Formatted 27 May 12

Printed 6/18/2012

EVALUATION AFTER TEST TO FAILURE

REINFORCEMENT STRESS AT MEASURED MAXIMUM LOAD

Note : Following calculations are made considering the supports not to have width in the direction of the span.

$$\text{Unit selfweight} \quad w_s := b \cdot h \cdot 150 \frac{\text{lb}}{\text{ft}^3} \quad w_s = 0.55 \cdot \frac{\text{kip}}{\text{ft}}$$

$$\text{Measured Maximum Applied Load} \quad P_{\max} := 39.7 \text{kip}$$

Moment at support related to selfweight and loading gear

Maximum moment at support

$$M_{\text{supmax}} := P_{\max} \cdot (a - 14 \text{in}) + M_{\text{supinit}}$$

Moment at 3 ft toward mid-span from support

$$M_{3\text{ft}} := M_{\text{supmax}} - \left(\frac{w_s \cdot L_m}{2} \cdot 3 \right) \text{ft} + w_s \cdot \frac{(3\text{ft})^2}{2}$$

$$M_{3\text{ft}} = 418 \cdot \text{kip} \cdot \text{ft}$$

NOTE : Strain distributions over the depth of the section at the supports and at ends of the spliced bars are not linear once cracking is initiated. To assume a linear strain distribution and then to use an "exact" stress-strain relationship for the concrete is not correct. In the following, stresses in the reinforcement will be calculated assuming both linear and nonlinear response in the compressed concrete, and the lower value determined will be taken as the stress achieved. In both sets of calculations, contribution of the tensile strength of the concrete will be considered negligible.

**SERIES B
B3****Reinforcement Stress****Formatted 27 May 12
Printed 6/18/2012****MAXIMUM REINFORCEMENT STRESS AT SUPPORT
ASSUMING FULLY NONLINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$f_{\text{supmaxnon}} := \frac{M_{\text{supmax}}}{2 \cdot A_{\text{sb}} \cdot d \cdot \left(1 - 0.4 \cdot \frac{\rho \cdot 72 \text{ksi}}{0.7 \cdot f'_c} \right)} = 72 \cdot \text{ksi}$$

**MAXIMUM REINFORCEMENT STRESS AT SUPPORT
ASSUMING FULLY LINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$\text{Conc. modulus } E_c := 57000 \cdot \sqrt{f'_c} \cdot \text{psi} \quad E_c = 3.9 \times 10^6 \text{ psi}$$

Steel modulus

$$E_s := 29000 \text{ ksi}$$

Modular ratio

$$n := \frac{E_s}{E_c} \quad n = 7$$

Depth to neutral axis from extreme fiber in compression

$$k := \sqrt{(\rho \cdot n)^2 + 2 \cdot \rho \cdot n} - \rho \cdot n \quad k = 0.28$$

$$f_{\text{supmaxlin}} := \frac{M_{\text{supmax}}}{2 \cdot A_{\text{sb}} \cdot d \cdot \left(1 - \frac{k}{3} \right)} = 74 \cdot \text{ksi}$$

Check related maximum compressive stress in concrete

$$f_{\text{clin1}} := \frac{M_{\text{supmax}}}{\left(\frac{k \cdot b \cdot d^2}{2} \right) \cdot \left(1 - \frac{k}{3} \right)} = 3.9 \times 10^3 \cdot \text{psi} \quad (\text{Compression})$$

**SERIES B
B3**

Reinforcement Stress

Formatted 27 May 12

Printed 6/18/2012

**MAXIMUM REINFORCEMENT STRESS IN CONTINUOUS
BAR AT END OF SPLICE ASSUMING FULLY NONLINEAR
DISTRIBUTION OF COMPRESSIVE STRESS IN THE
CONCRETE**

$$f_{snon3} := \frac{M_{3ft}}{2 \cdot A_{sb} \cdot d \cdot \left(1 - 0.4 \cdot \frac{\rho \cdot 70 \text{ksi}}{0.7 \cdot f'_c}\right)} = 70 \cdot \text{ksi}$$

**MAXIMUM REINFORCEMENT STRESS IN CONTINUOUS BAR
AT END OF SPLICE ASSUMING LINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$f_{slin3} := \frac{M_{3ft}}{2 \cdot A_{sb} \cdot d \cdot \left(1 - \frac{k}{3}\right)} = 73 \cdot \text{ksi}$$

Check related maximum concrete stress

$$f_{clin3} := \frac{M_{3ft}}{\left(\frac{k \cdot b \cdot d^2}{2}\right) \cdot \left(1 - \frac{k}{3}\right)} = 3.8 \times 10^3 \text{ psi} \quad (\text{Compression})$$

**SERIES B
B3**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/18/2012**

SUMMARY

Reinforcement stress based on observed maximum load

At support

NONLINEAR

LINEAR

$$f_{\text{supmaxnon}} = 72 \cdot \text{ksi}$$

$$f_{\text{supmaxlin}} = 74 \cdot \text{ksi}$$

At splice end

$$f_{\text{snon3}} = 70 \cdot \text{ksi}$$

$$f_{\text{slin3}} = 73 \cdot \text{ksi}$$

NOMINAL UNIT BOND STRESS

Length of splice

$$L_d := 79 \text{ in}$$

Bar diameter

$$d_b = 1.41 \cdot \text{in}$$

Average bond stress at maximum load

$$\mu_{\text{avg}} := \frac{f_{\text{snon3}} \cdot d_b}{4 \cdot L_d}$$

$$\text{round}\left(\frac{\mu_{\text{avg}}}{\text{psi}}, -1\right) \cdot \text{psi} = 310 \text{ psi}$$

The number listed above for bond stress has relevance to design but is irrelevant to the actual bond stress at maximum load.

The hard information from the test is that the 79-in splice for No. 11 bars has developed a maximum bar stress of at least


$$f_{\text{snon3}} = 70 \cdot \text{ksi}$$

**SERIES B
B4**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/18/2012**

TEST GIRDER B4



X-Sect. Area for a #11 Bar

Diameter, # 11 Bar

Nominal width of Section

Nominal height of Section

Top cover

Effective depth $d := 30\text{in} - c_t - \frac{d_b}{2}$

Yield Stress

Concrete Strength

Total Length

$L_t := 2 \cdot 14\text{in} + 2 \cdot 9\text{ft} + 2 \cdot 8.5\text{in} + 2 \cdot 3\text{ft} + 6\text{ft} + 7\text{in}$

Cantilevered Span $a := 10\text{ft} + 10.5\text{in}$

Interior Span $L_m := 12\text{ft} + 7\text{in}$

Reinforcement Ratio $\rho := 2 \cdot \frac{A_{sb}}{b \cdot d}$

Initial moment at support

$$A_{sb} := 1.56\text{in}^2$$

$$d_b := 1.41\text{in}$$

$$b := \left(17 + \frac{5}{8}\right) \cdot \text{in}$$

$$h := 30\text{in}$$

$$c_t := 5\text{in}$$

$$d = 24 \cdot \text{in}$$

$$f_y := 66\text{ksi}$$

$$f'_c := 5460\text{psi}$$

$$L_t = 34.3 \text{ ft}$$

$$a = 10.9 \text{ ft}$$

$$L_m = 13 \text{ ft}$$

$$\rho = 0.73 \cdot \%$$

$$M_{\text{supinit}} := 40.5\text{kip} \cdot \text{ft}$$

**SERIES B
B4**

Reinforcement Stress

Formatted 27 May 12

Printed 6/18/2012

EVALUATION AFTER TEST TO FAILURE

REINFORCEMENT STRESS AT MEASURED MAXIMUM LOAD

Note : Following calculations are made considering the supports not to have width in the direction of the span.

$$\text{Unit selfweight} \quad w_s := b \cdot h \cdot 150 \frac{\text{lb}}{\text{ft}^3} \quad w_s = 0.55 \cdot \frac{\text{kip}}{\text{ft}}$$

$$\text{Measured Maximum Applied Load} \quad P_{\max} := 39.7 \text{kip}$$

Moment at support related to selfweight and loading gear

Maximum moment at support

$$M_{\text{supmax}} := P_{\max} \cdot (a - 14 \text{in}) + M_{\text{supinit}} = 426 \cdot \text{kip} \cdot \text{ft}$$

Moment at 3 ft toward mid-span from support

$$M_{3\text{ft}} := M_{\text{supmax}} - \frac{w_s \cdot L_m}{2} \cdot 3\text{ft} + w_s \cdot \frac{(3\text{ft})^2}{2}$$

$$M_{3\text{ft}} = 418 \cdot \text{kip} \cdot \text{ft}$$

NOTE : Strain distributions over the depth of the section at the supports and at ends of the spliced bars are not linear once cracking is initiated. To assume a linear strain distribution and then to use an "exact" stress-strain relationship for the concrete is not correct. In the following, stresses in the reinforcement will be calculated assuming both linear and nonlinear response in the compressed concrete, and the lower value determined will be taken as the stress achieved. In both sets of calculations, contribution of the tensile strength of the concrete will be considered negligible.

**SERIES B
B4****Reinforcement Stress****Formatted 27 May 12
Printed 6/18/2012****MAXIMUM REINFORCEMENT STRESS AT SUPPORT
ASSUMING FULLY NONLINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$f_{\text{supmaxnon}} := \frac{M_{\text{supmax}}}{2 \cdot A_{\text{sb}} \cdot d \cdot \left(1 - 0.4 \cdot \frac{\rho \cdot 71 \text{ksi}}{0.7 \cdot f'_c} \right)} = 71 \cdot \text{ksi}$$

**MAXIMUM REINFORCEMENT STRESS AT SUPPORT
ASSUMING FULLY LINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$\text{Conc. modulus } E_c := 57000 \cdot \sqrt{f'_c \cdot \text{psi}} \quad E_c = 4.2 \times 10^6 \text{ psi}$$

Steel modulus

$$E_s := 29000 \text{ksi}$$

Modular ratio

$$n := \frac{E_s}{E_c} \quad n = 7$$

Depth to neutral axis from extreme fiber in compression

$$k := \sqrt{(\rho \cdot n)^2 + 2 \cdot \rho \cdot n} - \rho \cdot n \quad k = 0.27$$

$$f_{\text{supmaxlin}} := \frac{M_{\text{supmax}}}{2 \cdot A_{\text{sb}} \cdot d \cdot \left(1 - \frac{k}{3} \right)} = 74 \cdot \text{ksi}$$

Check related maximum compressive stress in concrete

$$f_{\text{clin1}} := \frac{M_{\text{supmax}}}{\left(\frac{k \cdot b \cdot d^2}{2} \right) \cdot \left(1 - \frac{k}{3} \right)} = 4 \times 10^3 \cdot \text{psi} \quad (\text{Compression})$$

**SERIES B
B4**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/18/2012**

**MAXIMUM REINFORCEMENT STRESS IN CONTINUOUS
BAR AT END OF SPLICE ASSUMING FULLY NONLINEAR
DISTRIBUTION OF COMPRESSIVE STRESS IN THE
CONCRETE**

$$f_{snon3} := \frac{M_{3ft}}{2 \cdot A_{sb} \cdot d \cdot \left(1 - 0.4 \cdot \frac{\rho \cdot 70 \text{ksi}}{0.7 \cdot f'_c}\right)} = 70 \cdot \text{ksi}$$

**MAXIMUM REINFORCEMENT STRESS IN CONTINUOUS BAR
AT END OF SPLICE ASSUMING LINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$f_{slin3} := \frac{M_{3ft}}{2 \cdot A_{sb} \cdot d \cdot \left(1 - \frac{k}{3}\right)} = 73 \cdot \text{ksi}$$

Check related maximum concrete stress

$$f_{clin3} := \frac{M_{3ft}}{\left(\frac{k \cdot b \cdot d^2}{2}\right) \cdot \left(1 - \frac{k}{3}\right)} = 3.9 \times 10^3 \text{ psi} \quad (\text{Compression})$$

**SERIES B
B4**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/18/2012**

SUMMARY

Reinforcement stress based on observed maximum load

At support

NONLINEAR

LINEAR

$$f_{\text{supmaxnon}} = 71 \cdot \text{ksi}$$

$$f_{\text{supmaxlin}} = 74 \cdot \text{ksi}$$

At splice end

$$f_{\text{snon3}} = 70 \cdot \text{ksi}$$

$$f_{\text{slin3}} = 73 \cdot \text{ksi}$$

NOMINAL UNIT BOND STRESS

Length of splice

$$L_d := 79 \text{in}$$

Bar diameter

$$d_b = 1.41 \cdot \text{in}$$

Average bond stress at maximum load

$$\mu_{\text{avg}} := \frac{f_{\text{snon3}} \cdot d_b}{4 \cdot L_d}$$

$$\text{round}\left(\frac{\mu_{\text{avg}}}{\text{psi}}, -1\right) \cdot \text{psi} = 310 \text{psi}$$

The number listed above for bond stress has relevance to design but is irrelevant to the actual bond stress at maximum load.

The hard information from the test is that the 79-in splice for No. 11 bars has developed a maximum bar stress of at least


$$f_{\text{snon3}} = 70 \cdot \text{ksi}$$

**SERIES B
B5**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/18/2012**

TEST GIRDER B5



X-Sect. Area for a #11 Bar

Diameter, # 11 Bar

Nominal width of Section

Nominal height of Section

Top cover

Effective depth $d := 30\text{in} - c_t - \frac{d_b}{2}$

Yield Stress

Concrete Strength

Total Length

$L_t := 2 \cdot 14\text{in} + 2 \cdot 9\text{ft} + 2 \cdot 8.5\text{in} + 2 \cdot 3\text{ft} + 6\text{ft} + 7\text{in}$

Cantilevered Span $a := 10\text{ft} + 10.5\text{in}$

Interior Span $L_m := 12\text{ft} + 7\text{in}$

Reinforcement Ratio $\rho := 2 \cdot \frac{A_{sb}}{b \cdot d}$

Initial moment at support

$$A_{sb} := 1.56\text{in}^2$$

$$d_b := 1.41\text{in}$$

$$b := \left(17 + \frac{5}{8}\right) \cdot \text{in}$$

$$h := 30\text{in}$$

$$c_t := 5\text{in}$$

$$d = 24 \cdot \text{in}$$

$$f_y := 66\text{ksi}$$

$$f'_c := 5260\text{psi}$$

$$L_t = 34.3 \text{ ft}$$

$$a = 10.9 \text{ ft}$$

$$L_m = 13 \text{ ft}$$

$$\rho = 0.73 \cdot \%$$

$$M_{\text{supinit}} := 40.5\text{kip} \cdot \text{ft}$$

**SERIES B
B5**

Reinforcement Stress

Formatted 27 May 12

Printed 6/18/2012

EVALUATION AFTER TEST TO FAILURE

REINFORCEMENT STRESS AT MEASURED MAXIMUM LOAD

Note : Following calculations are made considering the supports not to have width in the direction of the span.

$$\text{Unit selfweight} \quad w_s := b \cdot h \cdot 150 \frac{\text{lb}}{\text{ft}^3} \quad w_s = 0.55 \cdot \frac{\text{kip}}{\text{ft}}$$

$$\text{Measured Maximum Applied Load} \quad P_{\max} := 40.6 \text{kip}$$

Moment at support related to selfweight and loading gear

Maximum moment at support

$$M_{\text{supmax}} := P_{\max} \cdot (a - 14 \text{in}) + M_{\text{supinit}}$$

Moment at 3 ft toward mid-span from support

$$M_{3\text{ft}} := M_{\text{supmax}} - \frac{w_s \cdot L_m}{2} \cdot 3\text{ft} + w_s \cdot \frac{(3\text{ft})^2}{2}$$

$$M_{3\text{ft}} = 427 \cdot \text{kip} \cdot \text{ft}$$

NOTE : Strain distributions over the depth of the section at the supports and at ends of the spliced bars are not linear once cracking is initiated. To assume a linear strain distribution and then to use an "exact" stress-strain relationship for the concrete is not correct. In the following, stresses in the reinforcement will be calculated assuming both linear and nonlinear response in the compressed concrete, and the lower value determined will be taken as the stress achieved. In both sets of calculations, contribution of the tensile strength of the concrete will be considered negligible.

**SERIES B
B5****Reinforcement Stress****Formatted 27 May 12
Printed 6/18/2012****MAXIMUM REINFORCEMENT STRESS AT SUPPORT
ASSUMING FULLY NONLINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$f_{\text{supmaxnon}} := \frac{M_{\text{supmax}}}{2 \cdot A_{\text{sb}} \cdot d \cdot \left(1 - 0.4 \cdot \frac{\rho \cdot 73 \text{ksi}}{0.7 \cdot f'_c} \right)} = 73 \cdot \text{ksi}$$

**MAXIMUM REINFORCEMENT STRESS AT SUPPORT
ASSUMING FULLY LINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$\text{Conc. modulus } E_c := 57000 \cdot \sqrt{f'_c \cdot \text{psi}} \quad E_c = 4.1 \times 10^6 \text{ psi}$$

Steel modulus

$$E_s := 29000 \text{ ksi}$$

Modular ratio

$$n := \frac{E_s}{E_c} \quad n = 7$$

Depth to neutral axis from extreme fiber in compression

$$k := \sqrt{(\rho \cdot n)^2 + 2 \cdot \rho \cdot n} - \rho \cdot n \quad k = 0.27$$

$$f_{\text{supmaxlin}} := \frac{M_{\text{supmax}}}{2 \cdot A_{\text{sb}} \cdot d \cdot \left(1 - \frac{k}{3} \right)} = 76 \cdot \text{ksi}$$

Check related maximum compressive stress in concrete

$$f_{\text{clin1}} := \frac{M_{\text{supmax}}}{\left(\frac{k \cdot b \cdot d^2}{2} \right) \cdot \left(1 - \frac{k}{3} \right)} = 4 \times 10^3 \cdot \text{psi} \quad (\text{Compression})$$

**SERIES B
B5**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/18/2012**

**MAXIMUM REINFORCEMENT STRESS IN CONTINUOUS
BAR AT END OF SPLICE ASSUMING FULLY NONLINEAR
DISTRIBUTION OF COMPRESSIVE STRESS IN THE
CONCRETE**

$$f_{snon3} := \frac{M_{3ft}}{2 \cdot A_{sb} \cdot d \cdot \left(1 - 0.4 \cdot \frac{\rho \cdot 70\text{ksi}}{0.7 \cdot f'_c}\right)} = 72 \cdot \text{ksi}$$

**MAXIMUM REINFORCEMENT STRESS IN CONTINUOUS BAR
AT END OF SPLICE ASSUMING LINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$f_{slin3} := \frac{M_{3ft}}{2 \cdot A_{sb} \cdot d \cdot \left(1 - \frac{k}{3}\right)} = 74 \cdot \text{ksi}$$

Check related maximum concrete stress

$$f_{clin3} := \frac{M_{3ft}}{\left(\frac{k \cdot b \cdot d^2}{2}\right) \cdot \left(1 - \frac{k}{3}\right)} = 4 \times 10^3 \text{ psi} \quad (\text{Compression})$$

SUMMARY

Reinforcement stress based on observed maximum load

**SERIES B
B5**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/18/2012**

At support

NONLINEAR

LINEAR

$$f_{\text{supmaxnon}} = 73 \cdot \text{ksi}$$

$$f_{\text{supmaxlin}} = 76 \cdot \text{ksi}$$

At splice end

$$f_{\text{snon3}} = 72 \cdot \text{ksi}$$

$$f_{\text{slin3}} = 74 \cdot \text{ksi}$$

NOMINAL UNIT BOND STRESS

Length of splice

$$L_d := 79 \text{in}$$

Bar diameter

$$d_b = 1.41 \cdot \text{in}$$

Average bond stress at maximum load

$$\mu_{\text{avg}} := \frac{f_{\text{snon3}} \cdot d_b}{4 \cdot L_d}$$

$$\text{round}\left(\frac{\mu_{\text{avg}}}{\text{psi}}, -1\right) \cdot \text{psi} = 320 \text{psi}$$

The number listed above for bond stress has relevance to design but is irrelevant to the actual bond stress at maximum load.

The hard information from the test is that the 79-in splice for No. 11 bars has developed a maximum bar stress of at least


$$f_{\text{snon3}} = 72 \cdot \text{ksi}$$

SERIES B
B6

Reinforcement Stress

Formatted 27 May 12
Printed 6/18/2012

TEST GIRDER B6



X-Sect. Area for a #11 Bar

Diameter, # 11 Bar

Nominal width of Section

Nominal height of Section

Top cover

Effective depth $d := 30\text{in} - c_t - \frac{d_b}{2}$

Yield Stress

Concrete Strength

Total Length

$L_t := 2 \cdot 14\text{in} + 2 \cdot 9\text{ft} + 2 \cdot 8.5\text{in} + 2 \cdot 3\text{ft} + 6\text{ft} + 7\text{in}$

Cantilevered Span $a := 10\text{ft} + 10.5\text{in}$

Interior Span $L_m := 12\text{ft} + 7\text{in}$

Reinforcement Ratio $\rho := 2 \cdot \frac{A_{sb}}{b \cdot d}$

Initial moment at support

$$A_{sb} := 1.56\text{in}^2$$

$$d_b := 1.41\text{in}$$

$$b := \left(17 + \frac{5}{8}\right) \cdot \text{in}$$

$$h := 30\text{in}$$

$$c_t := 5\text{in}$$

$$d = 24 \cdot \text{in}$$

$$f_y := 66\text{ksi}$$

$$f'_c := 5230\text{psi}$$

$$L_t = 34.3 \text{ ft}$$

$$a = 10.9 \text{ ft}$$

$$L_m = 13 \text{ ft}$$

$$\rho = 0.73 \cdot \%$$

$$M_{\text{supinit}} := 40.5\text{kip} \cdot \text{ft}$$

**SERIES B
B6**

Reinforcement Stress

Formatted 27 May 12

Printed 6/18/2012

EVALUATION AFTER TEST TO FAILURE

REINFORCEMENT STRESS AT MEASURED MAXIMUM LOAD

Note : Following calculations are made considering the supports not to have width in the direction of the span.

$$\text{Unit selfweight} \quad w_s := b \cdot h \cdot 150 \frac{\text{lb}}{\text{ft}^3} \quad w_s = 0.55 \cdot \frac{\text{kip}}{\text{ft}}$$

$$\text{Measured Maximum Applied Load} \quad P_{\max} := 40.6 \text{kip}$$

Moment at support related to selfweight and loading gear

Maximum moment at support

$$M_{\text{supmax}} := P_{\max} \cdot (a - 14 \text{in}) + M_{\text{supinit}}$$

Moment at 3 ft toward mid-span from support

$$M_{3\text{ft}} := M_{\text{supmax}} - \frac{w_s \cdot L_m}{2} \cdot 3\text{ft} + w_s \cdot \frac{(3\text{ft})^2}{2}$$

$$M_{3\text{ft}} = 427 \cdot \text{kip} \cdot \text{ft}$$

NOTE : Strain distributions over the depth of the section at the supports and at ends of the spliced bars are not linear once cracking is initiated. To assume a linear strain distribution and then to use an "exact" stress-strain relationship for the concrete is not correct. In the following, stresses in the reinforcement will be calculated assuming both linear and nonlinear response in the compressed concrete, and the lower value determined will be taken as the stress achieved. In both sets of calculations, contribution of the tensile strength of the concrete will be considered negligible.

**SERIES B
B6****Reinforcement Stress**Formatted 27 May 12
Printed 6/18/2012

**MAXIMUM REINFORCEMENT STRESS AT SUPPORT
ASSUMING FULLY NONLINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$f_{\text{supmaxnon}} := \frac{M_{\text{supmax}}}{2 \cdot A_{\text{sb}} \cdot d \cdot \left(1 - 0.4 \cdot \frac{\rho \cdot 73 \text{ksi}}{0.7 \cdot f'_c} \right)} = 73 \cdot \text{ksi}$$

**MAXIMUM REINFORCEMENT STRESS AT SUPPORT
ASSUMING FULLY LINEAR DISTRIBUTION OF
COMPRESSIVE STRESS IN THE CONCRETE**

$$\text{Conc. modulus } E_c := 57000 \cdot \sqrt{f'_c \cdot \text{psi}} \quad E_c = 4.1 \times 10^6 \text{ psi}$$

Steel modulus

$$E_s := 29000 \text{ ksi}$$

Modular ratio

$$n := \frac{E_s}{E_c} \quad n = 7$$

Depth to neutral axis from extreme fiber in compression

$$k := \sqrt{(\rho \cdot n)^2 + 2 \cdot \rho \cdot n} - \rho \cdot n \quad k = 0.27$$

$$f_{\text{supmaxlin}} := \frac{M_{\text{supmax}}}{2 \cdot A_{\text{sb}} \cdot d \cdot \left(1 - \frac{k}{3} \right)} = 76 \cdot \text{ksi}$$

Check related maximum compressive stress in concrete

$$f_{\text{clin1}} := \frac{M_{\text{supmax}}}{\left(\frac{k \cdot b \cdot d^2}{2} \right) \cdot \left(1 - \frac{k}{3} \right)} = 4 \times 10^3 \cdot \text{psi} \quad (\text{Compression})$$

**SERIES B
B6**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/18/2012**

MAXIMUM REINFORCEMENT STRESS IN CONTINUOUS BAR AT END OF SPLICE ASSUMING FULLY NONLINEAR DISTRIBUTION OF COMPRESSIVE STRESS IN THE CONCRETE

$$f_{snon3} := \frac{M_{3ft}}{2 \cdot A_{sb} \cdot d \cdot \left(1 - 0.4 \cdot \frac{\rho \cdot 72 \text{ksi}}{0.7 \cdot f'_c}\right)} = 72 \cdot \text{ksi}$$

MAXIMUM REINFORCEMENT STRESS IN CONTINUOUS BAR AT END OF SPLICE ASSUMING LINEAR DISTRIBUTION OF COMPRESSIVE STRESS IN THE CONCRETE

$$f_{slin3} := \frac{M_{3ft}}{2 \cdot A_{sb} \cdot d \cdot \left(1 - \frac{k}{3}\right)} = 74 \cdot \text{ksi}$$

Check related maximum concrete stress

$$f_{clin3} := \frac{M_{3ft}}{\left(\frac{k \cdot b \cdot d^2}{2}\right) \cdot \left(1 - \frac{k}{3}\right)} = 4 \times 10^3 \text{ psi} \quad (\text{Compression})$$

SUMMARY

Reinforcement stress based on observed maximum load

At support

**SERIES B
B6**

Reinforcement Stress

**Formatted 27 May 12
Printed 6/18/2012**

NONLINEAR

LINEAR

$$f_{\text{supmaxnon}} = 73 \cdot \text{ksi}$$

$$f_{\text{supmaxlin}} = 76 \cdot \text{ksi}$$

At splice end

$$f_{\text{snon3}} = 72 \cdot \text{ksi}$$

$$f_{\text{slin3}} = 74 \cdot \text{ksi}$$

NOMINAL UNIT BOND STRESS

Length of splice

$$L_d := 79 \text{in}$$

Bar diameter

$$d_b = 1.41 \cdot \text{in}$$

Average bond stress at maximum load


$$\mu_{\text{avg}} := \frac{f_{\text{snon3}} \cdot d_b}{4 \cdot L_d}$$

$$\text{round}\left(\frac{\mu_{\text{avg}}}{\text{psi}}, -1\right) \cdot \text{psi} = 320 \text{psi}$$


The number listed above for bond stress has relevance to design but is irrelevant to the actual bond stress at maximum load.

The hard information from the test is that the 79-in splice for No. 11 bars has developed a maximum bar stress of at least


$$f_{\text{snon3}} = 72 \cdot \text{ksi}$$




Specimen: A-1	Sheet: 1	of 1
Average Load: 6 kips	Drawn by: MDN	Checked by:
Average Deflection:	Date: 6/4/12	




Specimen: A-1	Sheet: 1	of 1
Average Load: 12 KIPS	Drawn by: MDN	Checked by:
Average Deflection:	Date: 6/4/12	




Specimen: A-1	Sheet: 1	of 1
Average Load: 24 kips	Drawn by: MDN	Checked by:
Average Deflection: 1.25"	Date: 6/4/12	





Specimen: A-1	Sheet: 1	of 1
Average Load: 30 kips	Drawn by: MDN	Checked by:
Average Deflection: 1.66"	Date: 6/4/12	




Specimen: A-1	Sheet: 1	of 1
Average Load: 41 kIPS	Drawn by: MDN	Checked by:
Average Deflection: 4.00"	Date: 6/4/12	




Specimen: A-1	Sheet: 1	of 1
Average Load: 4100 0 kips	Drawn by: MDN	Checked by:
Average Deflection: 1.00"	Date: 6/4/12	




Specimen: A-1	Sheet: 1	of	1
Average Load: 11 12 KIPS (RELOADED)	Drawn by: MDN	Checked by:	
Average Deflection: 1/100"	Date: 6/4/12		





Specimen: A-1	Sheet: 1	of 1
Average Load: 44 kips 24 kips (RELEASED)	Drawn by: MDN	Checked by:
Average Deflection: 4.00"	Date: 6/4/12	




Specimen: A-1	Sheet: 1	of 1
Average Load: 44 KIPS 36 KIPS (RELOADED)	Drawn by: MDN	Checked by:
Average Deflection: 4.00"	Date: 6/4/12	




Specimen: A-2	Sheet: 1	of 1
Average Load: 6 kips	Drawn by: MDN	Checked by:
Average Deflection: 0.13"	Date: 06/01/12	




Specimen: A-2	Sheet: 1	of 1
Average Load: 30 kips	Drawn by:	Checked by:
Average Deflection: 1.54"	Date:	




Specimen: A-2	Sheet: 1	of 1
Average Load: 36 kips	Drawn by: MDN	Checked by:
Average Deflection: 1.91"	Date: 6-01-12	




Specimen: A-2	Sheet: 1	of 1
Average Load: 38 kIP (YIELD)	Drawn by:	Checked by:
Average Deflection:	Date:	




Specimen: A-3	Sheet: 1	of 1
Average Load: 6 KIPS	Drawn by: MDN	Checked by:
Average Deflection: 0.14"	Date: 5/30/12	




Specimen: A-3	Sheet: 1	of 1
Average Load: 12 kips	Drawn by: MDN	Checked by:
Average Deflection: 0.46"	Date:	




Specimen: A-3	Sheet: 1	of 1
Average Load: 18 kips	Drawn by: MDN	Checked by:
Average Deflection:	Date: 5-30-12	





Specimen: A-3	Sheet: 1	of 1
Average Load: 24 kips	Drawn by: MDN	Checked by:
Average Deflection: 1.2"	Date: 5-30-12	




Specimen: A-3	Sheet: 1 of 1
Average Load: 30 kips	Drawn by: MDN Checked by:
Average Deflection: 1.6"	Date: 5-30-12




Specimen: A-4	Sheet: 1	of 1
Average Load: 6k	Drawn by:	Checked by:
Average Deflection: 0.17"	Date: 6/8/12	




Specimen: A-4	Sheet: 1	of 1
Average Load: 12 K	Drawn by:	Checked by:
Average Deflection:	Date: 6-8-12	





Specimen: A-4	Sheet: 1	of 1
Average Load: 18 k	Drawn by:	Checked by:
Average Deflection:	Date: 6-8-12.	




Specimen: A-4	Sheet: 1	of 1
Average Load: 24 K	Drawn by:	Checked by:
Average Deflection:	Date: 6/8/12	



	Specimen: A-4	Sheet: 1	of 1
	Average Load: 30k	Drawn by:	Checked by:
	Average Deflection: 1.71"	Date: 6/8/12	




Specimen:	Sheet:	1	of	1
Average Load: 38 k (YIELD)	Drawn by:		Checked by:	
Average Deflection: 2.7"	Date:			




*AT LARGEST POINT




Specimen: A-4	Sheet: 1	of 1	1
Average Load: 40k	Drawn by:	Checked by:	
Average Deflection: 4"	Date: 6-8-12		





Specimen:	Sheet:	1	of	1
Average Load: OK	Drawn by:		Checked by:	
Average Deflection:	Date:			




Specimen:	Sheet:	1	of	1
Average Load: 24 K (RELOADED)	Drawn by:		Checked by:	
Average Deflection:	Date:			




Specimen: A-4	Sheet: 1 of 1
Average Load: 36k (RELOADED)	Drawn by: _____ Checked by: _____
Average Deflection:	Date: _____




Specimen: A-5	Sheet: 1	of 1
Average Load: 6k	Drawn by:	Checked by:
Average Deflection: 0.16"	Date: 6/7/12	




Specimen: A-5	Sheet: 1	of 1
Average Load: 12K	Drawn by:	Checked by:
Average Deflection: 0.49"	Date:	




Specimen:	Sheet:	1	of	1
Average Load: 18 k	Drawn by:		Checked by:	
Average Deflection:	Date:			




Specimen:	Sheet:	1	of	1
Average Load: 18 24 K	Drawn by:	Checked by:		
Average Deflection:	Date:			




Specimen:	Sheet:	1	of	1
Average Load: 30K 30K	Drawn by:	Checked by:		
Average Deflection:	Date:			




Specimen:	A-S	Sheet:	1	of	1
Average Load:	18 36 k	Drawn by:		Checked by:	
Average Deflection:		Date:			





Specimen:	Sheet:	1	of	1
Average Load: 38k(YIELD)	Drawn by:		Checked by:	
Average Deflection:	Date:			




Specimen: A-5	Sheet: 1	of 1
Average Load: 40k	Drawn by:	Checked by:
Average Deflection: 4.0"	Date: 6/7/12	




	Specimen: A-5	Sheet: 1 of 1
	Average Load: 0 WIPS	Drawn by: [] Checked by: []
	Average Deflection: 2.0"	Date: 6/7/12




Specimen: A-5	Sheet: 1 of 1
Average Load: 12k (RELOADED)	Drawn by: _____ Checked by: _____
Average Deflection: 2.57"	Date: 6/7/12




Specimen: A-5	Sheet: 1	of 1
Average Load: 24.1k (RELOADED)	Drawn by:	Checked by:
Average Deflection: 3.22"	Date: 6/7/12	




Specimen:	A-S	Sheet:	1	of	1
Average Load:	36 k (RELOADED)	Drawn by:		Checked by:	
Average Deflection:	3.89"	Date:	6/7/12		





Specimen: A-6	Sheet: 1	of 1
Average Load: 6 kips	Drawn by: MDN	Checked by:
Average Deflection:	Date: 6/05/12	




Specimen: A-6	Sheet: 1 of 1
Average Load: 12 KIPS	Drawn by: MDN Checked by:
Average Deflection:	Date: 6/5/12




Specimen: A-6	Sheet: 1	of 1
Average Load: 18 kips	Drawn by: MDN	Checked by:
Average Deflection:	Date: 6/05/12	




Specimen: A-6	Sheet: 1	of 1
Average Load: 24 kips	Drawn by: MDN	Checked by:
Average Deflection:	Date: 6/05/12	




Specimen: A-6	Sheet: 1	of	1
Average Load: 36 kips	Drawn by: MDN	Checked by:	
Average Deflection:	Date: 6/05/12		




Specimen: A-6	Sheet: 1 of 1
Average Load: 38k (YIELD)	Drawn by: MDN Checked by:
Average Deflection: 2.72"	Date: 6/05/12




Specimen: A-6	Sheet: 1	of 1
Average Load: 40k	Drawn by: MDN	Checked by:
Average Deflection: 4.0"	Date: 6/05/12	




Specimen: A-6	Sheet: 1 of 1
Average Load: 0 kips	Drawn by: MDN Checked by:
Average Deflection:	Date: 6/05/12




Specimen: A-6	Sheet: 1	of 1
Average Load: 12 kips (RELOADED)	Drawn by: MDN	Checked by:
Average Deflection: 2.6"	Date: 6/05/12	



Specimen: A-6	Sheet: 1	of 1
Average Load: 24 K (RELOADED)	Drawn by: MDN	Checked by:
Average Deflection:	Date: 6/05/12	




Specimen: A-6	Sheet: 1	of 1
Average Load: 36 k (RELOADED)	Drawn by: MDN	Checked by:
Average Deflection: 3.89"	Date: 6/05/12	



Specimen: B-1	Sheet: 1	of 1
Average Load: 3.5	Drawn by:	Checked by:
Midspan-Deflection: 0.045	Date: 05/10/2012	


Avg.



Specimen:	B-1	Sheet:	1	of	1
Average Load:	6.0 K	Drawn by:	Y.W.	Checked by:	
Midspan Deflection:	0.14	Date:	05/10/12		

Avg.


crack width measured at the level of steel



Specimen:	B-1	Sheet:	1	of	1
Average Load:	12.00 K	Drawn by:	Y.W.	Checked by:	
Midspan Deflection:	0.43	Date:	05/10/12		

Aug.


crack width measured at the level of steel



Specimen:	B-1	Sheet:	1	of	1
Average Load:	18.0 K	Drawn by:	Y.W.	Checked by:	
Midspan Deflection:	0.78 in	Date:	05/10/12		

Avg.


crack width measured at the level of steel crack width $\times 10^{-3}$



Specimen: B-1	Sheet: 1	of 1
Average Load: 24.0 k	Drawn by: Y.W.	Checked by:
Midspan Deflection: 1.08 in	Date: 05/10/12	

Avg.


crack width
 $\times 10^{-3}$



Specimen: B-1	Sheet: 1	of	1
Average Load: 36.0 k	Drawn by: Y.W.	Checked by:	
Midspan Deflection: 1.82 in	Date: 5/10/12		


Failure

Crack width $\times 10^{-3}$




Specimen: B-1	Sheet: 1	of 1
Average Load:	Drawn by: Y.W.	Checked by:
Midspan Deflection:	Date: 5/10/12	


* CTL crack comparator used in this test




Specimen: B-2	Sheet: 1	of 1
Average Load: 6K	Drawn by: BPR	Checked by:
Average Deflection: 0.15"	Date: 5/23/12	




Specimen: B-2	Sheet: 1	of 1
Average Load: 12K	Drawn by: BPR	Checked by:
Average Deflection: 0.45"	Date: 5/23/12	




Specimen: B-2	Sheet: 1	of 1
Average Load: 18K	Drawn by: BPR	Checked by:
Average Deflection: 0.80"	Date: 5/23/12	





Specimen: B-2	Sheet: 1	of 1
Average Load: 24K	Drawn by: BPR	Checked by:
Average Deflection: 1.13"	Date: 5/23/12	




Specimen: B-2	Sheet: 1	of 1	1
Average Load: 30K	Drawn by: BPR	Checked by:	
Average Deflection: 1.47"	Date: 5/23/12		




Specimen: B-2	Sheet: 1	of 1
Average Load: 18K unload	Drawn by: BPR	Checked by:
Average Deflection: 1.25"	Date: 5/23/12	





Specimen: B-2	Sheet: 1	of 1
Average Load: OK Unload	Drawn by: BPR	Checked by:
Average Deflection: 0.48"	Date: 5/23/12	




Specimen: B-2	Sheet: 1	of 1
Average Load: 12 K Reload	Drawn by: BPR	Checked by:
Average Deflection: 0.88"	Date: 5/23/12	




Specimen: B-2	Sheet: 1	of 1
Average Load: 24k	Drawn by: BPR	Checked by:
Average Deflection: 1.41"	Date: 5/23/12	




Specimen: B-2	Sheet: 1	of 1	1
Average Load: 36K Reload	Drawn by: BPR	Checked by:	
Average Deflection: 1.94"	Date: 5/23/12		




Specimen: B-3	Sheet: 1	of 1
Average Load: 6K	Drawn by: BPR	Checked by:
Average Deflection: 0.14"	Date: 5/21/12	




Specimen: B-3	Sheet: 1	of 1
Average Load: 12K	Drawn by: BPR	Checked by:
Average Deflection: 0.41"	Date: 5/21/12	





Specimen: B-3	Sheet: 1	of 1	1
Average Load: 24K	Drawn by: BPR	Checked by:	
Average Deflection: 1.08"	Date: 5/21/12		




Specimen: B-3	Sheet: 1	of 1
Average Load: 30K	Drawn by: BPR	Checked by:
Average Deflection: 1.42"	Date: 5/21/12	




Specimen: B-3	Sheet: 1	of 1
Average Load: 36K	Drawn by: BPR	Checked by:
Average Deflection: 1.79"	Date: 5/21/12	




Specimen: B-3	Sheet: 1	of 1
Average Load: 12K Reload	Drawn by: BPR	Checked by:
Average Deflection: 0.85"	Date: 5/21/12	



Specimen: B-3	Sheet: 1	of 1
Average Load: 24K Rebad	Drawn by: BPR	Checked by:
Average Deflection: 1.35"	Date: 5/21/12	




Specimen: B-4	Sheet: 1	of 1
Average Load: 5.2k	Drawn by: V.M	Checked by:
Midspan Deflection: 0.016 Avg.	Date: 5-14-12	



Specimen: B-4	Sheet: 1	of 1
Average Load: 12k	Drawn by: V.M.	Checked by:
Midspan-Deflection: .32	Date: 5-14-12	

Aug.



Specimen: B-4

Sheet: 1 of 1


Average Load: 18"

Drawn by: KM Checked by:


Midspan Deflection: 0.62

Date: 5-14-12

AVS




Specimen:	B-4	Sheet:	1	of	1
Average Load:	24k	Drawn by:	km	Checked by:	
Midspan Deflection:	0.94	Date:	5-14-12		




Specimen: B-4	Sheet: 1	of 1
Average Load: 30 ^k	Drawn by: KM	Checked by:
Midspan Deflection: 1.25	Date: 5-14-12	

Avg




Specimen: B-4	Sheet: 1	of 1
Average Load: 36 k	Drawn by: KM	Checked by:
Midspan Deflection: 1.62	Date: 5-14-12	


AVG




Specimen: B-5	Sheet: 1	of 1
Average Load: 6K	Drawn by: BPR	Checked by:
Average Deflection: 0.08"	Date: 5/17	




Specimen: B-5	Sheet: 1	of 1
Average Load: 12K	Drawn by: BPR	Checked by:
Average Deflection: 0.35"	Date:	




Specimen: B-S	Sheet: 1	of 1
Average Load: 18K	Drawn by: BPR	Checked by:
Average Deflection: 0.68"	Date: 5/17	




Specimen: B-5	Sheet: 1	of 1
Average Load: 24 K	Drawn by: BPR	Checked by:
Average Deflection: 1.0"	Date: 5/17	




Specimen: B-5	Sheet: 1	of 1
Average Load: 30K	Drawn by: BPR	Checked by:
Average Deflection: 1.31"	Date: 5/17	




Specimen: B-5	Sheet: 1	of 1
Average Load: 361K	Drawn by: BPR	Checked by:
Average Deflection: 1.66"	Date: 5/17	




Specimen: B-5	Sheet: 1	of 1	1
Average Load: 24K Reload	Drawn by: BPR	Checked by:	
Average Deflection: 1.23"	Date: 5/17/12		




Specimen: B-6	Sheet: 1	of 1
Average Load: 6K	Drawn by: BPR	Checked by: MDN
Average Deflection: 0.11"	Date: 5/25/12	




Specimen: B-6	Sheet: 1	of 1
Average Load: 12 k	Drawn by: MDN	Checked by:
Average Deflection: 0.38"	Date: 5-25-12	




Specimen: B-6	Sheet: 1 of 1
Average Load: 24 K	Drawn by: MDN Checked by:
Average Deflection: 1.06"	Date: 5-25-12




Specimen: B-6	Sheet: 1	of 1
Average Load: 30 K	Drawn by: MDN	Checked by:
Average Deflection: 1.39"	Date: 5-25-12	




Specimen: B-6	Sheet: 1	of 1
Average Load: 36K	Drawn by: MDN	Checked by:
Average Deflection: 1.73"	Date: 5-25-12	




Specimen: B-6	Sheet: 1	of 1
Average Load: OK (UNLOADING)	Drawn by: MDN	Checked by:
Average Deflection: 0.44"	Date:	




Specimen: B-6	Sheet: 1	of 1
Average Load: 12 K (RELOADED)	Drawn by:	Checked by:
Average Deflection: 0.81"	Date:	



Specimen: B-6	Sheet: 1	of 1
Average Load: 24 K (RELOADED)	Drawn by: MDN	Checked by:
Average Deflection: 1.30"	Date:	



Specimen: B-6	Sheet: 1	of 1
Average Load: 36 K (RELOADED)	Drawn by: MDN	Checked by:
Average Deflection: 1.82"	Date: 5-25-12	



Specimen: B-6	Sheet: 1	of 1
Average Load: 38K (Yield)	Drawn by: BPR	Checked by:
Average Deflection:	Date: 5/25/12	

Slump shall be measured before any other activity related to casting takes place to make sure that the delivered mix has satisfactory workability. The mixing truck shall deliver a ticket with the batched mix weights. These weights shall be examined to corroborate that the delivered mix has the specified proportions. Concrete shall not be accepted if it arrives more than 45 min. after leaving the batching plant. No water shall be added to the mix after the truck leaves the plant.

Specimens and cylinders shall be cast and vibrated in two lifts following the Specifications. The vibrators to be used shall have the following cross-sectional dimensions:

For cylinders: 3/4" - 7/8"
For Larger Specimens: 1-3/4"

Their frequencies shall be between 50 and 200 Hz.

Excess concrete shall be removed off the formwork. The exposed surfaces of the specimens shall be finished using cast magnesium floats. Lifting inserts shall be inserted in the fresh concrete as soon as the finishing is completed.

Each test beam shall be cast using concrete from a single mixing truck. A complete set of concrete samples (cylinders) shall be obtained from each truck. Test beams and samples shall be marked with a number referring to the truck from which they were cast and the date of casting. In each casting day, trucks shall be numbered sequentially starting at 1. The number assigned to a truck shall be written clearly on the mix ticket describing the mix proportions for the batch. Test beams shall be cast and tested oriented in the North-South axis of the laboratory. During finishing, the north end of each beam shall be marked with the letter N.

These activities shall be documented using Form 3

1.4 Curing

As soon as casting is completed all specimens shall be covered with impermeable sheets. When the concrete surface sets, wet burlap shall be inserted between these sheets and the exposed concrete. All formwork and molds shall be struck no later than three days after the cast.

All exposed concrete surfaces shall be covered by wet burlap and impermeable sheets for a total of at least seven days after casting.

Burlap shall be doused with water at least every other day during the curing period.

Curing activities shall be logged using Form 4.

Test cylinders shall be stored and cured next to the test specimens and under similar conditions of temperature and humidity.

The variation of concrete strength with time shall be monitored as specified in the Specifications. The results of cylinder tests shall be recorded using Form 5.

2. Calibration

Three types of measurements will be made: displacement, force, air content.

The apparatuses to be used to calibrate sensors to measure these quantities are:

Displacement Sensors: INSTRON Universal Testing Machine (S.N.:)
Load Sensors: INSTRON Universal Testing Machine (S.N.:)
Air Content: Calibrated Cylinder (S.N.)

Load and displacement sensors will be calibrated following steps listed below:

- 1) Connect the sensor to the data-acquisition system that is going to be used in the test
- 2) Set and record the excitation voltage to the maximum possible value (not exceeding the maxima specified for the data-acquisition system and the sensor)
- 3) Set the data-acquisition equipment to record voltage
- 4) Set the gain of the data-acquisition system to the first available level lower than the ratio of the maximum range of the system to the maximum expected output from the sensor.
- 5) Mount the sensor on the universal testing machine
- 6) Apply a series of known displacement or force increments to the sensor ranging between 10% and 90% of the rated capacity of the sensor
- 7) Record the voltage read on the data-acquisition system at each known displacement or force increment
- 8) Create a plot of change in output voltage vs. change in force or displacement
- 9) Fit a line to the plot from 7) using "least squares"
- 10) Record the slope of the line from 8) (sensor sensitivity)
- 11) Label the cable used in the calibration with the serial number of the sensor

Sensors shall be calibrated before the first test and after the final test.

The apparatus used to measure air content of the fresh concrete shall be calibrated following the procedure described in ASTM standard 231. Form 6B shall be used to document the calibration.

All calibrations shall be performed by at least two persons: one leading each step and the other checking the work of the first independently. A log of each calibration shall be made using Form 6 and it shall include an estimate of the accuracy of the sensor.

Sensors for which the sensitivity obtained in 9) above deviates by more than 10% from the nominal sensitivity (as reported by the manufacturer) shall not be used in any of the tests.

3. Setup

Each test beam shall be placed on two roller supports as described in the attached proposal. The final location of the supports shall be measured (to the nearest 1/16 in.) with maximum deviation of 1/4 in and reported using Form 7. As-built external dimensions of each test beam shall be recorded using the same form. The maximum deviation from nominal dimensions in the test region shall be 1/4 in.

The test beam shall be placed with the reinforcement facing up as shown in the attached proposal.

The shear spans shall be reinforced with external stirrups (pairs of 5/8-in threaded rods) installed at a spacing not exceeding 12 in. The locations of the stirrups shall be measured. The measurements shall be recorded using Form 7.

The loading rigs (consisting of a loading tube, two hydraulic rams, two threaded rods, plates and nuts, and one load cell per rig) shall be placed on the test specimen and connected to “the strong floor” of the laboratory (without applying load to the specimen other than the weight of the rigs) as described in the attached proposal. The rams in each rig shall be connected to a single manifold and pump using 10,000-psi hydraulic hoses. All hoses and other hydraulic hardware shall be inspected visually and replaced –if defective- before testing.

4. Instrumentation

Displacement sensors shall be installed at midspan, at each support, and at each load point. They shall be secured to the strong floor of the laboratory directly below the point where displacement is to be measured.

All sensors (displacement and force) shall be connected to the data acquisition system using the same cables used during calibration. The excitation voltage and gain shall also be set to the value used in calibration. The data acquisition system shall be set to record voltage changes caused by loading. Before applying load with the hydraulic rams, all sensors shall be set to read a voltage value between 10% and 90% of the voltage output of the sensor at its rated capacity. These voltages shall be referred to as the “zero offsets” of the sensors. If a sensor is set to have an initial

voltage exceeding 20% of its output at rated capacity, the sign of the initial “zero offset” shall be opposite to the sign of the expected change in its signal.

Set the data acquisition system to scan all sensors and save at least one record per sensor every 1 sec.

Record a file of “zero offsets” capturing at least 10 min. of data before any load is applied with the hydraulic system.

Means of initial voltages for all sensors (mean “zero offsets”), sensor serial numbers, the most recent sensitivity constants, excitation voltages, and the channels of the data-acquisition system used for each sensor shall be recorded using Form 8. The pairing of channels and sensors shall be checked by a second person working independently from the person making the initial connections.

Infrared targets to be used to measure displacements as described in the attached proposal shall be glued to one face of the test beam using epoxy adhesive. The numbering sequence of these targets shall be recorded using Form 9.

Video cameras (one for long-time lapse video and one for high-speed video) will be positioned to capture the response of the mid third of each specimen. To the extent possible, the location of the cameras shall be the same in all tests.

5. Testing

The following actions shall take place during each test:

At the end of each loading increment:

Mark Cracks: all visible cracks shall be marked using black permanent markers. Cracks shall be marked by drawing lines parallel to them and with an offset of approximately 0.25 in.

Measure Crack Widths: Crack widths shall be measured using crack comparators or graduated handheld microscopes.

Measure coordinates of infrared coordinates: A set of coordinates shall be obtained using an OptoTrack System 600 Pro. A set of four targets shall be attached to the strong floor. They shall be located at approximately the same distance to the OptoTrack cameras as targets attached to the test beam. Coordinates for these reference targets shall be obtained at each loading increment. They are to be used to monitor the stability of the Optotrack system by computing the variation in the distances between reference targets.

In-Test Data Backup: At every loading increment the data being produced by the data-acquisition system shall be copied to an external hard drive.

Photographs: a set of high-resolution photographs shall be obtained after cracks are marked at each loading increment. The photographs shall include views of both elevations of the test beam and the top concrete surface above lap splices.

The following data shall be recorded throughout each test:

Sensor readings: to be recorded on a hard drive in volts. Conversion to engineering units shall be done after the test as follows:

- Subtract zero offsets
- Divide the result by the sensitivity obtained in the most recent calibration

Lapse video photographs: to be obtained every 5 min.

Actions to be taken at failure

Trigger high-speed camera to record breaking away of the concrete cover and relative movement of the bars.

Actions to be taken after test

Generate a record of sensors that may have malfunctioned or been accidentally moved during the test

Remove from all files recordings from sensors for which the results of the after-test calibration differ by more than 5% from the before-test calibration.


6. Reporting and Backup

Produce all the captured data in two ways:


- By uploading data, photos, and video to a private project at nees.org.
- By recording all data, photos, and video on a magnetic hard drive

Reports shall be produced as described in the Specifications.

Form 1



Section A-A




*For section B-B through F-F see Sheet 3 of 3

Series A




Drawing:	Series A Formwork As-builts	Sheet:	1	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

Form 1



Section A-A




*For section B-B through F-F see Sheet 3 of 3

Series B




Drawing:	Series B Formwork As-builts	Sheet:	2	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

Form 1



Section C-C, D-D, & E-E
*Facing North



Section B-B & F-F
*Facing North



Drawing:	Formwork As-built Sections	Sheet:	3	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

Form 1

Project: Tests to Determine the Behavior of Spliced #11 Bars

As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: _____

Sheet 1 of 2

Section	Formwork As-built Dimensions							
	1	2	3	4	5	6	7	8
A-A								
B-B								
C-C								
D-D								
E-E								
F-F								
Recorded by:			Signature				Date	Time
Checked by:			Signature				Date	Time
Checked by:			Signature				Date	Time
Comments:								
*See formwork as-built drawings for dimension locations								

Form 1

Project: Tests to Determine the
Behavior of Spliced #11 BarsAs-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: _____


Sheet 2 of 2

Section	Formwork As-built Dimensions Key - Series A							
	1	2	3	4	5	6	7	8
A-A	14'-6"	10'-0"	14'-6"	14'-6"	10'-0"	14'-6"	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
D-D	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
E-E	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
F-F	3"	8-3/4"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
Section	Formwork As-built Dimensions Key - Series B							
	1	2	3	4	5	6	7	8
A-A	13'-10.5"	6'-7"	13'-10.5"	13'-10.5"	6'-7"	13'-10.5"	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
D-D	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
E-E	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
F-F	3"	8-3/4"	3"	23-5/8" 8 - 11	23-5/8"	30"	30"	17-5/8"

Revision 2

Form 2

Wire Ties



NORTH

Bar Marks



NORTH



Specimen:					
Project:	Behavior of Lap Splices of No. 11 Reinforcing Bars	Drawn by:		Checked by:	
		Date:			

Project: Tests to Determine the
Behavior of Spliced #11 BarsCasting Documentation v.1
(Rev. 03/30/2012)

Specimen: _____

Sheet 1 of 1

General Information					
Date	Disp Ticket Num	Truck No.	Time on Ticket	Time of Arrival	Temp. in Lab
Measurements made upon arrival of concrete					
Slump (ASTM C143 - 10a)		Air Content (ASTM C231 - 10)			
Time ₁	Result ₁	Time ₁	Result ₁	S/N of Air Meter	
Time ₂	Result ₂	Time ₂	Result ₂	S/N of Scale	
Unit Weight (ASTM C138 - 10b)					
Time ₁	Wt. of Cont. ₁	Total Wt. ₁	Wt. of Conc. ₁	Result ₁ = Wt. of Conc./Vol. of Cont.	
Time ₂	Wt. of Cont. ₂	Total Wt. ₂	Wt. of Conc. ₂	Result ₂ = Wt. of Conc./Vol. of Cont.	
Times of actions during and after casting					
Layer 1 placed	Layer 1 vibration complete	Layer 2 placed	Layer 2 vibration complete	Top surface struck off	Truck Departing Lab
Lifting Inserts Placed	Covered with plastic	Plastic removed	Covered with burlap	Burlap doused with water	Covered with plastic
Recorded by		Signature		Date	Time
Checked by		Signature		Date	Time
Checked by		Signature		Date	Time
Comments:					
*The following ASTM standards and specifications will be followed during casting: C172-10, C192-07, C470-09					

Project: Tests to Determine the Behavior of Spliced #11 Bars

Curing Documentation v.1 (Rev. 03/30/2012)

Purdue University - Bowen Laboratory Sheet 1 of 1

General Information			
Specimen(s)	Date	Specimen Age	
	Time Beginning	Time Ending	
	Temperature inside Lab (deg. F)		
Description of Work Performed			
Recorded by	Signature	Date	Time
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time
Comments:			
*Test specimens and associated cylinders are to be cured under wet burlap for seven days			

Form 5

Project: Tests to Determine the
Behavior of Spliced #11 BarsCylinder Compression Tests Documentation v.2
(Rev. 04/01/2012)

Specimen: _____

Sheet 1 of 2

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]		Length [nearest 0.05 in.]			P _{max} [lb _f]	Fracture Type (1-6)
				1	2	1	2	3		
1										
2										
3										
4										
5										
6										
S/N of Testing Machine:										
Recorded by:			Signature			Date			Time	
Checked by:			Signature			Date			Time	
Checked by:			Signature			Date			Time	
Comments:										
*Cylinders to be test per ASTM C-39-12 and C-1231-10a with a loading rate of 60,000lb _f /min at concrete ages of 3, 7, 14, 28 days, and on same day that test of corresponding specimen is conducted. Specimens and caps free of defects unless otherwise noted in comments. Average cylinder diameter and area and unit compressive stress (f' _c) calculated on sheet 2 of 2.										

Form 5

Project: Tests to Determine the Behavior of Spliced #11 Bars

Cylinder Compression Tests Documentation v.2 (Rev. 04/01/2012)

Specimen: _____

Sheet 2 of 2

Specimen	Date	Age	Time of Test	Wet/Dry	Average Measured Dia. [in.]	Cross-sectional Area [in ²]	P _{max} [lbf]	f' _c [psi]	Fracture Type (1-6)
1	0-Jan		12:00 AM	0	#DIV/0!	#DIV/0!	0	#DIV/0!	0
2	0-Jan		12:00 AM	0	#DIV/0!	#DIV/0!	0	#DIV/0!	0
3	0-Jan		12:00 AM	0	#DIV/0!	#DIV/0!	0	#DIV/0!	0
4									
5									
6									

S/N of Testing Machine:			
Recorded by:	Signature	Date	Time
0		0	0
Checked by:	Signature	Date	Time
0		0	0
Checked by:	Signature	Date	Time

Comments:

*Cylinders to be test per ASTM C-39-12 and C-1231-10a with a loading rate of 60,000lbf/min at concrete ages of 3, 7, 14, 28 days, and on same day that test of corresponding specimen is conducted. Specimens and caps free of defects unless otherwise noted in comments. Recorded data is shown on sheet 1 of 2.

Calibration Instrument Name and S.N.:					
Data Acquisition System:					
Gain:					
Excitation Voltage:					
Channel:					
Sensor:					
Sensor S.N.:					
Measurand	Voltage	Measurand	Voltage	Measurand	Voltage
Operator		Signature		Date	Time
Checked by		Signature		Date	Time
Checked by		Signature		Date	Time
Results	Sensitivity		Accuracy		
Notes:					


Project: Tests to Determine the Behavior of Spliced #11 Bars

Calibration Documentation v.1
(Rev. 04/06/2012)

Bowen Lab - Purdue University
Sheet 1 of 1

Meter S.N.			
Type of Meter			
Meter Brand Name			
Ambient Temperature			
	Target Air Content	Measured Air Content	
Operator	Signature	Date	Time
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time
Notes:			

Form 7



Specimen

Behavior of Lap Splices of No. 11
Reinforcing Bars

Sheet:

1

of


4

Drawn by:

Checked by:


Date:

Form 7




Top Plan

2 Spa. @



Profile

*For section B-B through F-F see Sheet 3 of 3




Bottom Plan




Drawing:	Series A Concrete As-builts	Sheet:	2	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

Form 7




Top Plan



Profile

*For section B-B through F-F see Sheet 3 of 3




Bottom Plan



Drawing:	Series B Concrete As-builts	Sheet:	3	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

Form 7



Section B-B, C-C, D-D, E-E & F-F
*Facing North



Drawing:	Concrete As-built Sections	Sheet:	4	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

Form 7

Project: Tests to Determine the Behavior of Spliced #11 Bars

Setup and As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: _____

Sheet 1 of 2

Section	Concrete As-built Dimensions							
	1	2	3	4	5	6	7	8
Plan								
B-B								
C-C								
D-D								
E-E								
F-F								
Recorded by:			Signature				Date	Time
Checked by:			Signature				Date	Time
Checked by:			Signature				Date	Time
Comments:								
*See concrete as-built drawings for dimension locations								

Form 7

Project: Tests to Determine the
Behavior of Spliced #11 BarsSetup and As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: _____

Sheet 2 of 2

Section	Concrete As-built Dimensions Key - Series A							
	1	2	3	4	5	6	7	8
Plan	39'-0"	39'-0"	39'-0"	39'-0"	N/A	N/A	N/A	N/A
B-B	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
C-C	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
D-D	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
E-E	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
F-F	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
Section	Concrete As-built Dimensions Key - Series B							
	1	2	3	4	5	6	7	8
Plan	34'-4"	34'-4"	34'-4"	34'-4"	N/A	N/A	N/A	N/A
B-B	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
C-C	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
D-D	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
E-E	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
F-F	17-5/8"	30"	17-5/8"	30" 8 - 24	N/A	N/A	N/A	N/A

Revision 2

Form 8


Project: Tests to Determine the Behavior of Spliced #11 Bars

Instrumentation Documentation v.1
(Rev. 04/01/2012)

Specimen: _____
Sheet _____ of _____

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity	Zero Offset	Location	Comments
Operator		Signature			Date		Time	
Checked by		Signature			Date		Time	
Checked by		Signature			Date		Time	
Notes:								

Form 9



Specimen

Behavior of Lap Splices of No. 11
Reinforcing Bars

Drawn by:

Checked by:

Date:

Purdue University

Specimen : A-1Date: 6/4/12

	Average Load (lb) \checkmark K	North Overhang (in)	South Overhang (in)	North Splice End (in)	Midspan (in)	South Splice End (in)	LVDT North Support	LVDT South Support	North Load Cell (lb) \checkmark K	South Load Cell (lb) \checkmark K	DG North Overhang (in)	DG South Overhang (in)	Time
1	0.2	0.01	0.01	0.00	-0.00	-0.00	0.000	-0.000	0.02 0.2	0.2 0.2	0.300 0.100	0.000	7:44A
2	3.6	first crack											
3	6	0.20	0.19	0.03	0.04	0.02	0.000	-0.000	6	6	0.294	0.171	8:16A
4	12	0.52	0.51	0.08	0.11	0.07	-0.000	-0.000	12	12	0.614	0.500	8:38A
5	18	0.87	0.90	0.13	0.19	0.13	-0.000	0.000	18	18	0.960	0.897	9:01A
6	24	1.23	1.27	0.18	0.28	0.19	-0.001	-0.001	24	24	1.329	1.268	9:35A
7	30	1.64	1.67	0.24	0.36	0.25	-0.002	-0.001	30	30	1.738	1.668	10:00A
8	N+S	DG reset									0.800	0.900	10:26A
9	36	2.05	2.09	0.31	0.46	0.31	-0.002	-0.001	36	36	1.236	1.338	10:28A
10	37.3	yield											
11	38	2.36	2.51	0.35	0.53	0.38	-0.003	-0.001			1.554	1.755	10:54A
12	40.5	3.87	4.14	0.65	0.90	0.68	-0.005	-0.004	40.7	40.3			10:33A
13	20.2	3.03	3.20	0.52	0.70	0.55	-0.005	-0.005	20.2	20.2			10:58A
14	0.2	1.91	2.14	0.32	0.43	0.36	-0.005	-0.004	0.2	0.2			12:05P
15	12	2.42	2.68	0.42	0.55	0.44	-0.005	-0.004	12.0	12.0			12:20P
16	24	3.05	3.34	0.52	0.70	0.55	-0.005	-0.004	24.0	24.0			12:37P
17	36	3.70	3.99	0.62	0.86	0.65	-0.004	-0.004	36.0	36.0			12:54P
18	40.7	4.33	4.61	0.73	1.01	0.77	-0.005	-0.005	40.1	40.0			1:22p
19	41.9	5.34	5.67	0.90	1.23	0.95	-0.006	-0.004	41.4	41.2			1:36p
20	43	6.34	6.67	1.09	1.48	1.13	-0.010	-0.010	42.2	42.1			1:44p

Purdue University

Specimen : A-2Date: 6/1/12

	Average Load (lbf)	North Overhang (in)	South Overhang (in)	North Splice End (in)	Midspan (in)	South Splice End (in)	LVDT North Support	LVDT South Support	North Load Cell (lbf)	South Load Cell (lbf)	DG North Overhang (in)	DG South Overhang (in)	Time
1	0.28	0	0	-0.01	0	-0.01	-0.001	-0.001	0.3	0.3	0.2	0.2	8:01A
2	1st crack at 2.7k								6 ^{cell}	6 ^{cell}			8:07A ^{cell}
3	6	0.14	0.11	0.01	0.03	0.01	-0.001	-0.001	6	6	0.340	0.312	8:07A
4	12	0.44	0.44	0.06	0.10	0.06	-0.000	-0.001	12	12	0.638	0.632	8:35A
5	18	0.79	0.78	0.11	0.18	0.11	-0.001	-0.001	18	18	0.985	0.968	8:54A
6	24	1.16	1.17	0.17	0.26	0.17	-0.001	-0.001	24	24	1.355	1.367	9:21A
7	30	1.56	1.53	0.22	0.34	0.22	-0.002	-0.001	30	30	1.765	1.720	9:55A
8	N + S DG reset										0.800 ^{cell}	0.800	
9	36	1.93	1.89	0.27	0.42	0.28	-0.002	-0.001	36	36	1.274	1.165	10:29A
10	38.4	2.29	2.22	0.33	0.48	0.32	-0.001	-0.000			1.499 ^{cell} 635	1.499	10:59A
11	40.8	3.63	3.39	0.55	0.72	0.53	-0.002	-0.001	40.6	41			11:32A
12	Max. Load ~44.5k.												
13													
14													
15													
16													
17													
18													
19													
20													

Purdue University

Specimen : A-3

Date: 5/30/12

	Average Load (lb) \checkmark K	North Overhang (in)	South Overhang (in)	North Splice End (in)	Midspan (in)	South Splice End (in)	LVDT North Support	LVDT South Support	North Load Cell (lb) \checkmark K	South Load Cell (lb) \checkmark K	DG North Overhang (in)	DG South Overhang (in)	Time
1	0.16	0.00	0.00	0.00	0.00	0.00	-0.002	-0.002	0.2	0.1	0.1	0.1	8:06
2	6.2	0.13	0.15	0.02	0.03	0.02	-0.002	-0.002	6.2	6.2	6.2 ^{0.234}	0.218	8:13
3	12	0.44	0.47	0.07	0.1	0.07	-0.002	-0.001	12	12	0.538	0.57	8:33
4	18	0.80	0.83	0.12	0.18	0.12	-0.003	0.000	17.9	18	0.894	0.932	9:03
5	24	1.19	1.19	0.18	0.26	0.17	-0.003	0.001	24	24	1.289	1.284	9:32
6	30	1.55	1.57	0.23	0.33	0.23	-0.003	0.002	30	30	1.657	1.657	10:11
7	36	1.93	1.96	0.29	0.42	0.29	-0.004	0.004	36	36	/	/	10:40
8													
9													
10													
11													
12													
13													
14													
15													
16													
17													
18													
19													
20													

Purdue University

Specimen : A-4Date: 6/8/12

	Average Load (lbf)	North Overhang (in)	South Overhang (in)	North Splice End (in)	Midspan (in)	South Splice End (in)	LVDT North Support	LVDT South Support	North Load Cell (lbf)	South Load Cell (lbf)	DG North Overhang (in)	DG South Overhang (in)	Time
1	0.3	-0.01	-0.01	-0.00	-0.00	0.00	-0.001	-0.001	0.3	0.3	0.000	0.000	7:43A
2	2.2	first crack											
3	6.0	0.17	0.16	0.02	0.04	0.02	-0.001	-0.001	6.0	6.0	0.169	0.171	7:52A
4	12.0	0.49	0.51	0.07	0.11	0.07	-0.001	-0.002	12.0	12.0	0.494	0.519	8:11A
5	18.0	0.96	0.92	0.14	0.21	0.14	-0.001	-0.001	18.0	18.0	0.963	0.929	8:36A
6	24.1	1.33	1.29	0.19	0.29	0.19	-0.001	-0.001	24.1	24.1	1.338	1.299	9:04A
7	29.9	1.73	1.69	0.25	0.38	0.26	-0.000	-0.001	29.9	29.9	1.740	1.706	9:24A
8	N+S	DG reset									0.000	0.000	
9	36.0	2.15	2.13	0.32	0.48	0.32	-0.000	0.001	36.0	36.0	0.428	0.439	9:51A
10	N+S	DG reset									0.000	0.000	
11	36.8	yield							36.8	36.7			
12	37.8	2.66	2.67	0.40	0.58	0.42	-0.001	0.002	37.8	37.8	0.520	0.538	10:20A
13	40.0	3.97	4.04	0.61	0.85	0.66	-0.003	0.003	39.9	40.1	1.825	2.922	10:54A
14	20.2	3.13	3.25	0.49	0.66	0.54	-0.003	0.003	20.2	20.2	0.983	1.110	11:25A
15	0.3	1.97	2.09	0.31	0.40	0.35	-0.003	0.001	0.3	0.3			11:30A
16	12.0	2.49	2.60	0.37	0.51	0.42	-0.003	0.001	12.0	12.0			11:46A
17	24.0	3.16	3.26	0.49	0.66	0.54	-0.003	0.002	24.1	24.0			11:59A
18	36.0	3.83	3.93	0.59	0.82	0.64	-0.003	0.003	36.0	36.0			12:16P
19	40.4	4.44	4.56	0.69	0.96	0.75	-0.003	0.005	40.5	40.4			12:35P
20	41.7	5.17	5.55	0.86	1.17	0.93	-0.003	0.005	41.6	41.9			12:53P

Purdue University

Specimen : A-5Date: 6/7/12

	Average Load (lbf)	North Overhang (in)	South Overhang (in)	North Splice End (in)	Midspan (in)	South Splice End (in)	LVDT North Support	LVDT South Support	North Load Cell (lbf)	South Load Cell (lbf)	DG North Overhang (in)	DG South Overhang (in)	Time
1	0.22	0.3	0.2	0.01	0.01	0.00	-0.002	-0.002	0.3	0.2	0.000	0.000	7:35A
2	3.2	first crack											
3	6.0	0.17	0.15	0.03	0.05	0.03	-0.002	-0.002	5.9	6.1	0.169	0.151	8:00A
4	12.0	0.49	0.49	0.07	0.11	0.07	-0.002	-0.001	12.0	12.0	0.488	0.488	8:21A
5	18.0	0.86	0.84	0.13	0.20	0.13	-0.002	-0.001	18.0	18.0	0.860	0.846	8:45A
6	24.0	1.23	1.25	0.18	0.28	0.18	-0.001	0.000	24.0	24.0	1.231	1.257	9:11A
7	30.0	1.61	1.63	0.25	0.37	0.24	-0.001	0.001	30.0	30.0	1.623	1.645	9:38A
8	N+S	DG reset									0.000	0.000	
9	36.0	2.07	2.10	0.31	0.47	0.32	-0.000	0.001	36.0	36.0	0.450	0.464	10:06A
10	37.5	yield											
11	37.38	2.44	2.61	0.37	0.55	0.39	-0.000	0.001	37.7	37.5	0.875	0.987	10:32A
12	N+S	DG reset									0.000	0.000	
13	40.2	3.90	4.12	0.63	0.85	0.66	-0.000	-0.001	40.2	40.2	1.540	1.531	10:58A
14	20.3	3.08	3.29	0.50	0.66	0.52	-0.000	-0.001	20.3	20.2	0.622	0.767	11:32A
15	0.2	1.95	2.12	0.32	0.40	0.34	-0.002	-0.001	0.2	0.2			11:38A
16	12.0	2.47	2.67	0.40	0.51	0.42	-0.002	-0.001	11.9	12.0			11:51A
17	24.0	3.11	3.34	0.50	0.67	0.53	-0.001	-0.001	24.1	24.0			12:04P
18	36.0	3.77	4.01	0.61	0.82	0.64	-0.000	-0.001	36.0	36.0			12:19P
19	40.7	4.38	4.62	0.71	0.97	0.75	0.000	-0.001	40.8	40.6			12:41P
20	42.2	5.39	5.63	0.88	1.20	0.94	0.000	-0.003	42.3	42.0			12:58P

Purdue University

Specimen: A-6Date: 6/5/12

	Average Load (k)	North Overhang (in)	South Overhang (in)	North Splice End (in)	Midspan (in)	South Splice End (in)	LVDT North Support	LVDT South Support	North Load Cell (k)	South Load Cell (k)	DG North Overhang (in)	DG South Overhang (in)	Time
1	0.23	0.00	0.00	0.00	-0.00	0.00	-0.000	-0.000	0.3	0.2	0.000	0.000	1:04 P
2	3.14	first crack											
3	6	0.15	0.15	0.02	0.03	0.03	0.001	-0.000	6.0	6.0	0.144	0.154	1:12 P
4	12	0.45	0.45	0.07	0.09	0.07	0.004	0.000	12.0	12.1	0.447	0.450	1:30 P
5	18	0.86	0.86	0.13	0.18	0.13	0.007	-0.001	18.0	17.9	0.851	0.845	1:55 P
6	24	1.27	1.23	0.18	0.27	0.18	0.008	-0.001	24.0	24.0	1.268	1.219	2:25 P
7	30	1.64	1.64	0.24	0.36	0.25	0.009	-0.002	30.0	30.0	1.639	1.651	2:48 P
8	N+S	DG reset									0.000	0.000	2:56 P
9	36	2.09	2.12	0.31	0.47	0.33	0.009	-0.003	36	36	0.458	0.475	3:51 P
10	37	Yield											
11	38	2.63	2.79	0.41	0.59	0.44	0.009	-0.004	37	37	1.003	1.163	3:55 P
12	N+S	DG reset									1.021	1.181	
13											0.000	0.000	4:26 P
14	39.8	3.84	4.19	0.62	0.86	0.68	0.009	-0.007	39.9	39.7	1.173	1.400	4:31 P
15	20.2	3.00	3.37	0.49	0.66	0.54	0.008	-0.007	20.1	20.3	0.733	0.556	4:57 P
16	0.22	1.86	2.20	0.31	0.40	0.35	0.007	-0.007	0.2	0.2			5:06 P
17	12	2.39	2.74	0.39	0.52	0.44	0.007	-0.007	12.0	12.0			5:22 P
18	24	3.04	3.40	0.50	0.67	0.55	0.008	-0.007	24.0	24.0			5:36 P
19	36	3.71	4.07	0.60	0.83	0.66	0.009	-0.007	36.0	36.0			5:49 P
20	10.3	4.32	4.70	0.70	0.97	0.77	0.009	-0.009	10.7	39.9			6:13 P

Purdue University

Specimen : A-6

Date: 6.5.12

	Average Load (lbf)	North Overhang (in)	South Overhang (in)	North Splice End (in)	Midspan (in)	South Splice End (in)	LVDT North Support	LVDT South Support	North Load Cell (lbf)	South Load Cell (lbf)	DG North Overhang (in)	DG South Overhang (in)	Time
21	41.1	5.07	5.44	0.83	1.15	0.93	0.008	-0.011	41.1	41.2			6:23P
22	Max Load: ~42.k												
23													
24													
25													
26													
27													
28													
29													
30													
31													
32													
33													
34													
35													
36													
37													
38													
39													
40													

Purdue University

Specimen: B-1Date: 5/10/12

	Average Load (kip)	North Overhang (in)	South Overhang (in)	North Splice End (in)	Midspan (in)	South Splice End (in)	LVDT North Support	LVDT South Support	North Load Cell (lbf)	South Load Cell (lbf)	TIME
1	0.2	0.01	-0.01	0	0	0	-0.001	-0.000	0.2	0.2	12:10
2	DGs	0	0								
3	3.5	0.05	0.04	0.01	0	0	0	0	3.5	3.5	
4	DGs	0.035	0.045								
5	2.3	0.04	0.04	0.01	0	0	-0.001	0	2.2	2.3	2 PM
6	DGs	0.033	0.044								
7	6	0.13	0.14	0.02	0.02	0.02	0.001	0.001	6	6	2:04
8	DGs	0.122	0.146								
9	12	0.44	0.42	0.05	0.07	0.06	0.003	0.001	12	12	2:21
10	DGs	0.414	0.429								
11	18	0.79	0.76	0.1	0.13	0.1	0.004	0.002	18	18	2:53
12	DGs	0.762	0.770								
13	24	1.1	1.07	0.15	0.18	0.14	0.007	0.002	24	24	3:16
14	DGs	1.069	1.079								
15	30	1.43	1.42	0.19	0.24	0.19	0.008	0.003	30	30	3:43
16	DGs	1.401	1.432	→ REMOVED							
17	36	1.82	1.81	0.25	0.31	0.25	0.009	0.003	36	36	4:16
18	~46 :	Failure.									
19											
20											

Purdue University

Specimen: B-2Date: 5/23/12

	Average Load (lb) K	North Overhang (in)	South Overhang (in)	North Splice End (in)	Midspan (in)	South Splice End (in)	LVDT North Support	LVDT South Support	North Load Cell (lb) kip	South Load Cell (lb) kip	DG North Overhang (in)	DG South Overhang (in)	Time
1	0.2	0	0.01	0	0	-0.01	-0.005	0.001	0.3	0.2	+0.100	0.100	7:57A
2	3.4	1 st CRACK											
3	6.0	0.14	0.16	0.02	0.02	0.01	-0.005	0.001	6	6	0.238	0.244	8:30A
4	12	0.47	0.42	0.06	0.07	0.05	-0.004	0.002	12	12	0.571	0.510	8:54A
5	18	0.81	0.78	0.11	0.13	0.10	-0.003	0.002	18	18	0.897	0.871	9:11A
6	24	1.14	1.11	0.15	0.19	0.15	-0.002	0.003	24	24	1.217	1.206	9:35A
7	30	1.48	1.46	0.2	0.25	0.2	-0.001	0.004	30	30	1.558	1.548	10:00A
8	36	1.88	1.85	0.26	0.33	0.26	-0.001	0.004	36	36	N.A.	1.945	10:26A
9											Reset: @ 1.9	RELATIVE MEASUREMENTS	
10	18	1.27	1.23	0.18	0.22	0.17	-0.002	0.005	18	18	1.296	1.320	11:10A
11	0.2	0.48	0.48	0.07	0.08	0.06	-0.004	0.001	0.2	0.2	0.500	0.550	11:15A
12	12	0.89	0.87	0.12	0.15	0.11	-0.002	0.002	12	12	0.914	0.960	11:30A
13	24	1.43	1.39	0.2	0.24	0.19	-0.001	0.004	24	24	1.444	1.480	11:45A
14	36	1.96	1.91	0.28	0.34	0.27	-0.001	0.006	36	36	—	2.009	12:00 N.
15	DG's Removed @ 36 k												
16	Max Load = 39k												
17													
18													
19													
20													

Purdue University

Specimen : B-3Date: 5/21/12

	Average Load lb k	North Overhang (in)	South Overhang (in)	North Splice End (in)	Midspan (in)	South Splice End (in)	LVDT North Support	LVDT South Support	North Load Cell lb k	South Load Cell lb k	DG North Overhang (in)	DG South Overhang (in)	Time
1	0.2	0	0	0	0	0	-0.001	-0.003	0.2	0.2	0	0	8A
2	3k	: 1st crack											
3	6.2	0.14	0.14	0.02	0.03	0.02	-0.001	-0.002	6.2	6.2	0.143	0.132	8:10A
4	12	0.42	0.40	0.05	0.07	0.05	-0.003	-0.002	12	12	0.429	0.407	8:35A
5	18	0.78	0.74	0.10	0.13	0.10	-0.004	-0.002	18	18	0.780	0.747	9:04A
6	24	1.09	1.07	0.14	0.19	0.15	-0.004	-0.002	24	24	1.087	1.080	9:27A
7	30	1.43	1.41	0.19	0.25	0.2	-0.004	-0.001	30	30	1.420	1.423	9:57A
8	36	1.79	1.78	0.25	0.32	0.25	-0.004	0.000	36	36	1.780	1.795	10:28A
9	0.2	0.44	0.44	0.06	0.09	0.06	-0.004	-0.006	0.2	0.2	0.435	0.436	11:05A
10	12	0.86	0.84	0.12	0.15	0.12	-0.004	-0.004	12.1	11.9	0.854	0.840	11:14A
11	24	1.36	1.34	0.18	0.24	0.19	-0.004	-0.002	24	24	1.352	1.352	11:25A
12	36	1.87	1.84 ⁵	0.26	0.34	0.26	-0.004	-0.001	36	36	1.855	1.864	11:47A
13	MAX LOAD:		39.8k										
14													
15													
16													
17													
18													
19													
20													

Purdue University

Specimen : B-4

Date: 5/14/12

	Average Load (lbf)	North Overhang (in)	South Overhang (in)	North Splice End (in)	Midspan (in)	South Splice End (in)	LVDT North Support	LVDT South Support	North Load Cell (lbf)	South Load Cell (lbf)	DG North Overhang (in)	DG South Overhang (in)	Time
21	0.2	0	0	0	0	0	0	0	0.2	0.2	0.2	0.2	4:10 P
22	3.5	0.02	0.03	0	0	0	0	0.001	3.5	3.5	0.225	0.228	4:17 P
23	0.2	0	0	0	0	0	0	0.001	0.2	0.2	0.202	0.202	4:27 P
24													
25													
26													
27													
28													
29													
30													
31													
32													
33													
34													
35													
36													
37													
38													
39													
40													

Purdue University

Specimen : B-4Date: 5/14

	Average Load (lbf)	North Overhang (in)	South Overhang (in)	North Splice End (in)	Midspan (in)	South Splice End (in)	LVDT North Support	LVDT South Support	North Load Cell (lbf)	South Load Cell (lbf)	DG North Overhang (in)	DG South Overhang (in)	Time
1	0.2	0	0	0	0	0	-0.002	-0.001	0.2	0.2	0.203	+0.205	1:20
2	5.2	0.04	0.05	0	0	0	-0.001	0	5.2	5.2	0.245	0.255	~1:35
3	L	1ST CRACK											
4	12	0.31	0.33	0.04	0.05	0.05	0	0.001	12	12	0.514	0.535	1:58
5	18	0.62	0.63	0.08	0.11	0.08	0.003	0.002	18	18	0.811	0.833	2:20
6	L	1ST SPLIT. CRACK							24	24			
7	24	0.95	0.94	0.13	0.16	0.13	0.004	0.003	24	24	1.131 ✓	1.148 ✓	2:57
8	30	1.26	1.25	0.17	0.21	0.17	0.006	0.004	30	30	1.439 ✓	1.459 ✓	3:33
9	36	1.62	1.61	0.21	0.27	0.22	0.006	0.004	36	36	1.898	1.824	4:09
10	DGs Removed.												
11	38	1.77	1.76	0.23	0.3	0.24	.008	.005	38	38	—	—	4:56
12													
13													
14													
15													
16													
17													
18													
19													
20													

Purdue University

Specimen : B-5Date: 5/17/12

	Average Load (lbf)	North Overhang (in)	South Overhang (in)	North Splice End (in)	Midspan (in)	South Splice End (in)	LVDT North Support	LVDT South Support	North Load Cell (lbf) \swarrow	South Load Cell (lbf) \swarrow	DG North Overhang (in)	DG South Overhang (in)	Time	
1	0.2	0	0	0	0	0	0	0	0.2	0.2	0	0.300	12:20 PM	
2	0.2	0	0	0	0	0	0.001	0.001	0.2	0.2	0	0.300	1:25 PM	
3	6	0.08	0.08	0	0.02	0.01	0.002	0.002	6	6	0.076	0.380	1:37 PM	
4	↳ 1 ST CRACK OBSERVED													
5	12	0.33	0.36	0.04	0.06	0.05	0.004	0.002	11.9	12	—	0.660	1:56 PM	
6	18	0.70	0.65	0.08	0.11	0.09	0.004	0.003	18	18	0.691	0.948	2:20 PM	
7	24	1.01	0.98	0.12	0.17	0.13	0.004	0.003	24	24	0.997	1.275	2:48 PM	
8	30	1.33	1.30	0.17	0.22	0.17	0.005	0.003	30	30	1.303	1.593	3:16 PM	
9	RESET DGS:											1.000	1.000	
10	36	1.68	1.63	0.22	0.28	0.22	0.005	0.004	36	36	1.343	1.342	3:44 PM	
11	0	0.39	0.39	0.05	0.07	0.05	0.003	0.002	0	0	0.082	0.085	4:14 PM	
12	12	0.76	0.74	0.09	0.13	0.10	0.004	0.002	12	12	0.444	0.441	4:42 PM	
13	24	1.25	1.21	0.15	0.21	0.16	0.004	0.003	24	24	0.918	0.915	4:49 PM	
14	32	1.56	1.53	0.2	0.27	0.21	0.005	0.004	32	32	—	—	5:30 PM	
15														
16														
17														
18														
19														
20														

Purdue University

Specimen: B-6Date: 5/25/12

	Average Load kip kip	North Overhang (in)	South Overhang (in)	North Splice End (in)	Midspan (in)	South Splice End (in)	LVDT North Support	LVDT South Support	North Load Cell kip kip	South Load Cell kip kip	DG North Overhang (in)	DG South Overhang (in)	Time
1	0.18	0	0.02	0	0	0	-0.006	0	0.2	0.2	0	0.100	8:22 A
2	3.9 k:	1st crack											
3	6	0.1	0.12	0.01	0.01	0.01	-0.005	0.002	6	6	0.105	0.207	8:29 A
4	12	0.37	0.39	0.05	0.06	0.04	-0.004	0.003	12	12	0.368	0.470	8:57 A
5	18	0.73	0.71	0.09	0.11	0.08	-0.003	0.003	18	18	0.718	0.805	9:06 A
6	24	1.09	1.04	0.14	0.17	0.13	-0.002	0.004	24	23.9	1.068	1.130	9:30 A
7									30 ↘	30 ↘			
8	30	1.42	1.36	0.19	0.22	0.17	-0.001	0.005	30 ↘	30 ↘	1.392	1.457	9:54 A
9	36	1.76	1.70	1.70 0.24	0.29	0.23	0.001	0.006	36	36	1.734	1.795	10:14 A
10	18.5	1.18	1.16	0.16	0.19	0.15	-0.001	0.005	18.5	18.5	1.169	1.256	10:39 A
11	0	0.43	0.43	0.06	0.07	0.05	-0.004	0.004	0.2	0.2	0.404	0.505	10:50 A
12	12	0.81	0.80	0.11	0.13	0.10	-0.002	0.004	12	12	0.805	0.892	11:06 A
13	24	1.33	1.29	0.18	0.21	0.17	-0.000	0.005	24	24	1.303	1.381	11:18 A
14	36	1.85	1.78	0.25	0.30	0.24	0.001	0.006	36	36.1	1.820	1.876	11:34 A
15	38	2.02	1.93								NO DG's		
16	MAX	LOAD:	~41.6										
17													
18													
19													
20													

TAKING ACCURATE THERMOMETER READINGS

COMMON TYPES OF THERMOMETERS AND FACTORS AFFECTING THEIR USE

TOTAL IMMERSION thermometers are designed with scales calibrated to indicate the true temperature when the bulb and the portion of the thermometer that contains the mercury column are exposed to the temperature to be measured (practically, less than an inch is permitted to extend above the surface, to permit the reading to be made). Most total immersion thermometers can also be used in a condition of complete immersion, in which case the entire thermometer is exposed to the temperature being measured, such as in a freezer.

PARTIAL IMMERSION thermometers are designed with scales calibrated to indicate the true temperature when the thermometers are immersed to specified depths. The portion that should be immersed is indicated on the back of each thermometer.

COMPUTATION OF EMERGENT STEM CORRECTION

When total immersion thermometers are used only partially immersed, a stem correction may be calculated and applied to the reading for precision results. To compute an emergent stem correction, the following variables must be defined:

T = the reading of the thermometer in situ.

N = the number of degrees on the thermometer scale between the liquid surface and the top of the mercury column.

A = the average temperature of the emergent mercury column. To find value A, suspend alongside the subject thermometer a secondary or auxiliary thermometer with its bulb centered between the liquid level and the temperature indicated on the subject thermometer.

The temperature indicated on this auxiliary thermometer will be value A.

Find the stem correction (SC) by computation from the following formula:

$SC = 0.00016 \times (N \times (T-A))$ for Celsius temperatures, or

$SC = 0.00009 \times (N \times (T-A))$ for Fahrenheit temperatures.

Example: A thermometer graduated from -1° to 101°C ., immersed to 20°C on its scale, reading 90°C . The auxiliary thermometer reads 42°C . Hence, $T=90$, $N=70$ (90.20). $A=42$

Working the formula, $SC = 0.00016 \times (70 \times (90 - 42))$ yields a value for SC of $+0.537$. This value must be added to the observed indication of the subject thermometer to determine the true temperature of the liquid. Hence, the true temperature of the liquid is $90^{\circ} + 0.54^{\circ}$ (rounded result) = 90.54°

GENERAL CONSIDERATIONS FOR MAKING AN ACCURATE READING

The error due to parallax may be eliminated by taking care that the reflection of the scale can be seen in the mercury thread, and by adjusting the line of sight so that the graduation of the scale nearest the meniscus exactly hides its own image: the line of sight will then be normal to the stem at that point. In reading thermometers, account must be taken of the fact that the lines are of appreciable width. The best practice is to consider the position of the lines as defined by their middle parts.

PERFORMING A CALIBRATION AT THE ICE POINT (0 DEGREES CELSIUS OR 32 DEGREES FAHRENHEIT)

Select clear pieces of ice, preferably made from relatively pure water. Discard any cloudy or unsound portions. Rinse the ice with distilled water and shave or crush into small pieces, avoiding direct contact with the hands or any chemically unclean objects. Fill a Dewar or other insulated vessel with the crushed ice and add sufficient distilled (and preferably precooled) water to form a slush, but not enough to float the ice. Insert the thermometer, packing the ice gently about the stem, to a depth sufficient to cover the 0°C (32°F) graduation. As the ice melts, drain off some of the water and add more crushed ice.

Raise the thermometer a few millimeters after at least 3 minutes have elapsed, tap the stem gently and observe the reading. Successive readings taken at least one minute apart should agree within one tenth of one graduation.

APPLYING THE CORRECTION AT ICE POINT

Record readings and compare with previous readings. If the readings are found to be higher or lower than the reading corresponding to a previous calibration, readings at all other temperatures will be correspondingly increased or decreased.

Reproduced in part from ASTM E77.



KESSLER THERMOMETER CORP.

Precision and Reliability . . . from a name you can trust.

CALSER CORPORATION 302 N. BELT EAST SWANSEA, IL 62226 (618)277-0329

TESTING MACHINE CERTIFICATE OF CALIBRATION

Owner : Purdue University
 Location : 1040 South River Rd. - Bowen Lab
 West Lafayette, IN 47907
 Machine : Forney 600,000lbf Model F-600-DFM/1
 Serial No. : 99058
 w/ Forney DFM/1 Digital R/O #9902182
 w/ Dynisco P/T #02-23-990747

Report # : VN# 6560

Page : 2 of 2

Date of Service: 06/06/11

This is to certify that the testing machine listed above has been calibrated by Calser Corporation personnel.

The method of verification and listed data are in accordance with ASTM E 4-09.

Accuracy of all calibration devices is traceable to the National Institute of Standards and Testing (NIST) and all calculations have been corrected for temperature where applicable.

Capacity Range	Loading Range	Max. Error
Run 1 600,000lbf Range	5,000 - 600,000	1.20 %
Run 2 600,000lbf Range	5,000 - 600,000	0.10 %
Run 3 600,000lbf Range	5,000 - 600,000	0.08 %

Verification Equipment Used:

(400,000 Load Cell Set)

Admet Gage Buster Digital Readout, Serial # GB-9911092,
 and Load Cell(s) Listed Below:

Serial #	Range	Calib. Date	Uncertainty
901120B	716.99 -10,000 lbf	08/19/2009	1.792 lbf
090716C (LO)	5,572.38 - 100,000 lbf	08/10/2010	13.931 lbf
090716C (HI)	39,281.95 - 400,000 lbf	08/10/2010	98.205 lbf

This certificate is issued as a statement of the fact that on the above date the listed testing machine has an accuracy as indicated. It should not be construed or regarded as a Guarantee or Warranty of any kind (in favor of the client, the client's customers, or the public at large) that the testing machine will continue to retain the same percentage (%) of accuracy or efficiency as determined on the date when the calibration, and adjustments if required, was performed and reported by "Calser Corporation" since the calibrator has absolutely no control over the future operation, damage, maintenance, repairs, and overall condition of the testing machine and hereby expressly disclaims any and all liability for damage or loss sustained by all parties arising or resulting from the deterioration, obsolescence, malfunction or substandard performance of said testing machine; which shall remain the sole responsibility of the machine's regular custodian, owner, and/or user. This certificate shall not be reproduced except in full, without the written approval of Calser Corporation.

CALSER CORPORATION

Quality Control Director



Thomas R. Gagen

Form # 104-01-Rev 3

CALSER CORPORATION

TESTING MACHINE CALIBRATION DATA AND REPORT

302 N. Belt East, Swansea, IL 62226

(618) 277-0329

Customer: Purdue University
 Location: 1040 South River Rd. - Bowen Lab
West Lafayette, IN 47907
 Machine: Fomey 600,000lbf Model F-600-DFM/1
 Serial No.: 99058
 Auxiliary Equipment: w/ Fomey DFM/1 Digital R/O #9902182
w/ Dynisco P/T #02-23-990747

Report #: VN# 6560
 Page 1 of 2
 Date of Service: 06/06/11
 Cust Order No.: Verbal
 Order Date: 06/02/11
 Temp.: 74° F
 Date Last Done: 05/19/10

Applied Force	*	Indicated Force	Error	%	*	Indicated Force	Error	%	*	Indicated Force	Error	%
Run #1		Run #1	"As Found" Condition			Run #2	"As Left" Condition			Run #3	"As Left" Condition	
600,000lbf Range	*	10lbf / DIV			*				*			
0	6C	0	0	0.00	6C	0	0	0.00	6C	0	0	0.00
5,000	6C	4,940	-60	1.20	6C	5,000	0	0.00	6C	5,000	0	0.00
10,000	7	9,880	-120	1.20	7	9,990	-10	0.10	7	10,000	0	0.00
20,000	7	19,790	-210	1.05	7	19,990	-10	0.05	7	19,990	-10	0.05
40,000	8	39,530	-470	1.18	8	40,000	0	0.00	8	40,000	0	0.00
60,000	8	59,340	-660	1.10	8	60,010	10	0.02	8	60,000	0	0.00
80,000	8	79,150	-850	1.06	8	80,050	50	0.06	8	80,030	30	0.04
100,000	8	98,940	-1,060	1.06	8	100,060	60	0.06	8	100,070	70	0.07
125,000	8	123,600	-1,400	1.12	8	125,090	90	0.07	8	125,100	100	0.08
150,000	8	148,330	-1,670	1.11	8	150,150	150	0.10	8	150,120	120	0.08
200,000	8	197,650	-2,350	1.18	8	199,980	-20	0.01	8	200,010	10	0.01
300,000	8	296,650	-3,350	1.12	8	300,060	60	0.02	8	300,040	40	0.01
400,000	8	395,880	-4,120	1.03	8	400,120	120	0.03	8	400,090	90	0.02
500,000	8	495,110	-4,890	0.98	8	500,260	260	0.05	8	500,210	210	0.04
600,000	8	593,770	-6,230	1.04	8	600,310	310	0.05	8	600,290	290	0.05
0	8	0	20	0.00	8	0	-10	0.00	8	0	-30	0.00

***CALIBRATION EQUIPMENT**

All verification equipment-including dead weights, proving rings, load cells, etc, is calibrated and traceable to the latest procedures stipulated by the National Institute of Standards and Testing (NIST) and ASTM E74-06. All equipment is traceable under guidelines set forth in ISO/IEC 17025. All instrument readings have been corrected for temperature where necessary.

Notes:

Calibration in accordance with ASTM E4-09, and Calser Corporation Procedure # 1-01, Rev 1.

ACCURACY SUMMARY

Capacity Range	Loading Range	Max. Error
Run 1		
600,000lbf Range	5,000 - 600,000	1.20 %
Run 2		
600,000lbf Range	5,000 - 600,000	0.10 %
Run 3		
600,000lbf Range	5,000 - 600,000	0.08 %

VERIFICATION EQUIPMENT

Manufacturer & Serial #	* L/C	Class A Range (in LBs) and Uncertainty (LBF)	Agency & Date
Strainsense 901120B	6C	716.99 -10,000 lbf 1.792 lbf	Morehouse 08/19/09
Strainsense 090716C (LO)	7	5,572.38 - 100,000lbf 13.931 lbf	Morehouse 08/10/10
Strainsense 090716C (HI)	8	39,281.95 - 400,000 lbf 98.205 lbf	Morehouse 08/10/10

Calibration Technician Jerry Parker

This report shall not be copied except in its entirety without express written approval of Calser Corp.

CERTIFICATE OF CALIBRATION

ISSUED BY: INSTRON CALIBRATION LABORATORY

DATE OF ISSUE: 30-Jan-12

CERTIFICATE NUMBER: 340013012113643



Lab code: 200301-0



Instron
 825 University Avenue
 Norwood, MA 02062-2643
 Telephone: (800) 473-7838
 Fax: (781) 575-5750
 Email: service_requests@instron.com

Page 1 of 3 pages

APPROVED SIGNATORY

**Richard
 Binford**

Digitally signed by Richard
 Binford
 DN: cn=Richard Binford,
 c=US, l=Norwood, st=MA,
 ou=OVR
 Date: 2012.01.30 12:01:16
 -05'00'

Type of Calibration: ~~Strain~~
Relevant Standard: **ASTM E83-10**
Date of Calibration: **30-Jan-12**

Customer

Name: PURDUE UNIVERSITY
Address: 550 STADIUM MALL DR.
 WEST LAFAYETTE, IN 47907
 KBROWER@PURDUE.EDU
P.O./Contract No.:
Contact: KEVIN BROWER

Machine

Manufacturer: BALDWIN
Serial Number: 120BTEC502040
System ID: 120BTEC502040
Range Type: Single

Transducer

Manufacturer: INSTRON
Transducer ID: 2630-115/590
Extensometer Type: Type 1
Travel (Tension): 1 in
Travel (Compression): 0.1 in
Gauge Length: 2 in
Mode: Static (Tension/Compression)

Classification

The following indicators of the extensometer system were verified and classed:

Indicator Type	Description	Indicator Units	Range Full Scale (%)	System Class
1. Digital Readout		strain	100	B-1

Certification Statement

All indicators listed above were verified on-site at customer location by Instron in accordance with ASTM E83.

The verification and equipment used conform to a controlled Quality Assurance program which meets the specifications outlined in ANSI/NCSL Z540-1, ISO 10012, ISO 9001:2008 and ISO/IEC 17025:2005.

The testing machine was verified in the 'as found' condition.

Instron Calpro Version 3.23

The results indicated on this certificate and the following report relate only to the items verified. If there are methods or data included that are not covered by the NVLAP accreditation it will be identified in the comments. Any limitations of use as a result of this verification will be indicated in the comments. This report must not be used to claim product endorsement by NVLAP or the United States government. This report shall not be reproduced, except in full, without the approval of the issuing laboratory.

CERTIFICATE OF CALIBRATION

NVLAP ACCREDITED CALIBRATION LABORATORY No. 200301-0

CERTIFICATE NUMBER:

340013012113643

Page 3 of 3 pages

Data**Indicator 1. - Digital Readout (strain)**

% of Range	Run 1		Run 2	
	Indicated (strain)	Applied (in)	Indicated (strain)	Applied (in)
100% Range (Full Scale: 1.00016 in)				
Run Temperature: 70.0 °F			Run Temperature: 70.1 °F	
40	0.19991	0.400580	0.1995	0.400013
70	0.34995	0.700010	0.349987	0.700023
100	0.49985	1.000162	0.49899	1.000050

Verification Equipment and Usage**Verification Equipment:**

Make/Model	Serial Number	Description	Calibration Agency	Measurement Range	Cal Date	Cal Due
Extech 445580	1003552	temp. indicator	Tektronix	NA	12-Feb-11	12-Feb-13
Epsilon 3590VHR	A5010 (ASTM)	disp. indicator	Instron Ltd	2.00 in	14-Feb-11	14-Feb-12
* Instron US Gauge Bar	I902	gauge bar	AA Jansson	NA	11-May-10	11-May-12
* HBM ML38	90630412	force indicator	Instron	NA	21-Jan-11	21-Jan-13
* Epsilon 3590VHR	A5010 (ASTM)	(Note: Also used for displacement measurements and listed above.)				

* Equipment used for gauge length measurements.

Verification Equipment Usage:

Measurement Type	Serial Number	Range (% Full Scale)	Percent(s) of Range
Displacement	A5010 (ASTM)	100	0/10/20/40/70/100

Instron standards are traceable to NIST and/or other National standards.

Comments

Verified by: Rich Binford
Field Service Engineer

NOTE: Clause 9 of ASTM E-83 states; It is recommended that extensometer systems be verified annually or more frequently if required. In no case shall the time interval between verifications exceed 18 months (unless an extensometer is being used in a long-time test running beyond the 18 month period). An extensometer system shall not be used after an adjustment or repair that could affect its accuracy without first verifying its accuracy utilizing the procedure described in this practice.


INSTRON®

CEAST / Dynatup / IST / SATEC / Wilson / WOLPERT

Instron® Service

825 University Avenue ■ Norwood, MA 02062-2643

Tel: +1-800-473-7838 ■ Fax: +1-781-575-5755

www.Instron.com
Field Service Report

Company: Purdue University
 Address: 550 Stadium Mall Drive
 Civil Room G151
 West Lafayette, IN 47907
 USA

Contact: Brower Kevin
 Service Order #: SV1201120017@@@1

Field Engineer: Richard Binford

Service Notes: Contract Total Amount: \$2330.

PO #: Credit Card

Reference #:

Verified force, displacement and the extensometer. Keep a regular check on the pressure transducer oil capsule gap regularly to insure the .030" gap for accurate force readings.

Labor Activities

Work Date	Product/SN	Tag Number	Work Hours	Charge Code	Description
01/30/2012		120BTEC502040	0.02	S1400-003-A	Zone 3 For Tensile Service
01/30/2012		120BTEC502040	1.00	S1460-011-A	Crosshead Displacement Verification
01/30/2012		120BTEC502040	2.00	S1481-017-C-A	Force Verification, 68K lb- 300K lb Compression
01/30/2012	2630-115/590	120BTEC502040	1.00	S1490-003-A	Strain Verification, Static Ext or Deflectometer

Materials

Part Number	Part Number Description	Qty	Serial #
-------------	-------------------------	-----	----------

CERTIFICATE OF CALIBRATION

ISSUED BY : INSTRON CALIBRATION LABORATORY

DATE OF ISSUE : 30-Jan-2012

CERTIFICATE NUMBER: 340013012110833

NVLAP

Lab code: 200301-0

Page 1 of 3



Instron
825 University Avenue
Norwood, MA 02062-2643
Telephone: (800) 473 - 7838
Fax: (781) 575 - 5755
Email: service_requests@instron.com

APPROVED SIGNATORY

**Richard
Binford**

Digitally signed by Richard
Binford
DN: cn=Richard Binford, c=US,
l=Norwood, st=MA, ou=OVR
Date: 2012.01.30 11:36:28
-05'00'

Type of Calibration: Displacement**Relevant Standard:** astm e2309**Date of Calibration:** 30-Jan-2012**Customer Requested Due Date:** 30-Jan-2013

Customer
PURDUE UNIVERSITY
550 STADIUM MALL DR.
WEST LAFAYETTE, IN 47907

Machine
Serial No : C502040
Make : BALDWIN
Model : 120BTE

P.O. Number :

Contact : HARRY TIDRICK

Readout Verified

1. Digital Readout (in)

Certification Statement

This certifies that the displacements verified with machine indicator 1 (listed above) were verified by Instron in accordance with ASTM E2309-05 (Follow-the-Displacement Method) and Instron work instruction ICA-8-07.

The testing machine was verified on-site at customer location. Adjustments are noted in the comments section of this report with a reference to the "As Found" data.

The verification and equipment used conform to a controlled Quality Assurance program which meets the specifications outlined in ANSI/NCSS Z540-1, ISO 10012, ISO 9001:2000, and ISO/IEC 17025:2005. The Instron measurement equipment used for verification is traceable to NIST.

Summary of Results

Indicator 1- Digital Readout (in)

Verified Range (in)	Max Error (in)	Max Error (%)	Max Repeat Error (in)	Max Repeat Error (%)	System Class*	Resolution (in)	Resolution Class	ASTM Lower Limit (in)
0.2 - 1	-0.00268	-0.355	0.00112	0.257	B	.001	B	0.2

*System Class is derived from assessment of the following: error, repeatability, resolution, and standard device classification.

The results indicated on this certificate and report relate only to the items verified. If there are methods or data included that are not covered by the NVLAP accreditation it will be identified in the comments. Any limitations of use as a result of this verification will be indicated in the comments. This report must not be used to claim product endorsement by NVLAP or the United States government. This report shall not be reproduced, except in full, without the approval of Instron.

CERTIFICATE OF CALIBRATION

ISSUED BY : INSTRON CALIBRATION LABORATORY

DATE OF ISSUE : 30-Jan-2012

CERTIFICATE NUMBER: 340013012110833

Page 2 of 3

Direction of Displacement : Ascending

Datapoint Summary - Indicator 1 - Digital Readout (in)

Suggested Value (in)	Run 1 Error (in)	Run 1 Error (%)	Run 2 Error (in)	Run 2 Error (%)	Run 3 Error (in)	Run 3 Error (%)	Repeat Error (in)	Uncertainty (in)*	Coverage Factor = k
0.2	0.00007	0.035	-0.00045	-0.222	-0.00026	-0.129	0.00052	0.00081	2.26
0.4	-0.00110	-0.276	-0.00086	-0.213	-0.00091	-0.227	0.00024	0.00070	2.26
0.6	-0.00105	-0.153	-0.00214	-0.355	-0.00176	-0.292	0.00109	0.00150	2.78
0.8	-0.00268	-0.331	-0.00156	-0.189	-0.00162	-0.203	0.00112	0.00165	2.78
1	-0.00168	-0.164	-0.00142	-0.142	-0.00198	-0.196	0.00056	0.00086	2.26

*The reported expanded uncertainty of measurement is based on a combined uncertainty multiplied by a coverage factor k to provide a level of confidence of approximately 95 %.

Runs 1 and 2 are performed to comply with the requirements of ASTM E2309, run 3 is performed to calculate the uncertainty of measurement.

Data - Indicator 1 - Digital Readout (in)

Temperature at start of verification : 67.9 °F

Suggested Value	Run 1			Run 2			Run 3	
	Applied	Indicated	Error Class	Applied	Indicated	Error Class	Applied	Indicated
0.2	0.19993	0.200	A	0.20245	0.202	A	0.20126	0.201
0.4	0.39810	0.397	A	0.40286	0.402	A	0.40091	0.400
0.6	0.68605	0.685	A	0.60314	0.601	A	0.60176	0.600
0.8	0.80968	0.807	A	0.82356	0.822	A	0.79962	0.798
1	1.02568	1.024	A	1.00142	1.000	A	1.00798	1.006

For runs 1 and 2: the worst Resolution Class is B and the worst Repeatability Class is A.

Temperature at end of verification : 70 °F

Starting Point of crosshead : 0 in

Verification Equipment

Make/Model	Serial No.	Description	Cal Agency	Uncertainty of Calibration	Resolution	Cal Date	Due Date
Instron LDS-10	06105014	Linear Gage	AA JANSSON	.000013 in	.00001 in	3-Aug-10	3-Aug-12
EXTECH 445580	1003552	Thermometer	TEKTRONIX	1 °F	.1 °F	12-Feb-11	12-Feb-13

The standards used for this verification are traceable to NIST.

CERTIFICATE OF CALIBRATION

ISSUED BY : INSTRON CALIBRATION LABORATORY

DATE OF ISSUE : **30-Jan-2012**

CERTIFICATE NUMBER: **340013012110833**

Page 3 of 3

Comments

Verified By: RICHARD BINFORD
SNR.SERV.ENGR,

CERTIFICATE OF CALIBRATION

ISSUED BY: INSTRON CALIBRATION LABORATORY

DATE OF ISSUE: 30-Jan-12

CERTIFICATE NUMBER: 340013012095410



Lab code: 200301-0

**Instron**

825 University Avenue
 Norwood, MA 02062-2643
 Telephone: (800) 473-7838
 Fax: (781) 575-5750
 Email: service_requests@instron.com

Page 1 of 4 pages

APPROVED SIGNATORY

**Richard
 Binford**

Digitally signed by Richard
 Binford
 DN: cn=Richard Binford,
 c=US, l=Norwood, st=MA,
 ou=OVR
 Date: 2012.01.30 11:08:19
 -05'00'

Type of Calibration: **Force**
 Relevant Standard: **ASTM E4-10**
 Date of Calibration: **30-Jan-12**

Customer Requested Due Date: 30-Jan-13

Customer

Name: PURDUE UNIVERSITY
 Address: 550 STADIUM MALL DR.
 WEST LAFAYETTE, IN 47907
 KBROWER@PURDUE.EDU

P.O./Contract No.:

Contact: KEVIN BROWER

Machine

Manufacturer: BALDWIN
 Serial Number: 120BTEC502040
 System ID: 120BTEC502040
 Range Type: Single

Transducer

Manufacturer: BALDWIN
 Transducer ID: 120BTEC502040
 Capacity: 120000 lbf
 Type: Compression

Classification

1. Digital Readout - PASSED

Certification Statement

This certifies that the forces verified with machine indicator(s) (listed above) that passed are WITHIN $\pm 1\%$ accuracy, 1% repeatability, and zero return tolerance.

All machine indicators were verified on-site at customer location by Instron in accordance with ASTM E4.

The certification is based on runs 1 and 2 only. A third run is taken to satisfy uncertainty requirements according to ISO 17025 specifications.

The verification and equipment used conform to a controlled Quality Assurance program which meets the specifications outlined in ANSI/NCSL Z540-1, ISO 10012, ISO 9001:2008 and ISO/IEC 17025:2005.

Method

The testing machine was verified in the 'as found' condition with no adjustments carried out.

Instron CalproCR Version 3.23

The results indicated on this certificate and the following report relate only to the items verified. If there are methods or data included that are not covered by the NVLAP accreditation it will be identified in the comments. Any limitations of use as a result of this verification will be indicated in the comments. This report must not be used to claim product endorsement by NVLAP or the United States government. This report shall not be reproduced, except in full, without the approval of the issuing laboratory.

CERTIFICATE OF CALIBRATION

NVLAP ACCREDITED CALIBRATION LABORATORY No. 200301-0

CERTIFICATE NUMBER:

340013012095410

Page 2 of 4 pages

Summary of Results

Temperature at start of verification: 67.00 °F.

Indicator 1. - Digital Readout (lbf)

Range	Tested Force Range	Mode	ASTM E4 Max Error (%)	ASTM E4 Max Repeat Error (%)	Zero Return	Resolution (lbf)	ASTM E4 Lower Limit (lbf)
100	-1194.4 to -119044.9	C	0.88	0.11	Pass	1	200

Temperature at end of verification: 67.80 °F.

Data Point Summary - Indicator 1. - Digital Readout (lbf)**COMPRESSION**

% of Range	Run 1 Error (%)	Run 2 Error (%)	Run 3 Error (%)	ASTM E4 Repeat Error (%)	Relative Uncertainty* (%)	Uncertainty of Measurement* (± lbf)
100% Range (Full Scale: -119044.9 lbf)						
1	0.47	0.43	0.43	0.04	0.14	1.661
2	0.41	0.48	0.49	0.07	0.14	3.321
4	0.42	0.46	0.45	0.04	0.13	6.213
7	0.77	0.76	0.77	0.01	0.14	11.254
10	0.82	0.75	0.76	0.07	0.14	16.908
20	0.88	0.77	0.78	0.11	0.15	36.187
40	0.81	0.81	0.80	0.00	0.14	64.283
70	0.81	0.80	0.81	0.01	0.14	112.494
100	0.80	0.81	0.81	0.01	0.14	160.702

* The reported expanded uncertainty is based on a standard uncertainty multiplied by a coverage factor $k = 2$, providing a level of confidence of approximately 95%.

Data - Indicator 1. - Digital Readout (lbf)**COMPRESSION**

% of Range	Run 1		Run 2		Run 3	
	Indicated (lbf)	Applied (lbf)	Indicated (lbf)	Applied (lbf)	Indicated (lbf)	Applied (lbf)
100% Range (Full Scale: -119044.9 lbf)						
0 Return	1		0		-1	
1	-1200	-1194.4	-1200	-1194.9	-1200	-1194.85
2	-2400	-2390.3	-2400	-2388.5	-2400	-2388.2
4	-4800	-4780.1	-4800	-4777.95	-4800	-4778.5
7	-8400	-8335.52	-8400	-8336.7	-8400	-8336.11
10	-12000	-11902.07	-12000	-11910.33	-12000	-11909.74
20	-24000	-23789.98	-24000	-23815.94	-24000	-23815.35
40	-48000	-47615.95	-48000	-47615.36	-48000	-47618.9
70	-84000	-83326.29	-84000	-83333.37	-84000	-83327.47
100	-120000	-119044.89	-120000	-119034.86	-120000	-119034.86

CERTIFICATE OF CALIBRATION


NVLAP ACCREDITED CALIBRATION LABORATORY No. 200301-0

CERTIFICATE NUMBER:

340013012095410

Page 3 of 4 pages

The Return to Zero tolerance is \pm the indicator resolution, 0.1 % of the maximum force verified in the range, or 1% of the lowest force verified in the range, whichever is greater.

Graphical Data - Indicator 1. - Digital Readout (lbf)**Verification Equipment**

Make/Model	Serial Number	Description	Calibration Agency	Capacity	Cal Date	Cal Due
Extech 445580	1003552	temp. indicator	Tektronix	NA	12-Feb-11	12-Feb-13
HBM ML38	90630412	force indicator	Instron	NA	21-Jan-11	21-Jan-13
Strainsense 050530	050530	load cell	Instron	120000 lbf	10-Dec-10	10-Dec-12
HBM 10KFRR	688077	load cell	Instron	12000 lbf	24-Apr-10	24-Apr-12

Verification Equipment Usage

Range	Full Scale (%)	Standard Serial Number	Mode	Percent(s) of Range	Lower Limit for Standard Class A / A1 (lbf)
100	100	050530	C	7/10/20/40/70/100	5000 / 5000
100	100	688077	C	1/2/4	200 / 200

Instron standards are traceable to NIST.

The standard Class A lower limit is used for systems with an accuracy of \pm 1.0% and the standard Class A1 lower limit is used for systems with an accuracy of \pm 0.5%.

Standard forces have been temperature compensated as necessary.

Comments

CERTIFICATE OF CALIBRATION

ISSUED BY: INSTRON CALIBRATION LABORATORY

DATE OF ISSUE: 12-Apr-12

CERTIFICATE NUMBER: 516041212091759



Lab code: 200301-0

**Instron**

825 University Avenue
 Norwood, MA 02062-2643
 Telephone: (800) 473-7838
 Fax: (781) 575-5750
 Email: service_requests@instron.com

Page 1 of 3 pages

APPROVED SIGNATORY

**Jimmy
 Warner**

Digitally signed by Jimmy Warner
 DN: cn=Jimmy Warner, c=US,
 l=Norwood, st=MA, ou=OVR
 Reason: I attest to the accuracy
 and integrity of this document
 Date: 2012.04.12 09:51:28 -04'00'

Type of Calibration: Strain
Relevant Standard: ASTM E83-10
Date of Calibration: 12-Apr-12

Customer Requested Due Date: 23-Mar-13**Customer**

Name: Purdue University
 Address: 550 Stadium Mall Drive
 Civil Room G151
 West Lafayette IN 47907
 sarahh@purdue.edu
 P.O./Contract No.:
 Contact: Kevin Brower

Machine

Manufacturer: BALDWIN
 Serial Number: 120BTEC502040
 System ID: 120BTEC502040
 Range Type: Single

Transducer

Manufacturer: EPSILON
 Transducer ID: 3543-0800-200T-ST/E89895
 Extensometer Type: Type 1
 Travel (Tension): 2 in
 Gauge Length: 8 in
 Mode: Static (Tension)

Classification

The following indicators of the extensometer system were verified and classed:

Indicator Type	Description	Indicator Units	Range Full Scale (%)	System Class
1. Digital Readout		strain	100	B-1

Certification Statement

All indicators listed above were verified on-site at customer location by Instron in accordance with ASTM E83.

The verification and equipment used conform to a controlled Quality Assurance program which meets the specifications outlined in ANSI/NCSL Z540-1, ISO 10012, ISO 9001:2008 and ISO/IEC 17025:2005.

The testing machine was verified in the 'as found' condition.

Instron Calpro Version 3.23

The results indicated on this certificate and the following report relate only to the items verified. If there are methods or data included that are not covered by the NVLAP accreditation it will be identified in the comments. Any limitations of use as a result of this verification will be indicated in the comments. This report must not be used to claim product endorsement by NVLAP or the United States government. This report shall not be reproduced, except in full, without the approval of the issuing laboratory.

CERTIFICATE OF CALIBRATION

NVLAP ACCREDITED CALIBRATION LABORATORY No. 200301-0

CERTIFICATE NUMBER:

516041212091759

Page 2 of 3 pages

Summary of Results

Indicator 1. - Digital Readout (strain)

Range	Full Scale (%)	Tested Range (in)	Mode	System Class*	Resolution (strain)	Resolution Class	ASTM E83 Lower Limit (in)
	100	0.2 to 2	Tension	B-1	0.000001	A	0.0008

* System Class for a range is the worst of the following classes: gauge length class, resolution class, individual point error class, repeatability class and is also based on the measurement capability of the laboratory.

Gauge Length Measurement and Classification

Nominal Gauge Length (in)	Actual Gauge Length (in)	Measurement Type	Error in Gauge Length (%)	ASTM E83 Gauge Length Class	Uncertainty of Measurement* (in)
8	7.9897	Direct	-0.13	B-1	0.0062

* The reported expanded uncertainty is based on a standard uncertainty multiplied by a coverage factor $k = 2$, providing a level of confidence of approximately 95%.

Data Summary and Classification

Indicator 1. - Digital Readout (strain)

% of Range	Run 1 Error		Run 2 Error		Repeat Error (strain)	Worst Class	Uncertainty of Measurement* (strain)
	Fixed (strain)	Relative (% of strain)	Fixed (strain)	Relative (% of strain)			
100% Range (Full Scale: 2 in)							
10	0.00000	0.012	-0.00001	-0.037	0.00001	A	0.000025
20	-0.00003	-0.054	0.00000	-0.004	0.00003	A	0.000042
40	0.00003	0.028	0.00003	0.034	0.00000	A	0.000079
70	0.00001	0.005	0.00005	0.028	0.00004	A	0.000137
100	-0.00016	-0.064	-0.00019	-0.074	0.00003	A	0.000195

* The reported expanded uncertainty is based on a standard uncertainty multiplied by a coverage factor $k = 2$, providing a level of confidence of approximately 95%.

Data

Indicator 1. - Digital Readout (strain)

% of Range	Run 1		Run 2	
	Indicated (strain)	Applied (in)	Indicated (strain)	Applied (in)
100% Range (Full Scale: 2 in)				
Run Temperature: 73.0 °F				
0	0.000001	0.000000	0.000006	0.000000
10	0.025004	0.200000	0.024998	0.200010
20	0.049975	0.400010	0.050004	0.400000
Run Temperature: 73.3 °F				

CERTIFICATE OF CALIBRATION

NVLAP ACCREDITED CALIBRATION LABORATORY No. 200301-0

CERTIFICATE NUMBER:

516041212091759

Page 3 of 3 pages

Data

Indicator 1. - Digital Readout (strain)

% of Range	Run 1		Run 2	
	Indicated (strain)	Applied (in)	Indicated (strain)	Applied (in)
100% Range (Full Scale: 2 in)				
	Run Temperature: 73.0 °F		Run Temperature: 73.3 °F	
40	0.100030	0.800010	0.100040	0.800000
70	0.175010	1.400000	0.175060	1.400040
100	0.249840	2.000000	0.249820	2.000000

Verification Equipment and Usage

Verification Equipment:

Make/Model	Serial Number	Description	Calibration Agency	Measurement Range	Cal Date	Cal Due
Extech 445580	984437	temp. indicator	Tektronix	NA	28-Dec-11	28-Dec-13
Boeckeler Micrometer 1398	20641 (ASTM)	disp. indicator	A.A. Jansson	2.00 in	07-Oct-11	07-Oct-12
* Fowler Economy Electronic	SH9J2879982	disp. indicator	AA Jansson	NA	20-Apr-10	20-Apr-12

* Equipment used for gauge length measurements.

Verification Equipment Usage:

Measurement Type	Serial Number	Range (% Full Scale)	Percent(s) of Range
Displacement	20641 (ASTM)	100	0/10/20/40/70/100

Instron standards are traceable to NIST and/or other National standards.

Comments

none

Verified by: James Warner
Field Service Engineer

NOTE: Clause 9 of ASTM E-83 states; It is recommended that extensometer systems be verified annually or more frequently if required. In no case shall the time interval between verifications exceed 18 months (unless an extensometer is being used in a long-time test running beyond the 18 month period). An extensometer system shall not be used after an adjustment or repair that could affect its accuracy without first verifying its accuracy utilizing the procedure described in this practice.

CALIBRATION CERTIFICATE

Address
86 Seabro Avenue
Amityville, NY 11701

Website
www.kesslerusa.com

KESSLER

KESSLER THERMOMETER CORPORATION

Telephone
631-841-5500
Facsimile
631-841-5553
E-mail
KesslerUSA@aol.com

CALIBRATION REPORT FOR THERMOMETER

THIS REPORT OF CALIBRATION SHALL DOCUMENT THAT THE INSTRUMENT DESCRIBED HEREIN WAS EXAMINED AND TESTED IN KESSLER'S CALIBRATION LABORATORY AGAINST NIST TRACEABLE REFERENCE STANDARDS, IN ACCORDANCE TO KESSLER'S PROCEDURE T-2008, WHICH IS BASED ON ASTM E-77-98 (2003) AND NIST PUBLICATION 250-23. THIS CALIBRATION MEETS THE REQUIREMENTS OF ISO/IEC 17025, ANSI/NCLC Z2540-1-1994 AND THE ISO 9000 AND QS 9000 SERIES OF QUALITY STANDARDS.

CUSTOMER INFORMATION: GILSON COMPANY, INC.

Purchase Order Number: PO00096475

Date Calibrated: September 20, 2011

Next Recommended Due Date: October 20, 2012

INSTRUMENT DESCRIPTION:

Serial No.: 689373 Marked: KESSLER USA Catalog No.: 6340-FC

Scale Range: 30/124°F Divisions: 0.2°F Immersion: 3"

RESULTS OF PHYSICAL EXAMINATION:

This instrument was examined under a polarized lens and strains in the glass, if any, were judged to be minimal and of no detriment to the function of the instrument. The capillary was examined under magnification and no irregularities or foreign material was discovered. It was determined that this instrument was suitable for calibration.

RESULTS OF CALIBRATION:

TEST TEMP	READING	CORRECTION	UNCERTAINTY
32.00	32.04	-0.04	+/-0.06
60.00	60.00	0.00	+/-0.06
80.00	80.20	-0.20	+/-0.06
100.00	100.20	-0.20	+/-0.06
120.00	120.20	-0.20	+/-0.06

- The above readings were made under magnification and resolved to one tenth of one scale division.
- The indications of this instrument cannot be adjusted or modified by ordinary means: accordingly, the readings given in the table above should be considered, in effect to be both "As Found" and "As Left" readings
- Laboratory Environment Conditions: Temperature: 25°C ± 5°C / Relative Humidity: Between 40% and 60%
- All temperatures given in this report are based on the International Scale of 1990 (ITS-90)

TRACEABILITY INFORMATION:

NIST Primary Standard: Rosemount Model 162CE Serial No. 5058
Transfer Standard: Hart Scientific 1502A Serial No. A14422 / 547027

Calibration Performed By: Barbara Plaza

Approved By: 

John Lewis

Calibration Report Prepared By: RP

Report No.: 092011-03



CALIBRATION REPORT

PI TAPE®

Report Number:	02221223040412
Date Issued:	Apr-04-12
Pi Tape Corporation Serial Number:	02221223
Tape Size:	2" - 12" O.D.

About this Calibration

Temperature	68 Degrees F \pm 2 Degrees	
Relative Humidity	45% \pm 15%	
Tension	Five Pounds	
Tape Tolerance	Within .001"	Within Mfg Tolerance of .001"
Uncertainty of Measurement	\pm .00025 Inches	

Calibration Performed by: Jerry Mathis

Actual Findings and Procedure Numbers

Tape Reads	4.9000	Over 4.9000"	Procedure 1
------------	--------	--------------	-------------

Remarks: New Gage

Calibration Equipment Used

Gage	Serial Number	Test Date	Due Date	NIST Traceable Report Number
4.9"	102098	May-12-11	May-12-12	86903-1

This tape has been checked at one or more points over a calibrated measuring standard. Calibration performed in accordance with ANSI/NCSS Z540-1-1994, ISO/IEC 17025 and the former MIL-STD 45662A.

All standards are traceable to the National Institute of Standards and Technology

Jerry Mathis, Quality Assurance Manager

This calibration report shall not be reproduced, except in full, without the written approval of the issuing laboratory.
Results listed relate only to the item being calibrated.

Pi Tape Corporation

344 N. Vinewood St. Escondido, CA 92029 USA
Phone (760) 746-9830 Fax (760) 746-9196
www.pitape.com



TRIMOS

CERTIFICAT D'ETALONNAGE
KALIBRIER-ZERTIFIKAT
CALIBRATION CERTIFICATE

N° 26594

Date

Datum

Date

13.10.2009

Objet Instrument vertical
Gegenstand Vertikal- Messgerät
Object Vertical instrument

Type
Typ V1004+
Model

Numéro de série
Serien-Nummer 10473 / A
Serial number

Date d'émission du certificat
Ausgabedatum des Zertifikates 13.10.2009
Certificate issue date

Déclaration de conformité

L'instrument de mesure
 auquel se réfère ce certificat
 a été réalisé conformément
 aux données techniques de
 TRIMOS contenues dans
 les documents de vente
 (prospectus, manuels
 d'utilisation).

Konformitätserklärung

Das Messgerät, auf
 welches sich dieses
 Zertifikat bezieht, wurde
 entsprechend den von
 TRIMOS in den Verkaufs-
 unterlagen (Prospekte,
 Gebrauchsanleitung)
 angegebenen technischen
 Daten hergestellt.

Conformity declaration

The measuring instrument
 to which this certificate
 refers to has been
 manufactured in
 accordance with the given
 TRIMOS specifications
 stated in sale documents
 (leaflets, instructions for
 use).

Responsable département qualité:
Leiter der Qualitätsabteilung:
Manager of quality department:

Gilbert Villard

Contrôleur:
Prüfer:
Inspector:

Philippe Desponds

La publication ou la reproduction de ce document n'est autorisée que dans sa forme intégrale.
 Der Inhalt dieses Dokumentes darf nur in vollständiger Form veröffentlicht oder weitergegeben werden.
 This document may not be published or forwarded other than in its entire form.

Page
Seite
Page

1 / 8

**CERTIFICAT D'ETALONNAGE****KALIBRIER-ZERTIFIKAT****CALIBRATION CERTIFICATE****N° 26594****Date****Datum****13.10.2009****Date****Caractéristique de l'objet mesuré****Merkmale des Gegenstandes der Kalibrierung****Features of the calibrated object**

Nombre d'axes de mesures

Anzahl der Messachsen

Number of measuring axis

1

Etendue de mesure

Messbereich

Measuring range

0 - 990 mm

0 - 38.976 in

Coefficient de dilatation linéaire

Linearer Ausdehnungskoeffizient

Linear expansion coefficient

11.5 µm/m

Etalonnage**Kalibrierung****Calibration**

Accessoire(s) utilisé(s)

Verwendete Zubehöre

Used accessories

V-1

Pas de mesure

Messstufen

Measuring steps

20 mm

(0.787 in)

Nombre de série de mesures

Anzahl von Messreihen

Number of measurement series

3

Principe de mesure

Messprinzip

Principle of measurement

En montant

Antastung aufwärts

Upwards direction

Condition de référence**Referenzbedingungen****Reference conditions**

Températures / Temperatur / Temperature

20°C +/- 0.5°C

Humidité relative / Relative Luftfeuchtigkeit / Relativ humidity

50% +/- 5%

Pression d'air / Luftdruck / Air pressure

722 mm Hg

La publication ou la reproduction de ce document n'est autorisée que dans sa forme intégrale.

Der Inhalt dieses Dokumentes darf nur in vollständiger Form veröffentlicht oder weitergegeben werden.

This document may not be published or forwarded other than in its entire form.

Page

Seite

Page

2 / 8



TRIMOS

CERTIFICAT D'ETALONNAGE
KALIBRIER-ZERTIFIKAT
CALIBRATION CERTIFICATE

N° 26594

Date

Datum

Date

13.10.2009

Etaon de référence et traçabilité
Bezugsnormal und Rückverfolgbarkeit
Reference standard and tracability

Les résultats de mesure contenus dans ce certificat d'étalonnage se réfèrent, par une traçabilité documentée, aux étalons reconnus sur le plan national et dont la conformité avec le système international d'unité (SI) est démontrée. L'étalon de référence est composé des éléments suivants :

Die in diesem Kalibrierzertifikat erhaltenen Ergebnisse von Messungen sind über Bezugsnormale bsw. Einrichtungen auf national Normale rückverfolgbar. Deren Übereinstimmung ist durch das Internationale Einheitensystem (SI) nachgewiesen. Das Bezugsnormal besteht aus folgenden Elementen :

All measurement results contained in this calibration certificate maintain a link of tracability recognized by national standards. Their accordance with the international unity system (SI) is proved. The reference standard is composed of the following components:

Etaon de référence Bezugsnormal Reference standard	N° de série Serien-Nr. Serial no.	N° du certificat Zertifikat-Nr. Certificate no.	Etaonné par Kalibriert durch Calibrated by
---	--	--	---

Check-Master	800002	81228	Fabricant
Equerre	215-904	E310Z106	Kunz SCS
Marbre 2000x1800	1644	R402B028	Kunz SCS

* Métrologie et accréditation suisse

La publication ou la reproduction de ce document n'est autorisée que dans sa forme intégrale.

Der Inhalt dieses Dokumentes darf nur in vollständiger Form veröffentlicht oder weitergegeben werden.

This document may not be published or forwarded other than in its entire form.

Page

Seite

Page

3 / 8



CERTIFICAT D'ETALONNAGE
KALIBRIER-ZERTIFIKAT
CALIBRATION CERTIFICATE

N° 26594


Date

Datum

13.10.2009

Date

Justesse
 Richtigkeit
 Freedom from bias



Valeur réelle Wahrer Wert True value mm	Série 1 Serie 1 Series 1 mm	Série 2 Serie 2 Series 2 mm	Série 3 Serie 3 Series 3 mm	Moyenne Mittenswert Average mm	Ecart moyen Mittlenabweichung Average deviation µm
0.0000	0.000	0.000	0.000	0.000	0.0
9.9999	10.000	10.000	10.000	10.000	0.1
30.0003	30.000	30.000	30.000	30.000	-0.3
50.0004	50.000	49.999	49.999	49.999	-1.1
70.0007	70.000	70.000	70.000	70.000	-0.7
90.0007	90.001	90.001	90.000	90.001	0.0
110.001	110.001	110.001	110.001	110.001	0.0
130.0009	130.001	130.001	130.001	130.001	0.1
150.0009	150.000	150.000	150.000	150.000	-0.9
170.0009	170.000	170.000	170.000	170.000	-0.9
190.0009	189.999	189.999	189.999	189.999	-1.9

La publication ou la reproduction de ce document n'est autorisée que dans sa forme intégrale.

Der Inhalt dieses Dokumentes darf nur in vollständiger Form veröffentlicht oder weitergegeben werden.

This document may not be published or forwarded other than in its entire form.

Page

Seite

Page

4 / 8



CERTIFICAT D'ETALONNAGE
KALIBRIER-ZERTIFIKAT
CALIBRATION CERTIFICATE

N° 26594

Date

Datum

13.10.2009

Date

Valeur vraie Wahrer Wert True value mm	Série 1 Serie 1 Series 1 mm	Série 2 Serie 2 Series 2 mm	Série 3 Serie 3 Series 3 mm	Moyenne Mittenswert Average mm	Ecart moyen Mittenabweichung Average deviation µm
210.0009	209.999	209.999	209.999	209.999	-1.90
230.001	230.000	230.000	230.000	230.000	-1.00
250.001	249.999	249.999	249.999	249.999	-2.00
270.001	269.998	269.998	269.998	269.998	-3.00
290.0009	289.998	289.998	289.998	289.998	-2.90
310.0009	309.999	309.999	309.998	309.999	-2.23
330.0007	329.999	329.998	329.998	329.998	-2.37
350.0006	349.998	349.998	349.998	349.998	-2.60
370.0006	369.998	369.998	369.998	369.998	-2.60
390.0006	389.999	389.999	389.998	389.999	-1.93
410.0006	409.998	409.998	409.998	409.998	-2.60
430.0006	429.998	429.998	429.998	429.998	-2.60
450.0004	449.998	449.998	449.998	449.998	-2.40
470.0006	469.998	469.998	469.998	469.998	-2.60
490.0003	489.998	489.998	489.998	489.998	-2.30
510.0004	509.998	509.998	509.998	509.998	-2.40
530.0002	529.997	529.997	529.998	529.997	-2.87
550.0002	549.998	549.998	549.998	549.998	-2.20
570.0001	569.997	569.997	569.997	569.997	-3.10
590.0001	589.998	589.998	589.998	589.998	-2.10
610	609.997	609.997	609.997	609.997	-3.00
630	629.998	629.998	629.998	629.998	-2.00
650	649.997	649.997	649.997	649.997	-3.00
670.0001	669.998	669.998	669.998	669.998	-2.10
689.9999	689.997	689.997	689.997	689.997	-2.90
709.9999	709.998	709.998	709.998	709.998	-1.90
729.9997	729.997	729.997	729.997	729.997	-2.70
749.9997	749.998	749.998	749.998	749.998	-1.70
769.9998	769.997	769.997	769.997	769.997	-2.80
789.9998	789.997	789.997	789.997	789.997	-2.80
809.9997	809.997	809.997	809.997	809.997	-2.70
829.9998	829.997	829.997	829.997	829.997	-2.80
849.9997	849.997	849.997	849.997	849.997	-2.70
869.9996	869.998	869.998	869.998	869.998	-1.60
889.9996	889.997	889.997	889.997	889.997	-2.60
909.9998	909.997	909.997	909.997	909.997	-2.80
929.9997	929.997	929.997	929.997	929.997	-2.70
949.9996	949.997	949.997	949.996	949.997	-2.93
969.9995	969.997	969.997	969.997	969.997	-2.50
989.9996	989.997	989.997	989.996	989.997	-2.93

La publication ou la reproduction de ce document n'est autorisée que dans sa forme intégrale.

Der Inhalt dieses Dokumentes darf nur in vollständiger Form veröffentlicht oder weitergegeben werden.

This document may not be published or forwarded other than in its entire form.

Page

Seite

5 / 8

Page

TRIMOS SA

++41 21 633 01 01

Av. de Longemalle 5

++41 21 633 01 02

CH-1020 Renens

office@trimos.ch

Switzerland

<http://www.trimos.ch>



TRIMOS

CERTIFICAT D'ETALONNAGE
KALIBRIER-ZERTIFIKAT
CALIBRATION CERTIFICATE

N° 26594

Date

Datum

13.10.2009

Date

Résultats de mesure
Messergebnisse
Measurement results

Erreur maximale autorisée

Max. Fehlergrenze

Maximum permissible error

5.8 µm

Erreur maximale mesurée

Grösste gemessene Abweichung

Maximum error measured

3.2 µm

Fidélité

Wiederholpräzision

Repeatability

+/- 2s < 2 µm

Incertitude de mesure

Messunsicherheit

Uncertainty of measurement

L'incertitude de mesure "U" indiquée ci-après pour la détermination des erreurs de mesures englobe :
 l'objet étalonné, l'étalon de référence, l'étendue de mesure et les conditions de référence.

Die nachstehend angegebene Messunsicherheit "U" für die Ermittlung der Messabweichungen umfasst
 folgende Komponente: das kalibrierte Objekt, das Bezugsnormal, den Messbereich und
 die Referenzbedingungen.

The uncertainty of measurement "U" for the determination of the errors of measurement given hereafter
 includes the calibrated object, the reference standard, the measuring range and the reference conditions.

le niveau de confiance est de 95%

Das Vertrauensniveau beträgt 95%

Confidence probability is 95%

K = 2

Incertitude de mesure

Messunsicherheit

Uncertainty of measurement

U 95 = 2.5µm + (L(mm) / 300)

La publication ou la reproduction de ce document n'est autorisée que dans sa forme intégrale.

Der Inhalt dieses Dokumentes darf nur in vollständiger Form veröffentlicht oder weitergegeben werden.

This document may not be published or forwarded other than in its entire form.

Page

Seite

Page

6 / 8

TRIMOS SA

++41 21 633 01 01

Av. de Longemalle 5

++41 21 633 01 02

CH-1020 Renens

office@trimos.ch

Switzerland


http://www.trimos.ch



CERTIFICAT D'ETALONNAGE
KALIBRIER-ZERTIFIKAT N° 26594
CALIBRATION CERTIFICATE

Date
Datum 13.10.2009
Date

Côntrole de la perpendicularité (direction de mesure)
 Kontrolle der Rechtwinkligkeit (Messrichtung)
 Checking of the squareness (measuring direction)



Hauteur
 Höhe
 Height
 mm

Ecart
 Abweichung
 Deviation
 µm

0	0.0
50	-1.0
100	-2.0
150	-2.0
200	-2.0
250	-2.0
300	-3.0
350	-3.0
400	-2.0
450	-2.0
500	-4.0

La publication ou la reproduction de ce document n'est autorisée que dans sa forme intégrale.

Page

Der Inhalt dieses Dokumentes darf nur in vollständiger Form veröffentlicht oder weitergegeben werden.

Seite

7 / 8

This document may not be published or forwarded other than in its entire form.

Page



TRIMOS

CERTIFICAT D'ETALONNAGE
KALIBRIER-ZERTIFIKAT
CALIBRATION CERTIFICATE

N° 26594

Date

Datum

13.10.2009

Date

Hauteur Höhe Height mm	Ecart Abweichung Deviation μm
550	-4.0
600	-4.0
650	-6.0
700	-6.0
750	-6.0
800	-6.0
850	-8.0
900	-8.0
950	-8.0
1000	-8.0

Resultats du contrôle de la perpendicularité (dans la direction de mesure) :

Ergebnisse der Rechtwinkligkeitsprüfung (in Messrichtung) :

Results of squareness checking (in measuring direction) :

Erreur maximale autorisée

Max. angegebene Fehlergrenze

Maximum permissible error

12.0 μm

Erreur de la perpendicularité mesurée

Gemessene Rechtwinkligkeitsabweichung

Squareness error measured

8.0 μm

La publication ou la reproduction de ce document n'est autorisée que dans sa forme intégrale.

Der Inhalt dieses Dokumentes darf nur in vollständiger Form veröffentlicht oder weitergegeben werden.

This document may not be published or forwarded other than in its entire form.

Page

Seite

Page

8 / 8



Calibration Certificate

201 Wolf Drive • P.O. Box 87 • Thorofare, NJ 08086-0087 • Phone: 856-686-1600 • Fax: 856-686-1601 • www.troemner.com • e-mail: troemner@troemner.com

Page 1 of 7 Pages
Weight


Certificate Number 663364-1
Date of Calibration 30-APR-2012

SECTION 1: NAME AND ADDRESS OF CUSTOMER

End user
Purdue University
1040 S. River Road
Bowen Laboratory
West Lafayette IN 47907

Client
Precision Weighing Balances
30 South Cross Road
Bradford MA 01835-8232

SECTION 2: APPROVED SIGNATORY


Joseph Moran, Metrology Manager

SECTION 3: PERSON PERFORMING WORK

Daniel Foglio

SECTION 4: CERTIFICATE INFORMATION

Description of Masses: Grip Handle

Accuracy Class	: NIST 105-1 Class F	Date Received	: 30-APR-2012
Order Number	: 100001369	Date of Calibration	: 30-APR-2012
Construction	: Two Piece	Date of Issue	: 30-APR-2012
Material	: Cast Iron	Weight Range	: 100 lb

SECTION 5: ENVIRONMENTAL CONDITIONS DURING TEST

Temperature: 21.84°C Pressure: 769.06 mm Hg Relative Humidity: 48%

SECTION 6: PERTINENT INFORMATION

The Weights listed on this calibration report have been compared to reference mass standards that are directly traceable to the National Institute of Standards and Technology under Test No. 822-275872-11.

Reference standards and balances used to perform the calibration are listed in Section 10.

The weights calibrated for this report have been calibrated in accordance with Troemner's calibration process. The calibration performed meets Level III criteria as described in the NIST/NVLAP Technical Guide 150-2.

This calibration also meets specifications as outlined in ISO 9001, ISO/IEC 17025, ANSI/NCSL Z540-1-1994, NRC Document 10CFR50 Appendix B, and applicable documents.



Calibration Certificate

201 Wolf Drive • P.O. Box 87 • Thorofare, NJ 08086-0087 • Phone: 856-686-1600 • Fax: 856-686-1601 • www.troemner.com • e-mail: troemner@troemner.com

Page 2 of 7 Pages
Weight

Certificate Number 663364-1
 Date of Calibration 30-APR-2012

NAME AND ADDRESS OF CUSTOMER


End user
 Purdue University
 1040 S. River Road
 Bowen Laboratory
 West Lafayette IN 47907

Client
 Precision Weighing Balances
 30 South Cross Road
 Bradford MA 01835-8232

SECTION 7: TRUE MASS (MASS IN VACUUM) CALIBRATION DATA

Nominal Mass Value	Serial Number	True Mass	Density ¹ of Weight	Uncertainty (+ or -)
100 lb		45362.709 g	7.2000 g/cm ³	450 mg

¹ Density is assumed unless otherwise stated



Calibration Certificate

201 Wolf Drive • P.O. Box 87 • Thorofare, NJ 08086-0087 • Phone: 856-686-1600 • Fax: 856-686-1601 • www.troemner.com • e-mail: troemner@troemner.com

Page 3 of 7 Pages
Weight

Certificate Number 663364-1
Date of Calibration 30-APR-2012


NAME AND ADDRESS OF CUSTOMER

End user
Purdue University
1040 S. River Road
Bowen Laboratory
West Lafayette IN 47907

Client
Precision Weighing Balances
30 South Cross Road
Bradford MA 01835-8232

SECTION 8: MASS IN AIR CALIBRATION VALUE VS. REFERENCE DENSITY 8000 kg m^{-3}

Nominal Mass Value	Serial Number	Conventional Mass Value	Uncertainty (+ or -)	Tolerance (+ or -)
100 lb		45361.953 g	450 mg	4.5000 g



Calibration Certificate

201 Wolf Drive • P.O. Box 87 • Thorofare, NJ 08086-0087 • Phone: 856-686-1600 • Fax: 856-686-1601 • www.troemner.com • e-mail: troemner@troemner.com

Page 4 of 7 Pages
Weight

Certificate Number 663364-1
 Date of Calibration 30-APR-2012

NAME AND ADDRESS OF CUSTOMER


End user
 Purdue University
 1040 S. River Road
 Bowen Laboratory
 West Lafayette IN 47907

Client
 Precision Weighing Balances
 30 South Cross Road
 Bradford MA 01835-8232

SECTION 9: MASS IN AIR CALIBRATION DATA VS. REFERENCE DENSITY 8000 kg m⁻³

Nominal Mass Value	Serial Number	Conventional Mass Correction	Uncertainty (+ or -)	Tolerance (+ or -)
100 lb		2716 mg	450 mg	4.5000 g





Calibration Certificate

201 Wolf Drive • P.O. Box 87 • Thorofare, NJ 08086-0087 • Phone: 856-686-1600 • Fax: 856-686-1601 • www.troemner.com • e-mail: troemner@troemner.com

Page 5 of 7 Pages
Weight

Certificate Number 663364-1
 Date of Calibration 30-APR-2012

NAME AND ADDRESS OF CUSTOMER

End user

Purdue University
 1040 S. River Road
 Bowen Laboratory
 West Lafayette IN 47907

Client

Precision Weighing Balances
 30 South Cross Road
 Bradford MA 01835-8232

SECTION 10: CALIBRATION PROCEDURE DATA

Nominal Mass Value	Serial Number	Standard Set No.	Cal Due	Balance Used	Cal Due	Procedure Used
100 lb		S1104	05/31/12	XP64003L-A01	11/30/12	Multi A-B





Calibration Certificate

201 Wolf Drive • P.O. Box 87 • Thorofare, NJ 08086-0087 • Phone: 856-686-1600 • Fax: 856-686-1601 • www.troemner.com • e-mail: troemner@troemner.com

Page 6 of 7 Pages

Weight

Certificate Number 663364-1

Date Of Calibration 30-APR-2012

NAME AND ADDRESS OF CUSTOMER

End user

Purdue University
1040 S. River Road
Bowen Laboratory
West Lafayette IN 47907

Client

Precision Weighing Balances
30 South Cross Road
Bradford MA 01835-8232

SECTION 11: GENERAL INFORMATION

This calibration was performed in Troemner's High Precision Level I Mass Metrology Laboratory at 201 Wolf Drive, Thorofare, New Jersey 08086 unless otherwise noted on page one. The internal procedures used are CAL-CLASSI and NIST HB145.

SECTION 12: DEFINITIONS AND TERMS

MASS IN A VACUUM - The mass of a weight as if it were measured in a vacuum. Also known as True Mass.

MASS IN AIR - The conventional value of the result of weighing in air, in accordance to International Recommendation OIML D 28. For a weight taken at 20° C, the conventional mass is the mass of a reference weight of a density of 8000 kg·m⁻³ which it balances in air of a density of 1.2 kg·m⁻³.

AS FOUND MASS IN A VACUUM - The measured value of the mass(es) as they were received by Troemner.

AS LEFT MASS IN A VACUUM - The measured value of the mass(es) after they were adjusted, repaired or replaced when necessary. The As Found Mass in a Vacuum will equal the As Left Mass in a Vacuum if the mass(es) did not require adjustment, repair or replacement.

NOMINAL MASS - The mass value as marked on the weight.

CORRECTION - The difference between the mass value of a weight and its nominal value. A positive correction indicates that the mass value is greater than the nominal value by the amount of the correction.

AS FOUND CONVENTIONAL MASS CORRECTION - The conventional correction of the result, as it was received by Troemner, of weighing in air in accordance to International Recommendation D 28. For a weight taken at 20° C, the conventional mass is the mass of a reference weight of density 8000 kg·m⁻³ which it balances in air density of 1.2 kg·m⁻³. If the customer requires cleaning prior to calibration, the after cleaning correction would be reported.

AS LEFT CONVENTIONAL MASS CORRECTION - The conventional correction of the result, after adjustment, repair, or replacement of weighing in air in accordance to International Recommendation D 28. For a weight taken at 20° C, the conventional mass is the mass of a reference weight of density 8000 kg·m⁻³ which it balances in air density of 1.2 kg·m⁻³. The As Found will equal the As Left Conventional Mass Correction if the mass(es) did not require adjustment, repair or replacement.

(continued on next page)



Calibration Certificate

201 Wolf Drive • P.O. Box 87 • Thorofare, NJ 08086-0087 • Phone: 856-686-1600 • Fax: 856-686-1601 • www.troemner.com • e-mail: troemner@troemner.com

Page 7 of 7 Pages

Weight

Certificate Number 663364-1

Date of Calibration 30-APR-2012

NAME AND ADDRESS OF CUSTOMER

End user

Purdue University
1040 S. River Road
Bowen Laboratory
West Lafayette IN 47907

Client

Precision Weighing Balances
30 South Cross Road
Bradford MA 01835-8232

SECTION 12: DEFINITIONS AND TERMS (continued)

UNCERTAINTY - The standard deviation associated with the result of the measurement that characterizes the dispersion of the values that could reasonably be attributed to the measurand. The uncertainty is calculated in accordance with NIST TechNote 1297 / UKAS M3003 using a coverage factor of $k = 2$ ($k = 2$ defines an interval having a level of confidence of approximately 95 percent). The uncertainty does not include possible effects of magnetism.



TOLERANCE - Defines the limits in which the correction value and the uncertainty must fall to meet the tolerance specification for the given Class.

AS FOUND CONVENTIONAL MASS VALUE - The measured value of the mass(es) as they were received by Troemner, of weighing in air in accordance to International Recommendation OIML D 28. For a weight taken at 20° C, the conventional mass is the mass of a reference weight of density 8000 kg·m⁻³ which it balances in air density of 1.2 kg·m⁻³. If the customer requires cleaning prior to calibration, the after cleaning value would be reported. F denotes Out of Tolerance Weight.

AS LEFT CONVENTIONAL MASS VALUE - The measured value of the mass(es) after they were adjusted, repaired or replaced when necessary, of weighing in air in accordance to International Recommendation OIML D 28. For a weight taken at 20° C, the Conventional Mass is the mass of a reference weight of density 8000 kg·m⁻³ which it balances in air density of 1.2 kg·m⁻³. The As Found will equal the As Left Conventional Mass Value if the mass(es) did not require adjustment, repair or replacement.

ASTM E617-97 - Weights meet the tolerance specification for ASTM E617-97. Weights 2kg - 1g screened for magnetism using a Gaussmeter.

Project: Tests to Determine the
Behavior of Spliced #11 BarsCalibration Documentation v.1
(Rev. 04/02/2012)Bowen Lab - Purdue University
Sheet 1 of 2

Calibration Instrument Name and S.N.:			Instron 1044172		
Data Acquisition System:			OptroTrack Pro Series 600		
Gain:			NA		
Excitation Voltage:			NA		
Channel:			NA		
Sensor:			OptroTrack Pro Series 600		
Sensor S.N.:			OptroTrack Pro Series 600		
Input [in.]	Output [in.]		Input [in.]	Output [in.]	
0	0		6.5	6.507	
0	0		6.5	6.507	
1	1.001		4	3.999	
1	1.001		4	3.999	
4	3.998		1.5	1.499	
4	3.997		1.5	1.498	
6.5	6.502				
6.5	6.502				
9	9.007				
9	9.007				
Operator		Signature		Date	Time
S.P.				6/13/12	10 AM
Checked by		Signature		Date	Time
BPR				6/13/12	10:15 AM
Checked by		Signature		Date	Time
Results		Sensitivity		Accuracy	
		1		0.007 in.	

Project: Tests to Determine the
Behavior of Spliced #11 Bars



Calibration Documentation v.1
(Rev. 04/02/2012)

Bowen Lab - Purdue University
Sheet 2 of 2

Notes: The accuracy of the INSTRON sensor is 0.003 in.

Calibration Instrument Name and S.N.:	INSTRON 1044172
Data Acquisition System:	NI-SCXI-1000 PCI 6289
Gain:	1
Excitation Voltage:	3.333
Channel:	M1-0
Sensor:	PA-20-NJC-DS-L3M
Sensor S.N.:	37100980



Measurand	Voltage	Measurand	Voltage	Measurand	Voltage
0.611	1.498				
0.611	0.038				
2.602	0.362				
4.553	0.675				
6.560	1.001				
8.630	1.332				

Operator	Signature	Date	Time
S.P.		5/9/12	
Checked by	Signature	Date	Time
BPR		5/9/12	
Checked by	Signature	Date	Time



Results	Sensitivity	Accuracy
	6.197 in/V	0.1%

Notes:



Project: Tests to Determine the
Behavior of Spliced #11 BarsCalibration Documentation v.1
(Rev. 04/02/2012)Bowen Lab - Purdue University
Sheet 1 of 1

Calibration Instrument Name and S.N.:		INSTRON 1044172			
Data Acquisition System:		NI-SCXI-1000 PCI 6289			
Gain:		1			
Excitation Voltage:		3.333			
Channel:		M1-1			
Sensor:		PA-20-NJC-DS-L3M			
Sensor S.N.:		37100981			
Measurand	Voltage	Measurand	Voltage	Measurand	Voltage
8.630	1.335				
6.618	1.011				
4.640	0.691				
2.655	0.369				
0.651	0.041				
Operator		Signature		Date	Time
S.P.				5/9/12	
Checked by		Signature		Date	Time
BPR				5/9/12	
Checked by		Signature		Date	Time
Results		Sensitivity		Accuracy	
		6.167 in/V		0.1%	
Notes:					



Project: Tests to Determine the
Behavior of Spliced #11 BarsCalibration Documentation v.1
(Rev. 04/02/2012)Bowen Lab - Purdue University
Sheet 1 of 1

Calibration Instrument Name and S.N.:		INSTRON 1044172			
Data Acquisition System:		NI SCXI-1000 PCI 6289			
Gain:		1			
Excitation Voltage:		3.333			
Channel:		M1-02			
Sensor:		PA-10-DS			
Sensor S.N.:		40010980			
Measurand	Voltage	Measurand	Voltage	Measurand	Voltage
8.594	2.578				
6.647	1.965				
4.600	1.323				
2.603	0.696				
0.642	0.071				
Operator		Signature		Date	Time
S.P.				5/9/12	
Checked by		Signature		Date	Time
BPR				5/9/12	
Checked by		Signature		Date	Time
Results		Sensitivity		Accuracy	
		3.175 in/v		0.2%	
Notes:					



Project: Tests to Determine the
Behavior of Spliced #11 BarsCalibration Documentation v.1
(Rev. 04/02/2012)Bowen Lab - Purdue University
Sheet 1 of 1

Calibration Instrument Name and S.N.:		INSTRON 1044172			
Data Acquisition System:		NI SCXI-1000 PCI 6289			
Gain:		1			
Excitation Voltage:		3.333			
Channel:		M1-03			
Sensor:		PA-10-DS			
Sensor S.N.:		40010985			
Measurand	Voltage	Measurand	Voltage	Measurand	Voltage
0.610	0.056				
2.578	0.682				
4.625	1.328				
6.566	1.939				
8.620	2.584				
Operator		Signature		Date	Time
S. P.				5/9/12	
Checked by		Signature		Date	Time
BPR				5/9/12	
Checked by		Signature		Date	Time
Results	Sensitivity		Accuracy		
	3.169 in/v		0.2%		
Notes:					



Project: Tests to Determine the
Behavior of Spliced #11 BarsCalibration Documentation v.1
(Rev. 04/02/2012)Bowen Lab - Purdue University
Sheet 1 of 1

Calibration Instrument Name and S.N.:		INSTRON 1044172			
Data Acquisition System:		NI SCXI-1000 PCI 6289			
Gain:		1			
Excitation Voltage:		3.333			
Channel:		M2-0			
Sensor:		PA-10-DS			
Sensor S.N.:		40010977			
Measurand	Voltage	Measurand	Voltage	Measurand	Voltage
8.620	2.590				
6.602	1.957				
4.607	1.331				
2.604	0.699				
0.611	0.065				
Operator		Signature		Date	Time
S.P.				5/9/12	
Checked by		Signature		Date	Time
BPR				5/9/12	
Checked by		Signature		Date	Time
Results		Sensitivity		Accuracy	
		3.173 in/V		0.2%	
Notes: M2-0					



Project: Tests to Determine the
Behavior of Spliced #11 BarsCalibration Documentation v.1
(Rev. 04/02/2012)Bowen Lab - Purdue University
Sheet 1 of 1

Calibration Instrument Name and S.N.:		Instron 1094172			
Data Acquisition System:		NI-SCXI-1000 PCI 6289			
Gain:		100			
Excitation Voltage:		10V			
Channel:		M2-02			
Sensor:		3175-50K			
Sensor S.N.:		443			
Measurand	Voltage	Measurand	Voltage	Measurand	Voltage
- 0	0				
6.1	-0.00240				
11.9	-0.00466				
15.3	-0.00600				
20.2	-0.00790				
25.3	-0.00990				
30.4	-0.01190				
Operator		Signature		Date	Time
S.P.				5/9/12	
Checked by		Signature		Date	Time
BPR				5/9/12	
Checked by		Signature		Date	Time
Results		Sensitivity		Accuracy	
		- 2556 K/V		0.1%	
Notes:					

Project: Tests to Determine the
Behavior of Spliced #11 BarsCalibration Documentation v.1
(Rev. 04/02/2012)Bowen Lab - Purdue University
Sheet 1 of 1

Calibration Instrument Name and S.N.:		Instron 1044172			
Data Acquisition System:		NI-SCXI-1000 PCI 6289			
Gain:		100			
Excitation Voltage:		10V			
Channel:		M2-3			
Sensor:		3175-50K			
Sensor S.N.:		442			
Measurand	Voltage	Measurand	Voltage	Measurand	Voltage
0	0				
5.5	-0.00215				
10.4	-0.00407				
15.5	-0.00605				
20.5	-0.00799				
25.5	-0.00996				
30.5	-0.01190				
0	+0.000010				
Operator		Signature		Date	Time
S.P.				5/9/12	
Checked by		Signature		Date	Time
BPR				5/9/12	
Checked by		Signature		Date	Time
Results		Sensitivity		Accuracy	
		-2563 K/V		0.1%	
Notes:					



Project: Tests to Determine the
Behavior of Spliced #11 BarsCalibration Documentation v.1
(Rev. 04/02/2012)Bowen Lab - Purdue University
Sheet 1 of 1

Calibration Instrument Name and S.N.:		INSTRON 1044172			
Data Acquisition System:		NI SCXI-1000 PCI 6289			
Gain:		1			
Excitation Voltage:		30			
Channel:		M3-0			
Sensor:		LUCAS DCEC-2000			
Sensor S.N.:		J7250			
Measurand	Voltage	Measurand	Voltage	Measurand	Voltage
1.835	-4.272				
1.500	-2.655				
1.000	-0.253				
0.500	2.133				
0.125	3.953				
Operator	Signature		Date	Time	
S.P.			5/9/12		
Checked by	Signature		Date	Time	
BPR			5/9/12		
Checked by	Signature		Date	Time	
Results	Sensitivity		Accuracy		
	- 0.208 in/v		0.1%		
Notes:					



Project: Tests to Determine the Behavior of Spliced #11 Bars

Calibration Documentation v.1
(Rev. 04/02/2012)



Bowen Lab - Purdue University
Sheet 1 of 1

Calibration Instrument Name and S.N.:		INSTRON 1044172			
Data Acquisition System:		NI SCXI-1000 PCI 6289			
Gain:		1			
Excitation Voltage:		30			
Channel:		M3-1			
Sensor:		LUCAS DCEC-2000			
Sensor S.N.:		J7251			
Measurand	Voltage	Measurand	Voltage	Measurand	Voltage
0.125	4.150				
0.507	2.318				
0.999	-0.020				
1.500	-2.414				
1.835	-4.025				
Operator		Signature		Date	Time
S.P.				5/9/12	
Checked by		Signature		Date	Time
BPR				5/9/12	
Checked by		Signature		Date	Time
Results		Sensitivity		Accuracy	
		-0.209 in/V		0.1%	
Notes:					



Project: Tests to Determine the
Behavior of Spliced #11 BarsCalibration Documentation v.1
(Rev. 04/02/2012)Bowen Lab - Purdue University
Sheet 1 of 1

Calibration Instrument Name and S.N.:		INSTRON PUID 1044172			
Data Acquisition System:		NI SCXI 1000 SN 1188607			
Gain:		1			
Excitation Voltage:		3.333V			
Channel:		M1-0			
Sensor:		PA-20			
Sensor S.N.:		37100980			
Measurand	Voltage	Measurand	Voltage	Measurand	Voltage
0.5"	0.307				
2.5"	0.627				
4.5"	0.952				
6.5"	1.271				
8.5"	1.594				
Operator		Signature		Date	Time
S.P.				6/13/12	3 PM
Checked by		Signature		Date	Time
BPR				6/13	3:10PM
Checked by		Signature		Date	Time
Results	Sensitivity		Accuracy		
	0.0483 V/V/in		0.1%		
Notes: Deviation from sensitivity computed before test*: 0.3% <u>OK</u> * 0.0484 V/V/in.					



Project: Tests to Determine the
Behavior of Spliced #11 BarsCalibration Documentation v.1
(Rev. 04/02/2012)Bowen Lab - Purdue University
Sheet 1 of 1

Calibration Instrument Name and S.N.:		INSTRON 1044172			
Data Acquisition System:		NI SCXI 1000 SN 1188607			
Gain:		1			
Excitation Voltage:		3.333V			
Channel:		M1-1			
Sensor:		PA-20			
Sensor S.N.:		37100981			
Measurand	Voltage	Measurand	Voltage	Measurand	Voltage
8.5"	1.612				
6.5	1.291				
4.5	0.968				
2.5	0.646				
0.5	0.320				
Operator		Signature		Date	Time
S.P.				6/13/12	3:20 P.
Checked by		Signature		Date	Time
BPR				6/13	3:30 PM
Checked by		Signature		Date	Time
Results		Sensitivity		Accuracy	
		0.0484		0.1%	
Notes: Deviation = 0.4%					

Project: Tests to Determine the
Behavior of Spliced #11 BarsCalibration Documentation v.1
(Rev. 04/02/2012)Bowen Lab - Purdue University
Sheet 1 of 1

Calibration Instrument Name and S.N.:		INSTRON 1044172			
Data Acquisition System:		NI SCXI 1000 1188607			
Gain:		1			
Excitation Voltage:		3.333V			
Channel:		M1-2			
Sensor:		PA-10			
Sensor S.N.:		40010980			
Measurand	Voltage	Measurand	Voltage	Measurand	Voltage
0.5"	0.584				
2.5	1.212				
4.5	1.839				
6.5	2.467				
8.0	2.942				
Operator		Signature		Date	Time
S.P.				6/13/12	3:30 P.
Checked by		Signature		Date	Time
BPR				6/13	3:40 PM
Checked by		Signature		Date	Time
Results		Sensitivity		Accuracy	
		0.0943 V/V/in		0.1%	
Notes: Deviation = 0.2%					



Project: Tests to Determine the
Behavior of Spliced #11 BarsCalibration Documentation v.1
(Rev. 04/02/2012)Bowen Lab - Purdue University
Sheet 1 of 1

Calibration Instrument Name and S.N.:		INSTRON 104172			
Data Acquisition System:		SCXI 1000 1188607			
Gain:		1			
Excitation Voltage:		3.333 V			
Channel:		M1-3			
Sensor:		PA-10			
Sensor S.N.:		40010985			
Measurand	Voltage	Measurand	Voltage	Measurand	Voltage
8 "	2.934				
6.5	2.462				
4.5	1.835				
2.5	1.207				
0.5	0.577				
Operator		Signature		Date	Time
S.P.				6/13/12	3:40 P.
Checked by		Signature		Date	Time
BPR				6/13	3:50 PM
Checked by		Signature		Date	Time
Results		Sensitivity		Accuracy	
		0.0943 v/v/in		0.03%	
Notes: Deviation: 0.4%					



Project: Tests to Determine the
Behavior of Spliced #11 BarsCalibration Documentation v.1
(Rev. 04/02/2012)Bowen Lab - Purdue University
Sheet 1 of 1

Calibration Instrument Name and S.N.:		INSTRON 1044172			
Data Acquisition System:		NI SCXI 1000 1188607			
Gain:		1			
Excitation Voltage:		3.333V			
Channel:		M2-0			
Sensor:		PA-10			
Sensor S.N.:		40010977			
Measurand	Voltage	Measurand	Voltage	Measurand	Voltage
0.5"	0.584				
2.5"	1.215				
4.5"	1.841				
6.5"	2.469				
8.0"	2.939				
Operator		Signature		Date	Time
S.P.		<i>A. Dujod</i>		6/13/12	3:55 P.
Checked by		Signature		Date	Time
BPR		<i>W. Hest</i>		6/13/12	4:00PM
Checked by		Signature		Date	Time
Results		Sensitivity		Accuracy	
		0.0942 v/v/in		0.1%	
Notes: Deviation = 0.4%					



Project: Tests to Determine the
Behavior of Spliced #11 BarsCalibration Documentation v.1
(Rev. 04/02/2012)Bowen Lab - Purdue University
Sheet 1 of 1

Calibration Instrument Name and S.N.:		INSTRON 1044172			
Data Acquisition System:		NI SCXI 1000 1188607			
Gain:		100			
Excitation Voltage:		10V			
Channel:		M2-2			
Sensor:		LEBOW 50K -443			
Sensor S.N.:		443			
Measurand	Voltage	Measurand	Voltage	Measurand	Voltage
-0.4+0.4=0	0				
5k+0.4	-0.00211				
10k+0.4	-0.00410				
14.6k+0.4	-0.00588				
19.7k+0.4	-0.00787				
24.7k+0.4	-0.00984				
29.7k+0.4	-0.01178				
Operator		Signature		Date	Time
S.P.				6/13/12	4:45 P
Checked by		Signature		Date	Time
BPR				6/13	4:50 PM
Checked by		Signature		Date	Time
Results		Sensitivity		Accuracy	
		-1.957 mV/V @ FSV		0.1%	
Notes: DEVIATION from prev. cal (5/4/12): 0.1%					



Project: Tests to Determine the
Behavior of Spliced #11 BarsCalibration Documentation v.1
(Rev. 04/02/2012)Bowen Lab - Purdue University
Sheet 1 of 1



Calibration Instrument Name and S.N.:		INSTRON 1044172			
Data Acquisition System:		NISCXI 1000 1188607			
Gain:		100			
Excitation Voltage:		10V			
Channel:		M2-3			
Sensor:		LEBOW 50K - 442			
Sensor S.N.:		442			
Measurand	Voltage	Measurand	Voltage	Measurand	Voltage
-0.4 + 0.4k	0.00001				
4.65 ^k + 0.4	-0.00196				
9.67 ^k + 0.4	-0.00392				
14.6 ^k + 0.4	-0.00584				
19.7 ^k + 0.4	-0.00785				
25.25k + 0.4	-0.01001				
29.6 ^k + 0.4	-0.01172				
Operator		Signature		Date	
S.P.				6/13/12	
Checked by		Signature		Date	
BPR				6/13	
Checked by		Signature		Date	
Results		Sensitivity		Accuracy	
		-1.955 mV/V @ 50k		0.1%	
Notes: Deviation : 0.2%					

Project: Tests to Determine the
Behavior of Spliced #11 BarsCalibration Documentation v.1
(Rev. 04/02/2012)Bowen Lab - Purdue University
Sheet 1 of 1


Calibration Instrument Name and S.N.:		INSTRON 1044172			
Data Acquisition System:		NI SCXI 1000 1188607			
Gain:		1			
Excitation Voltage:		30V			
Channel:		M3-0			
Sensor:		LUCAS DCDT $\pm 2''$			
Sensor S.N.:		J7250			
Measurand	Voltage	Measurand	Voltage	Measurand	Voltage
0.125"	4.288				
0.5"	2.477				
1.0"	0.106 ✓				
1.5"	-2.271 ✓				
2.0"	-4.663				
1.0	0.112				
0.5"	2.480				
0.125"	4.289				
Operator		Signature		Date	Time
S.P.				6/13/12	5:50 P
Checked by		Signature		Date	Time
BPR				6/13	6:00PM
Checked by		Signature		Date	Time
Results		Sensitivity		Accuracy	
		-4.769 V/in		0.2%	
Notes: Deviation from 5/4/12 cal. = 0.7%					

Project: Tests to Determine the
Behavior of Spliced #11 BarsCalibration Documentation v.1
(Rev. 04/02/2012)Bowen Lab - Purdue University
Sheet 1 of 1


Calibration Instrument Name and S.N.:		INSTRON 1044172			
Data Acquisition System:		NISCXI 1000 1188607			
Gain:		1			
Excitation Voltage:		30V			
Channel:		M3-1			
Sensor:		LUCAS DOT $\pm 2''$			
Sensor S.N.:		J 7251			
Measurand	Voltage	Measurand	Voltage	Measurand	Voltage
0.125"	4.293				
0.500"	2.496				
1.0"	0.140				
1.5"	-2.232				
2.0"	-4.606				
Operator		Signature		Date	Time
S.P.				6/13/12	6 PM
Checked by		Signature		Date	Time
BPR				6/13	6:10PM
Checked by		Signature		Date	Time
Results		Sensitivity		Accuracy	
		-4.742 V/in		0.2%	
Notes: Deviation = 0.7%.					



FIRST LOADING




GIRDER A1 – 41 kip




GIRDER A2 – 41 kip

FIRST LOADING




GIRDER A3 – 36 kip




GIRDER A4 – 40 kip

FIRST LOADING




GIRDER A5 – 40 kip



GIRDER A6 – 40 kip

RELOADING



GIRDER A1 – 42 kip


No reload

GIRDER A2

RELOADING


No reload

GIRDER A3




GIRDER A4 – 42 kip

RELOADING




GIRDER A5 – 42 kip




GIRDER A6 – 41 kip

FIRST LOADING




GIRDER B1 – 36 kip



GIRDER B2 – 36 kip

FIRST LOADING




GIRDER B3 – 36 kip



GIRDER B4 – 36 kip

FIRST LOADING



GIRDER B5 – 36 kip




GIRDER B6 – 1 kip

RELOADING


No reload

GIRDER B1 – kip



GIRDER B2 – Load = 36 kip.

RELOADING




GIRDER B3 – Load = 36 kip


No reload

GIRDER B4

RELOADING



GIRDER B5 – 24 kip.




GIRDER B6 – 36 kip.

Project: Tests to Determine the
Behavior of Spliced #11 Bars

Instrumentation Documentation v.1
(Rev. 04/01/2012)

Specimen: A-1
Sheet 1 of 1

Data Acquisition System:									
Channel #	Gain	Excitation V.	Sensor	S.N.	[$\mu\text{in}/\text{V}$] Sensitivity	[μin] Zero Offset	Location	Zeros [μV] Comments	
0	M1-0	1	3.333	PA-20	37100980	-6.197	-17.26	N. Overhang	2.785
1	M1-1	1	"	"	37100981	-6.167	-17.02	S. "	2.759
2	M1-2	1	"	PA-10	40010986	3.175	1.18	N. Splice End	0.372
3	M1-3	1	"	"	40010991	3.169	0.87	Midspan	0.274
4	M2-0	1	"	"	40010988	3.173	1.08	S. Splice End	0.339
5	M2-2	100	10	Lebow 50K	443	-2556	0.2 [K]	N. End	-0.000044
6	M2-3	100	10	"	442	-2563	0.2 [K]	S. "	-0.000033
7	M3-0	1	30	Lucas 2	J7250	0.208	0.005	N. Support	0.027
8	M3-1	1	30	"	J7251	0.209	0.000	S. "	0.000
Operator		Signature			Date		Time		
BPR		<i>[Signature]</i>			6/2/12		2:40 PM		
Checked by		Signature			Date		Time		
KAN		<i>[Signature]</i>			6-2-12		2:40 pm		
Checked by		Signature			Date		Time		
Notes:									



Specimen A-1 Behavior of Lap Splices of No. 11 Reinforcing Bars				
	Drawn by: BPR	Checked by: KAM		
	Date: 6/2/12			


Project: Tests to Determine the
Behavior of Spliced #11 Bars

Instrumentation Documentation v.1
(Rev. 04/01/2012)

Specimen: A-2
Sheet 1 of 1

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	(in/v) Sensitivity	(in) Zero Offset	Location	Zeros (v) Comments
0 M1-0	1	3.333	PA-20	37100980	-6.197	-17.04	N. Overhang	2.750
1 M1-1	1	"	"	37100981	-6.167	-17.31	S. "	2.807
2 M1-2	1	"	PA-10	40010986	3.175	1.26	N. Splice End	0.396
3 M1-3	1	"	"	40010991	3.169	0.82	Midspan	0.260
4 M2-0	1	"	"	40010988	3.173	0.99	S. Splice End	0.311
5 M2-2	100	10	Lebow 50K	443	-2556	0.3 [K]	N. End	-0.000060
6 M2-3	100	10	"	442	-2563	0.2 [K]	S. "	-0.000036
7 M3-0	1	30	Lucas 2	J7250	0.208	0.004	N. Support	0.013
8 M3-1	1	30	"	J7251	0.209	-0.004	S. "	-0.025
Operator		Signature			Date		Time	
BPR		<i>[Signature]</i>			5/31/12		5:10 PM	
Checked by		Signature			Date		Time	
KAM		<i>[Signature]</i>			5-31-12		5:30 pm	
Checked by		Signature			Date		Time	

Notes:






Specimen A-2			
Behavior of Lap Splices of No. 11 Reinforcing Bars	Drawn by: BPR	Checked by: DAM	
	Date: 5/31/12		

Project: Tests to Determine the
Behavior of Spliced #11 Bars

Instrumentation Documentation v.1
(Rev. 04/01/2012)

Specimen: A-3
Sheet 1 of 1

Data Acquisition System:		BPR 5/29/12						
Channel #	Gain	Excitation V.	Sensor	S.N.	[in/V] Sensitivity	[in] Zero Offset	Location	Zeros [V] Comments
0 M1-0	1	3.333	PA-20	37100980	-6.197	18 -17.43	N. Overhang	2.813
1 M1-1	1	"	"	37100981	-6.167	-17.13	S. "	2.777
2 M1-2	1	"	PA-10	40010986	3.175	1.19	N. Splice End	0.376
3 M1-3	1	"	"	40010991	3.169	0.90	Midspan	0.283
4 M2-0	1	"	"	40010988	3.173	1.15	S. Splice End	0.362
5 M2-2	100	10	Lebow 50K	443	-2556	0.2 [K]	N. End	-0.000034
6 M2-3	100	10	"	442	-2563	0.2 [K]	S. "	-0.000031
7 M3-0	1	30	Lucas 2	J7250	0.208	-0.003	N. Support	-0.016
8 M3-1	1	30	"	J7251	0.209	-0.001	S. "	-0.007
Operator		Signature			Date		Time	
BPR					5/29/12		9:20 PM	
Checked by		Signature			Date		Time	
J.N.H.					5.29.12		9:20	
Checked by		Signature			Date		Time	
Notes:								






Specimen	A-3						
Behavior of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	WAM			
	Date:	5/29/12					

Project: Tests to Determine the
Behavior of Spliced #11 Bars

Instrumentation Documentation v.1
(Rev. 04/01/2012)

Specimen: A-4
Sheet 1 of 1

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	($\mu\text{m}/\text{V}$) Sensitivity	[μm] Zero Offset	Location	Zeros [μV] Comments
0 M1-0	1	3.333	PA-20	37100980	-6.197	-17.08	N. Overhang	2.757
1 M1-1	1	"	"	37100981	-6.167	-17.45	S. "	2.830
2 M1-2	1	"	PA-10	40010986	3.175	1.22	N. Splice E.	0.383
3 M1-3	1	"	"	40010991	3.169	0.86	Midspan	0.271
4 M2-0	1	"	"	40010988	3.173	1.05	S. Splice E.	0.332
5 M2-2	100	10	Lebow 50K	443	-2556	0.007 ^{BPR 6/7} 0.3 [K]	N. End	-0.000056
6 M2-3	100	10	"	442	-2563	0.3 [K]	S. End	-0.000055
7 M3-0	1	30	Lucas 2	J7250	0.208	0.007	N. Support	0.035
8 M3-1	1	30	"	J7251	0.209	-0.007	S. "	-0.034
Operator		Signature			Date		Time	
BPR					6/7/12		10:30 PM	
Checked by		Signature			Date		Time	
KAM					6-7-12		10:30 pm	
Checked by		Signature			Date		Time	
Notes:								





Specimen <i>A-4</i>			
Behavior of Lap Splices of No. 11 Reinforcing Bars	Drawn by: <i>BPR</i>	Checked by: <i>KAM</i>	
	Date: <i>6/7/12</i>		

Project: Tests to Determine the Behavior of Spliced #11 Bars


Instrumentation Documentation v.1
(Rev. 04/01/2012)

Specimen: A-5
Sheet 1 of 1

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	(in/v) Sensitivity	[in] Zero Offset	Location	Zeros (v) Comments
0 M1-0	1	3.333	PA-20	37100980	-6.197	-17.40	N. Overhang	2.808
1 M1-1	1	"	"	37100981	-6.167	-16.96	S. "	2.750
2 M1-2	1	"	PA-10	40010986	3.175	1.10	N. Splice End	0.349
3 M1-3	1	"	"	40010991	3.169	0.72	Midspan	0.230
4 M2-0	1	"	"	40010988	3.173	0.98	S. Splice End	0.310
5 M2-2	100	10	Lebow 50K	443	-2556	0.2 [K]	N. End	-0.000038
6 M2-3	100	10	"	442	-2563	0.2 [K]	S. "	-0.000037
7 M3-0	1	30	Lucas 2	J7250	0.208	0.006	N. Support	0.027 ^{BPR} #616
8 M3-1	1	30	"	J7251	0.209	-0.005	S. "	-0.026 ^{BPR} #46

Operator	Signature	Date	Time
BPR		6/6/12	5:30 PM
Checked by	Signature	Date	Time
J.N.H.		6.6.12	5:45 P
Checked by	Signature	Date	Time

Notes:





Specimen	A-5						
Behavior of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPK	Checked by:	LAM			
	Date:	6/6/12					


Project: Tests to Determine the
Behavior of Spliced #11 Bars

Instrumentation Documentation v.1
(Rev. 04/01/2012)

Specimen: A-6
Sheet 1 of 1

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	(mV/V) Sensitivity	[mV] Zero Offset	Location	Zeros (V) Comments
0	M1-0	1	3.333	PA-20	37100980	-6.197	BPR 6/5 2.780 ^{-17.23}	N. Overhang 2.780
1	M1-1	1	"	"	37100981	-6.167	-17.01	S. " 2.758
2	M1-2	1	"	PA-10	40010986	3.175	1.10	N. Splice End 0.347
3	M1-3	1	"	"	40010991	3.169	0.84	Midspan 0.264
4	M2-0	1	"	"	40010988	3.173	1.00	S. Splice End 0.316
5	M2-2	100	10	Lebow 50K	443	-2556	BPR 6/5 0.006 ^{0.3} [K]	N. End -0.000057
6	M2-3	100	10	"	442	-2563	BPR 6/5 -0.007 ^{0.2} [K]	S. End -0.000036
7	M3-0	1	30	Lucas 2	J7250	0.208	0.006	N. Support 0.029
8	M3-1	1	30	"	J7251	0.209	-0.007	S. " -0.034
Operator		Signature			Date		Time	
BPR					6/4/12		11:00 AM	
Checked by		Signature			Date		Time	
KAM					6-4-12		11:00 am	
Checked by		Signature			Date		Time	

Notes:





Specimen <i>A-6</i>			
Behavior of Lap Splices of No. 11 Reinforcing Bars	Drawn by: <i>BPK</i>	Checked by: <i>KAM</i>	
	Date: <i>6/4/12</i>		


Project: Tests to Determine the
Behavior of Spliced #11 Bars

Instrumentation Documentation v.1
(Rev. 04/01/2012)

Specimen: B-1
Sheet 1 of 1

Data Acquisition System:									
Channel #	Gain	Excitation V.	Sensor	S.N.	(m.V) Sensitivity	(in.) Zero Offset	Location	Zeros (V.) Comments	
0	M1-0	1	3.333	PA-20	371 00980	-6.197 /	-18.68	N. Overhang	3.013
1	" 1	1	"	"	371 00981	-6.167	-17.01	S. "	2.745
2	" 2	1	"	PA-10	400 10980 ✓	3.175 /	0.74	N. Splice end	0.235
3	" 3	1	"	"	400 10985 ✓	3.169 /	0.54	Midspan	0.170
4	M2-0	1	"	"	400 10977 ✓	3.173 /	0.91	S. Splice end	0.287
5	M2-2	100	10	Lebow 50k	443	-2556	0.2	N. End	-0.000042
6	" -3	100	10	"	442	-2563	0.2	S. End	-0.000029
7	M3-0	1	30V	Lucas 2"	J7250	0.208 /	-0.008	N. Support	-0.041
8	M3-1	1	30V	" 2"	J7251	0.209 /	-0.006	S. "	-0.027
Operator		Signature			Date		Time		
S. P.					5/10/12		11 AM		
Checked by		Signature			Date		Time		
A.J.C.					5/16/12		11 am		
Checked by		Signature			Date		Time		



Notes:




Project: Tests to Determine the
Behavior of Spliced #11 Bars

Instrumentation Documentation v.1
(Rev. 04/01/2012)

Specimen: B-2
Sheet 1 of 1

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity	[in] Zero Offset	Location	Zeros (V) Comments
0 M1-0	1	3.333	PA-20	37100980	-6.197	-18.60	N. Overhang	3.002
1 M1-1	1	"	"	37100981	-6.167	-17.13	S. Overhang	2.778
2 M1-2	1	"	PA-10	40010986	3.175	+0.74	N. Splice End	0.234
3 M1-3	1	"	"	40010991	3.169	+0.56	Midspan	0.177
4 M2-0	1	"	"	40010988	3.173	+1.12	S. Splice End	0.352
5 M2-2	100	10V	Lebow 50K	443	-2556	0.2 [K]	N. End	-0.000041
6 M2-3	100	10V	"	442	-2563	0.2 [K]	S. End	-0.000036
7 M3-0	1	30V	Lucas 2	J7250	0.208	+0.010	N. Support	0.051
8 M3-1	1	30V	"	J7251	0.209	-0.005	S. Support	-0.024
Operator		Signature			Date		Time	
BPR					5/22/12		6:15PM	
Checked by		Signature			Date		Time	
J.N.H.					5.22.12		6:25 PM	
Checked by		Signature			Date		Time	

Notes:





Specimen	B-2					
Behavior of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	LAM		
	Date:	5/22/12				


Project: Tests to Determine the
Behavior of Spliced #11 Bars

Instrumentation Documentation v.1
(Rev. 04/01/2012)

Specimen: B-3
Sheet 1 of 1

Data Acquisition System:									
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity	[mV] Zero Offset	Location	Zeros (✓) Comments	
0 M1-0	1	3.333	PA-20	37100980	-6.197	-18.99	N. Overhang	3.064 ✓	
1 M1-1	1	"	"	37100981	-6.167	-16.99	S. " "	2.755 ✓	
2 M1-2	1	"	PA-10	40010986	3.175	0.97	N. Splice End	0.305 ✓	
3 M1-3	1	"	"	40010991	3.169	0.64	Midspan	0.203 ✓	
4 M2-0	1	"	"	40010988	3.173	1.07	S. Splice End	0.336 ✓	
5 M2-2	100	10	Lebow 50K	443	-2556	0.3 [K]	N. End	-0.000060 ✓	
6 M2-3	100	10	"	442	-2563	0.2 [K]	S. End	-0.000040 ✓	
7 M3-0	1	30	Lucas 2	J7250	0.208	0.014	N. Support	0.067 ✓	
8 M3-1	1	30	"	J7251	0.209	-0.006	S. " "	-0.028 ✓	
Operator		Signature			Date		Time		
BPR					5/19/12		5:25 PM		
Checked by		Signature			Date		Time		
SP					5/19/12		7:15 PM		
Checked by		Signature			Date		Time		

Notes:





Specimen	B-3		
Behavior of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by: LAM
	Date:	5/19/12	

Project: Tests to Determine the
Behavior of Spliced #11 Bars


Instrumentation Documentation v.1
(Rev. 04/01/2012)

Specimen: B-4

Sheet 1 of 1

Data Acquisition System:									
Channel #	Gain	Excitation V.	Sensor	S.N.	(mV/V) Sensitivity	in. Zero Offset	Location	Zero Offset V. Comments	
0	M1-0	1	3.333	PA-20	37100980	-6.197	-18.37	N. Overhang	2.965
1	M1-1	1	"	"	37100981	-6.167	-17.04	S. "	2.764
2	M1-2	1	"	PA-10	40010986	3.175	0.62	N. Splice End	0.195
3	M1-3	1	"	"	40010991	3.169	0.46	Midspan	0.146
4	M2-0	1	"	"	40010988	3.173	0.99	S. Splice End	0.312
5	M2-2	100	10V	LC443	443	-2556	0.2	N. End	-0.000042
6	M2-3	100	10V	LC442	442	-2563	0.2	S. End	-0.000040
7	M3-0	1	30V	LVDT	J7250	0.208	-0.005	N. Support	-0.026
8	M3-1	1	30V	LVDT	J7251	0.209	-0.003	S. "	-0.014
Operator		Signature			Date		Time		
S.P.					5/12/12		3:46 PM.		
Checked by		Signature			Date		Time		
BPR					5/12		4:00 PM		
Checked by		Signature			Date		Time		

Notes: All instruments & settings as in B-1




Project: Tests to Determine the
Behavior of Spliced #11 Bars

Instrumentation Documentation v.1
(Rev. 04/01/2012)

Specimen: B-5
Sheet 1 of 1

Data Acquisition System:									
Channel #	Gain	Excitation V.	Sensor	S.N.	(mV/V) Sensitivity	[mV] Zero Offset	Location	Zeros(V) Comments	
0	M1-0	1	3.333	PA-20	37100980	-6.197	-18.73	N. Overhang	3.022 ✓
1	M1-1	1	"	"	37100981	-6.167	-16.89	S. "	2.739 ✓
2	M1-2*	1	"	PA-10	40010986*	3.175	+0.72	N. Splice end	0.225 ✓
3	M1-3	1	"	"	40010991	3.169	+0.48	Midspan	0.153 ✓
4	M2-0	1	"	"	40010988	3.173	+0.97	S. Splice end	0.305
5	M2-2	100	10V	Lebow 50K	443	-2556	0.2 [K]	N. End	-0.000048
6	M2-3	100	10V	"	442	-2563	0.2 [K]	S. End	-0.000039
7	M3-0	1	30V	Lucas 2	J7250	0.208	-0.005	N. Support	-0.022
8	M3-1	1	30V	"	J7251	0.209	+0.011	S. "	0.054
Operator		Signature			Date		Time		
S. PUJOL									
Checked by		Signature			Date		Time		
BPR		<i>Mr. Nite</i>			5/17/12		12:20PM		
Checked by		Signature			Date		Time		

Notes: * Cable Replaced.



Specimen B-5 Behavior of Lap Splices of No. 11 Reinforcing Bars				
	Drawn by: BPR	Checked by: km		
	Date: 5/16/12			


Project: Tests to Determine the
Behavior of Spliced #11 Bars

Instrumentation Documentation v.1
(Rev. 04/01/2012)

Specimen: B-6
Sheet 1 of 1

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity	[in] Zero Offset	Location	Zeros [V] Comments
0 M1-0	1	3.333	PA-20	37100980	-6.197	-18.86	N. Overhang	3.043
1 M1-1	1	"	"	37100981	-6.167	-17.11	S. Overhang	2.774
2 M1-2	1	"	PA-10	40010986	3.175	0.86	N. Splice End	0.271
3 M1-3	1	"	"	40010991	3.169	0.59	Midspan	0.185
4 M2-0	1	"	"	40010988	3.173	1.15	S. Splice End	0.362
5 M2-2	100	10V	Lebow 50K	443	-2556	0.2 [K]	N. End	-0.000033
6 M2-3	100	10V	"	442	-2563	0.2 [K]	S. End	-0.000036
7 M3-0	1	30V	Lucas 2	J7250	0.208	0.000	N. Support	0.000
8 M3-1	1	30V	"	J7251	0.209	0.002	S. Support	0.013
Operator		Signature			Date		Time	
BPR		<i>Wm Mite</i>			5/24		5:30 PM	
Checked by		Signature			Date		Time	
KAM		<i>MLLL</i>			5-24		5:30 pm	
Checked by		Signature			Date		Time	

Notes:



Specimen	B- 5 6		
Behavior of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by: KAM
	Date:	5/24/12	

25884-000-30R-C01R-00002, Rev. 000

APPENDIX B

“Purdue Phase II Test Report”

**AN EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS
ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS**

A REPORT Submitted to

First Energy Nuclear Operating Company

Oak Harbor, Ohio

by

Mete A. Sozen



and

Santiago Pujol



08 June 2016

Bowen Laboratory

West Lafayette, IN

SUMMARY

Six girders containing pairs of 79-inch unconfined lap splices of #11 reinforcing bars were tested by loading them to a deflection beyond yield load to develop laminar cracks, unloading, and then loading them to failure. Concrete compressive strength ranged from 5200 to 5900 psi at time of test. Measured yield stress of the bars was 65 ksi.

The testing showed that crack widths of as much as 0.05 inches can be achieved while maintaining the full yield capacity of the #11 reinforcement with 79-inch long splices.

OBJECT AND SCOPE

A series of six reinforced concrete girders with unconfined 79-inch lap splices of Grade-60 #11 bars were tested to failure to:

- determine the effect of existing laminar cracks (cracks on or near the plane of the splice), on the capability of the splice to develop the yield stress of the reinforcing bar, and
- to try to establish the maximum crack width that can be reached while maintaining the yield capacity of the spliced reinforcing bars.

METHOD

Each test girder was initially loaded to beyond yield load to develop laminar cracks, unloaded, and then reloaded to failure. This report documents the measured load-deflection relationships, the initial and final widths of the laminar cracks, observed crack patterns, and the reinforcement stresses developed by the splices. The geometry of the specimens and the test setup were the same as those used in test Series B documented in our report from 2012 [Sozen and Pujol, 2012] to produce complementary test results. In the tests done in 2012, longer splices performed better in the presence of existing laminar cracks. For this reason, the tests described here do not include replicas of specimens in Test Series A from 2012.

The testing procedure used was similar to the procedure used in 2012. The loading sequences used were modified (by increasing peak deflection reached before unloading) to create (and measure) laminar cracks wider than the laminar cracks observed in the initial loading of comparable specimens tested in 2012. Initial loading was stopped at deflections deemed safe for personnel and instrumentation. Reloading to failure was conducted with reduced instrumentation and from a safe distance.

The profile and cross-sectional dimensions of the 34-foot 4-inch long test girders are shown in Fig. 1. They measured 17-5/8 inches by 30 inches in cross section. Each test girder contained two contiguous (i.e. not staggered) splices of length 6 feet 7 inches (56 bar diameters) with a side cover of 3 inches.

Each test girder was placed on two simple supports at a distance of 12 feet 7 inches from one another leaving two overhangs beyond each support. Loads were applied on the overhangs at 9 feet 8 ½ inches from the support leading to bending moment distribution shown qualitatively in Fig.2.

The test girders were tested statically with test durations ranging from 3.5 to 5.5 hours and had measured compressive strengths not exceeding 5900 psi. Yield stress of the reinforcement was determined to be 65ksi. Unit stresses developed in the reinforcement (at splice end) ranged from 73 to 75 ksi.

MATERIALS

The cross section in Fig.1 shows the arrangement of the spliced bars. Concrete was cast with the bars near the bottom of the form (and not as shown in the figure that refers to the position of the bars during the test) to make certain that the wet concrete would not settle away from the bars. Top cover, as shown in Fig. 1, was 5 inches and the side cover was 3 inches to have the laminar crack develop in the horizontal plane affecting the strength of both splices.

All test girders were cast on 2 February 2016 using normal-weight aggregate. Mix proportions by weight are shown in Table 1. Each girder and associated cylinders were cast using concrete from a single truck. After casting, the girders were kept under burlap cover for one week. Target air entrainment was 5%. The age of the concrete and measured concrete strengths at time of test are listed in Table 2.

All reinforcement came from the same heat. As mentioned above the measured yield stress of the reinforcement was 65 ksi (Table 3).

INSTRUMENTATION

The applied load was measured by load cells with an accuracy of 80 lbf as listed in Table 4.

Longitudinal and vertical deformations of the concrete surface were measured using OPTOTRAK (a coordinate tracking system) that had an accuracy of 0.005 inches. The locations of the OPTOTRAK targets are shown in Fig. 4.

Crack development was recorded by visual inspection. Laminar crack widths were determined using OPTOTRAK targets at 4 and 8 inches below the top surface of the test girder.

OBSERVED LOAD-DEFLECTION RELATIONSHIPS

The variations of the deflection at mid-span with applied load are shown in Fig. 5 through 10. Initial loading was continued to a mid-span deflection of 0.4 inches, approximately 4/3 of the deflection at yield, for test girders C1, C2, C3, and C5 and to 0.5 inches, approximately 5/3 of the deflection at yield, for test girders C4 and C6. The maximum deflection was observed to be approximately three times that at yield. Table 5 lists maximum loads and deflections.

CRACK PATTERNS AT END OF FIRST LOADING

Figures 11 to 16 illustrate the crack patterns observed during the tests. Each figure contains two photographs. The photograph on top of the page shows the test girder from the south support to mid-span. The lower one shows the test girder from mid-span to the north support.

HORIZONTAL DEFORMATIONS ALONG LENGTH OF SPLICE

Horizontal deformations along the middle 80 inches at the level of the reinforcement (between contiguous targets) of the test girders obtained by OPTOTRAK measurements are shown in Fig. 17 through 22. Each figure contains the measurements made during the first loading and to an indicated load level (not to the maximum load) during reloading. Despite the presence of laminar cracks near each end of each splice, the increases in deformation indicate that most of the force transfer by bond developed near the splice ends.

VERTICAL DEFORMATIONS ALONG LENGTH OF SPLICE

Vertical deformations measured over a gage length of 4 inches (using targets above and below the plane of the bars) and along the central 80 inches of the test girders are shown in Fig. 23 through 28. Figure 25 contains only the data obtained in the south 40 inches because the sensors for the north 40 inches did not function.

From these plots it is inferred that the stress transfer from bar to bar in the splice took place primarily over lengths at splice ends of approximately 15-bar diameters. (Once these parts of the splice started losing their strength and transferring the force towards the remaining portion of the splice, failure initiated because there was not sufficient remaining length to develop the required force).

Crack widths inferred from the data in Figures 23 to 28 are listed in Table 6. Figure 29 compares the load-deflection relationships measured for specimens C1 to C6. Whatever the size of the "existing" crack, all specimens responded in the same manner and developed more than the yield stress.

CONCLUSION

The test results summarized in Table 6 showed that crack widths of as a much as 0.05 inch can be achieved while maintaining the full yield capacity of the #11 reinforcement with 79" long splices.

REFERENCES

Sozen M., Pujol S., 2012, "An Investigation of the Effect of Laminar Cracks on Strength of Unconfined Lap Splices of #11 Reinforcing Bars." Report to FENOC, Oak Harbor, Ohio.

TABLES

Table 1 Concrete Mix Proportions

Component	Weight of Component / Weight of Cement
Cement	1
Fine Aggregate	2.4
Coarse Aggregate (max. size = 1¼ in.)	2.6
Water	0.55

Table 2 Concrete Strength

Test Girder	Cast Date	Test Date	Concrete Compressive Strength* (psi)	Concrete Splitting Cylinder Strength (psi)	Age of Specimen (days)
C1	2/2/2016	3/21/2016	5300	500	48
C2		3/28/2016	5200	450	55
C3		4/4/2016	5900	500	62
C4		4/11/2016	5700	500	69
C5		4/12/2016	5600	500	70
C6		4/14/2016	5300	400	72

*mean of six cylinder tests

Table 3 Reinforcement

Bar Designation	#11
Nominal Diameter, in.	1.41
Nominal Area, in ²	1.56
Nominal Perimeter, in.	4.43
Unit Weight, lbf/ft	5.31
Yield Stress*, ksi	65

*Note: means from tests of three coupons

Table 4 Sensors

Sensor Type	Manufacturer	Model Number	Serial Number	Location	Range	Accuracy
Load Cell	Lebow	3175 50K	1176585	North Load Point	50 kip	80 lbf
		3175 50K	442	South Load Point		
String Potentiometer	Unimeasure	PA 20	36030715	North Overhang	20 in.	0.05 in.
		PA 20	45110640	South Overhang		
		PA 10	40010981	North Splice End	10 in.	0.02 in.
		PA 10	40010984	Mid-span*		
		PA 10	40010987			
		PA 10	40010979	South Splice End		
LVDT	Schaevitz	DC EC 250	22439	North Support	+/-0.25 in.	0.001 in.
	Schaevitz	DC EC 250	22461	South Support		
Optotrak	Northern Digital Inc.	PRO Series 600	-	-	-	0.005 in.
Dial Gage	Federal	1 in. Dial Gage		North Overhang	1 in.	0.001 in.
				Mid-span		
				South Overhang		

*Sensor 40010981 was used for C1 and C2, sensor 40010987 was used for C3-C6

Table 5 Summary of Results

Test Girder Designation	Concrete Compressive Strength (psi)	Concrete Splitting Strength (Tensile) (psi)	Maximum Applied Load (kip)	Maximum Midspan Deflection (in.)	Maximum Moment at Support (kip-ft)	Maximum Moment at Splice End (kip-ft)	Calc. Reinf. Stress at Support (ksi)	Calc. Reinf. Stress at Splice End (ksi)
C1	5300	500	39.7	0.70	427	419	74	73
C2	5200	450	40.0	0.85	430	422	75	74
C3	5900	500	40.4	0.79	434	426	76	74
C4	5700	500	40.9	0.83	439	431	76	75
C5	5600	500	40.2	0.82	432	424	75	74
C6	5300	400	40.7	0.92	437	429	76	75

Table 6 Summary of Laminar Crack Widths and Lengths

Test Girder Designation	From Optotrak				From Crack Maps	
	Max. Mid-span Deflection at Initial Loading (in.)	Max. Crack Width at Initial Loading (10 ⁻³ in)	Mid-span Deflection at last reading during reload (in.)	Max. Crack Width at last reading during reload (10 ⁻³ in)	Maximum Crack Length at South Splice End (in.)	Maximum Crack Length at North Splice End (in.)
C1	0.42	42	0.70	90	27	23
C2	0.40	21	0.41	25	22	27
C3	0.41	39	0.41	42	23	11
C4	0.52	52	0.50	53	28	24
C5	0.43	54	0.42	57	24	18
C6	0.52	30	0.52	33	22	0

FIGURES





Figure 1 Test Girder Profile and Cross-Sectional Dimensions




Figure 2 Moment and Shear Diagrams




Figure 3: Locations of Deflection Measurements

- String Potentiometers were used to measure displacement at N Overhang, N Splice End, Midspan, S Splice End and S Overhang
- Displacement measurements were checked using dial gages at N Overhang, Midspan and S Overhang
- Linear Variable Differential Transformers (LVDTs) were used to measure displacement at N Support and S Support




Figure 4 Arrangement of Optotrak Targets




Figure 5 Load-Deflection Plot, C1




Figure 6 Load-Deflection Plot, C2




Figure 7 Load-Deflection Plot, C3




Figure 8 Load-Deflection Plot, C4




Figure 9 Load-Deflection Plot, C5




Figure 10 Load-Deflection Plot, C6



Figure 11 Photo C1



Figure 12 Photo C2




Figure 13 Photo C3




Figure 14 Photo C4



Figure 15 Photo C5




Figure 16 Photo C6




Figure 17 Horizontal Deformations, Load and Reload, C1

Note: Data series are labeled using midspan deflection and average load applied at ends




Figure 18 Horizontal Deformations, Load and Reload, C2

Note: Data series are labeled using midspan deflection and average load applied at ends




Figure 19 Horizontal Deformations, Load and Reload, C3

Note: Data series are labeled using midspan deflection and average load applied at ends




Figure 20 Horizontal Deformations, Load and Reload, C4

Note: Data series are labeled using midspan deflection and average load applied at ends




Figure 21 Horizontal Deformations, Load and Reload, C5

Note: Data series are labeled using midspan deflection and average load applied at ends




Figure 22 Horizontal Deformations, Load and Reload, C6

Note: Data series are labeled using midspan deflection and average load applied at ends




Figure 23 Vertical Deformations, Load and Reload, C1

Note: Data series are labeled using midspan deflection and average load applied at ends




Figure 24 Vertical Deformations, Load and Reload, C2

Note: Data series are labeled using midspan deflection and average load applied at ends




Figure 25 Vertical Deformations, Load and Reload, C3

Note: Data series are labeled using midspan deflection and average load applied at ends




Figure 26 Vertical Deformations, Load and Reload, C4

Note: Data series are labeled using midspan deflection and average load applied at ends




Figure 27 Vertical Deformations, Load and Reload, C5

Note: Data series are labeled using midspan deflection and average load applied at ends




Figure 28 Vertical Deformations, Load and Reload, C6

Note: Data series are labeled using midspan deflection and average load applied at ends







Figure 29 Comparison of Load-Deflection Relationships

Project: Tests to Determine the
Behavior of Spliced #11 Bars

Cylinder Compression Tests Documentation v.2
(Rev. 04/01/2012)

Specimen: C1 test day

Sheet 1 of 2

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]		Length [nearest 0.05 in.]			P _{max} [lbf]	Fracture Type (1-6)
				1	2	1	2	3		
1	3/21/16	11:55	Dry	5.93	6.05	12.00	12.00	12.00	151,608	5
2	3/21/16	11:59	Dry	5.93	6.05	12.00	12.00	12.00	151,425	4
3	3/21/16	12:03	Dry	5.93	6.05	12.00	12.00	12.00	144,778	3
4	3/21/16	12:07	Dry	5.93	6.04	12.00	12.00	12.00	149,386	5
5	3/21/16	12:12	Dry	5.93	6.02	12.00	12.00	12.00	150,020	5
6	3/21/16	12:15	Dry	5.93	6.04	12.00	12.00	12.00	153,955	4
S/N of Testing Machine:			Forney 99058							
Recorded by:			Signature			Date		Time		
Kinsey Skiller						3/21/16		12:19		
Checked by:			Signature			Date		Time		
JASPAL S SAHNI						03/21/16		12:19		
Checked by:			Signature			Date		Time		
S. PUJOL						3/22/16		9 AM.		

Comments:




*Cylinders to be test per ASTM C-39-12 and C-1231-10a with a loading rate of 60,000lb_f/min at concrete ages of 3, 7, 14, 28 days, and on same day that test of corresponding specimen is conducted. Specimens and caps free of defects unless otherwise noted in comments. Average cylinder diameter and area and unit compressive stress (f'_c) calculated on sheet 2 of 2.

Project: Tests to Determine the
Behavior of Spliced #11 Bars

Cylinder Split Tensile Tests Documentation v.1
(Rev. 05/14/2012)

Specimen: C1 test day

Sheet 1 of 2



Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]			Length [nearest 0.1 in.]		P _{max} [lb _f]	Fracture Sketch
				end	middle	end	1	2		
1	3/21/16	9:51	Dry	5.93	6.05	6.06	12.00	12.01	59,765	①
2	3/21/16	10:05	Dry	5.92	6.02	6.06	12.00	12.02	52,335	①
3	3/21/16	10:11	Dry	5.93	5.97	6.04	12.01	12.05	57,975	①
4	3/21/16	10:17	Dry	5.91	5.97	6.04	12.00	12.01	63,546	①
5	3/21/16	10:23	Dry	5.93	5.98	6.06	11.99	12.01	44,959	①
6	3/21/16	10:32		5.93	5.98	6.04	12.02	12.06	43,976	①
S/N of Testing Machine:			Forney 99058							
Recorded by:			Signature			Date		Time		
Kinsy Skiker						3/21/16		10:33		
Checked by:			Signature			Date		Time		
Will Porellis						3/21/16		10:35		
Checked by:			Signature			Date		Time		
S. PUSOL						3/22/16		9 AM		
Comments:										
*Cylinders to be test per ASTM C-496-11 with a loading rate of 15,000lb _f /min at a concrete age of 28 days and on same day that the test of the corresponding specimen is conducted. Specimens free of defects unless otherwise noted in comments. Average cylinder diameter and area and splitting tensile strength (f _t) calculated on sheet 2 of 2.										

Project: Tests to Determine the
Behavior of Spliced #11 Bars

Cylinder Compression Tests Documentation v.2
(Rev. 04/01/2012)

Specimen: C2 test day

Sheet 1 of 2

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]		Length [nearest 0.05 in.]			P _{max} [lbf]	Fracture Type (1-6)
				1	2	1	2	3		
1	3/28/16	10:54	Dry	5.93	6.04	12.00	11.95	12.00	145,661	6
2	3/28/16	10:58	Dry	5.94	6.05	11.95	12.00	12.00	747489	5
3	3/28/16	11:01	Dry	5.93	6.05	11.95	12.00	12.00	148412	5
4	3/28/16	11:07	Dry	5.93	6.03	12.00	12.00	12.00	143739	5
5	3/28/16	11:11	Dry	5.93	6.05	11.95	12.00	12.00	150473	5
6	3/28/16	11:16	Dry	5.93	6.05	11.95	12.00	11.95	150433	5
S/N of Testing Machine:			Forney 99058							
Recorded by:			Signature			Date		Time		
Kinsey Skiller						3/28/16		11:16		
Checked by:			Signature			Date		Time		
Henrik Skovgaard						3/30/16		8:48		
Checked by:			Signature			Date		Time		

Comments:

*Cylinders to be test per ASTM C-39-12 and C-1231-10a with a loading rate of 60,000lb_f/min at concrete ages of 3, 7, 14, 28 days, and on same day that test of corresponding specimen is conducted. Specimens and caps free of defects unless otherwise noted in comments. Average cylinder diameter and area and unit compressive stress (f'_c) calculated on sheet 2 of 2.

Project: Tests to Determine the Behavior of Spliced #11 Bars

Cylinder Split Tensile Tests Documentation v.1
(Rev. 05/14/2012)

Specimen: C2 test day
(56 day) Sheet 1 of 2

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]			Length [nearest 0.1 in.]		P _{max} [lb _f]	Fracture Sketch
				end	middle	end	1	2		
1	3/28/16	8:32	Dry	5.94	6.04	6.05	12.00	12.00	57,696	
2	3/28/16	8:37	Dry	5.93	6.04	6.05	12	12	55,073	
3	3/28/16	8:42	Dry	5.93	6.03	6.05	12	12	42,134	
4	3/28/16	8:46	Dry	5.93	6.02	6.05	12	12	50,648	
5	3/28/16	8:52	Dry	6.93	6.05	6.05	12	12	54,369	
6	3/28/16	8:56	Dry	5.93	6.03	6.04	12	12	45,287	
S/N of Testing Machine:			Forney 99058							
Recorded by:			Signature				Date		Time	
Kinsley Skiller							3/28/16		9:02	
Checked by:			Signature				Date		Time	
Henrik Stegaard							3/30/16		8:47	
Checked by:			Signature				Date		Time	

Comments:

*Cylinders to be test per ASTM C-496-11 with a loading rate of 15,000lb_f/min at a concrete age of 28 days and on same day that the test of the corresponding specimen is conducted. Specimens free of defects unless otherwise noted in comments. Average cylinder diameter and area and splitting tensile strength (f_t) calculated on sheet 2 of 2.

Project: Tests to Determine the
Behavior of Spliced #11 Bars

Cylinder Compression Tests Documentation v.2
(Rev. 04/01/2012)

Specimen: C3

Sheet 1 of 3

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]		Length [nearest 0.05 in.]			P _{max} [lbf]	Fracture Type (1-6)
				1	2	1	2	3		
1	4/5/16	7:17	Dry	5.94	6.02	12.05	12.00	12.00	166509	6
2	4/5/16	7:25	Dry	5.93	6.04	12.00	11.95	12.00	165239	5
3	4/5/16	7:33	Dry	5.94	6.05	12.00	11.95	11.95	168307	6
4	4/5/16	7:37	Dry	5.94	6.03	12.00	11.95	11.95	163382	5
5	4/5/16	7:41	Dry	5.93	6.04	12.05	12.00	12.05	162122	6
6	4/5/16	7:46	Dry	5.94	6.04	12.00	12.00	12.05	167221	5
S/N of Testing Machine:			Forney							
Recorded by:			Signature			Date		Time		
Kinsey Skiller			Signature			4/5/16		7:50		
Checked by:			Signature			Date		Time		
Sam WORTHY			Signature			4/5/16		0746		
Checked by:			Signature			Date		Time		

Comments:

*Cylinders to be test per ASTM C-39-12 and C-1231-10a with a loading rate of 60,000lb_f/min at concrete ages of 3, 7, 14, 28 days, and on same day that test of corresponding specimen is conducted. Specimens and caps free of defects unless otherwise noted in comments. Average cylinder diameter and area and unit compressive stress (f'_c) calculated on sheet 2 of 2.

Project: Tests to Determine the Behavior of Spliced #11 Bars

Cylinder Split Tensile Tests Documentation v.1
(Rev. 05/14/2012)

Specimen: C3 Sheet 1 of 3

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]			Length [nearest 0.1 in.]		P _{max} [lbf]	Fracture Sketch
				end	middle	end	1	2		
1	4/5/16	7:49	Dry	5.93	6.02	6.04	12.00	12	76206	
2	4/5/16	8:03	Dry	5.94	6.02	6.05	12	12	68902	
3	4/5/16	8:05	Dry	5.94	6.03	6.06	12	12	53916	
4	4/5/16	8:08	Dry	5.95	6.00	6.04	12	12	42549	
5	4/5/16	8:11	Dry	5.93	6.01	6.03	12	12	53347	
6	4/5/16	8:18	Dry	5.94	6.00	6.02	12	12	50127	
S/N of Testing Machine:			Forney							
Recorded by:			Signature				Date		Time	
Kinsey Skillen							4/5/16		8:18	
Checked by:			Signature				Date		Time	
Sam Woerthy							4/5/16		0722	
Checked by:			Signature				Date		Time	
Comments:										
*Cylinders to be test per ASTM C-496-11 with a loading rate of 15,000lb _i /min at a concrete age of 28 days and on same day that the test of the corresponding specimen is conducted. Specimens free of defects unless otherwise noted in comments. Average cylinder diameter and area and splitting tensile strength (f _t) calculated on sheet 2 of 2.										

Project: Tests to Determine the Behavior of Spliced #11 Bars

Cylinder Compression Tests Documentation v.2
(Rev. 04/01/2012)

Specimen: C4

Sheet 1 of 2

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]		Length [nearest 0.05 in.]			P _{max} [lbf]	Fracture Type (1-6)
				1	2	1	2	3		
1	4/11/16	9:20	Dry	5.94	6.04	12.00	12.00	11.95	161352	3
2	4/11/16	9:27	Dry	5.94	6.05	12.00	12.00	11.95	165941	5
3	4/11/16	9:34	Dry	5.93	6.06	12.00	12.10	12.05	162517	5
4	4/11/16	9:40	Dry	5.94	6.03	11.95	12.00	12.00	160794	5
5	4/11/16	9:46	Dry	5.94	6.02	11.95	12.00	11.95	151473	3
6	4/11/16	9:52	Dry	5.94	6.04	12.05	12.00	11.95	160,170	3

S/N of Testing Machine: Forney 99058

Recorded by: _____ Signature _____ Date _____ Time _____

Kinsey Skiller _____ Signature _____ Date 4/11/16 Time 9:55

Checked by: _____ Signature _____ Date _____ Time _____

Checked by: _____ Signature _____ Date _____ Time _____

Checked by: _____ Signature _____ Date _____ Time _____

Checked by: _____ Signature _____ Date _____ Time _____

Comments:

*Cylinders to be test per ASTM C-39-12 and C-1231-10a with a loading rate of 60,000lb_f/min at concrete ages of 3, 7, 14, 28 days, and on same day that test of corresponding specimen is conducted. Specimens and caps free of defects unless otherwise noted in comments. Average cylinder diameter and area and unit compressive stress (f'_c) calculated on sheet 2 of 2.

Project: Tests to Determine the Behavior of Spliced #11 Bars

Cylinder Split Tensile Tests Documentation v.1
(Rev. 05/14/2012)

Specimen: C4

Sheet 1 of 3

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]			Length [nearest 0.1 in.]		P _{max} [lbf]	Fracture Sketch
				end	middle	end	1	2		
1	4/11/16	10:11 10:11	Dry	6.04	6.01	5.95	12	12	54504	
2	4/11/16	10:17	Dry	6.03	5.99	5.94	12	12	46887	
3	4/11/16	10:24	Dry	6.04	5.99	5.93	12	12	62491	
4	4/11/16	10:29	Dry	6.03	5.99	5.94	12	12	60959	
5	4/11/16	10:35	Dry	6.04	5.96	5.93	12	12	62507	
6	4/11/16	10:40	Dry	6.04	5.99	5.93	12	12	41,151	
S/N of Testing Machine:			Forney 99058							
Recorded by:			Signature				Date		Time	
Kinsley Skillen							4/11/16		10:50	
Checked by:			Signature				Date		Time	
Tom SPRAGG							4/12/16		10:50	
Checked by:			Signature				Date		Time	
Comments:										
*Cylinders to be test per ASTM C-496-11 with a loading rate of 15,000lb./min at a concrete age of 28 days and on same day that the test of the corresponding specimen is conducted. Specimens free of defects unless otherwise noted in comments. Average cylinder diameter and area and splitting tensile strength (f _t) calculated on sheet 2 of 2.										

Project: Tests to Determine the Behavior of Spliced #11 Bars

Cylinder Compression Tests Documentation v.2
(Rev. 04/01/2012)

Specimen: C5

Sheet 1 of 2

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]		Length [nearest 0.05 in.]			P _{max} [lbf]	Fracture Type (1-6)
				1	2	1	2	3		
1	4/12/16	8:45	Dry	6.04	5.93	12.00	11.95	11.95	157909	5
2	4/12/16	8:50	Dry	6.03	5.95	11.95	11.95	11.95	145422	5
3	4/12/16	8:56	Dry	6.02	5.94	12.00	12.00	12.00	160573	5
4	4/12/16	9:04	Dry	6.03	5.93	12.05	12.00	12.05	162401	5
5	4/12/16	9:10	Dry	6.04	5.94	11.95	12.00	12.00	161381	3
6	4/12/16	9:15	Dry	6.02	5.93	12.05	12.1	12.05	158,264	6

S/N of Testing Machine: Forney 99058

Recorded by: _____ Signature _____ Date _____ Time _____

Kinsey Skillen _____ Signature _____ Date 4/12/16 Time 9:22 AM

Checked by: _____ Signature _____ Date _____ Time _____

Checked by: _____ Signature _____ Date _____ Time _____

Checked by: _____ Signature _____ Date _____ Time _____

Checked by: _____ Signature _____ Date _____ Time _____

Comments:

*Cylinders to be test per ASTM C-39-12 and C-1231-10a with a loading rate of 60,000lb_f/min at concrete ages of 3, 7, 14, 28 days, and on same day that test of corresponding specimen is conducted. Specimens and caps free of defects unless otherwise noted in comments. Average cylinder diameter and area and unit compressive stress (f'_c) calculated on sheet 2 of 2.

Project: Tests to Determine the Behavior of Spliced #11 Bars

Cylinder Split Tensile Tests Documentation v.1
(Rev. 05/14/2012)

Specimen: C5


Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]			Length [nearest 0.1 in.]		P _{max} [lbf]	Fracture Sketch
				end	middle	end	1	2		
1	4/12/16	7:45	Dry	6.04	5.97	5.93	12.00	12.00	55507	
2	4/12/16	8:00	Dry	6.02	5.98	5.94	12.00	12.00	51940	
3	4/12/16	8:07	Dry	6.04	5.96	5.93	12.00	12.00	64451	
4	4/12/16	8:13	Dry	6.03	5.98	5.94	12.00	12.00	62706	
5	4/12/16	8:20	Dry	6.04	5.99	5.95	12.00	12.00	54167	
6	4/12/16	8:26	Dry	6.03	5.99	5.94	12.00	12.00	40823	
S/N of Testing Machine:			Forney 99058							
Recorded by:			Signature				Date		Time	
Kinsey Skillen							4/12/16		8:30 AM	
Checked by:			Signature				Date		Time	
Checked by:			Signature				Date		Time	
Comments:										
*Cylinders to be test per ASTM C-496-11 with a loading rate of 15,000lb./min at a concrete age of 28 days and on same day that the test of the corresponding specimen is conducted. Specimens free of defects unless otherwise noted in comments. Average cylinder diameter and area and splitting tensile strength (f _t) calculated on sheet 2 of 2.										

Project: Tests to Determine the
Behavior of Spliced #11 Bars

Cylinder Compression Tests Documentation v.2
(Rev. 04/01/2012)

Specimen: CC test day

Sheet 1 of 2

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]		Length [nearest 0.05 in.]			P _{max} [lb _f]	Fracture Type (1-6)
				1	2	1	2	3		
1	4/14/16	9:42	Dry	6.04	5.95	12.00	12.00	12.00	143979	5
2	4/14/16	9:48	Dry	6.03	5.94	11.95	12.00	11.95	152771	4
3	4/14/16	9:52	Dry	6.03	5.93	12.05	12.00	12.00	150,079	3
4	4/14/16	9:56	Dry	6.04	5.92	12.00	12.05	12.05	154850	5
5	4/14/16	9:59	Dry	6.03	5.94	11.95	11.95	11.95	147712	5
6	4/14/16	10:05	Dry	6.05	5.94	12.05	12.00	12.00	153686	5
S/N of Testing Machine:			Forney 99058							
Recorded by:			Signature			Date		Time		
Kinsey Skiller						4/14/16		10:10 AM		
Checked by:			Signature			Date		Time		
Checked by:			Signature			Date		Time		

Comments:

*Cylinders to be test per ASTM C-39-12 and C-1231-10a with a loading rate of 60,000lb_f/min at concrete ages of 3, 7, 14, 28 days, and on same day that test of corresponding specimen is conducted. Specimens and caps free of defects unless otherwise noted in comments. Average cylinder diameter and area and unit compressive stress (f'_c) calculated on sheet 2 of 2.

Project: Tests to Determine the Behavior of Spliced #11 Bars

Cylinder Split Tensile Tests Documentation v.1
(Rev. 05/14/2012)

Specimen: CG test log
Sheet 1 of 3



Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]			Length [nearest 0.1 in.]		P _{max} [lbf]	Fracture Sketch
				end	middle	end	1	2		
1	4/14/16	9:10	Dry	6.05	5.99	5.93	12	12	53328	
2	4/14/16	9:15	Dry	6.03	6.00	5.94	12	12	54417	
3	4/14/16	9:18	Dry	6.03	6.01	5.94	12	12	43763	
4	4/14/16	9:23	Dry	6.04	5.98	5.94	12	12	51448	
5	4/14/16	9:28	Dry	6.03	5.99	5.94	12	12	35520	
6	4/14/16	9:32	Dry	6.02	5.98	5.93	12	12	40360	
S/N of Testing Machine:			Forney 77058							
Recorded by:			Signature				Date		Time	
Kinsey Skiller							4/14/16		9:40	
Checked by:			Signature				Date		Time	
Checked by:			Signature				Date		Time	
Comments:										
*Cylinders to be test per ASTM C-496-11 with a loading rate of 15,000lb _f /min at a concrete age of 28 days and on same day that the test of the corresponding specimen is conducted. Specimens free of defects unless otherwise noted in comments. Average cylinder diameter and area and splitting tensile strength (f _t) calculated on sheet 2 of 2.										

Form 3

Appendix 2, Pg 1 of 18

Project: Tests to Determine the
Behavior of Spliced #11 BarsCasting Documentation v.1
(Rev. 03/30/2012)Specimen: C1

Sheet 1 of 1

General Information					
Date	Disp Ticket Num	Truck No.	Time on Ticket	Time of Arrival	Temp. in Lab
FEB 02, 2016	11822021	1982	09:47	10:02	52
Measurements made upon arrival of concrete					
Slump (ASTM C143 - 10a)		Air Content (ASTM C231 - 10)		S/N of Air Meter	
Time ₁	Result ₁	Time ₁	Result ₁	S/N of Air Meter	
10:13	7 1/2"	10:21	4.3%	5431265256 / LAF 2	
Time ₂	Result ₂	Time ₂	Result ₂	S/N of Scale	
10:45	7 1/2"	10:39	4.1%	H 3802360	
Unit Weight (ASTM C138 - 10b)					
Time ₁	Wt. of Cont. ₁	Total Wt. ₁	Wt. of Conc. ₁	Result ₁ = Wt. of Conc./Vol. of Cont.	
10:19	8.45 lb	45.25 lb	36.70 lb	36.70# / 0.25 ft ³ = 146.8 $\frac{\text{lb}}{\text{ft}^3}$	
Time ₂	Wt. of Cont. ₂	Total Wt. ₂	Wt. of Conc. ₂	Result ₂ = Wt. of Conc./Vol. of Cont.	
10:38	8.45 lb	45.00 lb	36.55 lb	36.55# / 0.25 ft ³ = 146.2 $\frac{\text{lb}}{\text{ft}^3}$	
Times of actions during and after casting					
Layer 1 placed	Layer 1 vibration complete	Layer 2 placed	Layer 2 vibration complete	Top surface struck off	Truck Departing Lab
10:28	10:30	10:46	10:48	10:59	10:56
Lifting Inserts Placed	Covered with plastic	Plastic removed	Covered with burlap	Burlap doused with water	Covered with plastic
10:59	2:55	4:55	5:00 *	5:05 *	
Recorded by		Signature		Date	Time
JASPAL S SAINI				02/02/16	4 PM
Checked by		Signature		Date	Time
S. PWOL				2/2/16	4 PM
Checked by		Signature		Date	Time
Comments:					
CONC TEMP @ 10:12 = 70°F					
* cylinders done @ 5:50 pm & 5:55 pm					
*The following ASTM standards and specifications will be followed during casting: C172-10, C192-07, C470-09					

Truck	Driver	User	Disp Ticket Num	Ticket ID	Time	Date
1982	1076	user	11822021	0	9:47	2/2/16
Load Size	Mix Code	Returned	Qty	Mix Age	Seq	Load ID
5.75 CYDS	4000CC				D	32409

Description	Design Qty	Adj.T	Required	Batched	Actual Wat
Batch:	1 ----	Start:	End:	Time (hh:mm:ss):	
Buzzi	588 lb		3381 lb	3425 lb	>
STONE-8	940 lb		5416 lb	5420 lb	1 gl
STONE-4	620 lb		3583 lb	3580 lb	2 gl
SAND-23	1435 lb		8623 lb	8600 lb	44 gl
WATER	322.9 lb		1456.7 lb	1450.0 lb	173.8 gl
MICROAIR	1.10 /C		37.19 oz	37.00 oz	

Actual		Num Batches:	1								
Load	22477 lb	Design W/C:	0.549	Water/Cement:	0.542 T	Design	222.5 gl	Actual	221.6 gl	To Add:	0.9 gl
Slump:	6.00 in	#	Water in Truck:	0.0 lb	Adjust Water:	0.0 lb / Load	Trim Water:	0.0 lb /	CY		

Concrete Delivery Ticket

Appendix 2, Pg 3 of 18



Plant #	Ticket Number	Truck	Load Size	Mix	Slump	Use	Date	Customer
110	11032021	1982	5.75cy	4000CC	6.00	TFST	02/02/16	116

Sold To	Tax Code	Driver	Project No.	Order No.
LAB POWER LAB		BOB PIERCE		

Delivery Address	P.O. Number
------------------	-------------

ON SOUTH RIVER ROAD AT THE LAB 3 YARD TEST LOAD 1ST THEN 5.75
 406-697-1743 TRUCK RELEASE

Job No.)

Time Printed 09:39

Load Quantity	Total	Ordered Quantity	Product Code	Product Description	Unit Price	Amount
5.75	5.75cy	34.50cy	4000CC	4000-A-C-LSTONE-CC	115.00	661.25



WINTER FEE 23.00
 ENVIRONMENTAL FEE 12.00



Water Added At Customer's Request	Total No. Gallons	Slump Meter Reading	Subtotal
			696.25
On Job Time	Finish Pour Time	Grand Total	Tax
		744.99	48.74
			Total
			744.99

PROPERTY DAMAGE RELEASE / WARNING - Irritating To The Skin and Eyes

Dear Customer - The Seller is not responsible for slumps, strength or quality of concrete to which water or any other material has been added by the purchaser or at his request. The undersigned hereby authorizes Irving Materials, Inc. to use private property for making the delivery shown here on and assumes full responsibility for any damage or injury due to the premises. The undersigned agrees to reimburse said Company for loss of time and equipment by reason of such delivery and also to identify and save harmless said Company from any and all claims, demands and suits for or on account of or in any manner caused by or arising from private property delivery. The undersigned assumes responsibility for a suitable roadway from public highway to point of delivery and is responsible for any needed wrecker service charges as a result. SAFETY WARNING: Keep away from children. Contains Portland Cement. Irritating to the skin and eyes. Wear rubber boots, gloves and eye protection. Prolonged contact may cause burns. In case of contact with skin or eyes, flush thoroughly with water. If irritation persists, get medical attention. For additional information regarding the HAZARDS OF READY MIX CONCRETE, consult the Material Data Safety Sheet (MSDS) available upon request. PRODUCT NOTICE: Seller will not be held responsible for the final appearance of exposed aggregate, integral coloring, stamped and decorative surfacing, and all other forms of architectural and design concrete. DELIVERY NOTICE: Seller assumes no responsibility for deliveries beyond the public right of way. Buyer assumes responsibility for damages including but not limited to curb, sidewalk, driveway, or any property of the contractor or property owner or agents. NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE SAFETY AND HEALTH WARNING NOTICE AND ACCEPTANCE OF THE LOAD.

Release, Load and Terms Accepted By:

X *[Signature]*





Form 3

Appendix 2, Pg 4 of 18

Project: Tests to Determine the
Behavior of Spliced #11 BarsCasting Documentation v.1
(Rev. 03/30/2012)Specimen: C2

Sheet 1 of 1

General Information					
Date	Disp Ticket Num	Truck No.	Time on Ticket	Time of Arrival	Temp. in Lab
Feb 02, 2016	11822029	1693	10:45	11:06	57
Measurements made upon arrival of concrete					
Slump (ASTM C143 - 10a)			Air Content (ASTM C231 - 10)		
Time ₁	Result ₁	Time ₁	Result ₁	S/N of Air Meter	
11:16	7 $\frac{1}{2}$ "	11:22	4.3%	5431265256 / LAF 2	
Time ₂	Result ₂	Time ₂	Result ₂	S/N of Scale	
11:43	6 $\frac{1}{2}$ "	11:38	4.7%	H 3802360	
Unit Weight (ASTM C138 - 10b)					
Time ₁	Wt. of Cont. ₁	Total Wt. ₁	Wt. of Conc. ₁	Result ₁ = Wt. of Conc./Vol. of Cont.	
11:21	8.45 lb	45.00 lb	36.55 lb	$36.55 \# / 0.25 \text{ ft}^3 = 146.2 \frac{\text{lb}}{\text{ft}^3}$	
Time ₂	Wt. of Cont. ₂	Total Wt. ₂	Wt. of Conc. ₂	Result ₂ = Wt. of Conc./Vol. of Cont.	
11:36	8.45 lb	44.15 lb	35.70 lb	$35.70 \# / 0.25 \text{ ft}^3 = 142.8 \frac{\text{lb}}{\text{ft}^3}$	
Times of actions during and after casting					
Layer 1 placed	Layer 1 vibration complete	Layer 2 placed	Layer 2 vibration complete	Top surface struck off	Truck Departing Lab
11:25	11:30	11:46	11:48	11:53	11:50
Lifting Inserts Placed	Covered with plastic	Plastic removed	Covered with burlap	Burlap doused with water	Covered with plastic
12:00	2:55	4:55	5:00 *	5:05 *	
Recorded by		Signature		Date	Time
JASPAL S SAINI				02/02/16	4:15 PM
Checked by		Signature		Date	Time
S. PUJOL				2/2/16	4:15 PM
Checked by		Signature		Date	Time
Comments:					
CONC TEMP @ 11:17 = 70°F * Cylinders covered @ 5:55pm					
*The following ASTM standards and specifications will be followed during casting: C172-10, C192-07, C470-09					

C2

Truck	Driver	User	Disp Ticket Num	Ticket ID	Time	Date
1693	2774	user	11822029	0	10:54	2/2/16
Load Size	Mix Code	Returned	Qty	Mix Age	Seq	Load ID
5.75 CYDS	4000CC				D	32416

Description	Design Qty	Adj.T	Required	Batched	Actual Wat
Batch:	Start:	End:	Time (hh:mm:ss):	Time (hh:mm:ss):	
Buzzi	588 lb		3381 lb	3375 lb	
STONE-8	940 lb		5416 lb	5400 lb	1 gl
STONE-4	620 lb		3583 lb	3620 lb	2 gl
SAND-23	1435 lb		8664 lb	8660 lb	49 gl
WATER	322.9 lb		1415.5 lb	1406.0 lb	168.5 gl
MICROAIR	1.10 /C		37.19 oz	37.00 oz	

Actual	Num Batches: 1							
Load	22463 lb	Design W/C: 0.549	Water/Cement: 0.550 T	Design	222.5 gl	Actual	221.4 gl	To Add: 1.1 gl
Slump:	6.00 in	# Water in Truck:	0.0 lb	Adjust Water:	0.0 lb / Load	Trim Water:	0.0 lb /	CY

Concrete Delivery Ticket



Plant #	Ticket Number	Truck	Load Size	Mix	Slump	Use	Date	Customer
119	11823023	1693	5.75cy	1000CC	5.00	TEST	02/02/16	116
Sold To				Tax Code	Driver	Project No.		Order No.
COD BOWEN LAB				7	RON HOWARD	0		1020
Delivery Address							P.O. Number	

ON SOUTH RIVER ROAD AT THE LAB 3 YARD TEST LOAD 1ST THEN 5.75
 400-697-1743 TRUCK RELEASE

Job No.}

Time Printed 10:45

Load Quantity	Total	Ordered Quantity	Product Code	Product Description	Unit Price	Amount
5.75	11.50cy	34.50cy	4000CC	4000-A-C-LSTONE-CC	115.00	661.25



WINTER FEE 23.00
 ENVIRONMENTAL FEE 12.00

Water Added At Customer's Request		Total No. Gallons	Slump Meter Reading	900	Subtotal	696.25
On Job Time	Finish Pour Time	AUTH. #:	Grand Total:	1,489.95	Tax	48.74
				Total	744.99	

PROPERTY DAMAGE RELEASE / WARNING - Irritating To The Skin and Eyes

Dear Customer - The Seller is not responsible for slumps, strength or quality of concrete to which water or any other material has been added by the purchaser or at his request. The undersigned hereby authorizes Irving Materials, Inc. to use private property for making the delivery shown here on and assumes full responsibility for any damage or injury due to the premises. The undersigned agrees to reimburse said Company for loss of time and equipment by reason of such delivery and also to identify and save harmless said Company from any and all claims, demands and suits for or on account of or in any manner caused by or arising from private property delivery.

The undersigned assumes responsibility for a suitable roadway from public highway to point of delivery and is responsible for any needed wrecker service charges as a result.

SAFETY WARNING: Keep away from children. Contains Portland Cement. Irritating to the skin and eyes. Wear rubber boots, gloves and eye protection. Prolonged contact may cause burns. In case of contact with skin or eyes, flush thoroughly with water. If irritation persists, get medical attention. For additional information regarding the HAZARDS OF READY MIX CONCRETE, consult the Material Data Safety Sheet (MSDS) available upon request.



PRODUCT NOTICE: Seller will not be held responsible for the final appearance of exposed aggregate, integral coloring, stamped and decorative surfacing, and all other forms of architectural and design concrete.

DELIVERY NOTICE: Seller assumes no responsibility for deliveries beyond the public right of way. Buyer assumes responsibility for damages including but not limited to curb, sidewalk, driveway, or any property of the contractor or property owner or agents.

NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE SAFETY AND HEALTH WARNING NOTICE AND ACCEPTANCE OF THE LOAD.

Release, Load and Terms Accepted By:

X



Form 3



Appendix 2, Pg 7 of 18

Project: Tests to Determine the Behavior of Spliced #11 Bars

Casting Documentation v.1
(Rev. 03/30/2012)

Specimen: C3

Sheet 1 of 1

General Information					
Date	Disp Ticket Num	Truck No.	Time on Ticket	Time of Arrival	Temp. in Lab
FEB 02, 2016	11822035	1967	11:52	12:08	57
Measurements made upon arrival of concrete					
Slump (ASTM C143 - 10a)		Air Content (ASTM C231 - 10)			
Time ₁	Result ₁	Time ₁	Result ₁	S/N of Air Meter	
12:17	5 1/2"	12:22	4.2%	5431265256/LAF2	
Time ₂	Result ₂	Time ₂	Result ₂	S/N of Scale	
12:48	5 3/4"	12:42	4.2%	H3802360	
Unit Weight (ASTM C138 - 10b)					
Time ₁	Wt. of Cont. ₁	Total Wt. ₁	Wt. of Conc. ₁	Result ₁ = Wt. of Conc./Vol. of Cont.	
12:20	8.45 lb	45.55 lb	37.10 lb	$\frac{37.10 \#}{0.25 \text{ ft}^3} = 148.4 \frac{\text{lb}}{\text{ft}^3}$	
Time ₂	Wt. of Cont. ₂	Total Wt. ₂	Wt. of Conc. ₂	Result ₂ = Wt. of Conc./Vol. of Cont.	
12:41	8.45 lb	44.85 lb	36.40 lb	$\frac{36.40 \#}{0.25 \text{ ft}^3} = 145.6 \frac{\text{lb}}{\text{ft}^3}$	
Times of actions during and after casting					
Layer 1 placed	Layer 1 vibration complete	Layer 2 placed	Layer 2 vibration complete	Top surface struck off	Truck Departing Lab
12:27	12:30	12:40	12:43	12:52	12:47
Lifting Inserts Placed	Covered with plastic	Plastic removed	Covered with burlap	Burlap doused with water	Covered with plastic
12:57	4:20	5:45	5:50	5:55	6:00
Recorded by		Signature		Date	Time
JASPAL S SANI				02/02/16	4:15 PM
Checked by		Signature		Date	Time
S. PUJOL				2/2/16	4:15 PM
Checked by		Signature		Date	Time
Comments:					
CONC TEMP @ 12:18 = 71°F					
*The following ASTM standards and specifications will be followed during casting: C172-10, C192-07, C470-09					

Form 2

Form 2

Form 2

Truck	Driver	User	Disp Ticket Num	Ticket ID	Time	Date
1967	3002	user	11822035	0	11:52	2/2/16
Load Size	Mix Code	Returned	Qty	Mix Age	Seq	Load ID
5.75 CYDS	4000CC				D	32422

Description	Design Qty	Adj.T	Required	Batched	Actual Wat
Batch:	1 ----	Start:	End:	-----	Time (hh:mm:ss):
Buzzi	588 lb	11:52:23	3381 lb	3390 lb	
STONE-8	940 lb		5416 lb	5420 lb	1 gl
STONE-4	620 lb		3583 lb	3620 lb	2 gl
SAND-23	1435 lb		8664 lb	8660 lb	49 gl
WATER	317.9 lb		1386.7 lb	1372.0 lb	164.4 gl
MICROAIR	1.10 /C		37.19 oz	37.00 oz	

Actual	Num Batches: 1							
Load	22464 lb	Design W/C: 0.541	Water/Cement: 0.539 T	Design	219.0 gl	Actual	217.3 gl	To Add: 1.8 gl
Slump:	6.00 in	# Water in Truck: 0.0 lb	Adjust Water:	0.0 lb / Load	Trim Water:	0.0 lb /	CYT	

Concrete Delivery Ticket

Plant #	Ticket Number	Truck	Load Size	Mix	Slump	Use	Date	Customer
118	11039035	1967	5.75cy	4000CC	6.00	TEST	02/02/16	110

Sold To	Tax Code	Driver	Project No.	Order No.
COB BOWEN L&P	7	JOE MOREHOUSE	0	1022

Delivery Address	P.O. Number
------------------	-------------

ON SOUTH RIVER ROAD AT THE LAB 3 YARD TEST LOAD 1ST THEN 5.75
 406-697-1743 TRUCK RELEASE

Job No.)

Time Printed 11:49

Load Quantity	Total	Ordered Quantity	Product Code	Product Description	Unit Price	Amount
5.75	17.25cy	34.50cy	4000CC	4000-A-C-LSTONE-DC	115.00	661.25



WINTER FEE 23.00
 ENVIRONMENTAL FEE 12.00



Water Added At Customer's Request		Total No. Gallons	Slump Meter Reading					Subtotal	696.25
On Job Time	Finish Pour Time	AUTH. #:	Grand Total:	2,234.97	Tax	48.74	Total	744.99	

PROPERTY DAMAGE RELEASE / WARNING - Irritating To The Skin and Eyes

Dear Customer - The Seller is not responsible for slumps, strength or quality of concrete to which water or any other material has been added by the purchaser or at his request. The undersigned hereby authorizes Irving Materials, Inc. to use private property for making the delivery shown here on and assumes full responsibility for any damage or injury due to the premises. The undersigned agrees to reimburse said Company for loss of time and equipment by reason of such delivery and also to identify and save harmless said Company from any and all claims, demands and suits for or on account of or in any manner caused by or arising from private property delivery. The undersigned assumes responsibility for a suitable roadway from public highway to point of delivery and is responsible for any needed wrecker service charges as a result. SAFETY WARNING: Keep away from children. Contains Portland Cement. Irritating to the skin and eyes. Wear rubber boots, gloves and eye protection. Prolonged contact may cause burns. In case of contact with skin or eyes, flush thoroughly with water. If irritation persists, get medical attention. For additional information regarding the HAZARDS OF READY MIX CONCRETE, consult the Material Data Safety Sheet (MSDS) available upon request. PRODUCT NOTICE: Seller will not be held responsible for the final appearance of exposed aggregate, integral coloring, stamped and decorative surfacing, and all other forms of architectural and design concrete. DELIVERY NOTICE: Seller assumes no responsibility for deliveries beyond the public right of way. Buyer assumes responsibility for damages including but not limited to curb, sidewalk, driveway, or any property of the contractor or property owner or agents. NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE SAFETY AND HEALTH WARNING NOTICE AND ACCEPTANCE OF THE LOAD.

Release, Load and Terms Accepted By:

X





Form 3

Appendix 2, Pg 10 of 18

Project: Tests to Determine the
Behavior of Spliced #11 BarsCasting Documentation v.1
(Rev. 03/30/2012)Specimen: C4

Sheet 1 of 1

General Information					
Date	Disp Ticket Num	Truck No.	Time on Ticket	Time of Arrival	Temp. in Lab
FEB 02, 2016	11822042	1693	12:45	1:05	56
Measurements made upon arrival of concrete					
Slump (ASTM C143 - 10a)		Air Content (ASTM C231 - 10)			
Time ₁	Result ₁	Time ₁	Result ₁	S/N of Air Meter	
1:12	5 1/2"	1:18	3.9 %	5431265256 / LAF2	
Time ₂	Result ₂	Time ₂	Result ₂	S/N of Scale	
1:42	6"	1:35	3.8 %	H3802360	
Unit Weight (ASTM C138 - 10b)					
Time ₁	Wt. of Cont. ₁	Total Wt. ₁	Wt. of Conc. ₁	Result ₁ = Wt. of Conc./Vol. of Cont.	
1:16	8.45 lb	45.60 lb	37.15 lb	$37.15 \# / 0.25 \text{ ft}^3 = 148.6 \frac{\text{lb}}{\text{ft}^3}$	
Time ₂	Wt. of Cont. ₂	Total Wt. ₂	Wt. of Conc. ₂	Result ₂ = Wt. of Conc./Vol. of Cont.	
1:34	8.45 lb	44.50 lb	36.05 lb	$36.05 \# / 0.25 \text{ ft}^3 = 144.2 \frac{\text{lb}}{\text{ft}^3}$	
Times of actions during and after casting					
Layer 1 placed	Layer 1 vibration complete	Layer 2 placed	Layer 2 vibration complete	Top surface struck off	Truck Departing Lab
1:25	1:28	1:40	1:44	1:50	1:44
Lifting Inserts Placed	Covered with plastic	Plastic removed	Covered with burlap	Burlap doused with water	Covered with plastic
2:00	4:20	5:55	6:05	6:10	6:15
Recorded by		Signature		Date	Time
JASPAL S SAINI				02/02/16	4:15 PM
Checked by		Signature		Date	Time
S. PUJOL				2/2/16	4:15 PM
Checked by		Signature		Date	Time
Comments:					
CONC TEMP @ 1:13 = 70°F					
*The following ASTM standards and specifications will be followed during casting: C172-10, C192-07, C470-09					

C4

Appendix 2, Pg 11 of 18

Truck	Driver	User	Disp	Ticket Num	Ticket ID	Time	Date
1693	2774	user	11822042	0		12:45	2/2/16
Load Size	Mix Code	Returned	Qty	Mix Age	Seq	Load ID	
5.75 CYDS	4000CC				D	32429	

Description	Design Qty	Adj.T	Required	Batched	Actual Wat
Batch: 1 ----	Start: 12:45:26		End:	----- Time (hh:mm:ss):	: : ----
Buzzi	588 lb		3381 lb	3365 lb	
STONE-8	940 lb		5416 lb	5400 lb	1 gl
STONE-4	620 lb		3583 lb	3580 lb	2 gl
SAND-23	1435 lb		8664 lb	8680 lb	50 gl
WATER	317.9 lb		1386.7 lb	1376.0 lb	164.9 gl
MICROAIR	1.10 /C		37.19 oz	37.50 oz	

Actual	Num Batches: 1							
Load	22403 lb	Design W/C: 0.541	Water/Cement: 0.543 T	Design	219.0 gl	Actual	217.8 gl	To Add: 1.2 gl
Slump:	6.00 in	# Water in Truck: 0.0 lb	Adjust Water:	0.0 lb / Load	Trim Water:	0.0 lb /	CYL	

Concrete Delivery Ticket



Appendix 2, Pg 12 of 18

Plant #	Ticket Number	Truck	Load Size	Mix	Slump	Use	Date	Customer
110	11822012	1693	5.75cy	4000CC	6.00	TEST	02/02/16	112

Sold To	Tax Code	Driver	Project No.	Order No.
BOYEN LAB		RON HOWARD		

Delivery Address	P.O. Number
------------------	-------------

ON SOUTH RIVER ROAD AT THE LAB 3 YARD TEST LOAD 1ST THEN 5.75
 406-697-1743 TRUCK RELEASE

Job No.}

Time Printed 12:45

Load Quantity	Total	Ordered Quantity	Product Code	Product Description	Unit Price	Amount
5.75	23.00cy	34.50cy	4000CC	4000-A-C-LSTONE-CC	115.00	661.25





WINTER FEE 23.00
 ENVIRONMENTAL FEE 12.00

Water Added At Customer's Request		Total No. Gallons	Slump Meter Reading	900	Subtotal	696.25
On Job Time	Finish Pour Time	AUTH. #:	Grand Total:	2,979.96	Tax	48.74
					Total	744.99

PROPERTY DAMAGE RELEASE / WARNING - Irritating To The Skin and Eyes

Dear Customer - The Seller is not responsible for slumps, strength or quality of concrete to which water or any other material has been added by the purchaser or at his request. The undersigned hereby authorizes Irving Materials, Inc. to use private property for making the delivery shown here on and assumes full responsibility for any damage or injury due to the premises. The undersigned agrees to reimburse said Company for loss of time and equipment by reason of such delivery and also to identify and save harmless said Company from any and all claims, demands and suits for or on account of or in any manner caused by or arising from private property delivery. The undersigned assumes responsibility for a suitable roadway from public highway to point of delivery and is responsible for any needed wrecker service charges as a result. SAFETY WARNING: Keep away from children. Contains Portland Cement. Irritating to the skin and eyes. Wear rubber boots, gloves and eye protection. Prolonged contact may cause burns. In case of contact with skin or eyes, flush thoroughly with water. If irritation persists, get medical attention. For additional information regarding the HAZARDS OF READY MIX CONCRETE, consult the Material Data Safety Sheet (MSDS) available upon request. PRODUCT NOTICE: Seller will not be held responsible for the final appearance of exposed aggregate, integral coloring, stamped and decorative surfacing, and all other forms of architectural and design concrete. DELIVERY NOTICE: Seller assumes no responsibility for deliveries beyond the public right of way. Buyer assumes responsibility for damages including but not limited to curb, sidewalk, driveway, or any property of the contractor or property owner or agents. NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE SAFETY AND HEALTH WARNING NOTICE AND ACCEPTANCE OF THE LOAD.

Release, Load and Terms Accepted By:
X Bowen LAB






Form 3

Appendix 2, Pg 13 of 18

Project: Tests to Determine the
Behavior of Spliced #11 BarsCasting Documentation v.1
(Rev. 03/30/2012)Specimen: C5

Sheet 1 of 1

General Information					
Date	Disp Ticket Num	Truck No.	Time on Ticket	Time of Arrival	Temp. in Lab
FEB 02, 2016	11822044	1677	1:47	2:03	57
Measurements made upon arrival of concrete					
Slump (ASTM C143 - 10a)		Air Content (ASTM C231 - 10)			
Time ₁	Result ₁	Time ₁	Result ₁	S/N of Air Meter	
2:18	7 1/4"	2:16	4.4%	5431265256/AF2	
Time ₂	Result ₂	Time ₂	Result ₂	S/N of Scale	
2:48	6 1/2"	2:47	4.9%	H 380 2360	
Unit Weight (ASTM C138 - 10b)					
Time ₁	Wt. of Cont. ₁	Total Wt. ₁	Wt. of Conc. ₁	Result ₁ = Wt. of Conc./Vol. of Cont.	
2:15	8.45 lb	45.15 lb	36.7 lb	36.7# / 0.25 ft ³ = 146.8 $\frac{\text{lb}}{\text{ft}^3}$	
Time ₂	Wt. of Cont. ₂	Total Wt. ₂	Wt. of Conc. ₂	Result ₂ = Wt. of Conc./Vol. of Cont.	
2:46	8.45 lb	44.55 lb	36.1 lb	36.1# / 0.25 ft ³ = 144.4 $\frac{\text{lb}}{\text{ft}^3}$	
Times of actions during and after casting					
Layer 1 placed	Layer 1 vibration complete	Layer 2 placed	Layer 2 vibration complete	Top surface struck off	Truck Departing Lab
2:35	2:39	2:50	2:52	3:04	2:50
Lifting Inserts Placed	Covered with plastic	Plastic removed	Covered with burlap	Burlap doused with water	Covered with plastic
3:10	5:45	6:35	6:40	6:45	6:50
Recorded by		Signature		Date	Time
JASPAL S SAINI				02/02/16	4:20 PM
Checked by		Signature		Date	Time
 : S. PUOL				2/2/16	4:25 PM
Checked by		Signature		Date	Time
Comments:					
CONC TEMP @ 2:12 = 72°F					
*The following ASTM standards and specifications will be followed during casting: C172-10, C192-07, C470-09					

C5

Truck 1677	Driver 3304	User user	Disp Ticket Num. 11822044	Ticket ID 0	Time 13:47	Date 2/2/16
Load Size 5.75	Mix Code CYDS 4000CC	Returned	Qty	Mix Age	Seq D	Load ID 32431

Description	Design Qty	Adj.T	Required	Batched	Actual Wat
Batch: 1 ----	Start: 13:47:23		End:	----- Time (hh:mm:ss):	: : ----
Buzzi	588 lb		3381 lb	3375 lb	
STONE-8	940 lb		5416 lb	5400 lb	1 gl
STONE-4	620 lb		3583 lb	3600 lb	2 gl
SAND-23	1435 lb		8664 lb	8680 lb	50 gl
WATER	317.9 lb		1386.7 lb	1378.0 lb	165.1 gl
MICROAIR	1.10 /C		37.19 oz	37.00 oz	

Actual	Num Batches: 1							
Load	22435 lb	Design W/C: 0.541	Water/Cement: 0.542 T	Design	219.0 gl	Actual	218.1 gl	To Add: 0.9 gl
Slump:	6.00 in	# Water in Truck: 0.0 lb	Adjust Water:	0.0 lb / Load	Trim Water:	0.0 lb /	CYL	

Concrete Delivery Ticket

Appendix 2, Pg 15 of 18



Irving Materials, Inc.

Plant #	Ticket Number	Truck	Load Size	Mix	Slump	Use	Date	Customer
118	11020011	1877	5.75cy	4000CC	6.90	TEST	02/02/16	116

Sold To	Tax Code	Driver	Project No.	Order No.
CONCRETE LAB		CONCRETE WISE		1022

Delivery Address	P.O. Number
------------------	-------------

ON SOUTH RIVER ROAD AT THE LAB 3 YARD TEST LOAD 1ST THEN 5.75
 406-697-1743 TRUCK RELEASE

Job No.}

Time Printed 13:47

Load Quantity	Total	Ordered Quantity	Product Code	Product Description	Unit Price	Amount
5.75	28.75cy	34.50cy	4000CC	4000-A-C-LSTONE-CC	115.00	661.25



WINTER FEE 23.00
 ENVIRONMENTAL FEE 12.00

Water Added At Customer's Request		Total No. Gallons	Slump Meter Reading					Subtotal	696.25
On Job Time	Finish Pour Time	AUTH. #:	Grand Total:	3,724.95	Tax	48.74	Total	744.99	

PROPERTY DAMAGE RELEASE / WARNING - Irritating To The Skin and Eyes

Dear Customer - The Seller is not responsible for slumps, strength or quality of concrete to which water or any other material has been added by the purchaser or at his request. The undersigned hereby authorizes Irving Materials, Inc. to use private property for making the delivery shown here on and assumes full responsibility for any damage or injury due to the premises. The undersigned agrees to reimburse said Company for loss of time and equipment by reason of such delivery and also to identify and save harmless said Company from any and all claims, demands and suits for or on account of or in any manner caused by or arising from private property delivery. The undersigned assumes responsibility for a suitable roadway from public highway to point of delivery and is responsible for any needed wrecker service charges as a result.

SAFETY WARNING: Keep away from children. Contains Portland Cement. Irritating to the skin and eyes. Wear rubber boots, gloves and eye protection. Prolonged contact may cause burns. In case of contact with skin or eyes, flush thoroughly with water. If irritation persists, get medical attention. For additional information regarding the HAZARDS OF READY MIX CONCRETE, consult the Material Data Safety Sheet (MSDS) available upon request.




PRODUCT NOTICE: Seller will not be held responsible for the final appearance of exposed aggregate, integral coloring, stamped and decorative surfacing, and all other forms of architectural and design concrete.

DELIVERY NOTICE: Seller assumes no responsibility for deliveries beyond the public right of way. Buyer assumes responsibility for damages including but not limited to curb, sidewalk, driveway, or any property of the contractor or property owner or agents.

NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE SAFETY AND HEALTH WARNING NOTICE AND ACCEPTANCE OF THE LOAD.

Release, Load and Terms Accepted By:

X



Form 3

Appendix 2, Pg 16 of 18

Project: Tests to Determine the Behavior of Spliced #11 Bars

Casting Documentation v.1 (Rev. 03/30/2012)

Specimen: C6

Sheet 1 of 1

General Information					
Date	Disp Ticket Num	Truck No.	Time on Ticket	Time of Arrival	Temp. in Lab
PEB 02, 2016	11822046	1949	2:52	3:11	53
Measurements made upon arrival of concrete					
Slump (ASTM C143 - 10a)			Air Content (ASTM C231 - 10)		
Time ₁	Result ₁	Time ₁	Result ₁	S/N of Air Meter	
3:18	7"	3:22	4.3%	5431265256 LAF2	
Time ₂	Result ₂	Time ₂	Result ₂	S/N of Scale	
3:52	6 1/4"	3:37	4.8%	H3802360	
Unit Weight (ASTM C138 - 10b)					
Time ₁	Wt. of Cont. ₁	Total Wt. ₁	Wt. of Conc. ₁	Result ₁ = Wt. of Conc./Vol. of Cont.	
3:20	8.45 lb	45.30 lb	36.85 lb	36.85 # / 0.25 ft ³ = 147.4 ^{lb} / _{ft³}	
Time ₂	Wt. of Cont. ₂	Total Wt. ₂	Wt. of Conc. ₂	Result ₂ = Wt. of Conc./Vol. of Cont.	
3:35	8.45 lb	44.55 lb	36.10 lb	36.1 # / 0.25 ft ³ = 144.4 ^{lb} / _{ft³}	
Times of actions during and after casting					
Layer 1 placed	Layer 1 vibration complete	Layer 2 placed	Layer 2 vibration complete	Top surface struck off	Truck Departing Lab
3:32	3:37	3:50	3:55	4:04	3:53
Lifting Inserts Placed	Covered with plastic	Plastic removed	Covered with burlap	Burlap doused with water	Covered with plastic
4:10	6:45	7:25	7:30	7:35	7:40
Recorded by		Signature		Date	Time
JASPAL S SAINI				02/02/16	4:20 AM
Checked by		Signature		Date	Time
S. PWOL				2/2/16	4:25 PM
Checked by		Signature		Date	Time
Comments:					
CONC TEMP @ 3:18 = 70°F					
*The following ASTM standards and specifications will be followed during casting: C172-10, C192-07, C470-09					

Form 2

Form 2

Form 2

66

Truck	Driver	User	Disp Ticket Num	Ticket ID	Time	Date
1949	1395	user	11822046	0	14:52	2/2/16
Load Size	Mix Code	Returned	Qty	Mix Age	Seq	Load ID
5.75 CYDS	4000CC				D	32433

Description	Design Qty	Adj.T	Required	Batched	Actual Wat
Batch:	Start:	End:	End:	Time (hh:mm:ss):	
Buzzi	588 lb		3381 lb	3370 lb	
STONE-8	940 lb		5416 lb	5400 lb	1 gl
STONE-4	620 lb		3583 lb	3640 lb	2 gl
SAND-23	1435 lb		8664 lb	8680 lb	50 gl
WATER	317.9 lb		1386.7 lb	1376.0 lb	164.9 gl
MICROAIR	1.10 /C		37.19 oz	37.00 oz	

Actual		Num Batches:	1								
Load	22468 lb	Design W/C:	0.541	Water/Cement:	0.542 T	Design	219.0 gl	Actual	217.9 gl	To Add:	1.2 gl
Slump:	6.00 in	#	Water in Truck:	0.0 lb	Adjust Water:	0.0 lb / Load	Trim Water:	0.0 lb /	CYL		

Concrete Delivery Ticket

Appendix 2, Pg 18 of 18
imi
 Irving Materials, Inc.

Plant #	Ticket Number	Truck	Load Size	Mix	Slump	Use	Date	Customer
110	11022046	1743	5.75cy	4000CC	6.00	TEST	02/02/16	116

Sold To	Tax Code	Driver	Project No.	Order No.
BOB BOWEN LAB		THE TYGAE		1022

Delivery Address	P.O. Number
ON SOUTH RIVER ROAD AT THE LAB 3 YARD TEST LOAD 1ST THEN 5.75 406-697-1743 TRUCK RELEASE	

Job No.}

Time Printed 14:51

Load Quantity	Total	Ordered Quantity	Product Code	Product Description	Unit Price	Amount
5.75	34.50cy	34.50cy	4000CC	4000-A-C-LSTONE-CC	115.00	661.25



WINTER FEE 23.00
 ENVIRONMENTAL FEE 12.00

Water Added At Customer's Request	Total No. Gallons	Slump Meter Reading	Subtotal
		7.50	696.25
On Job Time	Finish Pour Time	AUTH. #:	Tax 48.74
		Grand Total:	Total 744.99

PROPERTY DAMAGE RELEASE / WARNING - Irritating To The Skin and Eyes

Dear Customer - The Seller is not responsible for slumps, strength or quality of concrete to which water or any other material has been added by the purchaser or at his request. The undersigned hereby authorizes Irving Materials, Inc. to use private property for making the delivery shown here on and assumes full responsibility for any damage or injury due to the premises. The undersigned agrees to reimburse said Company for loss of time and equipment by reason of such delivery and also to identify and save harmless said Company from any and all claims, demands and suits for or on account of or in any manner caused by or arising from private property delivery. The undersigned assumes responsibility for a suitable roadway from public highway to point of delivery and is responsible for any needed wrecker service charges as a result.



SAFETY WARNING: Keep away from children. Contains Portland Cement. Irritating to the skin and eyes. Wear rubber boots, gloves and eye protection. Prolonged contact may cause burns. In case of contact with skin or eyes, flush thoroughly with water. If irritation persists, get medical attention. For additional information regarding the HAZARDS OF READY MIX CONCRETE, consult the Material Data Safety Sheet (MSDS) available upon request.

PRODUCT NOTICE: Seller will not be held responsible for the final appearance of exposed aggregate, integral coloring, stamped and decorative surfacing, and all other forms of architectural and design concrete.

DELIVERY NOTICE: Seller assumes no responsibility for deliveries beyond the public right of way. Buyer assumes responsibility for damages including but not limited to curb, sidewalk, driveway, or any property of the contractor or property owner or agents.

NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE SAFETY AND HEALTH WARNING NOTICE AND ACCEPTANCE OF THE LOAD.

Release, Load and Terms Accepted By:



Project: Tests to Determine the Behavior of Spliced #11 Bars



Curing Documentation v.1 (Rev. 03/30/2012)

Appendix 3, Page 1 of 8
 Purdue University Bowen Laboratory
 Sheet 1 of 1

General Information		
Specimen(s)	Date	Specimen Age
C1-C6 all cylinders	2/2/16	After ^{directly} casting
	Time Beginning	Time Ending
	5:24	6:10
	Temperature inside Lab (deg. F)	
	55	

Description of Work Performed

Specimens + cylinders covered w/ plastic sheeting

Recorded by	Signature	Date	Time
Kinsey Skiller		2/2/16	6:10
Checked by	Signature	Date	Time
Will Palanis		2/2/16	6:10
Checked by	Signature	Date	Time

Comments:

*Test specimens and associated cylinders are to be cured under wet burlap for seven days

Project: Tests to Determine the Behavior of Spliced #11 Bars



Curing Documentation v.1
(Rev. 03/30/2012)

Appendix 3, Pg 2 of 8
Purdue University - Bowen Laboratory
Sheet 1 of 1

General Information		
Specimen(s)	Date	Specimen Age
C1-C6 all cylinders	2/2/16	After ^{directly} casting
	Time Beginning	Time Ending
	6:15	6:38
	Temperature inside Lab (deg. F)	
	55	

Description of Work Performed

Specimens + cylinders covered w/ damp burlap and plastic sheeting

Recorded by	Signature	Date	Time
Kinsy Skiller		2/2/16	6:40
Checked by	Signature	Date	Time
Will Pellalis		2/2/16	6:40
Checked by	Signature	Date	Time

Comments:

*Test specimens and associated cylinders are to be cured under wet burlap for seven days

Project: Tests to Determine the Behavior of Spliced #11 Bars


Curing Documentation v.1
(Rev. 03/30/2012)

Appendix 3, Pg 3 of 8
Purdue University - Bowen Laboratory
Sheet 1 of 1

General Information		
Specimen(s)	Date	Specimen Age
C1-C6 all cylinders	2/3/16	1 day
	Time Beginning	Time Ending
	10:05 am	10:25 am
	Temperature inside Lab (deg. F)	
	60	

Description of Work Performed

Specimens + cylinders doused w/ water and recovered.

Recorded by	Signature	Date	Time
Kinsley Skiller		2/3/16	10:25
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time

Comments:

*Test specimens and associated cylinders are to be cured under wet burlap for seven days

Project: Tests to Determine the Behavior of Spliced #11 Bars


Curing Documentation v.1
(Rev. 03/30/2012)

Appendix 3, Pg 4 of 8
Purdue University - Bowen Laboratory
Sheet 1 of 1

General Information		
Specimen(s)	Date	Specimen Age
C1 - C6 all cylinders	2/4/16	2 day
	Time Beginning	Time Ending
	9:45 am	10:12 am
	Temperature inside Lab (deg. F)	
	60	

Description of Work Performed

Specimens + cylinders burled doused w/ water and recovered w/ plastic sheeting

Recorded by	Signature	Date	Time
Kinsey Skiller		2/4/16	10:12
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time



Comments:

*Test specimens and associated cylinders are to be cured under wet burlap for seven days

Project: Tests to Determine the
Behavior of Spliced #11 Bars

Curing Documentation v.1
(Rev. 03/30/2012)

Appendix 3, Pg 5 of 8
Purdue University - Bowen Laboratory
Sheet 1 of 1

General Information			
Specimen(s)	Date	Specimen Age	
C1-C6 all cylinders	2/5/16	3 day	
	Time Beginning	Time Ending	
	10:30 am	9:15 pm	
	Temperature inside Lab (deg. F)		
	63		
Description of Work Performed			
<p>↔ specimens + cylinders doused w/ water</p> <p>↔ forms struck within casting times</p> <p>↔ cylinders stripped, placed next to specimens on tarp</p> <p>↔ specimens + cylinders covered w/ burlap and sheeting post form striking</p>			
Recorded by	Signature	Date	Time
Kinsay Skiller		2/5/16	9:15
Checked by	Signature	Date	Time
WKL POLLALIS		2/5/16	9:16
Checked by	Signature	Date	Time
Comments:			
*Test specimens and associated cylinders are to be cured under wet burlap for seven days			

Project: Tests to Determine the Behavior of Spliced #11 Bars


Curing Documentation v.1
(Rev. 03/30/2012)

Appendix 3, Pg 6 of 8
Purdue University - Bowen Laboratory
Sheet 1 of 1

General Information		
Specimen(s)	Date	Specimen Age
C1-C6 All cylinders	2/6/16	4 day
	Time Beginning	Time Ending
	2:00 pm	2:30
	Temperature inside Lab (deg. F)	
	62	

Description of Work Performed

Specimens + cylinders burled doused w/ water and recovered w/ plastic sheeting

Recorded by	Signature	Date	Time
Kinsey Skiller		2/6/16	2:30
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time

Comments:

*Test specimens and associated cylinders are to be cured under wet burlap for seven days

Project: Tests to Determine the Behavior of Spliced #11 Bars


Curing Documentation v.1
(Rev. 03/30/2012)

Appendix 3, Pg 7 of 8
Purdue University - Bowen Laboratory
Sheet 1 of 1

General Information		
Specimen(s)	Date	Specimen Age
C1-C6 all cylinders	2/8/16	6 day
	Time Beginning	Time Ending
	9:35 am	10:00 am
	Temperature inside Lab (deg. F)	
	58	

Description of Work Performed

Specimens + cylinders deized w/ water and covered w/ plastic sheeting.

Recorded by	Signature	Date	Time
Kinsley Skiller		2/8/16	10:00 am
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time

Comments:

*Test specimens and associated cylinders are to be cured under wet burlap for seven days

Project: Tests to Determine the Behavior of Spliced #11 Bars



Curing Documentation v.1
(Rev. 03/30/2012)

Appendix 3, Pg 8 of 8
Purdue University - Bowen Laboratory
Sheet 1 of 1

General Information		
Specimen(s)	Date	Specimen Age
C1 - C6 all cylinders	2/9/16	7 day
	Time Beginning	Time Ending
	3:00 pm	4:15 pm
	Temperature inside Lab (deg. F)	
	60	

Description of Work Performed

7 day Curing complete, Specimens and cylinders uncovered from wet burlap and plastic sheeting

Recorded by	Signature	Date	Time
Kinsy Skiller		2/9/16	4:15
Checked by	Signature	Date	Time
Will PELLALIS		2/9/16	4:15
Checked by	Signature	Date	Time

Comments:

*Test specimens and associated cylinders are to be cured under wet burlap for seven days

SOLD PRIMESOURCE BUILDING PRODUCTS
 4316 W MINNESOTA ST
TO: INDIANAPOLIS, IN 46241-



CERTIFIED MILL TEST REPORT

Ship from:
 MTR #: 0000046153
 Nucor Steel Marion, Inc.
 912 Cheney Avenue
 Marion, OH 43302
 7403834011

Date: 1-Dec-2015
 B.L. Number: 402908
 Load Number: 136352

SHIP PRIMESOURCE BUILDING PRODUCTS
 J&K Supply
TO: 3515 Coleman Ct
 LAFAYETTE, IN 47905-

Material Safety Data Sheets are available at www.nucorbar.com or by contacting your inside sales representative.

NBMG-08 January 1, 2012

LOT # HEAT #	DESCRIPTION	PHYSICAL TESTS					CHEMICAL TESTS							C.E.
		YIELD P.S.I.	TENSILE P.S.I.	ELONG % IN 8"	BEND	WT% DEF	C Ni	Mn Cr	P Mo	S V	Si Cb	Cu Sn		
PO# => MR1510554501 MR15105545	1040-4500197870 Nucor Steel - Marion, Inc. 13/#4 Rebar 20' A615M GR420 (Gr60) ASTM A615/A615M-14 GR 60[420] AASHTO M31-07	67,100 463MPa	104,100 718MPa	12.0%	OK	-4.5% .031	.40 .14	1.04 .20	.018 .048	.043 .003 0	.21 .00	.36		
PO# => MR1510603601 MR15106036	1040-4500197870 Nucor Steel - Marion, Inc. 16/#5 Rebar 20' A615M GR420 (Gr60) ASTM A615/A615M-15 GR 60[420] AASHTO M31-07	66,900 461MPa	104,500 721MPa	13.2%	OK	-4.6% .038	.40 .13	1.07 .19	.015 .047	.031 .005	.15 .002	.35		
PO# => MR1510603701 MR15106037	1040-4500197870 Nucor Steel - Marion, Inc. 16/#5 Rebar 20' A615M GR420 (Gr60) ASTM A615/A615M-15 GR 60[420] AASHTO M31-07	65,800 454MPa	103,200 712MPa	12.0%	OK	-5.0% .038	.41 .13	1.03 .20	.017 .046	.038 .005	.20 .002	.34		

I hereby certify that the material described herein has been manufactured in accordance with the specifications and standards listed above and that it satisfies those requirements.
 1.) Weld repair was not performed on this material.
 2.) Melted and Manufactured in the United States.
 3.) Mercury, Radium, or Alpha source materials in any form have not been used in the production of this material.

QUALITY ASSURANCE: Ignatius Okafor

NUCOR
NUCOR STEEL KANKAKEE, INC.

Mill Certification
7/17/2015

Appendix 4, Pg 2 of 2 R #: 0000080668
 NUCOR STEEL KANKAKEE, INC.
 One Nucor Way
 Bourbonnais, IL 60914-4127
 (815) 937-3131
 Fax: (815) 939-5599

Sold To: AMBASSADOR STEEL FAB LLC
 PO BOX 627
 AUBURN, IN 46706
 (260) 927-3075
 Fax: (765) 455-4225

Ship To: AMBASSADOR STEEL CORP
 149 SYCAMORE LANE
 MOORESVILLE, IN 46158
 (317) 834-3434

Customer P.O.	0000161822	Sales Order	312954.23
Product Group	Rebar	Part Number	900000367204200
Grade	ASTM A615/A615M-14 GR 60[420] AASHTO M31-07	Lot #	KN1510386801
Size	36/#11 Rebar	Heat #	KN15103868
Product	36/#11 Rebar 60' A615M GR420 (Gr60)	B.L. Number	K1-505038
Description	A615M GR 420 (Gr60)	Load Number	K1-5161822
Customer Spec		Customer Part #	MARKET

I hereby certify that the material described herein has been manufactured in accordance with the specifications and standards listed above and that it satisfies those requirements.

Roll Date: 6/30/2015 Melt Date: 6/25/2015 Qty Shipped LBS: 38,255 Qty Shipped Pcs: 120

Melt Date: 6/25/2015

C	Mn	P	S	Si	Cu	Ni	Cr	Mo	V	Cb	CEA706
0.38%	1.08%	0.013%	0.048%	0.20%	0.29%	0.18%	0.11%	0.057%	0.0165%	0.000%	0.58%

CEA706: A706 CARBON EQUIVALENT

Roll Date: 6/30/2015

Yield 1: 69,379psi
 End OK

Tensile 1: 105,322psi
 Weight Variation -004.0%

Elongation: 13.25% in 8" (% in 203.3mm)
 Avg Deformation Height: 0.077in

Specification Comments:

ALL MANUFACTURING PROCESSES OF THE STEEL MATERIALS IN THIS PRODUCT, INCLUDING MELTING, HAVE OCCURRED WITHIN THE UNITED STATES. ALL PRODUCTS PRODUCED ARE WELD FREE. MERCURY, IN ANY FORM, HAS NOT BEEN USED IN THE PRODUCTION OR TESTING OF THIS MATERIAL.

Matt Luymes

Matt Luymes

Division Metallurgist

Calculation of Moment and Stresses

$$b := \left(17 + \frac{5}{8}\right) \text{in}$$

Width

$$h := 30 \text{in}$$

Height

$$c := 5.7 \text{in}$$

Cover to centroid of reinforcement

$$d := h - c = 24.3 \cdot \text{in}$$

Effective depth

$$A_s := 2 \cdot 1.56 \text{in}^2$$

Area of steel outside the splice

$$\rho := \frac{A_s}{b \cdot d} = 0.73\%$$

Reinforcement ratio outside splice region

$$A_{sp} := 4 \cdot 1.56 \text{in}^2 = 6.24 \cdot \text{in}^2$$

Area of steel in spliced region

$$\rho_{sp} := \frac{A_{sp}}{b \cdot d} = 1.46\%$$

Reinforcement ratio inside splice region

$$f_c := 5500 \text{psi}$$

Concrete compressive strength
Assuming the average of the 6 tests which varied
between 5200psi and 5900psi

$$E_c := 57000 \cdot \sqrt{f_c \cdot \text{psi}} = 4.2 \times 10^3 \cdot \text{ksi}$$

Modulus of elasticity of concrete

$$E_s := 29000 \text{ksi}$$

Modulus of elasticity of steel

$$n := \frac{E_s}{E_c} = 6.9$$

Modular ratio

Calculating Moments

Contribution of self weight

$$\gamma := 150 \frac{\text{lb}}{\text{ft}^3}$$

Unit weight of concrete

$$w := \gamma \cdot b \cdot h = 0.55 \frac{\text{kip}}{\text{ft}}$$

Self weight per foot

$$L_T := 34\text{ft} + 4\text{in} = 412\text{in}$$

Total length of beam

$$L_S := 151\text{in}$$

Span between supports

$$L_{LP} := 9\text{ft} + 8.5\text{in} = 116.5\text{in}$$

$$L_{\text{end}} := \frac{L_T - L_S}{2} = 130.5\text{in}$$

Distance from support to load point
Distance from end to support

$$M(x) := \frac{w \cdot L_T}{2} \cdot (x - L_{\text{end}}) - w \cdot \left(\frac{x^2}{2} \right)$$

$$M_{\text{supp_SW}} := -M(L_{\text{end}}) = 32.6 \cdot \text{kip} \cdot \text{ft}$$

Moment at support due to SW

$$M_{\text{sup_SW}} := \frac{1}{2} \cdot L_{\text{end}} \cdot (w \cdot L_{\text{end}}) = 32.6 \cdot \text{kip} \cdot \text{ft}$$

Check

$$M_{\text{splice_SW}} := -M(L_{\text{end}} + 36\text{in}) = 24.7 \cdot \text{kip} \cdot \text{ft}$$

Moment at splice end due to SW

Applied LoadAt load point

$$P_{\text{hw}} := (2 \cdot 42 + 118 + 79 + 52 + 2 \cdot 65 + 2 \cdot 31) \text{lb} = 0.53 \cdot \text{kip} \text{Weight of hardware}$$

$$P_{\text{jack}} := \begin{pmatrix} 39.7 \\ 40 \\ 40.4 \\ 40.9 \\ 40.2 \\ 40.7 \end{pmatrix} \text{kip}$$

Load from hydraulic jacks

$$P_{\text{app}} := P_{\text{hw}} + P_{\text{jack}}$$

Total load applied at load point

Clamps

$$w_{\text{clamp}} := \frac{12 \cdot 66 \text{ lbf}}{L_{\text{end}}} = 0.073 \cdot \frac{\text{kip}}{\text{ft}}$$

$$M_{\text{clamp}} := \frac{1}{2} L_{\text{end}} \cdot w_{\text{clamp}} \cdot L_{\text{end}} = 4.3 \cdot \text{kip} \cdot \text{ft}$$

Assume the weight of 12 clamps is distributed uniformly from end of beam to support

Constant between supports

Maximum moment at support and splice end

$$i := 0..5$$

$$M_{\text{supp}_i} := (P_{\text{app}_i}) \cdot L_{\text{LP}} + M_{\text{supp_SW}} + M_{\text{clamp}}$$

$$M_{\text{supp}} = \begin{pmatrix} 427 \\ 430 \\ 434 \\ 439 \\ 432 \\ 437 \end{pmatrix} \cdot \text{kip} \cdot \text{ft}$$

$$M_{\text{splice}_i} := (P_{\text{app}_i}) \cdot L_{\text{LP}} + M_{\text{splice_SW}} + M_{\text{clamp}}$$

$$M_{\text{splice}} = \begin{pmatrix} 419 \\ 422 \\ 426 \\ 431 \\ 424 \\ 429 \end{pmatrix} \cdot \text{kip} \cdot \text{ft}$$

Estimating Stress in Steel at Support and Splice End

$$k := \sqrt{\rho^2 \cdot n^2 + 2 \cdot \rho \cdot n} - \rho \cdot n = 0.27$$

$$j := 1 - \frac{k}{3} = 0.91$$

$$M = A_s \cdot f_s \cdot j \cdot d$$

$$f_s = \frac{M}{A_s \cdot j \cdot d}$$



$$f_{s_supp_i} := \frac{M_{supp_i}}{A_s \cdot j \cdot d}$$

$$f_{s_sp_i} := \frac{M_{splice_i}}{A_s \cdot j \cdot d}$$

$$f_{s_supp} = \begin{pmatrix} 74.3 \\ 74.8 \\ 75.5 \\ 76.4 \\ 75.2 \\ 76 \end{pmatrix} \cdot \text{ksi}$$

$$f_{s_sp} = \begin{pmatrix} 73 \\ 73.5 \\ 74.1 \\ 75 \\ 73.8 \\ 74.7 \end{pmatrix} \cdot \text{ksi}$$

Crack width $\times 10^{-3}$ (in)



Specimen: C1

Average Load: 14.5^k

Average Deflection: .08"

Sheet:

1

of

1

Drawn by:


KS

Checked by:


Date:

3/21/16

Crack width $\times 10^{-3}$ (in)




Note: diam Crack Widths @ root of crack
: Vert. Crack @ top




Specimen: C1	Sheet: 1	of 1
Average Load: 23.2 ^k	Drawn by: KS	Checked by:
Average Deflection: .16 in	Date:	

Crack width $\times 10^{-3}$ (in)




Specimen: C1	Sheet: 1	of 1
Average Load: 31.5 ^k	Drawn by: KS	Checked by: LL
Average Deflection: .24 in	Date:	



largest long crack =




Specimen:	C1	Sheet:	1	of	1
Average Load:	35.6 k	Drawn by:	KS	Checked by:	
Average Deflection:	.32 in	Date:			




Specimen: C1	Sheet: 1	of 1
Average Load: OK (unload)	Drawn by: KS	Checked by:
Average Deflection: .163 in.	Date:	


Crack Width
 $\times 10^{-3}$





Specimen: C2	Sheet: 1	of 1
Average Load: 14.1k	Drawn by: KS	Checked by:
Average Deflection: 0.08 in	Date: 3/28/16	




Specimen:	C2	Sheet:	1	of	1
Average Load:	22.8 k	Drawn by:	KS	Checked by:	
Average Deflection:	.16 in	Date:	3/28/16		



Specimen: C2	Sheet: 1	of 1
Average Load: 31.1 k	Drawn by: KS	Checked by:
Average Deflection: .24 in	Date: 3/28/16	




Specimen:	C2	Sheet:	1	of	1
Average Load:	35.9 K	Drawn by:	KS	Checked by:	
Average Deflection:	.32 in	Date:	3/28/16		




Specimen: C2	Sheet: 1 of 1
Average Load: 0 ^k (unload)	Drawn by: KS Checked by:
Average Deflection: 0.16 in	Date: 3/28/16

Crack Widths
 $\times 10^{-3}$ (in)




Target 49 no-grad, kicked off
 (70)





Specimen: C3	Sheet: 1	of 1
Average Load: 15.2 K	Drawn by: KS	Checked by:
Average Deflection: .08 in	Date: 4/4/16	

Crack Widths
x 10⁻³ (in)





Specimen:	C3	Sheet:	1	of	1
Average Load:	23.6 k	Drawn by:	KS	Checked by:	
Average Deflection:	0.16 k	Date:	4/4/16		

Crack widths
 $\times 10^{-3}$ (in)




Specimen: C3	Sheet: 1 of 1
Average Load: 32.6 ^k	Drawn by: KS Checked by:
Average Deflection: .24 in	Date: 4/4/16

Crack widths
 $\times 10^{-3}$ (in)




Specimen:	C3	Sheet:	1	of	1
Average Load:	36.6 K	Drawn by:	RS	Checked by:	
Average Deflection:	.32 in	Date:	4/4/16		

Crack widths
 $\times 10^{-3}$ (in)




Specimen:	C3	Sheet:	1	of	1
Average Load:	OK unload	Drawn by:		Checked by:	
Average Deflection:	.16 in	Date:	4/4/16		


{ All Crack Widths }
 $\times 10^{-3}$ in }




Specimen: C4	Sheet: 1	of 1
Average Load: 15.2 K	Drawn by: KS	Checked by:
Average Deflection: 0.08 in	Date: 4/11/16	




Specimen:	C4	Sheet:	1	of	1
Average Load:	23.8 k	Drawn by:	KS	Checked by:	
Average Deflection:	0.16 in	Date:	4/11/16		





Specimen:	C4	Sheet:	1	of	1
Average Load:	32.6 ^k	Drawn by:	RS	Checked by:	
Average Deflection:	0.24 in	Date:	4/11/16		



Specimen: 04	Sheet: 1	of 1
Average Load: 36.6 K	Drawn by: KS	Checked by:
Average Deflection: 0.32 in	Date: 4/11/16	




Specimen: C4	Sheet: 1	of 1
Average Load: 37.8 k	Drawn by: KS	Checked by:
Average Deflection: 0.40 in	Date: 4/11/16	




Specimen: C4	Sheet: 1	of 1
Average Load: 35.1 ^K Reload	Drawn by: KS	Checked by:
Average Deflection: 0.48 in	Date: 4/11/16	


{ All crack widths
x 10⁻³ (in) }





Specimen: C5	Sheet: 1	of 1
Average Load: 15.5 ^k	Drawn by: KS	Checked by:
Average Deflection: 0.08 in	Date: 4/12/16	





Specimen: C5	Sheet: 1	of 1
Average Load: 24.4K	Drawn by: KS	Checked by:
Average Deflection: 0.10 in	Date: 4/12/16	





Specimen: C5	Sheet: 1	of 1
Average Load: 33.3K	Drawn by: KS	Checked by:
Average Deflection: 0.24 in.	Date: 4/12/16	



Specimen:	Cs	Sheet:	1	of	1
Average Load:	36 k	Drawn by:	KS	Checked by:	
Average Deflection:	0.32 in	Date:	4/12/16		




Specimen:	C5	Sheet:	1	of	1
Average Load:	37.2 ^k	Drawn by:	KS	Checked by:	
Average Deflection:	0.40 in	Date:	4/12/16		





Specimen: 05	Sheet: 1	of 1
Average Load: 37.2 k \rightarrow Unload	Drawn by: KS	Checked by:
Average Deflection: 0.16 in	Date: 4/12/16	



{ All crack widths }
x 10⁻³




Specimen: C6	Sheet: 1	of 1
Average Load: 14.5k	Drawn by: KS	Checked by:
Average Deflection: 0.08 in.	Date: 4/14/16	





Specimen: C6	Sheet: 1	of 1
Average Load: 23.7 K	Drawn by: KS	Checked by:
Average Deflection: 0.16 in.	Date: 4/14/16	





Specimen: CG	Sheet: 1	of 1
Average Load: 32.6 k	Drawn by: KS	Checked by:
Average Deflection: 0.24 in.	Date: 4/4/16	





Specimen:	06	Sheet:	1	of	1
Average Load:	36.2 k	Drawn by:	KS	Checked by:	
Average Deflection:	0.32 k	Date:	4/4/16		



Specimen: CG	Sheet: 1	of 1
Average Load: 37.3 ^k	Drawn by: KS	Checked by:
Average Deflection: 0.40 in	Date: 4/14/16	



Specimen:	C6	Sheet:	1	of	1
Average Load:	38.5 K	Drawn by:	KS	Checked by:	
Average Deflection:	0.50 in	Date:	4/14/16		



Specimen: <i>CG</i>	Sheet: 1	of 1
Average Load: <i>38.5^k → unload</i>	Drawn by: <i>KS</i>	Checked by:
Average Deflection: <i>0.23 in</i>	Date: <i>4/14/16</i>	

Tests to Determine the Behavior of #11 Bars with Lap Splices – TEST SERIES C

Bowen Laboratory

Purdue University

April 8, 2016

Test Procedure

This procedure refers to the test described in the proposal titled *Experimental Study of The Effect of Laminar Cracks on Strength and Ductility 79-in Splices of #11 Reinforcing Bars submitted to First Energy Corporation. Parameters for performance of tests are specified in this document.*

1. Fabrication

1.1 Formwork

The formwork shall be made using non-absorbent plywood. Its interior shall be caulked to prevent water leakage and it shall be covered with a thin layer of oil before casting. The dimensions of the formwork shall be checked and recorded using Form 1.

1.2 Reinforcement Cages

The steel reinforcement cages shall be built following the same drawings and forms used for test Series B (attached). Reinforcing bars shall be supported by steel chairs placed away from lap splices. To ensure alignment, the bars shall be tied to chairs and to one another using gage-16 steel wire. The location of the reinforcement shall be recorded using Form 1. The locations of wire ties and rebar markings shall be recorded using Form 2.

Tolerances (within the test region) are:

3/16" for horizontal cover and horizontal spacing measured to the surface of the bar (excluding ribs)

1/4" for vertical distances shown in Form 1

1.3 Casting

Fresh concrete properties to be measured include:

Unit Weight

Slump

Air Content

REV 02

These measurements shall be made following the Specifications and recorded using Form 3.

Slump shall be measured before any other activity related to casting takes place to make sure that the delivered mix has satisfactory workability. The mixing truck shall deliver a ticket with the batched mix weights. These weights shall be examined to corroborate that the delivered mix has the specified proportions. Concrete shall not be accepted if it arrives more than 45 min. after leaving the batching plant. No water shall be added to the mix after the truck leaves the plant.

Specimens and cylinders shall be cast and vibrated in two lifts following the Specifications. The vibrators to be used shall have the following cross-sectional dimensions:

For cylinders: 3/4" - 7/8"
For Larger Specimens: 1-3/4"

Their frequencies shall be between 50 and 200 Hz.

Excess concrete shall be removed off the formwork. The exposed surfaces of the specimens shall be finished using cast magnesium floats. Lifting inserts shall be inserted in the fresh concrete as soon as the finishing is completed.

Each test beam shall be cast using concrete from a single mixing truck. A complete set of concrete samples (cylinders) shall be obtained from each truck. Test beams and samples shall be marked with a number referring to the truck from which they were cast and the date of casting. In each casting day, trucks shall be numbered sequentially starting at 1. The number assigned to a truck shall be written clearly on the mix ticket describing the mix proportions for the batch. Test beams shall be cast and tested oriented in the North-South axis of the laboratory.. Beam ends facing North during casting shall face North during testing. During finishing, the North end of each beam shall be marked with the letter N.

These activities shall be documented using Form 3.

1.4 Curing

As soon as casting is completed all specimens shall be covered with impermeable sheets. When the concrete surface sets, wet burlap shall be inserted between these sheets and the exposed concrete. All formwork and molds shall be struck no later than three days after the cast.

All exposed concrete surfaces shall be covered by wet burlap and impermeable sheets for a total of at least seven days after casting.

REV 02

Burlap shall be doused with water at least every other day during the curing period.

Curing activities shall be logged using Form 4.

Test cylinders shall be stored and cured next to the test specimens and under similar conditions of temperature and humidity.

The variation of concrete strength with time shall be monitored as specified in the Specifications. The results of cylinder tests shall be recorded using Form 5.

2. Calibration

Three types of measurements will be made: displacement, force, air content.

The apparatuses to be used to calibrate sensors to measure these quantities are:

Displacement Sensors: INSTRON Universal Testing Machine (S.N.: _____)
Load Sensors: INSTRON Universal Testing Machine (S.N.: _____)
Air Content: Calibrated Cylinder (S.N.: _____)

Load and displacement sensors will be calibrated following steps listed below:

- 1) Connect the sensor to the data-acquisition system that is going to be used in the test
- 2) Set and record the excitation voltage to the maximum possible value (not exceeding the maxima specified for the data-acquisition system and the sensor)
- 3) Set the data-acquisition equipment to record voltage
- 4) Set the gain of the data-acquisition system to the first available level lower than the ratio of the maximum range of the system to the maximum expected output from the sensor.
- 5) Mount the sensor on the universal testing machine
- 6) Apply a series of known displacement or force increments to the sensor ranging between 10% and 90% of the rated capacity of the sensor
- 7) Record the voltage read on the data-acquisition system at each known displacement or force increment
- 8) Create a plot of change in output voltage vs. change in force or displacement
- 9) Fit a line to the plot from 7) using "least squares"
- 10) Record the slope of the line from 8) (sensor sensitivity)
- 11) Label the cable used in the calibration with the serial number of the sensor

Sensors shall be calibrated before the first test and after the final test.

REV 02

The apparatus used to measure air content of the fresh concrete shall be calibrated following the procedure described in ASTM standard 231. Form 6B shall be used to document the calibration.

All calibrations shall be performed by at least two persons: one leading each step and the other checking the work of the first independently. A log of each calibration shall be made using Form 6 and it shall include an estimate of the accuracy of the sensor.

Sensors for which the sensitivity obtained in 9) above deviates by more than 10% from the nominal sensitivity (as reported by the manufacturer) shall not be used in any of the tests.

3. Setup

Each test beam shall be placed on two roller supports as described in the attached proposal. The final location of the supports shall be measured (to the nearest 1/16 in.) and reported using Form 7. The maximum deviation from nominal setup dimensions shall be 1/4 in. As-built external dimensions of each test beam shall be recorded using the same form. The maximum deviation from nominal dimensions in the test region shall be 1/4 in.

The test beam shall be placed with the reinforcement facing up as shown in the attached proposal.

The shear spans shall be reinforced with external stirrups (pairs of 5/8-in threaded rods) installed at a spacing not exceeding 12 in. The locations of the stirrups shall be measured. The measurements shall be recorded using Form 7.

The loading rigs (consisting of a loading tube, two hydraulic rams, two threaded rods, plates and nuts, and one load cell per rig) shall be placed on the test specimen and connected to "the strong floor" of the laboratory (without applying load to the specimen other than the weight of the rigs) as described in the attached proposal. The rams in each rig shall be connected to a single manifold and pump using 10,000-psi hydraulic hoses. All hoses and other hydraulic hardware shall be inspected visually and replaced -if defective- before testing.

4. Instrumentation

Displacement sensors shall be installed at midspan, at each support, and at each load point. They shall be secured to the strong floor of the laboratory directly below the point where displacement is to be measured.

All sensors (displacement and force) shall be connected to the data acquisition system using the same cables used during calibration. The excitation voltage and gain shall also be set to the value used in calibration. The data acquisition system

REV 02

shall be set to record voltage changes caused by loading. Before applying load with the hydraulic rams, all sensors shall be set to read a voltage value between 10% and 90% of the voltage output of the sensor at its rated capacity. These voltages shall be referred to as the “zero offsets” of the sensors. If a sensor is set to have an initial voltage exceeding 20% of its output at rated capacity, the sign of the initial “zero offset” shall be opposite to the sign of the expected change in its signal.

Set the data acquisition system to scan all sensors and save at least one record per sensor every 1 sec.

Record a file of “zero offsets” capturing at least 10 min. of data before any load is applied with the hydraulic system.

Means of initial voltages for all sensors (mean “zero offsets”), sensor serial numbers, the most recent sensitivity constants, excitation voltages, and the channels of the data-acquisition system used for each sensor shall be recorded using Form 8. The pairing of channels and sensors shall be checked by a second person working independently from the person making the initial connections.

Infrared targets to be used to measure displacements as described in the attached proposal shall be glued to one face of the test beam using epoxy adhesive. The numbering sequence of these targets shall be recorded using Form 9.

Video cameras (one for long-time lapse video and one for high-speed video) will be positioned to capture the response of the mid third of each specimen. To the extent possible, the location of the cameras shall be the same in all tests.

5. Testing

The following actions shall take place during each test:

At the end of each loading increment:

Mark Cracks: all visible cracks shall be marked using black permanent markers. Cracks shall be marked by drawing lines parallel to them and with an offset of approximately 0.25 in.

Measure Crack Widths: Crack widths shall be measured using crack comparators or graduated handheld microscopes.

Measure coordinates of infrared coordinates: A set of coordinates shall be obtained using an OptoTrak System 600 Pro. A set of four targets shall be attached to the strong floor. They shall be located at approximately the same distance to the OptoTrak cameras as targets attached to the test beam. Coordinates for

REV 02

these reference targets shall be obtained at each loading increment. They are to be used to monitor the stability of the OptoTrak system by computing the variation in the distances between reference targets.

In-Test Data Backup: At every loading increment the data being produced by the data-acquisition system shall be copied to an external hard drive or USB memory.

Photographs: a set of high-resolution photographs shall be obtained after cracks are marked at each loading increment. The photographs shall include views of both elevations of the test beam and the top concrete surface above lap splices.

The following data shall be recorded throughout each test:

Sensor readings: to be recorded on a hard drive in volts. Conversion to engineering units shall be done after the test as follows:

- Subtract zero offsets
- Divide the result by the sensitivity obtained in the most recent calibration

Lapse video photographs: to be obtained every 5 min..

Actions to be taken at failure

Trigger high-speed camera to record breaking away of the concrete cover and relative movement of the bars.

Actions to be taken after test

Generate a record of sensors that may have malfunctioned or been accidentally moved during the test

Remove from all files recordings from sensors for which the results of the after-test calibration differ by more than 5% from the before-test calibration.

The referenced proposal states:

“The first loading is planned to be to a deflection at mid-span of 0.4 in. Previous investigation has shown that at that deflection the laminar cracks are likely to exceed a width of 0.03 in. The load will then be taken off and reapplied until failure is obtained.”

If deemed safe during testing, extending the first loading to a larger mid-span deflection shall be allowed.

REV 02

6. Reporting and Backup

Produce all the captured data in two ways:


By uploading data, photos, and video to datacenterhub.org or [ftp.ecn.purdue.edu](ftp://ecn.purdue.edu).

By recording all data, photos, and video on a magnetic hard drive


Reports shall be produced as described in the Specifications.

DRAWINGS AND FORMS

Form 1



Section A-A




*For section B-B through F-F see Sheet 3 of 3

Series B




Drawing:	Series B Formwork As-builts	Sheet:	2	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

Form 1



Section C-C, D-D, & E-E
*Facing North



Section B-B & F-F
*Facing North



Drawing:	Formwork As-built Sections	Sheet:	3	of	3
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

Form 1

Project: Tests to Determine the Behavior of Spliced #11 Bars

As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: _____

Section	Formwork As-built Dimensions							
	1	2	3	4	5	6	7	8
A-A								
B-B								
C-C								
D-D								
E-E								
F-F								
Recorded by:			Signature				Date	Time
Checked by:			Signature				Date	Time
Checked by:			Signature				Date	Time

Comments:

*See formwork as-built drawings for dimension locations

Form 1

Project: Tests to Determine the
Behavior of Spliced #11 BarsAs-built Dimensions v.1
(Rev. 04/04/2012)


Specimen: _____

Sheet 2 of 2

Section	Formwork As-built Dimensions Key - Series A							
	1	2	3	4	5	6	7	8
A-A	14'-6"	10'-0"	14'-6"	14'-6"	10'-0"	14'-6"	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
D-D	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
E-E	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
F-F	3"	8-3/4"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
Section	Formwork As-built Dimensions Key - Series B							
	1	2	3	4	5	6	7	8
A-A	13'-10.5"	6'-7"	13'-10.5"	13'-10.5"	6'-7"	13'-10.5"	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
D-D	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
E-E	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
F-F	3"	8-3/4"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"


Form 2

Wire Ties



NORTH

Bar Marks



NORTH



Specimen:					
Project:	Behavior of Lap Splices of No. 11 Reinforcing Bars	Drawn by:		Checked by:	
		Date:			

Project: Tests to Determine the
Behavior of Spliced #11 Bars

Casting Documentation v.1
(Rev. 03/30/2012)

Specimen: _____

Sheet 1 of 1

General Information					
Date	Disp Ticket Num	Truck No.	Time on Ticket	Time of Arrival	Temp. in Lab
Measurements made upon arrival of concrete					
Slump (ASTM C143 - 10a)		Air Content (ASTM C231 - 10)			
Time ₁	Result ₁	Time ₁	Result ₁	S/N of Air Meter	
Time ₂	Result ₂	Time ₂	Result ₂	S/N of Scale	
Unit Weight (ASTM C138 - 10b)					
Time ₁	Wt. of Cont. ₁	Total Wt. ₁	Wt. of Conc. ₁	Result ₁ = Wt. of Conc./Vol. of Cont.	
Time ₂	Wt. of Cont. ₂	Total Wt. ₂	Wt. of Conc. ₂	Result ₂ = Wt. of Conc./Vol. of Cont.	
Times of actions during and after casting					
Layer 1 placed	Layer 1 vibration complete	Layer 2 placed	Layer 2 vibration complete	Top surface struck off	Truck Departing Lab
Lifting Inserts Placed	Covered with plastic	Plastic removed	Covered with burlap	Burlap doused with water	Covered with plastic
Recorded by		Signature		Date	Time
Checked by		Signature		Date	Time
Checked by		Signature		Date	Time
Comments:					
*The following ASTM standards and specifications will be followed during casting: C172-10, C192-07, C470-09					

Project: Tests to Determine the Behavior of Spliced #11 Bars

Curing Documentation v.1 (Rev. 03/30/2012)

Purdue University - Bowen Laboratory Sheet 1 of 1

General Information			
Specimen(s)	Date	Specimen Age	
	Time Beginning	Time Ending	
	Temperature inside Lab (deg. F)		
Description of Work Performed			
Recorded by	Signature	Date	Time
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time
Comments:			
*Test specimens and associated cylinders are to be cured under wet burlap for seven days			

Form 5

Project: Tests to Determine the
Behavior of Spliced #11 Bars

Cylinder Compression Tests Documentation v.2
(Rev. 04/01/2012)

Specimen: _____

Sheet 1 of 2

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]		Length [nearest 0.05 in.]			P _{max} [lb _f]	Fracture Type (1-6)
				1	2	1	2	3		
1										
2										
3										
4										
5										
6										
S/N of Testing Machine:										
Recorded by:			Signature			Date			Time	
Checked by:			Signature			Date			Time	
Checked by:			Signature			Date			Time	
Comments:										
*Cylinders to be test per ASTM C-39-12 and C-1231-10a with a loading rate of 60,000lb _f /min at concrete ages of 3, 7, 14, 28 days, and on same day that test of corresponding specimen is conducted. Specimens and caps free of defects unless otherwise noted in comments. Average cylinder diameter and area and unit compressive stress (f' _c) calculated on sheet 2 of 2.										

Form 5

Project: Tests to Determine the Behavior of Spliced #11 Bars

Cylinder Compression Tests Documentation v.2 (Rev. 04/01/2012)

Specimen: _____

Specimen	Date	Age	Time of Test	Wet/Dry	Average Measured Dia. [in.]	Cross-sectional Area [in ²]	P _{max} [lbf]	f' _c [psi]	Fracture Type (1-6)
1	0-Jan		12:00 AM	0	#DIV/0!	#DIV/0!	0	#DIV/0!	0
2	0-Jan		12:00 AM	0	#DIV/0!	#DIV/0!	0	#DIV/0!	0
3	0-Jan		12:00 AM	0	#DIV/0!	#DIV/0!	0	#DIV/0!	0
4									
5									
6									

S/N of Testing Machine:			
Recorded by:	Signature	Date	Time
0		0	0
Checked by:	Signature	Date	Time
0		0	0
Checked by:	Signature	Date	Time


Comments:

*Cylinders to be test per ASTM C-39-12 and C-1231-10a with a loading rate of 60,000lbf/min at concrete ages of 3, 7, 14, 28 days, and on same day that test of corresponding specimen is conducted. Specimens and caps free of defects unless otherwise noted in comments. Recorded data is shown on sheet 1 of 2.

Calibration Instrument Name and S.N.:					
Data Acquisition System:					
Gain:					
Excitation Voltage:					
Channel:					
Sensor:					
Sensor S.N.:					
Measurand	Voltage	Measurand	Voltage	Measurand	Voltage
Operator		Signature		Date	Time
Checked by		Signature		Date	Time
Checked by		Signature		Date	Time
Results	Sensitivity			Accuracy	
Notes:					

Meter S.N.			
Type of Meter			
Meter Brand Name			
Ambient Temperature			
	Target Air Content	Measured Air Content	
Operator	Signature	Date	Time
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time
Notes:			

Form 7



Specimen

Behavior of Lap Splices of No. 11
Reinforcing Bars

Sheet:

1

of


4

Drawn by:



Checked by:

Date:

Form 7




Top Plan



Profile

*For section B-B through F-F see Sheet 3 of 3




Bottom Plan




Drawing:	Series A Concrete As-builts	Sheet:	2	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

Form 7




Top Plan



Profile

*For section B-B through F-F see Sheet 3 of 3




Bottom Plan



Drawing:	Series B Concrete As-builts	Sheet:	3	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

Form 7



Section B-B, C-C, D-D, E-E & F-F
*Facing North



Drawing:	Concrete As-built Sections	Sheet:	4	of	4
Project:	Experimental Investigation of Capacity of Lap Splices of No. 11 Reinforcing Bars	Drawn by:	BPR	Checked by:	SP
		Date:	04/04/2012		

Form 7

Project: Tests to Determine the Behavior of Spliced #11 Bars

Setup and As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: _____

Sheet 1 of 2

Section	Concrete As-built Dimensions							
	1	2	3	4	5	6	7	8
Plan								
B-B								
C-C								
D-D								
E-E								
F-F								
Recorded by:			Signature				Date	Time
Checked by:			Signature				Date	Time
Checked by:			Signature				Date	Time

Comments:

*See concrete as-built drawings for dimension locations

Form 7

Project: Tests to Determine the
Behavior of Spliced #11 Bars

Setup and As-built Dimensions v.1
(Rev. 04/04/2012)

Specimen: _____

Sheet 2 of 2

Section	Concrete As-built Dimensions Key - Series A							
	1	2	3	4	5	6	7	8
Plan	39'-0"	39'-0"	39'-0"	39'-0"	N/A	N/A	N/A	N/A
B-B	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
C-C	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
D-D	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
E-E	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
F-F	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
Section	Concrete As-built Dimensions Key - Series B							
	1	2	3	4	5	6	7	8
Plan	34'-4"	34'-4"	34'-4"	34'-4"	N/A	N/A	N/A	N/A
B-B	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
C-C	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
D-D	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
E-E	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A
F-F	17-5/8"	30"	17-5/8"	30"	N/A	N/A	N/A	N/A

Form 8

Project: Tests to Determine the Behavior of Spliced #11 Bars

Instrumentation Documentation v.1
(Rev. 04/01/2012)


Specimen: _____
Sheet _____ of _____

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity	Zero Offset	Location	Comments

Operator	Signature	Date	Time
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time

Notes:

Form 9



Specimen

Behavior of Lap Splices of No. 11
Reinforcing Bars

Drawn by:

Checked by:

Date:

REVERSE

	Average Load (lbf)	North Overhang (in)	South Overhang (in)	North Splice End (in)	Midspan (in)	South Splice End (in)	LVDT North Support	LVDT South Support	North Load Cell (lbf)	South Load Cell (lbf)	DG North Overhang (in)	DG South Overhang (in)	Time	DG Mid (in)
1	200	.014	-.007	-.003	-.003	.002	-.012	-.006	200	100	0.900	0.000	1:31	0.900
2	200	.013	-.007	-.003	-.002	.002	-.012	-.006	200	100	0.9	0	2:22	0.9
3	1ST CR	HEARD	AT 7.5	K	MEAN	LOAD	S.	SUPPORT	AFTER DROP					
4	14500	.510	.445	.06	.081	.064	-.015	-.005	13700	14100	0.398	0.446	2:43	0.812
5					.082				13.0	13.2			3:24	
6	23200	.965	0.912	0.120	0.158	0.124	-.017	-.004	22800	22800	OFFSC.	0.915	3:30	0.734
7									RESET		1.000	0.000		
8	31500	1.415	1.363	0.183	0.240	0.191	-.020	-.005	31000	31500	0.559	0.455	4:08	0.653
9	29.8k	1.419	1.366	0.184	0.241	0.192	-.020	-.005	29700	29800	0.556	0.458	4:39	—
10									RESET		1.0	0		—
11	35.6k													
12	34.8k	1.918	1.767	0.259	0.321	0.253	-.021	-.005	34600	34900	0.500	0.403	4:53	0.574
13	34.4k	1.920	1.769								0.499	0.404		
14									RESET		1.0	0		
15	37.5k	2.465	2.269	.34	.399	.340	-.022	-.005	36800	36600	<u>REMOVED</u>		5:24	0.480
16	0.2k	1.018	0.872	.142	.167	.140	-.018	-.004	0.2k	0.1k	—	—	5:40	0.737
17					.164								5:46	0.737
18	0.19k				.162								6:12	0.739
19	12.4k	1.448	1.273	.200	.240	.196	-.02	-.004	12.5K	12.2K	—	—	6:17	0.662
20	23K	1.897	1.718	.262	.320	.261	-.021	-.005	23K	23K	—	—	6:28	0.828
21	35.9k	2.465	2.266	.341	.400	.340	-.022	-.005	35.6 ^k	35.5k	—	—	6:40	0.480
22	35.5				.400									0.480
23														Remove
24														

Comp.

	Average Load (lbf)	North Overhang (in)	South Overhang (in)	North Splice End (in)	Midspan (in)	South Splice End (in)	LVDT North Support	LVDT South Support	North Load Cell (lbf)	South Load Cell (lbf)	DG North Overhang (in)	DG South Overhang (in)	Time	MID DG
1	0	.001	.002	-.001	-.001	0.000	-.000	-.000	0	0	1.0	0	12:00N	0.100
2	0.2K	.002	.002	-.001	-.001	0	0	0	0.2	0.2	0.999	0.002	12:45PM	0.1
3	0.2				-.005								1:17	0.104
4	14.1	0.497	0.458	0.052	0.079	0.065	-.016	-.002	13.5	13.6	0.503	0.450	1:31PM	0.021
5					0.080								RESET	0.900
6	22.8	0.949	0.913	0.115	0.160	0.128	-0.017	-.001	22.4	22.1	OFF	0.914	1:57PM	0.820
7	21.8		0.916						RESET			0.914		
8	21.8											0.000		
9	31.1	1.452	1.384	0.180	0.240	0.190	-0.019	-.003	31	30.7		0.471	2:37PM	0.739
10	35.9	1.812	1.866	0.243	0.320	0.265	-0.019	-.003	35.1	35.1		0.055	3:09PM	
11	34.5		1.871						RESET			0.057	3:14PM	0.657
12												0.000	3:15PM	
13	37.1K	2.250	2.261	0.309	.397	.332	-.019	-.003	36.2	36.3		0.388	3:43PM	0.583
14	0.19	0.847	0.850	0.116	0.150	0.133	-.016	-.002	0.2	0.1			4:11PM	0.835
15	14.6K	1.382	1.370	0.187	0.241	0.204	-.018	-.002	14.6	14.4			4:26PM	
16	25.8K	1.835	1.827	0.251	0.320	0.271	-.018	-.003	25.7	25.5			4:38PM	0.659
17	36.7K	2.337	2.332	0.322	0.411	0.343	-.018	-.003	36.1	36.1			4:53PM	0.568
18	REMOVE OPTOTRAK TARGETS & D.G.													
19	LOAD TO FAILURE													
20														
21														
22														
23														
24														

	Average Load (lbf)	North Overhang (in)	South Overhang (in)	North Splice End (in)	Midspan (in)	South Splice End (in)	LVDT North Support	LVDT South Support	North Load Cell (lbf)	South Load Cell (lbf)	DG North Overhang (in)	DG South Overhang (in)	P.C. Time	MID DG.	
1	0.2	0.060	0.001	0	-0.001	-0.001	0	0	0.2	0.1	1.000	0.000	11:55A	0.900	
2	15.2	0.489	0.472	0.057	-0.080	0.067	-0.017	-0.010	13.2	14.9	0.554	0.474	2:11P		
3	13.0	0.442	0.472		0.078				11.2	14.9	0.560	0.472	2:15P	0.824	
4	23.6	0.941	0.937	0.117	0.156	0.123	-0.018	-0.011	22.6	22.8	0.052	0.945	2:42P	0.742	
5		0.941									0.049				
6										RESET	1.000	0.945	2:48P		
7	OPTOT	TARGET 49	WAS KICKED DURING TEST									RESET	0	2:49P	
8	32.6	1.403	1.400	0.180	0.239	0.188	-0.018	-0.012	32.1	31.9			3:10P		
9	31.6								31.6	31.6	0.535	0.459	3:15P	0.658	
10	36.6	1.816	1.890	0.243	0.318	0.262	-0.019	-0.014							
11	35.3	MAX CRCK = 0.025"							35.4	35.2	0.112	0.943	3:44	0.583	
12	34.8									RESET	1.000	0	3:51		
13	37.5	2.216	2.367	0.311	0.4	0.339	-0.019	-0.015	37.1	36.7	0.592	0.469	4:10	0.502	
14		MAX CRCK > 0.040"													
15		~ 0.050"													
16	0.12	0.883	0.969	0.123	0.157	0.145	-0.017	-0.010	0.2	0.1	REMOVED		4:30P		
17	0.13				0.154								4:34P	0.748	
18	14.1	1.340	1.455	0.188	0.238	0.212	-0.017	-0.013	13.8	13.9			4:49P	0.660	
19	13.5													0.640	
20	25.4	1.780	1.918	0.250	0.318	0.274	-0.017	-0.014	25.3	25.3			5:02		
21	36	2.21	2.38	0.311	0.4	0.339	-0.017	-0.015	35.7	35.7			5:13		
22		MOVED			0.400		MOVED						5:25	0.51	
23	34.9	2.210	2.383	0.315	0.400	0.348							5:27		
24	↓ TEST TO FAILURE														

	Average Load (lbf)	North Overhang (in)	South Overhang (in)	North Splice End (in)	Midspan (in)	South Splice End (in)	LVDT North Support	LVDT South Support	North Load Cell (lbf)	South Load Cell (lbf)	DG North Overhang (in)	DG South Overhang (in)	PC Time	MID DG
1	.12	0	0	0	0	0.001	0	0	0.2	0.1	0	1.0	8:04	0.9
2	.12	0.023	-0.006	-0.008	-0.005	-0.000	-0.014	-0.004	0.2	0.1	0.020	1.009	8:14	0.905
3	15.2	0.480	0.459	0.056	0.078	0.066	-0.014	-0.005	13	14.3	0.469	0.542	8:33	0.819
4	23.8	0.975	0.924	0.117	0.160	0.130	-0.014	-0.007	22.6	22.9	1.077 OFF SCALE	0.072	8:58	0.736
5	32.6	1.441	1.405							RESET	0	1.000		
6	32.6	1.441	1.405	0.180	0.240	0.196	-0.013	-0.007	32.1	32.0	0.472	0.516	9:20	0.666
7	36.6	1.810	1.930	0.240	0.321	0.275	-0.011	-0.009	35.5	35.4	0.842	OFF SC.	9:47	
8	35.1	1.815	1.932		0.322					RESET	0	1.0		0.574
9	37.8	2.226	2.317	0.308	0.401	0.344	-0.01	-0.01	37	36.4	0.409	0.535	10:22	0.493
10	39	2.697	3.089	0.387	0.501	0.443	-0.008	-0.011	37.8	37.6			10:34	0.393
11	0.1	1.207	1.559	0.177	0.230	0.225	-0.012	-0.008	0.2	0.1			10:59	0.671
12	14.5	1.701	2.095	0.249	0.321	0.298	-0.011	-0.009	13.3	14.4			11:22	0.577
13	24.7	2.156	2.543	0.310	0.4	0.361	-0.010	-0.010	24.7	24.7			11:37	0.494
14	34.6	2.592	2.993	0.373	0.482	0.428	-0.008	-0.010	34.4	34.6			11:50	0.413
15														
16														
17														
18														
19														
20														
21														
22														
23														
24														

MAX SPLIT CRACK ~0.05"

↓ TEST TO FAILURE

	Average Load (k) - kip	North Overhang (in)	South Overhang (in)	North Splice End (in)	Midspan (in)	South Splice End (in)	LVDT North Support	LVDT South Support	North Load Cell (lbf)	South Load Cell (lbf)	DG North Overhang (in)	DG South Overhang (in)	Time	DG Mid
	.11	0	0	0	0	0	0	0	.2	.1	0	0.1	1:50	.9
Bolts removed	.11	.008	.02	-.014	-.013	-.012	-.002	-.005	.2	.1	.008	0.112	1:59	.91
LOAD ↓	15.5	0.556	0.575	0.058	0.081	0.063	-0.003	-0.009	13.9	14.8	0.451	0.562	2:00	0.815
	24.4	1.032	1.054	0.117	0.160	0.127	-0.003	-0.010	23.7	24.0	1.004	0.951	2:20	0.736
	33.3	1.508	1.532	0.181	0.240	0.193	-0.003	-0.011	32.8	32.8	OFF 1.004 RES. 0.700	OFF 0.951 RES. 0.200	2:47	0.654
	36	1.911	2.023	0.248	0.320	0.267	-0.003	-0.010	35.3	35.1	0.301 RES. 0.800	0.702 RES. 0.300	3:14	0.575
s. side crack ~0.060 in. *	37.2	2.317	2.513	0.319	0.401	0.344	-0.003	-0.009	36.5	36.1	0.401	0.784	3:47	0.492
unloaded	0	0.913	1.094	0.126	0.156	0.146	-0.003	-0.009	0.1	0.1	OFF	OFF	4:06	0.744
	13.9	1.392	1.590	0.190	0.239	0.215	-0.002	-0.010	13.5	13.9	—	—	4:32	0.654
	24.8	1.848	2.042	0.253	0.320	0.278	-0.003	-0.009	24.8	24.6	—	—	4:46	0.573
s. side crack ~0.070 in.	35.1	2.290	2.497	0.316	0.399	0.342	-0.003	-0.009	34.9	34.9	—	—	5:00	0.494
12														
13														
14														
15														
16														
17														
18														
19														
20														
21														
22														
23														
24														

small-big

	Average Load (#ft) K(12)	North Overhang (in)	South Overhang (in)	North Splice End (in)	Midspan (in)	South Splice End (in)	LVDT North Support	LVDT South Support	North Load Cell (lbf)	South Load Cell (lbf)	DG North Overhang (in)	DG South Overhang (in)	Time	DC Mid
1	0.13	-0.001	0.000	-0.002	-0.001	0.000	-0.001	-0.000	0.2	0.1	0.000	0.000	1:39	.900
2	0.11	0.025	-0.004	-0.014	-0.008	-0.005	-0.021	-0.008	.1	.1	0.020	0.010	1:47	.894
3	14.5	0.519	0.525	0.055	0.081	0.070	-0.021	-0.013	13.3	13.7	0.491	0.523	1:58	0.814
4	23.7	1.007	0.988	0.114	0.160	0.133	-0.021	-0.015	23.3	23.2	1.012 RES. 0.800	0.958 RES. 0.100	2:20	0.735
5	32.6	1.466	1.452	0.176	0.240	0.198	-0.020	-0.016	31.8	31.8	0.298 R 0.800	0.565 R 0.006	2:42	0.653
6	36.2	1.861	1.922	0.243	0.321	0.268	-0.018	-0.017	35.2	35.1	0.391 R 0.700	0.474	3:05	0.574
7	37.3	2.296	2.364	0.311	0.400	0.342	-0.016	-0.017	36.8	36.8	0.275 R 0.800	0.918 R 0.200	3:28	0.495
8	↗ Max crack		width = 25×10^{-3} in.											
9	38.5	2.796	2.920	0.398	0.500	0.433	-0.014	-0.017	37.6	37.7	0.297	0.747	3:44	0.395
10	↗ Max crack		width = 40×10^{-3} in.								—	—		
11	0.1	1.311	1.396	0.187	0.232	0.216	-0.017	-0.017	0.1	0.1	—	—	3:58	0.671
12	13.8	1.791	1.896	0.256	0.320	0.284	-0.015	-0.017	13.3	13.8	—	—	4:18	0.581
13	24.6	2.254	2.355	0.320	0.400	0.352	-0.014	-0.017	24.3	24.4	—	—	4:32	0.499
14	36.7	2.791	2.916	0.398	0.561	0.433	-0.014	-0.017	36.4	36.3	—	—	4:46	0.395
15														
16														
17														
18														
19														
20														
21														
22														
23														
24														

did not
mark cracks →

↙

unload

CERTIFICATE OF CALIBRATION

ISSUED BY: INSTRON CALIBRATION LABORATORY

DATE OF ISSUE: 09-Dec-15

CERTIFICATE NUMBER: **340120915110036****Instron**

825 University Avenue
 Norwood, MA 02062-2643
 Telephone: (800) 473-7838
 Fax: (781) 575-5750
 Email: service_requests@instron.com

Page 1 of 4 pages

APPROVED SIGNATORY

**Richard
 Binford**

Digitally signed by Richard Binford
 DN: cn=Richard Binford, c=US, l=Norwood,
 st=MA, o=Instron, ou=OVR, Calibration
 Laboratory, A division of Illinois Tool Works,
 Inc. (ITW, Inc.),
 email=Richard_Binford@Instron.com
 Reason: I attest to the accuracy and integrity of
 this document
 Date: 2015.12.09 11:23:52 -0500'

Date of Calibration: 09-Dec-15**Customer Requested Due Date: 31-Dec-16*** * * **CALIBRATION RESULTS** * * ***Type of Calibration:** Strain **Relevant Standard:** ASTM E83-10a**System ID:** 120BTE502040 **Transducer ID:** 2630-115/590**Indicator 1. - Digital Readout (strain)****PASSED Class B-1 - 100% Range in Tension mode****Customer**

Name: PURDUE UNIVERSITY
 Address: US 231 BOWEN LABORATORY
 WEST LAFAYETTE, IN 47907
 KBROWER@PURDUE.EDU
 P.O./Contract No.:
 Contact: KEVIN BROWER

Machine

Manufacturer: SATEC
 Serial Number: 120BTE502040
 System ID: 120BTE502040
 Range Type: Single

Transducer

Manufacturer: INSTRON
 Transducer ID: 2630-115/590
 Extensometer Type: Type 1
 Travel (Tension): 1 in
 Travel (Compression): 0.1 in
 Gauge Length: 2 in
 Mode: Static (Tension/Compression)

Certification Statement

All indicators listed above were verified on-site at customer location by Instron in accordance with ASTM E83.

The verification and equipment used conform to a controlled Quality Assurance program which meets the specifications outlined in ANSI/NCSL Z540-1, ISO 10012, ISO 9001:2008 and ISO/IEC 17025:2005.

The testing machine was verified in the 'as found' condition.

Instron Calpro Version 3.30

The results indicated on this certificate and the following report relate only to the items verified. If there are methods or data included that are not covered by the NVLAP accreditation it will be identified in the comments. Any limitations of use as a result of this verification will be indicated in the comments. This report must not be used to claim product endorsement by NVLAP or the United States government. This report shall not be reproduced, except in full, without the approval of the issuing laboratory.

CERTIFICATE OF CALIBRATION

NVLAP ACCREDITED CALIBRATION LABORATORY No. 200301-0

CERTIFICATE NUMBER:

340120915110036

Page 2 of 4 pages

Summary of Results**Indicator 1. - Digital Readout (strain)**

Full Scale (%)	Tested Range (in)	Mode	System Class*	Resolution (strain)	Resolution Class	ASTM E83 Lower Limit (in)
100	0.1002 to 1.00369	Tension	B-1	0.00001	A	0.002

* System Class for a range is the worst of the following classes: gauge length class, resolution class, individual point error class, repeatability class and is also based on the measurement capability of the laboratory.

Gauge Length Measurement and Classification

Nominal Gauge Length (in)	Actual Gauge Length (in)	Measurement Type	Relative Error of Gauge Length for Each Measurement Made (%)			ASTM E83 Gauge Length Class	Uncertainty of Measurement* (in)
			-0.229	-0.117	0.143		
2	1.99865	Indirect	-0.229	-0.117	0.143	B-1	0.0032

* The reported expanded uncertainty is based on a standard uncertainty multiplied by a coverage factor $k = 2$, providing a level of confidence of approximately 95%.

Data Summary and Classification**Indicator 1. - Digital Readout (strain)**

% of Range	Run 1 Error		Run 2 Error		Repeat Error (strain)	Worst Class	Uncertainty of Measurement* (strain)
	Fixed (strain)	Relative (% of strain)	Fixed (strain)	Relative (% of strain)			
100% Range (Full Scale: 1.00369 in)							
10	-0.00018	-0.354	-0.00010	-0.199	0.00008	B-1	0.00093
20	-0.00043	-0.427	-0.00047	-0.466	0.00004	B-1	0.00017
40	-0.00082	-0.406	-0.00097	-0.482	0.00015	B-1	0.00033
70	-0.00059	-0.168	-0.00035	-0.101	0.00024	B-1	0.00058
100	-0.00184	-0.367	-0.00156	-0.311	0.00028	B-1	0.00082

* The reported expanded uncertainty is based on a standard uncertainty multiplied by a coverage factor $k = 2$, providing a level of confidence of approximately 95%.

Data**Indicator 1. - Digital Readout (strain)**

% of Range	Run 1		Run 2	
	Indicated (strain)	Applied (in)	Indicated (strain)	Applied (in)
100% Range (Full Scale: 1.00369 in)				
Run Temperature: 67.6 °F				
0	0	-0.000001	0	0.000000
10	0.050027	0.100410	0.05	0.100200
20	0.1	0.200858	0.1	0.200936
40	0.2	0.401631	0.2	0.401937
Run Temperature: 69.8 °F				

CERTIFICATE OF CALIBRATION

NVLAP ACCREDITED CALIBRATION LABORATORY No. 200301-0

CERTIFICATE NUMBER:

340120915110036

Page 3 of 4 pages

Data**Indicator 1. - Digital Readout (strain)**

% of Range	Run 1		Run 2	
	Indicated (strain)	Applied (in)	Indicated (strain)	Applied (in)
100% Range (Full Scale: 1.00369 in)				
Run Temperature: 67.6 °F			Run Temperature: 69.8 °F	
70	0.35	0.701182	0.35	0.700708
100	0.5	1.003686	0.5	1.003124

Verification Equipment

Make/Model	Serial Number	Description	Calibration Agency	Measurement Range	Cal Date	Cal Due
Extech 445580	1041758	temp. indicator	Masy Systems Inc.	NA	13-Feb-15	13-Feb-17
Epsilon 3590VHR	A5010 (ASTM)	disp. indicator	Epsilon Technology	2.00 in	29-Jan-15	29-Jan-16
Instron US Gauge Bar Interface 9840	1902 (ASTM) 93112	gauge bar force indicator	A.A. Jansson Instron	NA NA	29-May-14 24-Sep-14	29-May-16 24-Sep-16

Verification Equipment Usage

Measurement Type	Serial Number	Range (% of FS)	Mode	Percent(s) of Range	Accuracy (+/-)
Displacement	A5010 (ASTM)	100	T	10/ 20	0.00004 in
				40/ 70	0.000075 in
				100	0.00015 in
Gauge Length	93112	NA		NA*	0.015% of reading
	A5010 (ASTM)	NA		NA*	0.00004 in
	I902 (ASTM)	NA		NA*	0.00021 in
Temperature	1041758	All		All	1.8 °F

* Refer to Gauge Length Measurement and Classification section for usage.

Instron standards are traceable to the SI (The International System of Units) through standards maintained by the National Institute of Standards and Technology (NIST) or other internationally recognized National Metrology Institutes (NMIs).

The accuracy of the verification equipment used was equal to or better than the accuracy indicated in the table above.

Comments

Verified by: Rich Binford
Field Service Engineer

CERTIFICATE OF CALIBRATION

NVLAP ACCREDITED CALIBRATION LABORATORY No. 200301-0

CERTIFICATE NUMBER:

340120915110036

Page 4 of 4 pages

NOTE: Clause 9 of ASTM E-83 states; It is recommended that extensometer systems be verified annually or more frequently if required. In no case shall the time interval between verifications exceed 18 months (unless an extensometer is being used in a long-time test running beyond the 18 month period). An extensometer system shall not be used after an adjustment or repair that could affect its accuracy without first verifying its accuracy utilizing the procedure described in this practice.

CERTIFICATE OF CALIBRATION

ISSUED BY: INSTRON CALIBRATION LABORATORY

DATE OF ISSUE: 09-Dec-15

CERTIFICATE NUMBER: **340120915102905****Instron**

825 University Avenue
 Norwood, MA 02062-2643
 Telephone: (800) 473-7838
 Fax: (781) 575-5750
 Email: service_requests@instron.com

Page 1 of 4 pages

APPROVED SIGNATORY

Type of Calibration: Force
Relevant Standard: ASTM E4-14
Date of Calibration: 09-Dec-15

Customer Requested Due Date: 31-Dec-16**Customer**

Name: PURDUE UNIVERSITY
 Address: US 231 BOWEN LABORATORY
 WEST LAFAYETTE, IN 47907
 KBROWER@PURDUE.EDU
 P.O./Contract No.:
 Contact: KEVIN BROWER

Machine

Manufacturer: SATEC
 Serial Number: 120BTE502040
 System ID: 120BTE502040
 Range Type: Single

Transducer

Manufacturer: SATEC
 Transducer ID: 120BTE502040
 Capacity: 120000 lbf
 Type: Compression

Classification

1. Digital Readout - PASSED**

Certification Statement

This certifies that the forces verified with machine indicator(s) (listed above) that passed are WITHIN $\pm 1\%$ accuracy, 1% repeatability, and zero return tolerance.

All machine indicators were verified on-site at customer location by Instron in accordance with ASTM E4.

The certification is based on runs 1 and 2 only. A third run is taken to satisfy uncertainty requirements according to ISO 17025 specifications.

The verification and equipment used conform to a controlled Quality Assurance program which meets the specifications outlined in ANSI/NCSL Z540-1, ISO 10012, ISO 9001:2008 and ISO/IEC 17025:2005.

** within $\pm 0.5\%$ accuracy and 0.5% repeatability.

Method

The testing machine was verified in the 'as found' condition with no adjustments carried out.

Instron CalproCR Version 3.30

The results indicated on this certificate and the following report relate only to the items verified. If there are methods or data included that are not covered by the NVLAP accreditation it will be identified in the comments. Any limitations of use as a result of this verification will be indicated in the comments. This report must not be used to claim product endorsement by NVLAP or the United States government. This report shall not be reproduced, except in full, without the approval of the issuing laboratory.

CERTIFICATE OF CALIBRATION

NVLAP ACCREDITED CALIBRATION LABORATORY No. 200301-0

CERTIFICATE NUMBER:

340120915102905

Page 2 of 4 pages

Summary of Results

Temperature at start of verification: 71.20 °F.

Indicator 1. - Digital Readout (lbf)

Range	ASTM E4	ASTM E4	Zero	Resolution	ASTM E4	
Full Scale (%)	Tested Force Range (lbf)	Mode	Max Error (%)	Max Repeat Error (%)	Return	Lower Limit (lbf)
100	-1196.65 to -119941.1	C	0.28	0.19	Pass	200

Temperature at end of verification: 71.20 °F.

Data Point Summary - Indicator 1. - Digital Readout (lbf)**COMPRESSION**

% of Range	Run 1 Error (%)	Run 2 Error (%)	Run 3 Error (%)	ASTM E4 Repeat Error (%)	Relative Uncertainty*	Uncertainty of Measurement* (± lbf)
100% Range (Full Scale: -119941.1 lbf)						
1	0.28	0.26	0.29	0.02	0.14	1.6
2	0.15	0.16	0.16	0.01	0.13	3.1
4	0.03	0.03	0.03	0.00	0.13	6.1
7	-0.02	-0.01	-0.01	0.01	0.13	11
10	0.11	0.11	0.12	0.00	0.13	15
20	0.14	0.14	0.15	0.00	0.13	31
40	0.10	0.10	0.10	0.00	0.13	61
70	0.21	0.05	0.07	0.16	0.16	137
100	0.24	0.05	0.07	0.19	0.18	211

* The reported expanded uncertainty is based on a standard uncertainty multiplied by a coverage factor $k = 2$, providing a level of confidence of approximately 95%.

Data - Indicator 1. - Digital Readout (lbf)**COMPRESSION**

% of Range	Run 1		Run 2		Run 3	
	Indicated (lbf)	Applied (lbf)	Indicated (lbf)	Applied (lbf)	Indicated (lbf)	Applied (lbf)
100% Range (Full Scale: -119941.1 lbf)						
0 Return	4		3		12	
1	-1200	-1196.65	-1200	-1196.85	-1200	-1196.55
2	-2400	-2396.45	-2400	-2396.25	-2400	-2396.05
4	-4800	-4798.6	-4800	-4798.4	-4800	-4798.35
7	-8400	-8401.4	-8400	-8400.85	-8400	-8400.8
10	-12000	-11986.44	-12000	-11987.03	-12000	-11985.26
20	-24000	-23967.57	-24000	-23965.8	-24000	-23964.03
40	-48000	-47953.43	-48000	-47950.48	-48000	-47949.89
70	-84000	-83820.71	-84000	-83957	-84000	-83944.02
100	-120000	-119711	-120000	-119941.1	-120000	-119918.68

CERTIFICATE OF CALIBRATION


NVLAP ACCREDITED CALIBRATION LABORATORY No. 200301-0

CERTIFICATE NUMBER:

340120915102905

Page 3 of 4 pages

The Return to Zero tolerance is \pm the indicator resolution, 0.1% of the maximum force verified in the range, or 1% of the lowest force verified in the range, whichever is greater.

Graphical Data - Indicator 1. - Digital Readout (lbf)**Verification Equipment**

Make/Model	Serial Number	Description	Calibration Agency	Capacity	Cal Date	Cal Due
Extech 445580	1041758	temp. indicator	Masy Systems Inc.	NA	13-Feb-15	13-Feb-17
HBM 10KFRR	688077	load cell	Instron	12000 lbf	16-May-14	16-May-16
Interface 9840	93112	force indicator	Instron	NA	24-Sep-14	24-Sep-16
Strainsense 050530	050530	load cell	Instron	120000 lbf	16-Oct-14	16-Oct-16

Verification Equipment Usage

Range	Full Scale (%)	Standard Mode	Serial Number	Percent(s) of Range	Lower Limit for Standard (lbf)	Accuracy (+/-)
100	C	688077	1/ 2/ 4/ 7	Class A1: 256	0.1% of reading	
		050530	10/ 20/ 40/ 70/ 100	Class A1: 10552	0.1% of reading	
All	C	1041758	All	NA	1.8 °F	

CERTIFICATE OF CALIBRATION

NVLAP ACCREDITED CALIBRATION LABORATORY No. 200301-0

CERTIFICATE NUMBER:

340120915102905

Page 4 of 4 pages

Instron standards are traceable to the SI (The International System of Units) through standards maintained by the National Institute of Standards and Technology (NIST) or other internationally recognized National Metrology Institutes (NMIs).

The standard Class A lower limit is used for systems with an accuracy of $\pm 1.0\%$ and the standard Class A1 lower limit is used for systems with an accuracy of $\pm 0.5\%$.

The accuracy of the force indicator used with elastic devices is incorporated into the devices stated accuracy.

Standard forces have been temperature compensated as necessary.

The accuracy of the verification equipment used was equal to or better than the accuracy indicated in the table above.

Comments

Verified by: Rich Binford
Field Service Engineer

NOTE: Clause 19 of ASTM E4 states; It is recommended that testing machines be verified annually or more frequently if required. In no case shall the time interval between verifications exceed 18 months (except for machines in which long term test runs beyond the 18 month period). Testing machines shall be verified immediately after repairs that may in any way affect the operation of the weighing system or values displayed. Verification is required immediately after a testing machine is relocated and where there is a reason to doubt the accuracy of the force indicating system, regardless of the time interval since the last verification.

CALSER CORPORATION

302 N. Belt East, Swansea, IL 62226

(618) 277-0329

TESTING MACHINE CALIBRATION DATA AND REPORT

Report #: VN# 10097
Page 1 of 2

Customer Purdue University
Location 1040 South Rive Rd. - Bowen Lab
West Lafayette, IN 47907
Manufacturer Forney **Model** F-600-DFM/I
Serial No. 99058 **Capacity** 600,000 lbf
Resolution 1 lbf / DIV
Customer Asset No. 1009085
Auxiliary Equipment: w/ Forney CA-0396 Auto Digital R/O #15087
w/ Gefran P/T

Date of Service 08/19/15
Customer Order No. Verbal
Order Date 08/03/15
Temp. 71° F
Date Last Done 06/04/14
Calibration Next Due 08/19/16
Method of Verification Set the Force

Applied Force	*	Indicated Force	Error	%	Applied Force	*	Indicated Force	Error	%
Run #1		"As Found" Condition			Run #2		"As Left" Condition		
600,000lbf Range	*	1lbf / DIV			600,000lbf Range	*	1lbf / DIV		
0	6C	0	0	0.00	0	6C	0	0	0.00
5,000	6C	5,002	2	0.04	5,000	6C	5,004	4	0.08
10,000	6C	10,012	12	0.12	10,000	6C	10,008	8	0.08
20,000	17S	20,034	34	0.17	20,000	17S	20,039	39	0.20
40,000	17S	40,058	58	0.15	40,000	17S	40,064	64	0.16
60,000	17S	60,066	66	0.11	60,000	17S	60,069	69	0.12
80,000	12	80,087	87	0.11	80,000	12	80,091	91	0.11
100,000	12	100,120	120	0.12	100,000	12	100,132	132	0.13
150,000	12	150,161	161	0.11	150,000	12	150,174	174	0.12
200,000	12	200,094	94	0.05	200,000	12	200,102	102	0.05
300,000	12	300,166	166	0.06	300,000	12	300,170	170	0.06
400,000	12	400,075	75	0.02	400,000	12	400,081	81	0.02
500,000	12	500,210	210	0.04	500,000	12	500,199	199	0.04
600,000	12	600,182	182	0.03	600,000	12	600,174	174	0.03
0	12	0	0	0.00	0	12	0	0	0.00

Notes:

***CALIBRATION EQUIPMENT**

Calibration in accordance with ASTM E4,
 and Calser Corporation Procedure # 1-01, Rev 1.

All verification equipment-including dead weights, proving rings, load cells, etc, is calibrated and traceable to the latest procedures stipulated by the National Institute of Standards and Technology (NIST) and ASTM E74-06. All equipment is traceable under guidelines set forth in ISO/IEC 17025 . All instrument readings have been corrected for temperature where necessary.

ACCURACY SUMMARY

Verification Equipment

Capacity Range	Loading Range	Max. Error	Manufacturer and Serial #	* L/C	Range and uncertainty	Verification Agency and Date
Run 1						
600,000lbf Range	5,000 - 600,000	0.17 %	Interface	6C	307.21 - 10,000 lbf	Morehouse
			426017A		0.768	12/09/13
			Strainsense	17S	6,201.28 - 100,000 lbf	Morehouse
			990918		15.503	09/23/13
Run 2						
600,000lbf Range	5,000 - 600,000	0.20 %	Strainsense	12	58,630.96 - 600,000 lbf	Morehouse
			990921		146.577	01/02/14

**This report shall not be copied except in its entirety
 without express written approval of Calser Corp.**

Calibration Technician Jerry Parker

CALSER CORPORATION 302 N. BELT EAST SWANSEA, IL 62226 (618)277-0329

TESTING MACHINE CERTIFICATE OF CALIBRATION

Owner : Purdue University
Location : 1040 South Rive Rd. - Bowen Lab
 West Lafayette, IN 47907

Report # : VN# 10097
Page : 2 of 2

Date of Service: 08/19/15

Manufacturer: Forney **Model:** F-600-DFM/I
Serial No. : 99058 **Capacity:** 600,000 lbf

Auxillary Equip: w/ Forney CA-0396 Auto Digital R/O #15087
 w/ Gefran P/T

This is to certify that the testing machine listed above has been calibrated by Calser Corporation personnel.

The method of verification and listed data are in accordance with ASTM E 4.

Accuracy of all calibration devices is traceable to the National Institute of Standards and Technology (NIST)
 and all calculations have been corrected for temperature where applicable.

Capacity Range	Loading Range	Max. Error
Run 1 600,000lbf Range	5,000 - 600,000	0.17 %
Run 2 600,000lbf Range	5,000 - 600,000	0.20 %

VERIFICATION EQUIPMENT

<u>Manufacturer & Serial #</u>	<u>Load Cell #</u>	<u>Range & Uncertainty</u>	<u>Verification Agency & Date</u>	<u>Digital Serial #</u>
Interface 426017A	6C	307.21 - 10,000 lbf 0.768	Morehouse 12/09/13	GB-9911092
Strainsense 990918	17S	6,201.28 - 100,000 lbf 15.503	Morehouse 09/23/13	GB-9911092
Strainsense 990921	12	58,630.96 - 600,000 lbf 146.577	Morehouse 01/02/14	GB-9908261

This certificate is issued as a statement of the fact that on the above date the listed testing machine has an accuracy as indicated. It should not be construed or regarded as a Guarantee or Warranty of any kind (in favor of the client, the client's customers, or the public at large) that the testing machine will continue to retain the same percentage (%) of accuracy or efficiency as determined on the date when the calibration, and adjustments if required, was performed and reported by "Calser Corporation" since the calibrator has absolutely no control over the future operation, damage, maintenance, repairs, and overall condition of the testing machine and hereby expressly disclaims any and all liability for damage or loss sustained by all parties arising or resulting from the deterioration, obsolescence, malfunction or substandard performance of said testing machine; which shall remain the sole responsibility of the machine's regular custodian, owner, and/or user. This certificate shall not be reproduced except in full, without the written approval of Calser Corporation.


CALSER CORPORATION

Quality Control Director


 Thomas R. Gagen

CERTIFICATE OF CALIBRATION

Appendix 9, Pg 11 of 43



ISSUED BY : INSTRON CALIBRATION LABORATORY

Lab code: 200301-0

DATE OF ISSUE : 09-Dec-2015

CERTIFICATE NUMBER: 340120915130058

Page 1 of 3



Instron
825 University Avenue
Norwood, MA 02062-2643
Telephone: (800) 473 - 7838
Fax: (781) 575 - 5755
Email: service_requests@instron.com

APPROVED SIGNATORY

Type of Calibration: Displacement**Relevant Standard:** ASTM E2309/E2309M-05(2011)e1**Date of Calibration:** 09-Dec-2015**Customer Requested Due Date:** 31-Dec-2016

Customer	Machine
PURDUE UNIVERSITY CIVIL RM G151 550 STADIUM MALL DR WEST LAFAYETTE, IN 47907	Serial No : 502040 Make : BALDWIN Model : 120BTE

P.O. Number :

Contact : KEVIN BROWER

Readout Verified

1. Digital Readout (in)

Certification Statement

This certifies that the displacements verified with machine indicator 1 (listed above) were verified by Instron in accordance with ASTM E2309/E2309M (Follow-the-Displacement Method) and Instron work instruction ICA-8-07.

The verification and equipment used conform to a controlled Quality Assurance program which meets the specification outlined in ANSI/NCSS Z540-1, ISO 10012, ISO 9001:2008, and ISO/IEC 17025:2005. The Instron measurement equipment used for verification is traceable to NIST.

The testing machine was verified on-site at customer location. The testing machine was verified in the 'As Found' condition with no adjustments or repairs carried out. This is also the 'As Left' condition.

Summary of Results

Indicator 1- Digital Readout (in)

Verified Range (in)	Max Error (in)	Max Error (%)	Max Repeat Error (in)	Max Repeat Error (%)	System Class*	Resolution (in)	Resolution Class	ASTM Lower Limit (in)
0.6 - 3	-0.00883	-0.484	0.00224	0.117	A	.001	A	0.6

*System Class is derived from assessment of the following: error, repeatability, resolution, and standard device classification.

The results indicated on this certificate and report relate only to the items verified. If there are methods or data included that are not covered by the NVLAP accreditation it will be identified in the comments. Any limitations of use as a result of this verification will be indicated in the comments. This report must not be used to claim product endorsement by NVLAP or the United States government. This report shall not be reproduced, except in full, without the approval of Instron.

CERTIFICATE OF CALIBRATION

Appendix 9, Pg 12 of 13

ISSUED BY : INSTRON CALIBRATION LABORATORY

DATE OF ISSUE : 09-Dec-2015

CERTIFICATE NUMBER: 340120915130058

Page 2 of 3

Direction of Displacement : Ascending

Datapoint Summary - Indicator 1 - Digital Readout (in)

Suggested Value (in)	Run 1 Error (in)	Run 1 Error (%)	Run 2 Error (in)	Run 2 Error (%)	Run 3 Error (in)	Run 3 Error (%)	Repeat Error (in)	Uncertainty (in)*	Coverage Factor = k
0.6	-0.00167	-0.278	-0.00103	-0.173	-0.00166	-0.273	0.00064	0.00098	2.31
1.2	-0.00545	-0.454	-0.00449	-0.368	-0.00499	-0.414	0.00096	0.0013	2.57
1.8	-0.00581	-0.484	-0.00667	-0.367	-0.00805	-0.446	0.00224	0.0031	3.18
2.4	-0.00710	-0.296	-0.00883	-0.356	-0.00828	-0.345	0.00173	0.0026	3.18
3	-0.00467	-0.155	-0.00352	-0.117	-0.00537	-0.178	0.00185	0.0027	3.18

*The reported expanded uncertainty of measurement is based on a combined uncertainty multiplied by a coverage factor k to provide a level of confidence of approximately 95 %.

Runs 1 and 2 are performed to comply with the requirements of ASTM E2309/E2309M, run 3 is performed to calculate the uncertainty of measurement.

Data - Indicator 1 - Digital Readout (in)

Temperature at start of verification : 71.3 °F

Suggested Value	Run 1			Run 2			Run 3	
	Applied	Indicated	Error Class	Applied	Indicated	Error Class	Applied	Indicated
0.6	0.60167	0.6	A	0.59603	0.595	A	0.60766	0.606
1.2	1.19945	1.194	A	1.21849	1.214	A	1.20499	1.2
1.8	1.19981	1.194	A	1.81667	1.81	A	1.80505	1.797
2.4	2.40210	2.395	A	2.48083	2.472	A	2.40228	2.394
3	3.00467	3	A	3.00652	3.003	A	3.01537	3.01

For runs 1 and 2: the worst Resolution Class is A and the worst Repeatability Class is A.

Temperature at end of verification : 71.2 °F

Starting Point of crosshead : 0 in

Verification Equipment

Make/Model	Serial No.	Description	Cal Agency	Cal Date	Due Date
Instron LDS-10	06105014	Linear Gage	AA JANNSON	21-Jul-15	21-Jul-17
EXTECH 445580	1041758	Thermometer	MASY	13-Feb-15	13-Feb-17

CERTIFICATE OF CALIBRATION

Appendix 9, Pg 13 of 13

ISSUED BY : INSTRON CALIBRATION LABORATORY

DATE OF ISSUE : **09-Dec-2015**CERTIFICATE NUMBER: **340120915130058**

Page 3 of 3

Verification Equipment Specifications

Serial No.	Resolution	Accuracy (+/-)
06105014	0.00001 in	0.0002 in
1041758	0.1 °F	2 °F


Instron standards are traceable to the SI (The International System of Units) through standards maintained by the National Institute of Standards and Technology (NIST) or other internationally recognized National Metrology Institutes (NMIs).

The accuracy of the verification equipment used was equal to or better than the accuracy indicated in the table above.


Comments

Verified By: RICHARD BINFORD
FIELD SYSTEMS ENGINEER

FIRST LOADING




GIRDER C1: Midspan deflection = 0.4 in., Load = 37.5 kips



GIRDER C2: Midspan deflection = 0.4 in., Load = 37.1 kips

FIRST LOADING




GIRDER C3: Midspan deflection = 0.4 in., Load = 37.5 kips



GIRDER C4: Midspan deflection = 0.5 in., Load = 39 kips

FIRST LOADING




GIRDER C5: Midspan Deflection = 0.4 in., Load = 37.2 kips




GIRDER C6: Midspan deflection = 0.5 in., Load = 38.5 kips

RELOADING




GIRDERS C1: Midspan deflection = 0.4 in., Load = 35.9 kips



GIRDERS C2: Midspan deflection = 0.4 in., Load = 36.7 kips

RELOADING




GIRDER C3: Midspan deflection = 0.4 in., Load = 36 kips



GIRDER C4: Midspan deflection = 0.5 in., Load = 35.1 kips

RELOADING



GIRDER C5: Midspan deflection = 0.4 in., Load = 35.1 kips



GIRDER C6: Midspan deflection = 0.5 in., Load = 36.7 kips

25884-000-30R-C01R-00002, Rev. 000

APPENDIX C

“Purdue Phase III Test Report”

**AN EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS
ON STRENGTH OF 79-IN. LAP SPLICES OF #11 REINFORCING BARS
WITH POST-INSTALLED TRANSVERSE REINFORCEMENT.**

A REPORT Submitted to

First Energy Nuclear Operating Company

Oak Harbor, Ohio

by

Mete A. Sozen



and

Santiago Pujol



27 September 2017

Bowen Laboratory

West Lafayette, IN

SUMMARY

Eighteen test specimens containing two 79 in. lap splices of #11 reinforcing bars were tested by subjecting them to tensile forces applied directly to the spliced bars. The bars were stressed beyond their yield stress to develop laminar cracks, unloaded, and then reloaded to failure.

Three series of tests were conducted. In the Series 1 (specimens D1-D3, D9, D11, D17), splices were unconfined. They confirmed results from beam tests reported earlier indicating that laminar cracks with widths of up to 0.05 in. did not affect the ability of the lap splice to develop yielding in the spliced bars. In the other two series of tests, lap splices were confined by transverse reinforcement installed after initial laminar cracks of widths of at least 0.06 in. were developed. Transverse reinforcement was installed using ASTM A193 ¾" diameter threaded rod drilled and epoxied into the concrete in the direction perpendicular to the plane of the bars. In Series 2 (D4-D7), transverse reinforcement had embedment lengths of 5 in. measured below the surface of the spliced reinforcing bars. In Series 3 (D8, D10, D12-D16, D18), all anchors had an embedment length of 12 in. below the spliced bars and bearing plates, washers and nuts at the concrete surface (Figure 6). Specimen dimensions and threaded rod spacings are shown and listed in Figures 4-6 and Table 5. Maximum initial crack widths reached before unloading and reloading are listed in Table 5.

Concrete compressive strength ranged from 4000 psi to 4500 psi at time of test. Measured yield stress of the ASTM 615 reinforcing bars was 67 ksi. The measured yield stress of the ASTM A193 threaded rod was 120 ksi.

In specimens D4-D8, D10, and D12, anchors were installed at an ambient temperature of approximately 55° F. In specimens D13-D16, and D18, anchors were installed at an ambient temperature of approximately 75° F. Epoxy was cured for 24 hours prior to reloading, except in specimen D7, in which epoxy was cured for 48 hours. The curing of epoxy and anchor installation was performed indoors in laboratory conditions.

Test results confirmed that crack widths as large as 0.05 in. can be achieved while maintaining the full yield capacity of the #11 reinforcement with 79 in. long splices. Test results also showed that crack widths of nearly 1/8 in. or wider (and bar stresses of approximately 80 ksi) can be reached before failure in lap splice pairs confined by at least three epoxied ASTM A193 ¾" diameter threaded rods with an embedment length of 12 in. below the surface of the splice, spaced at no more than 26.5 in. in the direction of the splice, and fastened to the concrete surface with a bearing plate and nut (Series 3).

OBJECT AND SCOPE

Eighteen reinforced concrete specimens with 79 in. lap splices of ASTM 615 Gr. 60 #11 bars were tested to failure to:

- 1) Examine splices with wider laminar cracks than those produced in previous tests (An Experimental Investigation Of The Effects Of Laminar Cracks On Strength Of Unconfined 79-in. Lap Splices Of #11 Reinforcing bars, Series C, Submitted 5/10/16).
- 2) Evaluate the effects of transverse reinforcement (that can be provided in the field by post-installed threaded rods installed after development of laminar cracks) on the response of splices with laminar cracks.

METHOD

The test specimens are depicted in Figure 1. They had the same cross sections and materials as the specimens used previous tests (30" x 17-5/8" with top cover of 5" and side cover of 3"), but their length was 80 in.

Each specimen had a pair of lap spliced bars with a length of 79 in. Test specimens were subjected to tensile forces applied directly to the spliced bars to produce effects similar to the effects that bending would produce in a structural element. Force was applied through the "self-reacting" loading frame shown in Figure 1. The loading frame and the specimen rested on the laboratory floor during the tests (Figure 100).

Six specimens (D1, D2, D3, D9, D11, D17) were tested without any transverse reinforcement. The remaining twelve specimens were reinforced in their transverse direction.

Transverse reinforcement was installed (after formation of laminar cracks) by using ASTM A193 3/4" - diameter threaded rods drilled and epoxied into the concrete in the direction perpendicular to the plane of the bars. These anchor bolts were centered along the specimen and had two different embedment lengths: 5 in. and 12 in. (measured below the spliced reinforcing bars) (Figures 4, 5, 6 and Table 5). Transverse reinforcement spacing s was 40" for specimen D4, 53" for specimen D6, and 26.5" for specimens D5, D7-D18 (Figures 4, 5, 6).

The test specimens were tested statically. Initial cracks were first caused by applying tension up to the stresses shown in Table 5. Maximum initial crack widths are listed in Table 5. After formation of these cracks, specimens were unloaded and reloaded to failure (when possible). In test Series 2 and 3, unloading was followed by installation of threaded anchor rods and curing of the epoxy.

Test durations ranged from 1 to 2 hours (after installation of anchors). Measured concrete compressive strengths ranged from 4000 to 4500 psi. The yield stress of the ASTM 615 reinforcement was measured to be 67 ksi. Measured yield stress of the ASTM A193 threaded rod was 120 ksi. Maximum unit stresses developed in the reinforcement (at the splice end) ranged from 71 to 81 ksi in Series 1, 73 to 79 ksi in Series 2, and 78 to 83 ksi in Series 3 (Table 5) with mean values of 75, 75, and 80 ksi.

MATERIALS

The cross section in Figure 1 shows the arrangement of the spliced bars. Concrete was cast with the bars near the bottom of the form (and not as shown in the figure that refers to the position of the bars during the test) to make certain that the wet concrete would not settle away from the bars. Top cover, as shown in Figure 1, was 5 in. and the side cover was 3 in. to have the laminar crack develop in the horizontal plane affecting the strength of both splices.

Test specimens were cast using normal-weight aggregate on the dates listed in Table 2. Mix proportions by weight are shown in Table 1. All specimens fabricated on each of the dates in Table 2 and the associated cylinders were fabricated using concrete from a single mixing truck. After casting, the specimens were kept under wet burlap cover for one week. Target air entrainment was 5%. The age of the concrete and measured concrete strengths at time of test are listed in Table 2.

All reinforcement came from the same heat. As mentioned above the measured yield stress of the ASTM 615 reinforcement was 67 ksi (Table 3). ASTM A193 threaded rod yield stress was 120 ksi.

Square bearing plates were installed after insertion of the threaded anchors immediately after the application of the epoxy. Bearing plates, washer and nuts were installed on Series 3 (specimens D8, D10, D12-D16, D18). The plates were made of A36 steel with the dimensions shown in Figure 8. After curing the epoxy for at least 24 hours, a nut with a washer was torqued to 100 ft-lbf to ensure contact between the bearing plate and the concrete surface.

A Hilti TE70 hammer drill was used to drill holes for the transverse reinforcement. The drill bit diameter was $\frac{7}{8}$ ". A hole cleaning method using compressed air, a steel wire brush, and vacuum was used to clean each hole. All holes were cleaned by vacuuming, brushing, and blowing compressed air into each hole. The cleaning sequence was performed six times before installation of the threaded rods. Hilti HIT-RE 500 V3 epoxy was injected into each hole, starting from the bottom of the hole and withdrawing the epoxy dispenser upward. The hole was filled to mid-height before insertion of the threaded rod. The ASTM A193 $\frac{3}{4}$ " threaded rods were inserted into the hole and given a half turn once the threaded rod made contact with the bottom of the hole. Epoxy glue was cured for at least 24 hours in laboratory conditions. In Series 3, bearing plates were placed over the anchor right after the anchor was placed into the drilled and epoxied hole. Torque was applied to a washer and nut after epoxy curing.

In specimens D4-D8, D10, and D12, anchors were installed at an ambient temperature of approximately 55° F. In specimens D13-D16, and D18, anchors were installed at an ambient temperature of approximately 75° F. Epoxy was cured for 24 hours prior to reloading, except in specimen D7, in which epoxy was cured for 48 hours. The curing of epoxy and anchor installation was performed indoors in laboratory conditions.

INSTRUMENTATION

Bar forces were measured using two force transducers (one per bar) opposite to the hydraulic jacks used to apply load (Figure 1). Infrared targets were installed on the west faces of the specimens, above and below the plane of the spliced bars to measure horizontal and vertical deformation of the concrete surface (Figure 2). Displacement sensors (LVDTs) were installed across the plane of the lap splices to measure the widths of laminar cracks forming near the ends of each splice at each of the four corners of each specimen –in plan view- (Figure 3). Table 4 lists the instrumentation details.

MAXIMUM STRESSES AND CRACK WIDTHS REACHED

In all specimens initial loading produced cracks with widths exceeding 0.05 in. and as large as 0.13 in. Maximum crack widths reached during initial loading and at failure are listed in Table 5.

In Series 1, the spliced bars in unconfined specimens D1 to D3 (with initial crack widths exceeding 0.05 in.) were able to reach stresses larger than the yield stress after unloading and reloading them to failure. Specimens D9, D11 and D17, nevertheless, failed during initial loading at stresses exceeding the yield stress and crack widths ranging from 0.06 in. to 0.13 in.

Specimens in Series 2, reached bar stresses at failure ranging from 73 to 79 ksi (mean = 75 ksi). Maximum laminar crack width at failure exceeded 0.08 in. in Series 2. Specimens in Series 3 reached stresses at failure ranging from 78 to 83 ksi (mean = 80 ksi). Maximum laminar crack width at failure exceeded 0.1 in. in Series 3.

The measurements indicate that the use of at least three ASTM A193 $\frac{3}{4}$ " diameter threaded rods with an embedment length of 12 in. below the surface of the splice, spaced at 26.5 in. in the direction of the splice, and furnished with bearing plates and nuts, was effective in increasing the ability of the lap splices to reach stresses beyond the yield stress of the bars.

OBSERVATIONS

Figures 64 to 81 show measured force-elongation curves. Reported elongations are measured changes in the distance between the outer infrared targets mounted on the bars closer to the East face of the specimen and the infrared targets mounted on the center of the specimen (Figure 2). The curves show that specimens in Series 3 (with anchors with 12 in. embedment, 26.5 in. spacing, and bearing plates, washers and nuts) were more ductile than other specimens.

Crack patterns photographed near failure are shown in Figures 82 to 99. Force-crack width curves are shown in Figures 10 to 27. Four LVDTs were used in each specimen to measure laminar crack width near splice ends (one LVDT at each corner of the specimen –in a plan view-). The reported laminar crack widths are measurements from the LVDT producing the largest reading at failure.

Measured force-crack width curves confirm that specimens in Series 3 reached larger laminar crack widths at failure.

Vertical and horizontal deformations measured with infrared targets (Figure 2) are shown in Figures 28 to 63. They were calculated as the changes in distances between adjacent targets. Comparisons between LVDT readings and Optotrak readings at the same load point are shown in Table 6.

CONCLUSIONS

The tests of 79-in. lap splices of #11 reinforcing bars resulted in the following three conclusions:

1. If the existing laminar crack does not exceed 0.05 in., the test splices developed a minimum tensile stress of 67 ksi and a maximum tensile stress of 80 ksi.
2. If the existing laminar crack width was more than 0.05 in. and did not exceed 0.08 in., the transverse reinforcement as described in Figure 6 made it possible to develop a minimum tensile stress of 78 ksi and a maximum tensile stress of 83 ksi. Transverse reinforcement was installed using ASTM A193 $\frac{3}{4}$ " diameter threaded rod drilled and epoxied into the concrete in the direction perpendicular to the plane of the bars.
3. The observed increase in strength was associated with increased ductility.

TABLES

Table 1 Concrete Mix Proportions

Component	Weight of Component / Weight of Cement
Type 1 Portland Cement	1
Fine Aggregate (#23 sand, max. size = 1/20 in.)	2.4
Coarse Aggregate (#4 and #8 stone, max. size = 1¼ in.)	2.6
Water	0.55

Table 2 Concrete Strength

Test Specimen	Cast Date	Test Date	Concrete Compressive Strength* (psi)	Concrete Splitting Cylinder Strength* (psi)	Age of Specimen (days)
D1	1/11/2017	2/13/2017	3900	450	33
D2		2/15/2017	3900	450	35
D3		2/15/2017	3900	450	35
D4		2/20/2017	4000	350	40
D5		2/22/2017	4000	350	42
D6		2/23/2017	4000	350	43
D7		2/26/2017	4200	400	46
D8		3/6/2017	4100	450	54
D9		3/10/2017	4100	400	58
D10		3/14/2017	4200	450	62
D11		3/17/2017	4300	400	65
D12		3/22/2017	4100	450	70
D13	4/27/2017	6/14/2017	4400	450	48
D14		6/19/2017	4300	450	53
D15		6/22/2017	4500	400	56
D16		6/29/2017	4300	400	63
D17		7/5/2017	4400	450	69
D18		7/6/2017	4300	450	70

*Mean from 3 tests

Table 3 Reinforcement

Bar Designation	#11
Nominal Diameter, in.	1.41
Nominal Area, in ²	1.56
Nominal Perimeter, in.	4.43
Unit Weight, lbf/ft	5.31
Yield Stress*, ksi	67

*Note: mean from tests of twelve coupons

Table 4 Sensors

Sensor Type	Manufacturer	Model Number	Serial Number	Location	Range	Accuracy
Load Cell	Tokyo Sokki	KCB-500KNA	ALU03006	East	112 kip	400 lbf
		KCB-500KNA	ALU03005	West		
LVDT	Schaevitz	DE EC 250	12838	NE	+/-0.25 in.	0.002 in.
		DC EC 500	23618	SE	+/-0.50 in.	0.001 in.
		DC EC 1000	8702*	NE	+/-1.00 in.	0.004 in.
		DC EC 1000	J4914*	SE		
		DC EC 1000	X00598	NW		
		DC EC 1000	J4913	SW		
Optotrak	Northern Digital Inc.	PRO Series 600	-	-	-	0.005 in.

*12838 was changed to 8702 starting from test D2, 23618 was changed to J4914 starting from test D11

Table 5 Summary of Results

Test Series	ID	Concrete Comp. Strength (psi)	Concrete Splitting Strength (Tensile) (psi)	Threaded anchor spacing (in)	Number of Anchors	Threaded rod embedment depth below bottom of splice (in)	Bearing Plate Y/N	Max reinf. Stress at Splice Ends During Initial Loading (ksi)	Max Reinf. Stress at Splice End (ksi)	Max Lam. Crack Width During Initial Loading** (in)	Max Lam. Crack Width at Failure** (in)
1	D1	3900	450	N/A	0	N/A	N	72	73	0.07	0.08
1	D2	3900	450	N/A	0	N/A	N	71	71	0.06	0.07
1	D3	3900	450	N/A	0	N/A	N	80	81	0.11	0.18
2	D4	4000	350	40	2	5	N	75	79	0.06	0.08
2	D5	4000	350	26.5	2	5	N	70	74	0.07	0.24
2	D6	4000	350	53	2	5	N	71	75	0.06	0.09
2	D7	4200	400	26.5	3	5	N	71	73	0.06	0.10
3	D8	4100	450	26.5	3	12	Y	69	83	0.08	0.18
1	D9*	4100	400	N/A	0	N/A	N	76	76	0.09	0.09*
3	D10	4200	450	26.5	3	12	Y	72	79	0.06	0.13
1	D11*	4300	400	N/A	0	N/A	N	71	71	0.06	0.06*
3	D12	4100	450	26.5	3	12	Y	71	78	0.06	0.11
3	D13	4400	450	26.5	3	12	Y	71	80	0.06	0.24
3	D14	4300	450	26.5	3	12	Y	67	79	0.06	0.23
3	D15	4500	400	26.5	3	12	Y	74	81	0.06	0.23
3	D16	4300	400	26.5	3	12	Y	71	80	0.08	0.22
1	D17*	4400	450	N/A	0	N/A	N	77	77	0.13	0.13*
3	D18	4300	450	26.5	3	12	Y	67	80	0.06	0.25


*Note: Denotes initial loading splice failure prior to anchor installation.

**Note: Crack widths based on LVDT measurement.


Table 6 Comparison of Crack Width Measurements Made at NW and SW Corners

Specimen	Load Step (kip)	NW crack width (in)		SW crack width (in)	
		LVDT reading	Mean of two closest Optotrak readings	LVDT reading	Mean of two closest Optotrak readings
D1	110	0	0	0.04	0.04
D2	110	0.01	0.02	0.02	0.02
D3	110	0	0	00	0
D4	110	0	0	0	0
D5	110	0	0	0	0
D6	110	0.02	0.03	0.02	0.02
D7	110	0.04	0.04	0.03	0.03
D8	110	0	0	0.03	0.03
D9	110	0.02	0.02	0	0.01
D10	110	0	0	0.02	0.02
D11	110	0.04	0.04	0.02	0.02
D12	110	0.01	0.01	0.01	0.01
D13	105	0.04	0.04	0.04	0
D14	100	0.05	0.05	0.02	0.04
D15	110	0.04	0.04	0.04	0.04
D16	110	0.03	0.03	0.03	0
D17	110	0.03	0.03	0.02	0.02
D18	110	0.01	0	0.01	0.02

FIGURES



Plan View



Cross Section

Figure 1 Test Specimen Loading Frame Setup and Cross-Sectional Dimensions




Figure 2 Optotrak Target Layout




Figure 3 LVDT Layout





Figure 4 Anchor Configuration for Specimens D4 and D6 (Series 2). Dimension A was 20'' for Specimen D4 and 13.5'' for Specimen D6. Dimension B was 40'' for Specimen D4 and 53'' for Specimen D6.





Figure 5 Anchor configuration for Specimens D5 and D7 (Series 2)





Figure 6 Anchor Configuration for Specimens D8, D10, D12-D16, D18 (Note: Plates, nuts and washers were used in specimens D8, D10, D12-D16, D18 –Series 3)




Figure 7 Anchor Plate Assembly for Specimens D8, D10, D12-D16, D18 (Series 3)




Figure 8 Maximum Crack Width at Splice Ends at Failure




Figure 9 Maximum Reinforcement Stress at Splice Ends at Failure




Figure 10 D1 Load vs. Crack Width Plot




Figure 11 D2 Load vs. Crack Width 1




Figure 12 D3 Load vs. Crack Width




Figure 13 D4 Load vs. Crack Width




Figure 14 D5 Load vs. Crack Width




Figure 15 D6 Load vs. Crack Width




Figure 16 D7 Load vs. Crack Width




Figure 17 D8 Load vs. Crack Width




Figure 18 D9 Load vs. Crack Width




Figure 19 D10 Load vs. Crack Width




Figure 20 D11 Load vs. Crack Width




Figure 21 D12 Load vs. Crack Width




Figure 22 D13 Load vs. Crack Width




Figure 23 D14 Load vs. Crack Width




Figure 24 D15 Load vs. Crack Width




Figure 25 D16 Load vs. Crack Width




Figure 26 D17 Load vs. Crack Width




Figure 27 D18 Load vs. Crack Width




Figure 28 Horizontal Deformations, Load and Reload, D1





Figure 29 Horizontal Deformations, Load and Reload, D2





Figure 30 Horizontal Deformations, Load and Reload, D3




Figure 31 Horizontal Deformations, Load and Reload, D4





Figure 32 Horizontal Deformations, Load and Reload, D5





Figure 33 Horizontal Deformations, Load and Reload, D6





Figure 34 Horizontal Deformations, Load and Reload, D7





Figure 35 Horizontal Deformations, Load and Reload, D8




Figure 36 Horizontal Deformations, First Loading, D9





Figure 37 Horizontal Deformations, Load and Reload, D10




Figure 38 Horizontal Deformations, First Loading, D11




Figure 39 Horizontal Deformations, Load and Reload, D12





Figure 40 Horizontal Deformations, Load and Reload, D13




Figure 41 Horizontal Deformations, Load and Reload, D14




Figure 42 Horizontal Deformations, Load and Reload, D15





Figure 43 Horizontal Deformations, Load and Reload, D16




Figure 44 Horizontal Deformations, First Loading, D17





Figure 45 Horizontal Deformations, Load and Reload, D18




Figure 46 Vertical Deformations, Load and Reload, D1




Figure 47 Vertical Deformations, Load and Reload, D2





Figure 48 Vertical Deformations, Load and Reload, D3




Figure 49 Vertical Deformations, Load and Reload, D4




Figure 50 Vertical Deformations, Load and Reload, D5





Figure 51 Vertical Deformations, Load and Reload, D6




Figure 52 Vertical Deformations, Load and Reload, D7




Figure 53 Vertical Deformations, Load and Reload, D8




Figure 54 Vertical Deformations, First Loading, D9




Figure 55 Vertical Deformations, Load and Reload, D10




Figure 56 Vertical Deformations, First Loading, D11




Figure 57 Vertical Deformations, Load and Reload, D12




Figure 58 Vertical Deformations, Load and Reload, D13




Figure 59 Vertical Deformations, Load and Reload, D14




Figure 60 Vertical Deformations, Load and Reload, D15




Figure 61 Vertical Deformations, Load and Reload, D16




Figure 62 Vertical Deformations, Load and Reload, D17




Figure 63 Vertical Deformations, Load and Reload, D18




Figure 64 Specimen Elongation, Load and Reload, D1




Figure 65 Specimen Elongation, Load and Reload, D2




Figure 66 Specimen Elongation, Load and Reload, D3




Figure 67 Specimen Elongation, Load and Reload, D4




Figure 68 Specimen Elongation, Load and Reload, D5




Figure 69 Specimen Elongation, Load and Reload, D6




Figure 70 Specimen Elongation, Load and Reload, D7




Figure 71 Specimen Elongation, Load and Reload, D8




Figure 72 Specimen Elongation, Load and Reload, D9




Figure 73 Specimen Elongation, Load and Reload, D10




Figure 74 Specimen Elongation, Load and Reload, D11




Figure 75 Specimen Elongation, Load and Reload, D12




Figure 76 Specimen Elongation, Load and Reload, D13




Figure 77 Specimen Elongation, Load and Reload, D14




Figure 78 Specimen Elongation, Load and Reload, D15




Figure 79 Specimen Elongation, Load and Reload, D16




Figure 80 Specimen Elongation, Load and Reload, D17




Figure 81 Specimen Elongation, Load and Reload, D18




Figure 82 Test Photo Specimen D1, SE corner, 108 kips



Figure 83 Test Photo Specimen D2, NE corner, 90 kips



Figure 84 Test Photo Specimen D3, NW corner, 108 kips



Figure 85 Test Photo Specimen D4, NW corner, 122 kips




Figure 86 Test Photo Specimen D5, SE corner, 108 kips



Figure 87 Test Photo Specimen D6, SW corner, 110 kips




Figure 88 Test Photo Specimen D7, SW corner, 110 kips



Figure 89 Test Photo Specimen D8, SE corner, 126 kips




Figure 90 Test Photo Specimen D9, NW corner, 115 kips




Figure 91 Test Photo Specimen D10, SW corner, 120 kips




Figure 92 Test Photo Specimen D11, NW corner, 110 kips




Figure 93 Test Photo Specimen D12, NE corner, 120 kips



Figure 94 Test Photo Specimen D13, SW corner, 120 kips




Figure 95 Test Photo Specimen D14, SE corner, 120 kips



Figure 96 Test Photo Specimen D15, SW corner, 120 kips




Figure 97 Test Photo Specimen D16, NE corner, 120 kips



Figure 98 Test Photo Specimen D17, NE corner, 110 kips






Figure 99 Test Photo Specimen D18, NE corner, 120 kips



Figure 100 Testing Setup



General Information					
Date	Disp Ticket Num	Truck No.	Time on Ticket	Time of Arrival	Temp. in Lab
01/11/17	11832573	1982	16:12	4:26 PM	
Measurements made upon arrival of concrete					
Slump (ASTM C143 - 10a)		Air Content (ASTM C231 - 10)			
Time ₁	Result ₁	Time ₁	Result ₁	S/N of Air Meter	
4:34 PM	8 1/2"	4:49 PM	8 1/4%	LAF 8	
Time ₂	Result ₂	Time ₂	Result ₂	S/N of Scale	
4:51 PM	8 1/2"			H3802360	
Unit Weight (ASTM C138 - 10b)					
Time ₁	Wt. of Cont. ₁	Total Wt. ₁	Wt. of Conc. ₁	Result ₁ = Wt. of Conc./Vol. of Cont.	
4:40 PM	8.50	43.20	34.70	138.8	
Time ₂	Wt. of Cont. ₂	Total Wt. ₂	Wt. of Conc. ₂	Result ₂ = Wt. of Conc./Vol. of Cont.	
Times of actions during and after casting					
Layer 1 placed	Layer 1 vibration complete	Layer 2 placed	Layer 2 vibration complete	Top surface struck off	Truck Departing Lab
4:38 PM	4:46 PM	4:52 PM	4:58 PM		4:56 PM
Lifting Inserts Placed	Covered with plastic	Plastic removed	Covered with burlap	Burlap doused with water	Covered with plastic
8:30 pm	9:30 pm	see curing	9:15 pm	see curing	see curing
Recorded by		Signature		Date	Time
JASPAL S SAINI				01/11/17	
Checked by		Signature		Date	Time
Kinsy Skiller				1/11/17	9:30 pm
Checked by		Signature		Date	Time
Comments:					
*The following ASTM standards and specifications will be followed during casting: C172-10, C192-07, C470-09					

Truck Appendix 1, Pg 2 of 41

Truck	Driver	User	Disp Ticket Num	Ticket ID	Time	Date
1982	1076	user	11832573	0	16:13	1/11/17
Load Size	Mix Code	Returned	Qty	Mix Age	Seq	Load ID
7.00 CYDS	4000CC				D	43104

Description	Design Qty	Adj.T	Required	Batched	Actual Wat
Batch: 1 ----	Start: 16:13:10		End:	Time (hh:mm:ss):	
Buzzi	588 lb		4116 lb	4105 lb	
STONE-8	940 lb		6629 lb	6600 lb	6 gl
STONE-4	620 lb		4373 lb	4360 lb	4 gl
SAND-23	1435 lb		10547 lb	10520 lb	60 gl
WATER	322.4 lb		1742.7 lb	1732.0 lb	207.5 gl
MICROAIR	1.10 /C		45.28 oz	45.00 oz	
GLENIUM 7511	2.00 /C #		82.32 oz	82.00 oz	

Actual		Num Batches:	1									
Load	27325 lb	Design W/C:	0.548	Water/Cement:	0.564	A	Design	270.4 gl	Actual	277.4 gl	To Add:	0.0 gl
Slump:	4.00 in	Water in Truck:	0.0 lb	Adjust Water:	0.0 lb / Load	Trim Water:	10.0 lb /	CYE				



General Information					
Date	Disp Ticket Num	Truck No.	Time on Ticket	Time of Arrival	Temp. in Lab
01/11/17	11832575	1669	16:39	4:58 PM	
Measurements made upon arrival of concrete					
Slump (ASTM C143 - 10a)		Air Content (ASTM C231 - 10)			
Time ₁	Result ₁	Time ₁	Result ₁	S/N of Air Meter	
5:04 PM	8 1/4"	5:12 PM	7.9%	LAF 8	
Time ₂	Result ₂	Time ₂	Result ₂	S/N of Scale	
5:19 PM	8 3/4"			H3802360	
Unit Weight (ASTM C138 - 10b)					
Time ₁	Wt. of Cont. ₁	Total Wt. ₁	Wt. of Conc. ₁	Result ₁ = Wt. of Conc./Vol. of Cont.	
5:09 PM	8.50	43.70	35.20	140.8	
Time ₂	Wt. of Cont. ₂	Total Wt. ₂	Wt. of Conc. ₂	Result ₂ = Wt. of Conc./Vol. of Cont.	
Times of actions during and after casting					
Layer 1 placed	Layer 1 vibration complete	Layer 2 placed	Layer 2 vibration complete	Top surface struck off	Truck Departing Lab
5:10 PM	5:12 PM	5:22 PM	5:24 PM		5:25 PM
Lifting Inserts Placed	Covered with plastic	Plastic removed	Covered with burlap	Burlap doused with water	Covered with plastic
8:30 pm	9:30 pm	see curing	9:15 pm	see curing	see curing
Recorded by		Signature		Date	Time
JASPAL S SAINI				01/11/17	
Checked by		Signature		Date	Time
Kinsley Skiller				1/11/17	9:30 pm
Checked by		Signature		Date	Time
Comments:					
*The following ASTM standards and specifications will be followed during casting: C172-10, C192-07, C470-09					

Truck 2 D7-D12
Appendix 1, Pg 4 of 41

Truck 1669	Driver 2140	User user	Disp Ticket Num 11832575	Ticket ID 0	Time Date 16:40 1/11/17
Load Size 7.00 CYDS	Mix Code 4000CC	Returned	Qty	Mix Age	Seq D
					Load ID 43106

Description	Design Qty	Adj.T	Required	Batched	Actual Wat
Batch: 1 -----	Start: 16:40:24		End:	Time (hh:mm:ss):	
Buzzi	588 lb		4116 lb	4110 lb	
STONE-8	940 lb		6629 lb	6580 lb	6 gl
STONE-4	620 lb		4373 lb	4420 lb	4 gl
SAND-23	1435 lb		10547 lb	10520 lb	60 gl
WATER	322.4 lb		1742.7 lb	1732.0 lb	207.5 gl
MICROAIR	1.10 /C		45.28 oz	44.50 oz	
GLENIUM 7511	2.00 /C #		82.32 oz	82.00 oz	



Actual Load	27370 lb	Num Batches:	1	Design	270.4 gl	Actual	277.4 gl	To Add:	0.0 gl
Slump:	4.00 in	Design W/C:	0.548	Water/Cement:	0.563 A	Adjust Water:	0.0 lb / Load	Trim Water:	10.0 lb /
		Water in Truck:	0.0 lb						CYL Note: Manual feed occurred

General Information			
Specimen(s)	Date	Specimen Age	
D1-D12 + cylinders	1/11/17	0 hrs.	
	Time Beginning	Time Ending	
	8:30 pm	9:30 pm	
	Temperature inside Lab (deg. F)		
	55 ° F		
Description of Work Performed			
<p>↔ Tiff inserts placed into fresh concrete</p> <p>↔ concrete specimens + cylinders covered w/ burlap + w/ plastic tarp</p>			
Recorded by	Signature	Date	Time
Kinsy Skillen		1/11/17	9:38 pm
Checked by	Signature	Date	Time
Prateek Shah		1/11/17	9:38 pm
Checked by	Signature	Date	Time
Comments:			
*Test specimens and associated cylinders are to be cured under wet burlap for seven days			

General Information		
Specimen(s)	Date	Specimen Age
D1-D12 + cylinders	1/12/17	~ 18 hrs
	Time Beginning	Time Ending
	7:45 am	8:20 am
	Temperature inside Lab (deg. F)	
	55° F	



Description of Work Performed


concrete specimens + cylinders doused
 w/ water. Burlap + plastic tarp covering.



Recorded by	Signature	Date	Time
Kinscy Skiller		1/12/17	8:25 am
Checked by	Signature	Date	Time
Pateek Shah		1/12/17	8:25 am
Checked by	Signature	Date	Time



Comments:



*Test specimens and associated cylinders are to be cured under wet burlap for seven days



General Information			
Specimen(s)	Date	Specimen Age	
D1-D12 + cylinders	1/12/17	1 day	
	Time Beginning	Time Ending	
	7:30 pm	7:45 pm	
	Temperature inside Lab (deg. F)		
	55° F		
Description of Work Performed			
Specimens + cylinders doused w/ water and recovered w/ plastic tarp			
Recorded by	Signature	Date	Time
Kinsay Skillen		1/12/17	8:00 pm
Checked by	Signature	Date	Time
Prateek Shah		1/12/17	8:00 pm
Checked by	Signature	Date	Time
Comments:			
*Test specimens and associated cylinders are to be cured under wet burlap for seven days			

General Information			
Specimen(s)	Date	Specimen Age	
D1-D12 + cylinders	1/13/17	2 days	
	Time Beginning	Time Ending	
	7:30 am	8:00 am	
	Temperature inside Lab (deg. F)		
	55° F		
Description of Work Performed			
specimens + cylinders doused w/ water + covered w/ plastic tarp.			
Recorded by	Signature	Date	Time
Kinsay Skillin		1/13/17	8:10 am
Checked by	Signature	Date	Time
Prateek Slah	P.Slah	1/13/17	8:10 am
Checked by	Signature	Date	Time
Comments:			
*Test specimens and associated cylinders are to be cured under wet burlap for seven days			

General Information			
Specimen(s)	Date	Specimen Age	
D1-D12 + cylinders	1/13/17	2 days	
	Time Beginning	Time Ending	
	2:00 pm	5:30 pm	
	Temperature inside Lab (deg. F)		
	55° F		
Description of Work Performed			
<p>- cylinder molds struck, specimens removed from formwork.</p> <p>- re-covered w/ doused burlap and plastic sheeting upon form + cylinder striking.</p>			
Recorded by	Signature	Date	Time
Kinsy Skillen		1/13/17	6:00 pm
Checked by	Signature	Date	Time
Prateek Shah		1/13/17	6:00 pm
Checked by	Signature	Date	Time
Comments:			
*Test specimens and associated cylinders are to be cured under wet burlap for seven days			

General Information			
Specimen(s)	Date	Specimen Age	
D1-D12 + cylinders	1/14/17	3 days	
	Time Beginning	Time Ending	
	9:00 am	9:15 am	
	Temperature inside Lab (deg. F)		
	55 °F		
Description of Work Performed			
<p>cylinders & specimens doused w/ water and recovered w/ plastic sheeting.</p>			
Recorded by	Signature	Date	Time
Kinscy Skillen		1/14/17	9:30 am
Checked by	Signature	Date	Time
Prateek Seal		1/14/17	9:30 am
Checked by	Signature	Date	Time
Comments:			
*Test specimens and associated cylinders are to be cured under wet burlap for seven days			



General Information			
Specimen(s)	Date	Specimen Age	
D1-D12 + cylinders	1/14/17	3 day	
	Time Beginning	Time Ending	
	6:00 pm	6:15 pm	
	Temperature inside Lab (deg. F)		
	55°F		
Description of Work Performed			
cylinders + specimens doused w/ water and recovered w/ plastic tarp			
Recorded by	Signature	Date	Time
Kinsay Skillen		1/14/17	6:30 pm
Checked by	Signature	Date	Time
Prateek Shah		1/14/17	6:30 pm
Checked by	Signature	Date	Time
Comments:			
*Test specimens and associated cylinders are to be cured under wet burlap for seven days			

General Information			
Specimen(s)	Date	Specimen Age	
D1-D12 + cylinders	1/15/17	4 day	
	Time Beginning	Time Ending	
	9:30 am	9:45 am	
	Temperature inside Lab (deg. F)		
	55° F		
Description of Work Performed			
Specimens doused w/ water and recorded			
Recorded by	Signature	Date	Time
Kinsy Skiller		1/15/17	9:50 am
Checked by	Signature	Date	Time
Prateek Shah		1/15/17	9:50 am
Checked by	Signature	Date	Time
Comments:			
*Test specimens and associated cylinders are to be cured under wet burlap for seven days			

General Information		
Specimen(s)	Date	Specimen Age
D1-D12 + cylinders	1/15/17	4 day
	Time Beginning	Time Ending
	5:15 pm	5:25 pm
	Temperature inside Lab (deg. F)	
	55°F	



Description of Work Performed


specimens doused w/ water
+ recovered



Recorded by	Signature	Date	Time
Kinsley Skiller		1/15/17	5:30 pm
Checked by	Signature	Date	Time
Prateek Shah		1/15/17	5:30 pm
Checked by	Signature	Date	Time


Comments:

*Test specimens and associated cylinders are to be cured under wet burlap for seven days

General Information			
Specimen(s)	Date	Specimen Age	
D1-D12 + cylinders	1/16/17	8 day	
	Time Beginning	Time Ending	
	7:45 am	7:55 am	
	Temperature inside Lab (deg. F)		
	55° F		
Description of Work Performed			
specimens doused w/ water and covered			
Recorded by	Signature	Date	Time
Kinsy Skiller		1/16/17	8:00 am
Checked by	Signature	Date	Time
Prateek Shah		1/16/17	8:00 am
Checked by	Signature	Date	Time
Comments:			
*Test specimens and associated cylinders are to be cured under wet burlap for seven days			

General Information			
Specimen(s)	Date	Specimen Age	
DI-D12 + cylinders	1/16/17	5 days	
	Time Beginning	Time Ending	
	6:30 pm	6:45 pm	
	Temperature inside Lab (deg. F)		
	55° F		
Description of Work Performed			
Specimens doused w/ water and covered			
Recorded by	Signature	Date	Time
Kinsay Skiller		1/16/17	6:50 pm
Checked by	Signature	Date	Time
Prateek Shah	PSL	1/16/17	6:50 pm
Checked by	Signature	Date	Time
Comments:			
*Test specimens and associated cylinders are to be cured under wet burlap for seven days			



General Information			
Specimen(s)	Date	Specimen Age	
D1-D12 + cylinders	1/17/17	6 days	
	Time Beginning	Time Ending	
	8:15 am	8:30 am	
	Temperature inside Lab (deg. F)		
	55°F		
Description of Work Performed			
specimens doused w/ water and covered			
Recorded by	Signature	Date	Time
Kinsy Skiller		1/16/17	8:40 am
Checked by	Signature	Date	Time
Prateek Stal		1/16/17	8:40 am
Checked by	Signature	Date	Time
Comments:			
*Test specimens and associated cylinders are to be cured under wet burlap for seven days			

General Information			
Specimen(s)	Date	Specimen Age	
DI-D1Z ← cylinders	1/17/17	6 days	
	Time Beginning	Time Ending	
	7:15 pm	7:30 pm	
	Temperature inside Lab (deg. F)		
	55° F		
Description of Work Performed			
Specimens doused w/ water and covered			
Recorded by	Signature	Date	Time
Kinsy Skinner		1/17/17	7:35 pm
Checked by	Signature	Date	Time
Prateek Shah	PSL	1/17/17	7:35 pm
Checked by	Signature	Date	Time
Comments:			
*Test specimens and associated cylinders are to be cured under wet burlap for seven days			

General Information		
Specimen(s)	Date	Specimen Age
D1-D12 + cylinders	1/18/17	7 day
	Time Beginning	Time Ending
	8:15 am	8:25 am
	Temperature inside Lab (deg. F)	
	55° F	

Description of Work Performed

specimens + cylinders dased w/ water + covered

Recorded by	Signature	Date	Time
Kinsy Skiller		1/18/17	8:40 am
Checked by	Signature	Date	Time
Prateek Shah		1/18/17	8:40 am
Checked by	Signature	Date	Time



Comments:

*Test specimens and associated cylinders are to be cured under wet burlap for seven days

General Information		
Specimen(s)	Date	Specimen Age
D1-D12 + cylinders	1/18/17	7 days
	Time Beginning	Time Ending
	4:20 pm	4:30 pm
	Temperature inside Lab (deg. F)	
	55° F	

Description of Work Performed

Specimens + cylinders doused w/
water + covered

Recorded by	Signature	Date	Time
Kinsy Skilce		1/18/17	5:10 pm
Checked by	Signature	Date	Time
Prateek Sriv		1/18/17	5:10 pm
Checked by	Signature	Date	Time

Comments:

*Test specimens and associated cylinders are to be cured under wet burlap for seven days

Statement Of Traceability

This Thermometer with Serial number 330717
has been calibrated and tested against standards traceable to the
National Institute of Standards and Technology (NIST) using the methods
outlined in Monograph 150, Monograph 250-23 from NIST and ASTM E77-
07 in THERMCO's ISO/IEC and ILAC accredited calibration laboratory.
Each thermometer has a unique serial number for identification.
The thermometer can be calibrated or certified at individual temperature
points of your choice at an additional charge by contacting Thermco
Products, Inc. technical support team.

R. CASARIO

R. Casario, Laboratory Director
email: Lab@ThermcoProducts.com
fax: 973-940-1112

CAL DATE FEB 09 2016

THERMCO
PRODUCTS, INC.

www.ThermcoProducts.com
10 Millpond Drive Unit #10 Lafayette, NJ 07846 - Phone: 973.300.9100

CL-033

Statement Of Traceability

This Thermometer with Serial number 330706
has been calibrated and tested against standards traceable to the
National Institute of Standards and Technology (NIST) using the methods
outlined in Monograph 150, Monograph 250-23 from NIST and ASTM E77-
07 in THERMCO's ISO/IEC and ILAC accredited calibration laboratory.
Each thermometer has a unique serial number for identification.
The thermometer can be calibrated or certified at individual temperature
points of your choice at an additional charge by contacting Thermco
Products, Inc. technical support team.

R. CASARIO

R. Casario, Laboratory Director
email: Lab@ThermcoProducts.com
fax: 973-940-1112

CAL DATE FEB 09 2016

THERMCO
PRODUCTS, INC.

CALSER CORPORATION

302 N. Belt East, Swansea, IL 62226 (618) 277-0329

SCALE CALIBRATION DATA AND REPORT

Report #: VN# 10576-011

Page 1 of 1

Customer	Patriot Engineering & Environmental
Location	717 C Farabee Court Lafayette, IN 47905
Machine	AND 150lb Scale Model FG-60K
Serial No.	H3802360
Customer Asset No.	N/A

Date	03/23/16
Customer Order No.	Email
Order Date	02/22/16
Temp.	64° F
Date Last Done	03/25/15
Calibration Next Due	3/17

Applied Force	*	Indicated Force	Error	%	Applied Force	*	Indicated Force	Error	%
Run #1					Run #2				
"As Found" Condition					"As Left" Condition				
150lb Range	*	.05lb / DIV			150lb Range	*	.05lb / DIV		
0	W	0	0	0.00	0	W	0	0	0.00
2	W	2.00	0.00	0.00	2	W	2.00	0.00	0.00
4	W	4.00	0.00	0.00	4	W	4.00	0.00	0.00
6	W	6.00	0.00	0.00	6	W	6.00	0.00	0.00
8	W	8.00	0.00	0.00	8	W	8.00	0.00	0.00
10	W	10.00	0.00	0.00	10	W	10.00	0.00	0.00
20	W	20.00	0.00	0.00	20	W	20.00	0.00	0.00
30	W	30.00	0.00	0.00	30	W	29.90	-0.10	0.33
40	W	40.05	0.05	0.13	40	W	40.05	0.05	0.13
50	W	50.00	0.00	0.00	50	W	50.00	0.00	0.00
60	W	60.05	0.05	0.08	60	W	60.05	0.05	0.08
70	W	70.05	0.05	0.07	70	W	70.05	0.05	0.07
80	W	80.05	0.05	0.06	80	W	80.05	0.05	0.06
90	W	90.05	0.05	0.06	90	W	90.05	0.05	0.06
100	W	100.05	0.05	0.05	100	W	100.05	0.05	0.05
109	W	109.05	0.05	0.05	109	W	109.05	0.05	0.05
0	W	0	0	0.00	0	W	0	0	0.00

Notes:

1. Calibration done according to NIST Handbook 44 and Calser Corporation Procedure # 4-01, Rev 1.
2. Uncertainties of all weights meet class F tolerance and certificates for individual weights are available.
3. Linearity was checked.
4. Weights meet specifications of ASTM E-4 (Par. 12.1)

***CALIBRATION EQUIPMENT**

All verification equipment-including dead weights, proving rings, load cells, etc, is calibrated and traceable to the latest procedures stipulated by the National Institute of Standards and Technology (NIST). All instrument readings have been corrected for temperature where necessary.

ACCURACY SUMMARY

Verification Equipment

Capacity Range	Loading Range Within	Error (%)	Manufacturer and Serial #	* L/C	Range	Verification Agency and Date
Run 1						
150lb Range	2 - 109	0.13 %	Rice Lake	W	1 - 109lb	MO Dept. of Agriculture
			Set # 99-452 & Various dead weights			06/03/10
Run 2						
150lb Range	2 - 109	0.33 %				

Calibration Technician: Jerry Parker

This report shall not be copied except in its entirety without express written approval of Calser Corp.




**PATRIOT ENGINEERING
and ENVIRONMENTAL, INC.**

717 C Farabee Court
Lafayette, IN 47905
(765) 447-4477 FAX: (765) 447-4045

Air Meter Calibration

Air Meter Calibration Record

Calibrated by:	Amy Kolzow	Date:	12/9/2016											
Equipment:	Type B Pressure Meter													
Serial No:	LAF-8	Range of Calibration:	5.0 +/- 0.1%											
Previous Calibration Date:	8/30/2016	Next Due Date:	3/9/2017											
Calibration Equip Used:	Traceable Thermometer 112003335, O'Haus 8,100g Scale Model AV8101, O'Haus 35lb Scale 2407-00	Calib.Procedure:	CME #21											
Action Recommended:	Repair <input type="checkbox"/> Replace <input type="checkbox"/> None <input checked="" type="checkbox"/>	Other <input type="checkbox"/> Explain: _____												
PROCEDURE:														
<p>Screw short pipe into threaded hole on underside of lid. Fill bowl with water and attach the lid to the bowl. Open both petcocks and fill the meter with water through the petcock that has the pipe affixed to it. Attach the curved pipe to the petcock to which the short pipe has been affixed. Close the opposite petcock and pump the meter up to its initial pressure. Place the measuring device under the curved pipe and release the air from the meter, filling the device to capacity. Release the remaining air, remove the curved pipe, then pump the meter back to its set point. Release the air, tapping on the gauge until a constant reading is reached. This should equal 5%.</p>														
CALIBRATION:														
	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 15%;">Trial #</th> <th style="width: 35%;">Theoretical</th> <th style="width: 35%;">Actual</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>5%</td> <td>5.1</td> </tr> <tr> <td>2</td> <td>5%</td> <td>5.1</td> </tr> <tr> <td>3</td> <td>5%</td> <td>5.1</td> </tr> </tbody> </table>	Trial #	Theoretical	Actual	1	5%	5.1	2	5%	5.1	3	5%	5.1	IP: <u>3</u> % Volume: <u>0.2513</u> cf <u>0.0071</u> cm
Trial #	Theoretical	Actual												
1	5%	5.1												
2	5%	5.1												
3	5%	5.1												
COMMENTS: _____														

General Information					
Date	Disp Ticket Num	Truck No.	Time on Ticket	Time of Arrival	Temp. in Lab
04/27/17	11633525	506	12:32	12:55	50° F
Measurements made upon arrival of concrete					
Slump (ASTM C143 - 10a)		Air Content (ASTM C231 - 10)			
Time ₁	Result ₁	Time ₁	Result ₁	S/N of Air Meter	
1:15 pm	7 3/4"	1:15 pm	6.7%	LAF-3	
Time ₂	Result ₂	Time ₂	Result ₂	S/N of Scale	
1:30 pm	6 3/4"	1:30 pm	6.8%	AE40116811	
Unit Weight (ASTM C138 - 10b)				v = 0.2503 cf	
Time ₁	Wt. of Cont. ₁	Total Wt. ₁	Wt. of Conc. ₁	Result ₁ = Wt. of Conc./Vol. of Cont.	
1:15 pm	8.15 lb	44.20 lb	36.05 lb		
Time ₂	Wt. of Cont. ₂	Total Wt. ₂	Wt. of Conc. ₂	Result ₂ = Wt. of Conc./Vol. of Cont.	
1:30 pm	8.15 lb	43.70 lb			
Times of actions during and after casting					
Layer 1 placed	Layer 1 vibration complete	Layer 2 placed	Layer 2 vibration complete	Top surface struck off	Truck Departing Lab
1:00 pm +	1:15 pm	1:15 pm +	1:35 pm	2:00 pm	1:36 pm
Lifting Inserts Placed	Covered with plastic	Plastic removed	Covered with burlap	Burlap doused with water	Covered with plastic
Recorded by		Signature		Date	Time
Checked by		Signature		Date	Time
Kinsay Skillen				4/27/17	1:45 pm
Checked by		Signature		Date	Time
Comments:					
*The following ASTM standards and specifications will be followed during casting: C172-10, C192-07, C470-09					

Truck	Driver	User	Disp Ticket Num	Ticket ID	Time	Date
506	3634	user	11633525	0	12:32	4/27/17
Load Size	Mix Code	Returned	Qty	Mix Age	Seq	Load ID
7.00 CYDS	4000CC				W	45861

Description	Design Qty	Required	Batched	% Var	% Moisture	Actual	Wat
buzzl	588 lb #	4116 lb	4100 lb	-0.39%			
STONE-8	940 lb #	6613 lb	6560 lb	-0.80%	0.50% M	4 gl	
STONE-4	620 lb #	4340 lb	4300 lb	-0.92%			
SAND-23	1435 lb #	10547 lb	10580 lb	0.31%	5.00% M	60 gl	
WATER	322.4 lb #	1721.7 lb	1745.0 lb	1.41%		209.2 gl	
GLEN 3030	.00 /C #	.00 oz	.00 oz				
microsil	1.10 /C #	45.28 oz	45.00 oz	-0.61%			
GLEN 7911	2.00 /C #	82.32 oz	83.00 oz	0.83%			


Actual	Design	270.4 gl	Num Batches:	1	Actual	273.5 gl	To Add:	0.0 gl
81u	4.00 in							

General Information		
Specimen(s)	Date	Specimen Age
D13 - D18 + cylinders	4/27/17	0 hrs.
	Time Beginning	Time Ending
	5:00 pm	5:30 pm
	Temperature inside Lab (deg. F)	
	65° F	

Description of Work Performed

↔ lift inserts placed

↔ Specimens covered w/ burlap, doused and covered w/ plastic

Recorded by	Signature	Date	Time
Kinsy Skiller		4/27/17	5:45 pm
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time

Comments:

*Test specimens and associated cylinders are to be cured under wet burlap for seven days

General Information			
Specimen(s)	Date	Specimen Age	
D13 - D18 + cylinders	4/28/17	~ 16 hrs	
	Time Beginning	Time Ending	
	10:00 am	10:15 am	
	Temperature inside Lab (deg. F)		
	65° F		
Description of Work Performed			
specimens + cylinders doused w/ water and covered w/ plastic			
Recorded by	Signature	Date	Time
Kinsy Skiller	K.C. Skiller	4/27/17	10:20 am
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time
Comments:			
*Test specimens and associated cylinders are to be cured under wet burlap for seven days			

General Information		
Specimen(s)	Date	Specimen Age
D13 + D18 + cylinders	4/28/17	1 day
	Time Beginning	Time Ending
	6:00 pm	6:15 pm
	Temperature inside Lab (deg. F)	
	65° F	

Description of Work Performed

specimens + cylinders deaired w/ water and covered w/ plastic

Recorded by	Signature	Date	Time
Kinscy Skiller	K. C. Skiller	4/29/17	6:20 pm
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time

Comments:

*Test specimens and associated cylinders are to be cured under wet burlap for seven days

General Information			
Specimen(s)	Date	Specimen Age	
D13 - D18 + cylinders	4/29/17	2 day	
	Time Beginning	Time Ending	
	8:00 am	8:15 am	
	Temperature inside Lab (deg. F)		
	65° F		
Description of Work Performed			
specimens watered, cylinders watered, recovered w/ plastic			
Recorded by	Signature	Date	Time
Kinsley Skiller	K.C. Skiller	4/30/17	8:20 am
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time
Comments:			
*Test specimens and associated cylinders are to be cured under wet burlap for seven days			

General Information			
Specimen(s)	Date	Specimen Age	
D13 - D18 + cylinders	4/29/17	2 days	
	Time Beginning	Time Ending	
	5:00 pm	5:15 pm	
	Temperature inside Lab (deg. F)		
	65° F		
Description of Work Performed			
Specimens, cylinders watered and covered			
Recorded by	Signature	Date	Time
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time
Comments:			
*Test specimens and associated cylinders are to be cured under wet burlap for seven days			

General Information			
Specimen(s)	Date	Specimen Age	
D13-D18 + cylinders	4/30/17	3 days	
	Time Beginning	Time Ending	
	7:45 am	8:00 am	
	Temperature inside Lab (deg. F)		
	65°F		
Description of Work Performed			
specimens, cylinders watered and covered			
Recorded by	Signature	Date	Time
Kinsay Skillen	K. C. Skillen	4/30/17	8:05 am
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time
Comments:			
*Test specimens and associated cylinders are to be cured under wet burlap for seven days			

General Information			
Specimen(s)	Date	Specimen Age	
D13 - D15 + cylinders	4/30/17	3 days	
	Time Beginning	Time Ending	
	4:00 pm	7:30 pm	
	Temperature inside Lab (deg. F)		
	65° F		
Description of Work Performed			
<p>↔ forms struck</p> <p>↔ specimens, cylinders watered and covered</p>			
Recorded by	Signature	Date	Time
Kinsy Skiller	K.C. Skiller	4/30/17	7:40 pm
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time
Comments:			
*Test specimens and associated cylinders are to be cured under wet burlap for seven days			

General Information			
Specimen(s)	Date	Specimen Age	
D13- D18 + cylinders	5/1/17	4 day	
	Time Beginning	Time Ending	
	9:00 am	9:15 am	
	Temperature inside Lab (deg. F)		
	65° F		
Description of Work Performed			
Specimens, cylinders watered and covered			
Recorded by	Signature	Date	Time
Kinsay Skiller	K.C. Skiller	5/1/17	9:20 am
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time
Comments:			
*Test specimens and associated cylinders are to be cured under wet burlap for seven days			

General Information			
Specimen(s)	Date	Specimen Age	
D13- D18 + cylinders	5/1/17	4 day	
	Time Beginning	Time Ending	
	5:00 pm	6:00 pm	
	Temperature inside Lab (deg. F)		
	65°F		
Description of Work Performed			
specimens and cylinders watered and covered			
Recorded by	Signature	Date	Time
Kinsy Skiller	K.C. Skiller	5/1/17	6:00 pm
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time
Comments:			
*Test specimens and associated cylinders are to be cured under wet burlap for seven days			

General Information			
Specimen(s)	Date	Specimen Age	
D13 - D18 4 cylinders	5/2/17	5 days	
	Time Beginning	Time Ending	
	9:30 am	9:45 am	
	Temperature inside Lab (deg. F)		
	70° F		
Description of Work Performed			
specimens, cylinders watered and covered			
Recorded by	Signature	Date	Time
Kinsy Skiller	K. C. Skiller	5/2/17	10:00 am
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time
Comments:			
*Test specimens and associated cylinders are to be cured under wet burlap for seven days			

General Information			
Specimen(s)	Date	Specimen Age	
D13 - D18 4 cylinders	5/2/17	5 days	
	Time Beginning	Time Ending	
	6:00 pm	6:15 pm	
	Temperature inside Lab (deg. F)		
	70° F		
Description of Work Performed			
cylinders, specimens watered and covered			
Recorded by	Signature	Date	Time
Kinsey Skiller	K.C. Skiller	5/2/17	6:30 pm
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time
Comments:			
*Test specimens and associated cylinders are to be cured under wet burlap for seven days			

General Information		
Specimen(s)	Date	Specimen Age
D13-D18 4 cylinders	5/3/17	6 day
	Time Beginning	Time Ending
	10:00 am	10:15 am
	Temperature inside Lab (deg. F)	
	65° F	

Description of Work Performed

specimens, cylinders watered and covered

Recorded by	Signature	Date	Time
Kinsey Skiller	K. P. Skiller	5/3/17	10:30 am
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time

Comments:

*Test specimens and associated cylinders are to be cured under wet burlap for seven days

General Information			
Specimen(s)	Date	Specimen Age	
D13-D18 + cylinders	5/3/17	6 day	
	Time Beginning	Time Ending	
	7:00 pm	7:15 pm	
	Temperature inside Lab (deg. F)		
	65°F		
Description of Work Performed			
specimens and cylinders watered and covered			
Recorded by	Signature	Date	Time
Kinsy Skiller	K.C. Skiller	5/3/17	7:30 pm
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time
Comments:			
*Test specimens and associated cylinders are to be cured under wet burlap for seven days			

General Information			
Specimen(s)	Date	Specimen Age	
D13- D18 + cylinders	5/4/17	7 day	
	Time Beginning	Time Ending	
	9:00 am	9:15 am	
	Temperature inside Lab (deg. F)		
	65°F		
Description of Work Performed			
specimens, cylinders watered and covered			
Recorded by	Signature	Date	Time
Kinsley Skitter	K.C. Skitter	5/4/17	9:30 am
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time
Comments:			
*Test specimens and associated cylinders are to be cured under wet burlap for seven days			

General Information			
Specimen(s)	Date	Specimen Age	
D13 - D18 + cylinders	5/4/17	7 days	
	Time Beginning	Time Ending	
	4:30 pm	5:00 pm	
	Temperature inside Lab (deg. F)		
	65°F		
Description of Work Performed			
specimens, cylinders watered + covered			
Recorded by	Signature	Date	Time
Kinsay Skiller	K.C. Skiller	5/4/17	5:15 pm
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time
Comments:			
*Test specimens and associated cylinders are to be cured under wet burlap for seven days			

CALSER CORPORATION

302 N. Belt East, Swansea, IL 62226 (618) 277-0329

SCALE CALIBRATION DATA AND REPORT

Report #: VN# 11467-007

Page 1 of 1

Customer	Patriot Engineering & Environmental
Location	717 C Farabee Court Lafayette, IN 47905
Machine	Adam 165lb Scale Model CPW Plus 75
Serial No.	AE40116811
Customer Asset No.	N/A

Date	03/07/17
Customer Order #	Email
Order Date	02/14/17
Temp.	71
Date Last Done	03/23/16
Condition of Machine	Good

Verification Reading	*	Machine Reading	Error	%	*	Machine Reading	Error	%	*	Machine Reading	Error	%			
Run #1				"As Found" Condition				Run #2				"As Left" Condition			
165lb Range				.05lb / DIV											
0	S	0	0	0.00	S	0	0	0.00	S	0	0	0.00			
10	S	10.10	0.10	1.00	S	10.00	0.00	0.00	S	10.00	0.00	0.00			
20	S	20.20	0.20	1.00	S	20.00	0.00	0.00	S	20.00	0.00	0.00			
30	S	30.30	0.30	1.00	S	30.00	0.00	0.00	S	30.00	0.00	0.00			
50	S	50.50	0.50	1.00	S	50.00	0.00	0.00	S	50.00	0.00	0.00			
60	S	60.60	0.60	1.00	S	60.00	0.00	0.00	S	60.00	0.00	0.00			
80	S	80.85	0.85	1.06	S	80.00	0.00	0.00	S	80.00	0.00	0.00			
100	S	101.00	1.00	1.00	S	100.00	0.00	0.00	S	100.00	0.00	0.00			
120	S	121.25	1.25	1.04	S	119.95	-0.05	0.04	S	120.00	0.00	0.00			
130	S	131.35	1.35	1.04	S	130.00	0.00	0.00	S	130.00	0.00	0.00			
0	S	0	0	0.00	S	0	0	0.00	S	0	0	0.00			

Notes:

1. Calibration done according to NIST Handbook 44 and Calser Corporation Procedure # 4-01, Rev 1.
2. Uncertainties of all weights meet class F tolerance and certificates for individual weights are available.
3. Linearity was checked.
4. Weights meet specifications of ASTM E-4 (Par. 12.1)

***CALIBRATION EQUIPMENT**

All verification equipment-including dead weights, proving rings, load cells, etc, is calibrated and traceable to the latest procedures stipulated by the National Institute of Standards and Technology (NIST). All instrument readings have been corrected for temperature where necessary.

ACCURACY SUMMARY

Capacity Range	Loading Range Within	Error (%)
Run 1		
165lb Range	10 - 130	1.06 %
Run 2		
165lb Range	10 - 130	0.04 %
Run 3		
165lb Range	10 - 130	0.00 %

VERIFICATION EQUIPMENT

Manufacturer & Serial #	* L/C	Class A Range	Agency & Date
Rice Lake	S	1 - 151 lb	Itin Scale Company
Various			05/06/14
Taylor	TH4	30°F - 120°F	Quality Calibration
TH4			08/26/16

This report shall not be copied except in its entirety without express written approval of Calser Corp.

Calibration Technician Ronnie Agne



**PATRIOT ENGINEERING
and ENVIRONMENTAL, INC.**
717 C Farabee Court
Lafayette, IN 47905
(765) 447-4477 FAX: (765) 447-4045

Air Meter Calibration

Calibrated by: Ken Bosar Date: 3/6/2017
 Equipment: Type B Pressure Meter
 Serial No: LAF-3 Range of Calibration: 5.0 +/- 0.1%
 Previous Calibration Date: 1/16/2017 Next Due Date: 11/15/2016
 Calibration Equip Used: Traceable Thermometer 112003335, O'Haus 8,100g Calib.Procedure: CME #21
Scale Model AV8101, O'Haus 35lb Scale 2407-00
 Action Recommended: Repair Replace None Other Explain: _____

PROCEDURE: Screw short pipe into threaded hole on underside of lid. Fill bowl with water and attach the lid to the bowl. Open both petcocks and fill the meter with water through the petcock that has the pipe affixed to it. Attach the curved pipe to the petcock to which the short pipe has been affixed. Close the opposite petcock and pump the meter up to its initial pressure. Place the measuring device under the curved pipe and release the air from the meter, filling the device to capacity. Release the remaining air, remove the curved pipe, then pump the meter back to its set point. Release the air, tapping on the gauge until a constant reading is reached. This should equal 5%.

CALIBRATION:

Trial #	Theoretical	Actual
1	5%	5
2	5%	5
3	5%	5

IP: 3 %
 Volume: 0.2503 cf
0.0071 cm

COMMENTS: _____

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Cylinder Compression Tests Documentation v.3
(Rev. 11/1/2016)

Specimen: D1-D3 week 1

Sheet 1 of 2

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]		Length [nearest 0.05 in.]			P _{max} [lb _f]	Fracture Type (1-6)
				1	2	1	2	3		
D1-D3	2/16/17	6:00 pm	Dry	6	5.98	12.00	12.00	12.00	104,000	5
D1-D3	2/16/17	6:00 pm	"	6.01	5.98	12.00	12.00	12.00	116,000	5
D1-D3	2/16/17	6:00 pm	"	6.01	5.98	11.95	12.00	12.00	111,000	5
S/N of Testing Machine:			Fomey 9T058							
Recorded by:			Signature			Date		Time		
Aishwarya Puranam			Aishwarya			2/16/17		6:00 pm		
Checked by:			Signature			Date		Time		
Juan Langhany			Juan Langhany			2/16/17		6:00 pm		
Checked by:			Signature			Date		Time		
Comments:										
*Cylinders to be test per ASTM C-39-12 and C-1231-10a with a loading rate of 60,000lb _f /min at concrete ages of 3, 7, 14, 28 days, and on same day that test of corresponding specimen is conducted. Specimens and caps free of defects unless otherwise noted in comments. Average cylinder diameter and area and unit compressive stress (f' _c) calculated on sheet 2 of 2.										

Appendix 2, Pg 1 of 28

APPENDIX C: Purdue Phase III Test Report

25884-000-30R-C01R-00002, Rev. 000, Sheet 150 of 575

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Cylinder Split Tensile Tests Documentation v.2 (Rev. 11/1/2016)

Specimen: D1-D3 week 1

Sheet 1 of 2

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]			Length [nearest 0.1 in.]		P _{max} [lbf]	Fracture Sketch
				end	middle	end	1	2		
D 1	2/16/17	5:30 pm	Dry	5.95	5.95	6.00	12.00	12.00	49,000	①
D 2	2/16/17	↓	Dry	6.00	5.95	6.00	12.00	12.00	54,000	①
D 3	2/16/17		Dry	6.00	5.95	6.00	12.00	12.00	52,000	①
4										
5										
6										

S/N of Testing Machine:

Forney 99058

Recorded by:

Signature

Date

Time

Aishwarya Puranam

Aishwarya

2/16/17

5:00 pm

Checked by:

Signature

Date

Time

Lucas Langhery

Lucas Langhery

2/16/17

5:30 pm

Checked by:

Signature

Date

Time

Comments:

$$f_t = \frac{2P_{max}}{ITD L_{avg}}$$

*Cylinders to be test per ASTM C-496-11 with a loading rate of 15,000lb_f/min at a concrete age of 28 days and on same day that the test of the corresponding specimen is conducted. Specimens free of defects unless otherwise noted in comments. Average cylinder diameter and area and splitting tensile strength (f_t) calculated on sheet 2 of 2.

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]		Length [nearest 0.05 in.]			P _{max} [lbf]	Fracture Type (1-6)
				1	2	1	2	3		
D3-D6	2/24/17	4:35 pm	Dry	5.99	6.05	11.95	12.00	12.00	121,000	6
D3-D6	2/24/17	4:42 pm	Dry	5.95	6.04	12.00	12.00	11.95	118,000	6
D3-D6	2/24/17	4:50 pm	Dry	5.99	6.00	12.00	12.00	11.95	104,000	6
S/N of Testing Machine:			Forney 99058							
Recorded by:			Signature			Date		Time		
Kinsley Skinner			[Signature]			2/24/17		5:14 pm		
Checked by:			Signature			Date		Time		
Checked by:			Signature			Date		Time		
Comments:										
*Cylinders to be test per ASTM C-39-12 and C-1231-10a with a loading rate of 60,000lb _f /min at concrete ages of 3, 7, 14, 28 days, and on same day that test of corresponding specimen is conducted. Specimens and caps free of defects unless otherwise noted in comments. Average cylinder diameter and area and unit compressive stress (f' _c) calculated on sheet 2 of 2.										

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.


Cylinder Split Tensile Tests Documentation v.2
(Rev. 11/1/2016)

Specimen: D4-D6 week 2

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]			Length [nearest 0.1 in.]		P _{max} [lb _f]	Fracture Sketch
				end	middle	end	1	2		
1										
2										
3										
D 4	2/24/17	4:55 pm	Dry	6.03	6.01	5.99	12.00	12.00	38,000	①
D 5	2/24/17	5:00 pm	Dry	5.98	6.02	6.00	12.00	12.00	28,000	①
S 6	2/24/17	5:08 pm	Dry	5.99	6.02	6.04	12.00	12.00	47,000	③
S/N of Testing Machine:			Forney 9905B							
Recorded by:			Signature			Date		Time		
Kinsley Skillen						2/24/17		5:30 pm		
Checked by:			Signature			Date		Time		
Checked by:			Signature			Date		Time		
Comments: $f_t = \frac{2P_{max}}{\pi D_{avg} L_{avg}}$										
*Cylinders to be test per ASTM C-496-11 with a loading rate of 15,000lb _f /min at a concrete age of 28 days and on same day that the test of the corresponding specimen is conducted. Specimens free of defects unless otherwise noted in comments. Average cylinder diameter and area and splitting tensile strength (f _t) calculated on sheet 2 of 2.										

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]		Length [nearest 0.05 in.]			P _{max} [lb _f]	Fracture Type (1-6)
				1	2	1	2	3		
D7	2/26/17	8:00 pm	Dry	6.00	5.98	12.00	12.00	12.00	118000	5
"	"	8:15 pm	Dry	6.00	5.97	12.00	12.00	12.00	121000	5
"	"	8:23 pm	Dry	6.00	5.99	12.00	12.00	12.00	115000	6

S/N of Testing Machine: Forney 99058

Recorded by:	Signature	Date	Time
<u>Kinsley Skiller</u>		<u>2/26/17</u>	<u>8:30 pm</u>
Checked by:	Signature	Date	Time
Checked by:	Signature	Date	Time

Comments:

*Cylinders to be test per ASTM C-39-12 and C-1231-10a with a loading rate of 60,000lb_f/min at concrete ages of 3, 7, 14, 28 days, and on same day that test of corresponding specimen is conducted. Specimens and caps free of defects unless otherwise noted in comments. Average cylinder diameter and area and unit compressive stress (f'_c) calculated on sheet 2 of 2.





APPENDIX 2, Pg 5 of 28
25884-000-30R-C01R-00002, Rev. 000, Sheet 154 of 575

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Cylinder Split Tensile Tests Documentation v.2
(Rev. 11/1/2016)


Specimen: D7

Sheet 1 of 2

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]			Length [nearest 0.1 in.]		P _{max} [lbf]	Fracture Sketch
				end	middle	end	1	2		
D7	2/26/17	8:45 pm	Dry	6.01	6.00	5.99	12.00	12.00	44000	
D7	"	8:50 pm	"	6.00	6.00	6.01	12.00	11.99	48000	
D7	"	8:55 pm	"	5.99	6.02	6.02	12.00	12.03	39000	
S/N of Testing Machine:			Forney 99058							
Recorded by:			Signature				Date		Time	
Kinsey Skiller							2/26/17		9:00 pm	
Checked by:			Signature				Date		Time	
Checked by:			Signature				Date		Time	
Comments:										
*Cylinders to be test per ASTM C-496-11 with a loading rate of 15,000lb _f /min at a concrete age of 28 days and on same day that the test of the corresponding specimen is conducted. Specimens free of defects unless otherwise noted in comments. Average cylinder diameter and area and splitting tensile strength (f _t) calculated on sheet 2 of 2.										

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]		Length [nearest 0.05 in.]			P _{max} [lb _f]	Fracture Type (1-6)
				1	2	1	2	3		
D8	3/6/17	6:00 pm	Dry	5.98	6.01	12.00	11.95	12.00	112000	5
D8	3/6/17	6:12 pm	"	5.98	6.00	12.00	12.00	11.95	114000	5
D8	3/6/17	6:20 pm	"	5.95	6.00	12.00	11.95	11.95	119000	5


S/N of Testing Machine:

Recorded by:	Signature	Date	Time
Kinsy Skiller		3/6/17	6:25 pm
Checked by:	Signature	Date	Time
Checked by:	Signature	Date	Time

Comments:


*Cylinders to be test per ASTM C-39-12 and C-1231-10a with a loading rate of 60,000lb_f/min at concrete ages of 3, 7, 14, 28 days, and on same day that test of corresponding specimen is conducted. Specimens and caps free of defects unless otherwise noted in comments. Average cylinder diameter and area and unit compressive stress (f'_c) calculated on sheet 2 of 2.

APPENDIX 2, PG 7 OF 28
25884-P00-30-R-C01-R-00002, Rev. 000, Sheet 156 of 575

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]			Length [nearest 0.1 in.]		P _{max} [lbf]	Fracture Sketch
				end	middle	end	1	2		
D8	3/6/17	6:33 pm	Dry	5.97	6.01	6.02	12.00	12.00	46000	
"	"	6:40 pm	"	5.95	6.00	6.00	12.00	12.00	51000	
"	"	6:45 pm	"	6.02	5.99	5.97	12.00	12.00	53000	
S/N of Testing Machine:			Forney 99058							
Recorded by:			Signature				Date		Time	
Kinsy Skiller							3/6/17		7:00 pm	
Checked by:			Signature				Date		Time	
Checked by:			Signature				Date		Time	
Comments:										
*Cylinders to be test per ASTM C-496-11 with a loading rate of 15,000lb _f /min at a concrete age of 28 days and on same day that the test of the corresponding specimen is conducted. Specimens free of defects unless otherwise noted in comments. Average cylinder diameter and area and splitting tensile strength (f _t) calculated on sheet 2 of 2.										

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]		Length [nearest 0.05 in.]			P _{max} [lbf]	Fracture Type (1-6)
				1	2	1	2	3		
09	3/10/17	4:30 pm	Dry	6.03	5.99	12.00	11.95	12.00	115000	5
09	3/10/17	4:41 pm	Dry	6.02	5.96	12.00	12.00	12.00	117000	6
09	3/10/17	4:50 pm	Dry	5.98	6.01	12.00	12.00	12.00	114000	6


S/N of Testing Machine: _____

Recorded by:	Signature	Date	Time
Kinsy Skiller		3/10/17	5:00 pm
Checked by:	Signature	Date	Time
Checked by:	Signature	Date	Time

Comments:


*Cylinders to be test per ASTM C-39-12 and C-1231-10a with a loading rate of 60,000lbf/min at concrete ages of 3, 7, 14, 28 days, and on same day that test of corresponding specimen is conducted. Specimens and caps free of defects unless otherwise noted in comments. Average cylinder diameter and area and unit compressive stress (f'_c) calculated on sheet 2 of 2.

APPENDIX 2, Pg 9 of 28
25884-000-30R-C01 R-00002, Rev. 000, Sheet 158 of 575

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]			Length [nearest 0.1 in.]		P _{max} [lb _f]	Fracture Sketch
				end	middle	end	1	2		
D9	3/10/17	5:20 pm	Dry	5.96	5.99	6.00	12.00	12.00	43000	
"	"	5:25 pm	"	5.99	6.00	6.00	12.00	12.00	51000	
"	"	5:30 pm	"	6.01	6.02	5.99	12.00	12.00	46000	
S/N of Testing Machine:			Forney 9905s							
Recorded by:			Signature			Date		Time		
Kinsley Skiller						3/10/17		5:45 pm		
Checked by:			Signature			Date		Time		
Checked by:			Signature			Date		Time		
Comments:										
*Cylinders to be test per ASTM C-496-11 with a loading rate of 15,000lb _f /min at a concrete age of 28 days and on same day that the test of the corresponding specimen is conducted. Specimens free of defects unless otherwise noted in comments. Average cylinder diameter and area and splitting tensile strength (f _t) calculated on sheet 2 of 2.										

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]		Length [nearest 0.05 in.]			P _{max} [lb _f]	Fracture Type (1-6)
				1	2	1	2	3		
D10	3/14/17	5:30 pm	Dry	6.03	6.01	11.95	12.00	12.00	118000	6
"	"	5:40 pm	Dry	5.98	5.99	12.00	12.00	12.00	120000	5
"	"	5:48 pm	Dry	6.01	6.00	11.95	12.00	12.00	117000	6


S/N of Testing Machine: Fomey 99058


Recorded by:		Date	Time
<u>Kinsey Skiller</u>		<u>3/14/17</u>	<u>6:00 pm</u>
Checked by:		Date	Time
Checked by:		Date	Time

Comments:

*Cylinders to be test per ASTM C-39-12 and C-1231-10a with a loading rate of 60,000lb_f/min at concrete ages of 3, 7, 14, 28 days, and on same day that test of corresponding specimen is conducted. Specimens and caps free of defects unless otherwise noted in comments. Average cylinder diameter and area and unit compressive stress (f'_c) calculated on sheet 2 of 2.


APPENDIX 2, PG 11 OF 28


Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]			Length [nearest 0.1 in.]		P _{max} [lbf]	Fracture Sketch
				end	middle	end	1	2		
D10	3/14/17	6:20 pm	Dry	5.95	6.01	6.02	12.00	12.00	55000	
"	"	6:26 pm	"	5.99	6.00	6.00	12.00	12.00	52000	
"	"	6:32 pm	"	6.00	5.98	6.01	12.00	12.00	46000	
S/N of Testing Machine:			Forney 99058							
Recorded by:			Signature			Date		Time		
Kinsey Skinner						3/14/17		6:45 pm		
Checked by:			Signature			Date		Time		
Checked by:			Signature			Date		Time		
Comments:										
*Cylinders to be test per ASTM C-496-11 with a loading rate of 15,000lbf/min at a concrete age of 28 days and on same day that the test of the corresponding specimen is conducted. Specimens free of defects unless otherwise noted in comments. Average cylinder diameter and area and splitting tensile strength (f _t) calculated on sheet 2 of 2.										

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]		Length [nearest 0.05 in.]			P _{max} [lb _f]	Fracture Type (1-6)
				1	2	1	2	3		
D11	3/17/17	4:00 pm	Dry	5.99	6.04	12.00	12.05	11.95	123000	6
D11	3/17/17	4:12 pm	Dry	6.02	5.96	12.00	12.00	11.95	119000	5
D11	3/17/17	4:19 pm	Dry	6.00	5.99	12.00	12.00	12.00	121000	5
S/N of Testing Machine:				Formy 99058						
Recorded by:				Signature			Date		Time	
Kinsy Skiller							3/17/17		4:45 pm	
Checked by:				Signature			Date		Time	
Checked by:				Signature			Date		Time	

Comments:

*Cylinders to be test per ASTM C-39-12 and C-1231-10a with a loading rate of 60,000lb_f/min at concrete ages of 3, 7, 14, 28 days, and on same day that test of corresponding specimen is conducted. Specimens and caps free of defects unless otherwise noted in comments. Average cylinder diameter and area and unit compressive stress (f'_c) calculated on sheet 2 of 2.


Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]			Length [nearest 0.1 in.]		P _{max} [lb _f]	Fracture Sketch
				end	middle	end	1	2		
D11	3/17/17	5:02 pm	Dry	6.01	5.98	6.01	12.00	12.00	48000	
"	"	5:08 pm	"	6.00	6.00	5.97	12.00	12.00	52000	
"	"	5:15 pm	"	6.03	5.95	6.02	12.00	12.00	41000	
S/N of Testing Machine:			Forney 99058							
Recorded by:			Signature			Date		Time		
Kinsley Skillon						3/17/17		5:20 pm		
Checked by:			Signature			Date		Time		
Checked by:			Signature			Date		Time		
Comments:										
*Cylinders to be test per ASTM C-496-11 with a loading rate of 15,000lb _f /min at a concrete age of 28 days and on same day that the test of the corresponding specimen is conducted. Specimens free of defects unless otherwise noted in comments. Average cylinder diameter and area and splitting tensile strength (f _t) calculated on sheet 2 of 2.										

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]		Length [nearest 0.05 in.]			P _{max} [lb _f]	Fracture Type (1-6)
				1	2	1	2	3		
D12	3/22/17	2:00 pm	Dry	5.97	6.00	12.00	12.00	12.00	112000	6
D12	3/22/17	2:15 pm	Dry	5.98	6.02	11.95	11.95	12.00	117000	6
D12	3/22/17	2:24 pm	Dry	5.99	6.00	12.00	11.95	12.00	119000	6
S/N of Testing Machine:			Forney 99058							
Recorded by:			Signature			Date		Time		
Kinsy Skillen						3/22/17		2:30 pm		
Checked by:			Signature			Date		Time		
Checked by:			Signature			Date		Time		

Comments:

*Cylinders to be test per ASTM C-39-12 and C-1231-10a with a loading rate of 60,000lb_f/min at concrete ages of 3, 7, 14, 28 days, and on same day that test of corresponding specimen is conducted. Specimens and caps free of defects unless otherwise noted in comments. Average cylinder diameter and area and unit compressive stress (f'_c) calculated on sheet 2 of 2.

APPENDIX 2, PG 15 OF 28
26884-000-30R-C01R-00002, REV. 000, SHEET 1 OF 5

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]			Length [nearest 0.1 in.]		P _{max} [lbf]	Fracture Sketch
				end	middle	end	1	2		
D12	3/22/17	3:30 pm	Dry	5.95	6.02	6.04	12.00	12.00	55000	
"	"	3:37 pm	"	5.99	6.00	6.01	12.00	12.00	42000	
"	"	3:45 pm	"	5.99	6.00	6.02	12.00	12.00	51000	
S/N of Testing Machine:			Forney 99055							
Recorded by:			Signature			Date		Time		
Kinsey Skiller						3/22/17		4:00 pm		
Checked by:			Signature			Date		Time		
Checked by:			Signature			Date		Time		
Comments:										
*Cylinders to be test per ASTM C-496-11 with a loading rate of 15,000lb _f /min at a concrete age of 28 days and on same day that the test of the corresponding specimen is conducted. Specimens free of defects unless otherwise noted in comments. Average cylinder diameter and area and splitting tensile strength (f _t) calculated on sheet 2 of 2.										

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]		Length [nearest 0.05 in.]			P _{max} [lb _f]	Fracture Type (1-6)
				1	2	1	2	3		
D13	6/14/17	9:30 am	Dry	6	6	12	12	12	125000	5
D13	6/14/17	9:36 am	Dry	6	6	12	12	12	127000	5
D13	6/14/17	9:42 am	Dry	6	6	12	12	12	119000	5

S/N of Testing Machine:		Forney 99058	
Recorded by:	Signature	Date	Time
Kinsey Skillen	<i>K.C. Skillen</i>	6/14/17	10:15 am
Checked by:	Signature	Date	Time
Checked by:	Signature	Date	Time

Comments:

*Cylinders to be test per ASTM C-39-12 and C-1231-10a with a loading rate of 60,000lb_f/min at concrete ages of 3, 7, 14, 28 days, and on same day that test of corresponding specimen is conducted. Specimens and caps free of defects unless otherwise noted in comments. Average cylinder diameter and area and unit compressive stress (f'_c) calculated on sheet 2 of 2.

APPENDIX C - Purdue Phase III Test Report

25984-000-30R-C01R-00002-Rev-000-Sheet 1 of 28
Appendix 2, Pg 17 of 28

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Cylinder Split Tensile Tests Documentation v.2
(Rev. 11/1/2016)

Specimen: D13

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]			Length [nearest 0.1 in.]		P _{max} [lb _f]	Fracture Sketch
				end	middle	end	1	2		
D13	6/14/17	9:50 am	Dry	6	6	6	12	12	56000	
D13	6/14/17	9:55 am	Dry	6	6	6	12	12	43000	
D13	6/14/17	10:00 am	Dry	6	6	6	12	12	53000	
S/N of Testing Machine:			Forney 99058							
Recorded by:		Signature				Date		Time		
Kinsley Skillen		K.C. Skillen				6/14/17		10:15 am		
Checked by:		Signature				Date		Time		
Checked by:		Signature				Date		Time		
Comments:										
*Cylinders to be test per ASTM C-496-11 with a loading rate of 15,000lb _f /min at a concrete age of 28 days and on same day that the test of the corresponding specimen is conducted. Specimens free of defects unless otherwise noted in comments. Average cylinder diameter and area and splitting tensile strength (f _t) calculated on sheet 2 of 2.										

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]		Length [nearest 0.05 in.]			P _{max} [lb _f]	Fracture Type (1-6)
				1	2	1	2	3		
D14	6/19/17	10:15 am	Dry	6	6	12	12	12	123000	5
D14	6/19/17	10:20 am	Dry	6	6	12	12	12	118000	6
D14	6/19/12	10:25 am	Dry	6	6	12	12	12	120000	5

S/N of Testing Machine:	Forney 99058		
Recorded by:	Signature	Date	Time
Kinsey Skillen	<i>K Skillen</i>	6/19/17	10:30 am
Checked by:	Signature	Date	Time
Checked by:	Signature	Date	Time

Comments:

*Cylinders to be test per ASTM C-39-12 and C-1231-10a with a loading rate of 60,000lb_f/min at concrete ages of 3, 7, 14, 28 days, and on same day that test of corresponding specimen is conducted. Specimens and caps free of defects unless otherwise noted in comments. Average cylinder diameter and area and unit compressive stress (f'_c) calculated on sheet 2 of 2.

APPENDIX C: Purdue Phase III Test Report

25984-000-30R-G01R-000002-Rev-000-Sheet 1 of 28

Appendix 2, Pg 19 of 28

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Cylinder Split Tensile Tests Documentation v.2
(Rev. 11/1/2016)

Specimen: D14

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]			Length [nearest 0.1 in.]		P _{max} [lbf]	Fracture Sketch
				end	middle	end	1	2		
D14	6/19/17	10:35 am	Dry	6	6	6	12	12	47000	
D14	6/19/17	10:39 am	Dry	6	6	6	12	12	51000	
D14	6/19/17	10:45 am	Dry	6	6	6	12	12	48000	
S/N of Testing Machine:			Forney 99058							
Recorded by:			Signature			Date		Time		
Kinsey Skiller			K.C. Skiller			6/19/17		10:50 am		
Checked by:			Signature			Date		Time		
Checked by:			Signature			Date		Time		
Comments:										
*Cylinders to be test per ASTM C-496-11 with a loading rate of 15,000lb _f /min at a concrete age of 28 days and on same day that the test of the corresponding specimen is conducted. Specimens free of defects unless otherwise noted in comments. Average cylinder diameter and area and splitting tensile strength (f _t) calculated on sheet 2 of 2.										

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]		Length [nearest 0.05 in.]			P _{max} [lb _f]	Fracture Type (1-6)
				1	2	1	2	3		
D15	6/22/17	10:00 am	Dry	6	6	12	12	12	127000	5
D15	6/22/17	10:07 am	Dry	6	6	12	12	12	125000	5
D15	6/22/17	10:11 am	Dry	6	6	12	12	12	128000	6

S/N of Testing Machine:	Forney 99058		
Recorded by:	Signature	Date	Time
Kinsey Skillen	<i>K.C. Skillen</i>	6/22/17	10:20 am
Checked by:	Signature	Date	Time
Checked by:	Signature	Date	Time

Comments:

*Cylinders to be test per ASTM C-39-12 and C-1231-10a with a loading rate of 60,000lb_f/min at concrete ages of 3, 7, 14, 28 days, and on same day that test of corresponding specimen is conducted. Specimens and caps free of defects unless otherwise noted in comments. Average cylinder diameter and area and unit compressive stress (f'_c) calculated on sheet 2 of 2.

APPENDIX C: Purdue Phase III Test Report

25884-000-30R-C01R-00002-Rev-000-Sheet 170 of 675

Appendix 2, Pg 21 of 28

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Cylinder Split Tensile Tests Documentation v.2
(Rev. 11/1/2016)

Specimen: D15

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]			Length [nearest 0.1 in.]		P _{max} [lb _f]	Fracture Sketch
				end	middle	end	1	2		
D15	6/22/17	10:23 am	Dry	6	6	6	12	12	38000	
D15	6/22/17	10:27 am	Dry	6	6	6	12	12	49000	
D15	6/22/17	10:32 am	Dry	6	6	6	12	12	48000	
S/N of Testing Machine:			Forney 99058							
Recorded by:			Signature			Date		Time		
Kinsy Skills			K.C. Skills			6/22/17		10:40 am		
Checked by:			Signature			Date		Time		
Checked by:			Signature			Date		Time		
Comments:										
*Cylinders to be test per ASTM C-496-11 with a loading rate of 15,000lb _f /min at a concrete age of 28 days and on same day that the test of the corresponding specimen is conducted. Specimens free of defects unless otherwise noted in comments. Average cylinder diameter and area and splitting tensile strength (f _t) calculated on sheet 2 of 2.										

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]		Length [nearest 0.05 in.]			P _{max} [lb _f]	Fracture Type (1-6)
				1	2	1	2	3		
D16	6/29/17	11:30 am	Dry	6	6	12	12	12	123000	S
D16	6/29/17	11:33 am	Dry	6	6	12	12	12	119000	6
D16	6/29/17	11:38 am	Dry	6	6	12	12	12	125000	6

S/N of Testing Machine: Forney 99058

Recorded by: Kinsey Skillen Signature: *K.C. Skillen* Date: 6/29/17 Time: 11:45 am

Checked by: Signature: Date: Time:

Checked by: Signature: Date: Time:

Checked by: Signature: Date: Time:

Checked by: Signature: Date: Time:

Checked by: Signature: Date: Time:

Comments:

*Cylinders to be test per ASTM C-39-12 and C-1231-10a with a loading rate of 60,000lb_f/min at concrete ages of 3, 7, 14, 28 days, and on same day that test of corresponding specimen is conducted. Specimens and caps free of defects unless otherwise noted in comments. Average cylinder diameter and area and unit compressive stress (f'_c) calculated on sheet 2 of 2.

APPENDIX C: Purdue Phase III Test Report

25884-000-30R-C01R-00002 Rev. 000 Sheet 172 of 525 Appendix 2, Pg 23 of 28

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]			Length [nearest 0.1 in.]		P _{max} [lb _f]	Fracture Sketch
				end	middle	end	1	2		
D16	6/29/17	11:50 am	Dry	6	6	6	12	12	43000	
D16	6/29/17	11:54 am	Dry	6	6	6	12	12	50000	
D16	6/29/17	12:00 pm	Dry	6	6	6	12	12	52000	
S/N of Testing Machine:			Fomey 99058							
Recorded by:			Signature			Date		Time		
Kinsy Skiller			K.S. Skiller			6/29/17		12:05 pm		
Checked by:			Signature			Date		Time		
Checked by:			Signature			Date		Time		
Comments:										
*Cylinders to be test per ASTM C-496-11 with a loading rate of 15,000lb _f /min at a concrete age of 28 days and on same day that the test of the corresponding specimen is conducted. Specimens free of defects unless otherwise noted in comments. Average cylinder diameter and area and splitting tensile strength (f _t) calculated on sheet 2 of 2.										

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]		Length [nearest 0.05 in.]			P _{max} [lb _f]	Fracture Type (1-6)
				1	2	1	2	3		
D17	7/5/17	9:05 am	Dry	6	6	12	12	12	128000	6
D17	7/5/17	9:10 am	Dry	6	6	12	12	12	120000	5
D17	7/5/17	9:14 am	Dry	6	6	12	12	12	127000	5

S/N of Testing Machine: Forney 99058

Recorded by:	Signature	Date	Time
--------------	-----------	------	------

Kinsey Skillen	<i>KCSkellen</i>	7/5/17	9:20 am
----------------	------------------	--------	---------

Checked by:	Signature	Date	Time
-------------	-----------	------	------

--	--	--	--

Checked by:	Signature	Date	Time
-------------	-----------	------	------

--	--	--	--

Comments:

*Cylinders to be test per ASTM C-39-12 and C-1231-10a with a loading rate of 60,000lb_f/min at concrete ages of 3, 7, 14, 28 days, and on same day that test of corresponding specimen is conducted. Specimens and caps free of defects unless otherwise noted in comments. Average cylinder diameter and area and unit compressive stress (f'_c) calculated on sheet 2 of 2.

APPENDIX C - Purdue Phase III Test Report 25884-000-30R-C01B-00002 Rev. 000 Sheet 174 of 575 Appendix 2, Pg 25 of 28

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Cylinder Split Tensile Tests Documentation v.2
(Rev. 11/1/2016)

Specimen: D17

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]			Length [nearest 0.1 in.]		P _{max} [lbf]	Fracture Sketch
				end	middle	end	1	2		
D17	7/5/17	9:25 am	Dry	6	6	6	12	12	52000	
D17	7/5/17	9:30 am	Dry	6	6	6	12	12	46000	
D17	7/5/17	9:34 am	Dry	6	6	6	12	12	49000	

S/N of Testing Machine:		Farnley 99058	
Recorded by:	Signature	Date	Time
Kinzy Skiller	K.C. Skiller	7/5/17	9:40 am
Checked by:	Signature	Date	Time
Checked by:	Signature	Date	Time

Comments:

*Cylinders to be test per ASTM C-496-11 with a loading rate of 15,000lb_f/min at a concrete age of 28 days and on same day that the test of the corresponding specimen is conducted. Specimens free of defects unless otherwise noted in comments. Average cylinder diameter and area and splitting tensile strength (f_t) calculated on sheet 2 of 2.

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]		Length [nearest 0.05 in.]			P _{max} [lb _f]	Fracture Type (1-6)
				1	2	1	2	3		
D18	7/6/17	9:00 am	Dry	6	6	12	12	12	121000	5
D18	7/6/17	9:05 am	Dry	6	6	12	12	12	120000	6
D18	7/6/17	9:10 am	Dry	6	6	12	12	12	126000	5

S/N of Testing Machine:	Forney 99058		
Recorded by:	Signature	Date	Time
Kinsey Skillen	<i>K Skillen</i>	7/6/17	9:15 am
Checked by:	Signature	Date	Time
Checked by:	Signature	Date	Time

Comments:

*Cylinders to be test per ASTM C-39-12 and C-1231-10a with a loading rate of 60,000lb_f/min at concrete ages of 3, 7, 14, 28 days, and on same day that test of corresponding specimen is conducted. Specimens and caps free of defects unless otherwise noted in comments. Average cylinder diameter and area and unit compressive stress (f'_c) calculated on sheet 2 of 2.

APPENDIX C: Purdue Phase III Test Report 25984-000-20R-G01R-000002-Rev-000-Sheet 126 of 626 Appendix 2, Pg 27 of 28

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Cylinder Split Tensile Tests Documentation v.2
(Rev. 11/1/2016)

Specimen: DIS

Specimen	Date	Time of Test	Wet/Dry	Diameter [nearest 0.01 in.]			Length [nearest 0.1 in.]		P _{max} [lb _f]	Fracture Sketch
				end	middle	end	1	2		
DIS	7/6/17	9:20 am	Dry	6	6	6	12	12	41000	
DIS	7/6/17	9:25 am	Dry	6	6	6	12	12	53000	
DIS	7/6/17	9:29 am	Dry	6	6	6	12	12	58000	
S/N of Testing Machine:			Forney 99058							
Recorded by:			Signature			Date		Time		
Kinsy Skille			K.C. Skille			7/6/17		9:40 am		
Checked by:			Signature			Date		Time		
Checked by:			Signature			Date		Time		
Comments:										
*Cylinders to be test per ASTM C-496-11 with a loading rate of 15,000lb _f /min at a concrete age of 28 days and on same day that the test of the corresponding specimen is conducted. Specimens free of defects unless otherwise noted in comments. Average cylinder diameter and area and splitting tensile strength (f _t) calculated on sheet 2 of 2.										

SOLD WHITACRE ENGINEERING CO INC
 PO BOX 8444
 TO: CANTON, OH 44711-8444

NUCOR
 NUCOR STEEL MARION, INC.

CERTIFIED MILL TEST REPORT

Ship from:
 MTR #: 0000061674
 Nucor Steel Marion, Inc.
 912 Cheney Avenue
 Marion, OH 43302
 7403834011

Date: 6-Jun-2016
 B.L. Number: 409367
 Load Number: 141652

SHIP WHITACRE ENGINEERING CO INC
 3171 MAGNOLIA RD NW
 TO: MAGNOLIA, OH 44643-9527


Material Safety Data Sheets are available at www.nucorbar.com or by contacting your inside sales representative.

NBMC-08 January 1, 2012

LOT # HEAT #	DESCRIPTION	PHYSICAL TESTS					CHEMICAL TESTS								
		YIELD P.S.I.	TENSILE P.S.I.	ELONG % IN 8"	BEND	WT% DEF	C Ni	Mn Cr	P Mo	S V	SI Cb	Cu Sn	C.E.		
PO# => MR1610248001	W20165 Nucor Steel - Marion, Inc.	68,800	111,800	13.2%	OK	-5.3%	.42	1.28	.014	.033	.27	.34	.66		
MR16102480	36/#11 Rebar 64' A615M GR420 (Gr60) ASTM A615/A615M-14 GR 60[420] AASHTO M31-07	474MPa	771MPa			.078	.11	.18	.042	.005	.002				
PO# => MR1610248102	W20165 Nucor Steel - Marion, Inc.	66,500	111,400	8.9%	OK	-5.3%	.42	1.25	.019	.033	.26	.32	.66		
MR16102481	36/#11 Rebar 64' A615M GR420 (Gr60) ASTM A615/A615M-14 GR 60[420] AASHTO M31-07	459MPa	768MPa			.078	.13	.21	.054	.005	.002				

I hereby certify that the material described herein has been manufactured in accordance with the specifications and standards listed above and that it satisfies those requirements.
 1.) Weld repair was not performed on this material.
 2.) Melted and Manufactured in the United States.
 3.) Mercury, Radium, or Alpha source materials in any form have not been used in the production of this material.

QUALITY ASSURANCE: Ignatius Okafor









Project: Tests to Determine the
Behavior of Spliced #11 Bars

Specimen: 01

Safety and Test Procedure Briefing Documentation

By signing your name below you acknowledge that you were briefed on the safety concerns and testing procedure for beam tests to determine the behavior of spliced No. 11 bars at Bowen Laboratory on:


2/13/17 prior to participation in the test:

Print Name	Sign Name	Date
Kinsy Skillen		2/13/17
Prateek Shah		2/13/17
Pelz Corrado		2/13/17
Santiago Pujol		2/13/2017
Lucas Laughery		13/Feb/2017
AISHWARYA PURNAM		02/13/17

Recorded by: Kinsy Skillen

Checked by:

Checked by:

Test: D1						Date: 2/13/17		
load step	time	LC E (kips)	LC W (kips)	LVDT NE (in)	LVDT NW (in)	LVDT SE (in)	LVDT SW (in)	Max crack width (in)
25 ^k	7:05	25.3	24.9	-.0009	.001	.0002	0	0
50 ^k	7:10	30.6	50	-.0001	.0014	.0006	.0000	0.0014
75 ^k	7:17	75.1	75	.0014	.0014	.0011	.0006	.0014
100 ^k	7:23	100.2	99.5	.0028	.0014	.0049	.0042	.0049
110 ^k	7:30	109.5	108.9	.0039	.0014	.0085	.0077	.0085
115 ^k	7:35	113.6	113.3	.0061	.0014	.0106	.0122	.0122
120 ^k	7:41	117.7	118.5	.011	.0014	.0165	.0192	.0192
122 ^k	7:48	121.0	122.2	.0128	.0014	.0345	.0356	.0356
125 ^k	7:54	124	125.3	.0148	.0014	.0596	.0643	.0643
0 ^k	8:00	0	0	.0109	.0014	.0423	.0459	.0459
30 ^k R	8:07	30.2	29.7	.0107	.0014	.0423	.0455	.0455
60 ^k R	8:14	60.3	60.3	.0107	.0014	.0449	.0474	.0474
90 ^k R	8:20	90.5	90.5	.0118	.0014	.0534	.0571	.0571
120 ^k R	8:26	119.3	119	.0255	.0002	.0676	.0719	.0719
Failure	8:33	126 ^k	126 ^k					.075
Notes: LVOTE 1.227 in @ 120 ^k reload, then reset to -.0479 in LVDTW 1.113 in @ 120^k reload, then reset to -.0329 in						Recorded by: Kinsy Skiller		
						Signature: 		


.060" crack width achieved before unload

Crack widths
 $\times 10^{-3}$ in

25^k No cracks

SOUTH


NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

75^k

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

100^k

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

110^k

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

115^{1/2}

SOUTH

NORTH



Series D



Drawing:

Series D crack map

Sheet:

1

of

1

Project:

EXPERIMENTAL INVESTIGATION OF THE
EFFECT OF LAMINAR CRACKS ON
STRENGTH OF UNCONFINED 79-IN. LAP
SPLICES OF #11 REINFORCING BARS

Drawn by:

KCS

Checked by:

SP


Date:

11/16/2016

120^k

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

123^k

no cracks
marked, see photos

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

125^k no cracks
marked

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

OK Unload

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

30^k R no new cracks

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

60 K R no new cracks

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

90^k R no new cracks

SOUTH

NORTH



Series D




	Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
			Date:	11/16/2016		

120^k R cracks not measured See photos.

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

Project: Tests to Determine the
Behavior of Spliced #11 Bars

Specimen: D2

Safety and Test Procedure Briefing Documentation

By signing your name below you acknowledge that you were briefed on the safety concerns and testing procedure for beam tests to determine the behavior of spliced No. 11 bars at Bowen Laboratory on:

2/15/17 prior to participation in the test:

Print Name

Sign Name


Date

Kinsy Skillen



2/15/17

Ash



02/15/17

Pete Corrado



2/15/17

Prateek Shah



2/15/17

WILL POLLAKIS



2/15/17

LUCAS LAUGHERY



2/15/2017

Recorded by:

Checked by:


Checked by:

Test: D2		Date: 2/15/17									
load step	time	LC E (kips)	LC W (kips)	LVDT NE (in)	LVDT NW (in)	LVDT SE (in)	LVDT SW (in)	Max crack width (in)			
20 ^k	7:51	20.2	20.2	0	0	0	0	0			
40 ^k	7:56	40.5	39.9	.001	.001	.001	0	.001			
60 ^k	8:00	60.7	59.3	.003	.001	.001	0	.003			
80 ^k	8:05	80	79.8	.009	.002	.001	0	.009			
100 ^k	8:10	99.8	99.5	.019	.005	.003	0	.019			
110 ^k	8:17	109.9	109.9	.029	.007	.003	0	.029			
120 ^k	8:26	118	117	.041	.010	.014	.022	.041			
123 ^k	8:31	122	121.6	.057	.014	.039	.041	.057			
0 ^k <small>5 min</small>	8:38	0	0								
20 ^k R	8:48	20	20.3	.040	.007	.027	.033	.040			
40 ^k R	8:54	40.2	40.5	.040	.007	.028	.033	.040			
60 ^k R	8:59	61	60.3	.041	.007	.031	.033	.041			
80 ^k R	9:07	80	80.1	.046	.009	.036	.034	.046			
100 ^k R	9:08	100	100	.054	.011	.041	.039	.054			
120 ^k R											

Recorded by:

Kinsay Skiller

Signature:



Notes:

0.60" crack with arching below
 below


D2

2/15/17

20^k no cracks

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		


D2

2/15/17

40^K

SOUTH

NORTH



Series D



Drawing:

Series D crack map

Sheet:

1

of

1

Project:

EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS

Drawn by:

KCS

Checked by:

SP

Date:

11/16/2016


D2

2/15/17

60^k

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D2 2/15/17

80k

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		


D2

2/15/17

100^x

SOUTH

NORTH



Series D



Drawing:

Series D crack map

Sheet:

1

of

1

Project:

EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS

Drawn by:

KCS

Checked by:

SP

Date:

11/16/2016


D2

2/15/17

110^K

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

120.123^K no cracks

SOUTH


NORTH




Series D



Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

60^KR only low cracks measured

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

80K R

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

100 k R see photos

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

120^k R see photos

SOUTH

NORTH



Series D



Drawing:

Series D crack map

Sheet:

1

of

1

Project:

EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS

Drawn by:

KCS

Checked by:

SP

Date:

11/16/2016










Project: Tests to Determine the
Behavior of Spliced #11 Bars

Specimen: D3

Safety and Test Procedure Briefing Documentation

By signing your name below you acknowledge that you were briefed on the safety concerns and testing procedure for beam tests to determine the behavior of spliced No. 11 bars at Bowen Laboratory on:


2/15/17 prior to participation in the test:

Print Name	Sign Name	Date
Kinsy Skillen		2/15/17
Prateek Shah		2/15/17
Mek Ashrafi		2/15/17
Pete Carrato		2/15/17
WILL PELLAZIS		2/15/17
Ash		02/15/17
S. Pujol		02/15/17
Merve Usta		02/15/17
Lucas Laughery		15 Feb 17

Recorded by:

Checked by:


Checked by:

Test: D3						Date: 2/15/17		
load step	time	LC E (kips)	LC W (kips)	LVDT NE (in)	LVDT NW (in)	LVDT SE (in)	LVDT SW (in)	Max crack width (in)
Start	6:39							
20 ^K	6:40	20.2	20	0	0	0	0	0
40 ^K	6:44	40.5	39.7	0	.001	0	0	.001
60 ^K	6:48	60.3	59	0	.001	0	0	.001
80 ^K	6:54	80.2	80.1	0	.001	0	0	.001
100 ^K	7:00	100	99.6	0	.001	0	0	.001
110 ^K	7:04	109	109	0	.001	0	0	.001
120 ^K	7:09	118.5	117.4	.001	.001	0	.001	.001
125 ^K	7:14	123.6	122.5	.001	.001	0	.001	.001
128 ^K	7:19	127.5	126.3	.002	.001	0	.001	.002
135 ^K	7:25	134.4	133.2	.016	-.003	0	.001	.016
138 ^K	7:30	137	138	.110	.105			.110
Unload	7:34	0	0	.088	-.085	0	0	.088
30 ^K R	7:39	30.5	30.3	.088	.084	0	0	.088
60 ^K R	7:44	60.5	60.2	.090	.085	0	0	.090
@ 128 ^K NW spot Notes: none to -.003 .1" crack width achieved before reload					Recorded by: Kinsy Skiller Signature: 			

20k no cracks

SOUTH


NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		


D3 2/15/17



60k

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

80^k

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1	
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
			Date:	11/16/2016		

100k no beam marks

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

120^k No cracks marked

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

125^k no cracks

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

138^k → unload

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

30^k Reload

SOUTH

NORTH



Series D










Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

Project: Tests to Determine the Behavior of Spliced #11 Bars

Specimen: D4

Safety and Test Procedure Briefing Documentation

By signing your name below you acknowledge that you were briefed on the safety concerns and testing procedure for beam tests to determine the behavior of spliced No. 11 bars at Bowen Laboratory on: 2/20/17 prior to participation in the test:

Print Name	Sign Name	Date
Kinsey Skiller		2/20/17
Prateek Shah		2/20/17
AISHWARYA PURANAM		2/20/17
Will Pollalis		2/20/17
LUCAS LAUGHERY		20 Feb / 17
JASPAL SAINI		02/20/17
Meta A. Sozen		12/20/17

Recorded by:

Checked by:

Checked by:

Test: D4						Date: 2/20/17		
load step	time	LC E (kips)	LC W (kips)	LVDT NE (in)	LVDT NW (in)	LVDT SE (in)	LVDT SW (in)	Max crack width (in)
0 ^k	3:43	0	0	0	0	0	0	—
20 ^k	3:55	20.7	20.3	.001	0	0	0	—
40 ^k	3:58	40.1	40.2	.001	0	0	0	—
60 ^k	4:03	60.6	60.3	.003	0	0	0	—
80 ^k	4:09	79.7	79.7	.004	0	0	0	—
100 ^k	4:15	100	100	.006	0	0	.001	—
110 ^k	4:23	109	109	.008	0	.001	.001	.008
120 ^k	4:29	118	118	.009	0	.001	0	.009
127 ^k	4:36	127	127	.036	0	.001	0	.036
130 ^k	4:40	130	130	.060	0	.001	0	.060
0 ^k	4:43	0	0	.043	0	0	0	.043
Epoxy	6:00 pm							

Notes:

Anchors embedded 10", possible dust in hole
 0.60" crack width achieved before
 anchor installed, 24 hr cure time

Recorded by:

Kinsey Skiller

Signature:




D4 20^k

SOUTH

No cracks

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D4 40^k

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D4 60k

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D4 80k

SOUTH

NORTH



Series D



Drawing: Series D crack map

Sheet: 1 of 1

Project: EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS


Drawn by: KCS Checked by: SP

Date: 11/16/2016

D4 100K

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		


D4 110K

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D4 130^K

no cracks marked
SOUTH reached .060 in crack @ LVDT NE

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D4 unload Ok

SOUTH


NORTH




Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

Test: DM Release w/ Anchors						Date: 2/21/17		
load step	time	LC E (kips)	LC W (kips)	LVDT NE (in)	LVDT NW (in)	LVDT SE (in)	LVDT SW (in)	Max crack width (in)
0 ^k	6:48 ^{pm}	0	0	.043	0	0	-.003	.043
20 ^k	6:54	19.9	20	.043	0	0	-.003	.043
40 ^k	6:59	39.9	39.8	.044	0	0	-.003	.044
60 ^k	7:01	60.1	59.9	.045	0	0.001	-.003	.045
80 ^k	7:07	80	80.7	.049	0	.001	-.003	.049
100 ^k	7:13	100	99.9	.053	0	.001	-.003	.053
110 ^k	7:19	110	110	.056	0	.001	-.003	.056
120 ^k	7:24	120	120	.059	0	.001	-.003	.059
125 ^k	7:29	124.5	124.5	.061	0	.001	-.003	.061
130 ^k	7:34	130.2	130.4	.065	-.001	.002	-.003	.065
135 ^k	7:40	134.4	134.6	.071	-.001	.002	-.003	.071
137 ^k								
Failure								
Notes: 24 hr cure time from anchor install					Recorded by: Kinsley Skillen			
					Signature: 			

D4 20^K No new cracks
 Reload w/ Anchor



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		


D4 40^k Reload w/ Anchor

2/21/17

no new cracks

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

D4 60^K Rebad w/ Anchors

no new cracks

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

D4 80k Road w/ Anchor

no new cracks

SOUTH

NORTH



Series D



Drawing:

Series D crack map

Sheet:

1

of

1

Project:

EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS

Drawn by:

KCS

Checked by:

SP

Date:


11/16/2016

D4 Reload w/ Anchors

100^R

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

D4 110^k Reload w/ Anchors

No new cracks

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

D4 120^k Reload w/ Anchors

no new cracks, none drawn

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D4 125^k Reload w/ Anchor

no cracks drawn or manually measured

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D4 130k Reload w/ Anchor


no new cracks drawn

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		






Project: Tests to Determine the
Behavior of Spliced #11 Bars

Specimen: D5

Safety and Test Procedure Briefing Documentation

By signing your name below you acknowledge that you were briefed on the safety concerns and testing procedure for beam tests to determine the behavior of spliced No. 11 bars at Bowen Laboratory on:

2/22/17 prior to participation in the test:

Print Name	Sign Name	Date
Kinsey Skiller		2/22/17
JASPAL SAINI		02/22/17
WILL POLLALIS		2/22/17
LUCAS LAUGHERY		22-Feb-17
AISHWARYA PORANAM		02/22/17

Recorded by:

Checked by:

Checked by:


D5

20^k

no cracks

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D5 40k

SOUTH

NORTH



Series D



Drawing:

Series D crack map

Sheet:

1

of

1

Project:

EXPERIMENTAL INVESTIGATION OF THE
EFFECT OF LAMINAR CRACKS ON
STRENGTH OF UNCONFINED 79-IN. LAP
SPLICES OF #11 REINFORCING BARS

Drawn by:

KCS

Checked by:

SP


Date:

11/16/2016

D5 60K

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

D5 80^K

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D5

100 K

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D5 120^k

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

D5 130^K Unload

SOUTH

NORTH



Series D



Drawing:

Series D crack map

Sheet:

1

of

1

Project:

EXPERIMENTAL INVESTIGATION OF THE
EFFECT OF LAMINAR CRACKS ON
STRENGTH OF UNCONFINED 79-IN. LAP
SPLICES OF #11 REINFORCING BARS

Drawn by:

KCS

Checked by:


SP

Date:

11/16/2016

ANCHOR INSTALLATION AS-BUILTS

NTS



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

LVDT W -10500 mV → Rest → 3376
 LVDT E 712 mV

Test: D5 Reload w/ Anchors Date: 2/23/17

load step	time	LC E (kips)	LC W (kips)	LVDT NE (in)	LVDT NW (in)	LVDT SE (in)	LVDT SW (in)	Max crack width (in)
0	10:23 am	0	.551	-.003	0	.041	.027	.041
20 ^K	10:40	21	20.2	-.003	0	.041	.027	.041
40 ^K	10:48	40.5	40	-.003	0	.043	.027	.043
60 ^K	10:53	60.2	60.2	-.003	0	.050	.029	.050
80 ^K	11:00	80.2	80.2	-.002	0	.060	.032	.060
100 ^K	11:10	100.2	100.3	-.002	0	.073	.037	.073
120 ^K	11:19	119.5	119.6	-.001	0	.096	.050	.096
130 ^K								
→ Failed						7.2		

Notes:
 Anchors cured for 24 hrs.
 LVDT W -10500 mV → Rest → 3376 mV
 LVDT E 712 mV → OK


Recorded by:
 Kinsy Skiller
 Signature: 

D5 Reload w/ Anchors

20^k

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		


D5 Reload w/ Anchors

40^k

SOUTH

NORTH

no new cracks or growth from 20^k



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

D5 Reload w/ Anchor

60^k

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

D5 Reload w/ Anchor

80*

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		


D5 Reload w/ Anchors

100^{kr}

SOUTH

NORTH

no new cracks, only listing laminar crack widths.



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		


D5 Release w/ Anchor

120 K

SOUTH

NORTH

no cracks drawn, see photos.



Series D



Drawing:

Series D crack map

Sheet:

1

of

1

Project:

EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS

Drawn by:

KCS

Checked by:

SP

Date:

11/16/2016









Project: Tests to Determine the
Behavior of Spliced #11 Bars

Specimen: D6

Safety and Test Procedure Briefing Documentation

By signing your name below you acknowledge that you were briefed on the safety concerns and testing procedure for beam tests to determine the behavior of spliced No. 11 bars at Bowen Laboratory on:

2/23/17 - 2/24/17 prior to participation in the test:

Print Name	Sign Name	Date
Kinsey Skiller		2/23/17
Jacob Munsh		2/23/17
Mete A Sozen		23 Feb 2017
S. PUJOL		2/23/17
ASHI		02/23/17
Pateek Shah		02/23/17
WILL POZAKIS		2/24/17
LUCAS LAUGHERY		24/Feb/17

Recorded by:

Checked by:

Checked by:

DG

2/23/17


6:00 pm

20^k

no cracks

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

DC 40^K

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

D6 60k

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

DG 80k

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D6 100^K

SOUTH

NORTH



Series D



Drawing:

Series D crack map

Sheet:

1

of

1

Project:

EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS

Drawn by:

KCS

Checked by:

SP


Date:

11/16/2016

DG 110^k

NO new cracks drawn,
SOUTH laminar cracks measured

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D6 110^k → unlead

6:47 pm

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D6 unload

SOUTH

NORTH

40

25

Series D



Drawing:

Series D crack map

Sheet:

1

of

1

Project:

EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS

Drawn by:

KCS

Checked by:

SP

Date:

11/16/2016


OK

D6 Releand w/ Anchors

starting crack configuration

SOUTH

NORTH



Series D



Drawing:

Series D crack map

Sheet:

1

of

1

Project:

EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS

Drawn by:

KCS

Checked by:

SP

Date:

11/16/2016


20^k

D6 Reload w/ Anchors

SOUTH

NORTH

no new cracks + growth



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

40^k
D6 Reload w/ Anchor

SOUTH

NORTH

no new cracks + growth



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

60k

D6 Reload w/ Anchors

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1	
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
			Date:	11/16/2016		

80k

D6 Release w/ Anchor

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

100k

D6 Release w/ Anchors

SOUTH

NORTH



Series D



Drawing:

Series D crack map

Sheet:

1

of

1

Project:

EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS

Drawn by:

KCS

Checked by:

SP

Date:


11/16/2016

110k

D6 Release w/ Anchor

SOUTH

NORTH



Series D



Drawing:

Series D crack map

Sheet:

1

of

1

Project:

EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS

Drawn by:

KCS

Checked by:

SP

Date:

11/16/2016

Project: Tests to Determine the Behavior of Spliced #11 Bars

Specimen: D7

Safety and Test Procedure Briefing Documentation

By signing your name below you acknowledge that you were briefed on the safety concerns and testing procedure for beam tests to determine the behavior of spliced No. 11 bars at Bowen Laboratory on:

 2/26/17 prior to participation in the test:

Print Name

Sign Name

Date

S. PUJOL LLANO



FEB 26, 2017

ASHWARYA Y. PURANAM



02/26/17

LUCAS LAUHERY



26/FEB/17

Mete A. Sozer



26 Feb 2017

Recorded by:

Checked by:


Checked by:

Test: D7						Date: 26-FEB-17		
load step	time	LC E (kips)	LC W (kips)	LVDT NE (in)	LVDT NW (in)	LVDT SE (in)	LVDT SW (in)	Max crack width (in)
∅	16:36	∅	∅	∅	∅	∅	∅	∅
20k	16:41	21.9	19.6	0.00	0.001	0.00	0.00	
40k	16:50	40.1	39.9	0	0.004	0.00	0	0.004
60k	17:00	60.2	60.2	0.001	0.007	0.002	0.002	0.007
80k	17:09	80	80	0.004	0.013	0.006	0.005	0.013
100k	17:18	99	99.3	0.01	0.026	0.016	0.011	0.026
110k	17:30	108.7	108	0.017	0.036	0.028	0.032	0.036
UNLOAD	17:40	200	260	0.014	0.025	0.029	0.046	0.046
→ went up to CW = 0.060 SW LVDT (check photograph)								
Notes:								
Recorded by:						AISHWARYA PURANAM		
						Signature: <i>Aishwarya</i>		

meas. in $\frac{1}{1000}$ in.

SOUTH

NORTH




Series D



Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

SOUTH

NORTH




Series D



Drawing:	Series D crack map	Sheet:	1	of	1	
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
			Date:	11/16/2016		


80k



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		




Series D



Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1	
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
			Date:	11/16/2016		


D7

20k Reload w/ Anchor

2/28/17

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D7 40^k Reload w/ Anchors

SOUTH

NORTH

See crack map + widths as 20^k reload



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D7 60K Reload w/ Anchor

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

D7 80k Reload w/ Anchors

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

D7 100^k Reload w/ Anchors

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		





Project: Tests to Determine the Behavior of Spliced #11 Bars

Specimen: D8

Safety and Test Procedure Briefing Documentation

By signing your name below you acknowledge that you were briefed on the safety concerns and testing procedure for beam tests to determine the behavior of spliced No. 11 bars at Bowen Laboratory on:

3/6/17 prior to participation in the test:

Print Name	Sign Name	Date
Kinsey Skillen		3/6/17
Pete Corrado		3/6/17
Prateek Shah	PPS	3/6/17
Lucas Laughery		6-Mar-17
Mete A. Sozen		3/6/17/2017

Recorded by:

Checked by:


Checked by:

20^k

SOUTH

Zero cracks

NORTH



Series D



Drawing:

Series D crack map

Sheet:

1

of

1

Project:

EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS

Drawn by:

KCS

Checked by:

SP

Date:


11/16/2016

40 K

SOUTH

NORTH

no laminar cracks



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

60

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

80 K

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

100K

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

120k unload

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

Test: D8 Reload						Date: 3/7/17		
load step	time	LC E (kips)	LC W (kips)	LVDT NE (in)	LVDT NW (in)	LVDT SE (in)	LVDT SW (in)	Max crack width (in)
0 ^k	4:22	0	0	.032	-.065	.048	.049	.049
20 ^k	4:28	26.1	19.9	.032	-.065	.048	.049	.049
40 ^k	4:31	40.2	40.2	.032	-.065	.051	.051	.051
60 ^k	4:37	60	60.7	.035	-.065	.055	.056	.056
80 ^k	4:41	80.1	80.2	.039	-.065	.060	.062	.062
100 ^k	4:48	99.4	99.6	.045	-.062	.065	.069	.069
110 ^k	4:55	109.4	109.4	.049	-.062	.068	.074	.074
120 ^k	5:01	119.8	119.8	.057	-.060	.073	.081	.081
126 ^k	5:05	126 ^k	126 ^k	.093	-.023	.090	.090	.098
130 ^k	5:08							.105
↳ Failed								

Notes:

NW LVDT bumped during anchor install, correct value from unload value in photos.

Recorded by:

Kinsey Skiller

Signature:


D8 Reload

20k

SOUTH

no new cracks from unload

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D8 Rebar 40K

SOUTH

NORTH

no new cracks or growth from inload



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D8 Relead 60K

SOUTH

NORTH

no new cracks or growth from reload



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D8 Reload 80 K

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D8 Released 100K

SOUTH

NORTH

no cracks drawn, see photos



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D8 Releand 110^K

SOUTH

NORTH

no cracks down, see photos



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

D8 Reload 120^k, 126^k, 130^k

SOUTH

NORTH

no cracks marked
see photos



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		



Project: Tests to Determine the
Behavior of Spliced #11 Bars

Specimen: 09

Safety and Test Procedure Briefing Documentation

By signing your name below you acknowledge that you were briefed on the safety concerns and testing procedure for beam tests to determine the behavior of spliced No. 11 bars at Bowen Laboratory on:

3/10/17 prior to participation in the test:

Print Name	Sign Name	Date
Kinsay Skiller		3/10/17
Mete A. Sozen	Mete Sozen	10 March 2017
Prateek Shah	PPS	3/10/17
Lucas Laughery	Lucas Laughery	10/Mar/17
S. PUJOL		10/MAR/2017

Recorded by:

Checked by:

Checked by:


Test: D9						Date: 3/10/17		
load step	time	LC E (kips)	LC W (kips)	LVDT NE (in)	LVDT NW (in)	LVDT SE (in)	LVDT SW (in)	Max crack width (in)
0 ^K	1:51	0	0	0	0	0	0	0
20 ^K	1:54	19.8	20.3	.004	.000	.000	-.009	.004
40 ^K	1:58	39.6	40.2	.006	0	0	.009	.006
60 ^K	2:04	59.9	59.9	.009	.002	0	-.009	.009
80 ^K	2:09	79.7	79.7	.014	.005	0	-.007	.014
100 ^K	2:16	99.6	99.8	.019	.016	0	-.004	.019
110 ^K	2:24	108.1	108.3	.027	.024	0	0	.027
115 ^K	2:30	114.1	114.3	.050	.048	0	.004	.050
Notes:					Recorded by:			
					Signature:			

20^{KL}

3/10/17

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

40^r

3/10/17

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1	
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
			Date:	11/16/2016		

60k

3/10/17

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

80K

3/10/17

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

100k

3/10/17

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1	
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
			Date:	11/16/2016		


D9

110^{rk}

3/10/17

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1	
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
			Date:	11/16/2016		


115*

.050 in crack

SOUTH

NORTH

no cracks down, see photos



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		



Project: Tests to Determine the
Behavior of Spliced #11 Bars

Specimen: D10

Safety and Test Procedure Briefing Documentation

By signing your name below you acknowledge that you were briefed on the safety concerns and testing procedure for beam tests to determine the behavior of spliced No. 11 bars at Bowen Laboratory on:

3/14/17 prior to participation in the test:

Print Name	Sign Name	Date
Kinsay Skillen		3/14/17
Mete A. Sozen	Mete A Sozen	3/14/2017
Aishwarya Y. Puranam	Aishwarya	03/14/2017
S. Pujol		3/14/17

Recorded by:

Checked by:

Checked by:


D10

20k

SOUTH

no cracks

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

D10 40k

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

D10 60K

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

D10 80K

SOUTH

NORTH



Series D



Drawing:

Series D crack map

Sheet:

1

of

1

Project:

EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS

Drawn by:

KCS

Checked by:

SP


Date:

11/16/2016

D10 100K

SOUTH

NORTH



Series D



Drawing:

Series D crack map

Sheet:

1

of

1

Project:

EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS

Drawn by:

KCS

Checked by:

SP

Date:


11/16/2016

D10 110^K

SOUTH

no cracks measured, see photos

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		


D10 Reload w/ Anchors

3/15/17

20K

SOUTH

NORTH



Series D



Drawing:

Series D crack map

Sheet:

1

of

1

Project:

EXPERIMENTAL INVESTIGATION OF THE
EFFECT OF LAMINAR CRACKS ON
STRENGTH OF UNCONFINED 79-IN. LAP
SPLICES OF #11 REINFORCING BARS

Drawn by:

KCS

Checked by:

SP

Date:

11/16/2016


D10

Reload

3/15/17

40^k
SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		


D10 Reload w/ anchor

3/15/17

60K

SOUTH

NORTH



Series D



Drawing:

Series D crack map

Sheet:

1

of

1

Project:

EXPERIMENTAL INVESTIGATION OF THE
EFFECT OF LAMINAR CRACKS ON
STRENGTH OF UNCONFINED 79-IN. LAP
SPLICES OF #11 REINFORCING BARS

Drawn by:

KCS

Checked by:

SP

Date:


11/16/2016

D10 Reload w/ Anchor 80k

3/15/17

SOUTH

NORTH



Series D



Drawing:

Series D crack map

Sheet:

1

of

1

Project:

EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS

Drawn by:

KCS

Checked by:

SP

Date:


11/16/2016

D10 Reload w/ Anchors

100k 3/15/17

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

D10 110K Reload w/ Anchors

SOUTH

no cracks drawn see photos.

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		




Project: Tests to Determine the Behavior of Spliced #11 Bars

Specimen: D11

Safety and Test Procedure Briefing Documentation

By signing your name below you acknowledge that you were briefed on the safety concerns and testing procedure for beam tests to determine the behavior of spliced No. 11 bars at Bowen Laboratory on:

 3/17/17 prior to participation in the test:

Print Name	Sign Name	Date
Kinsey Skiller		3/17/17
Santiago Pujol		3/17/17
AISHWARYA Y. PURANAM		03/17/17

Recorded by:

Checked by:

Checked by:

Test: 011						Date: 3/17/17		
load step	time	LC E (kips)	LC W (kips)	LVDT NE (in)	LVDT NW (in)	LVDT SE (in)	LVDT SW (in)	Max crack width (in)
0 ^k	1:28	0	0	0	0	0	0	—
20 ^k	1:30	20.3	20.2	0	0	0	0	—
40 ^k	1:39	40.4	40.2	.001	.001	0	0	.001
60 ^k	1:50	60.4	59.7	.004	.002	.001	.001	.004
80 ^k	1:58	80.1	80.6	.008	.005	.001	.001	.008
100 ^k	2:09	99.8	99.4	.021	.015	.005	.011	.021
110 ^k	2:12	108.2	108.3	.036	.039	.016	.025	.039
Notes:					Recorded by:			
					Signature:			


D11 3/17/17

20^k

no cracks

SOUTH

NORTH



Series D



Drawing:

Series D crack map

Project:

EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS

Sheet:

1

of

1

Drawn by:

KCS

Checked by:

SP

Date:


11/16/2016

D11 3/17/17

40 K

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

D11 3/17/17

60 K
SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		


D11

3/17/17

80k

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1	
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
			Date:	11/16/2016		

D11 3/17/17

100^k

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

D11 3/17/17

110^k
SOUTH

no cracks down, see photos

NORTH



Series D



Drawing:

Series D crack map

Sheet:

1

of

1

Project:

EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS

Drawn by:

KCS

Checked by:

SP

Date:

11/16/2016


Project: Tests to Determine the Behavior of Spliced #11 Bars

Specimen: D12

Safety and Test Procedure Briefing Documentation

By signing your name below you acknowledge that you were briefed on the safety concerns and testing procedure for beam tests to determine the behavior of spliced No. 11 bars at Bowen Laboratory on:

3/22/17 prior to participation in the test:

Print Name	Sign Name	Date
Kinsy Skillen		3/22/17
Prateek Shah		3/22/17

Recorded by:

Checked by:

Checked by:

Test: D12 Reload w/ Anchor						Date: 3/23/17		
load step	time	LC E (kips)	LC W (kips)	LVDT NE (in)	LVDT NW (in)	LVDT SE (in)	LVDT SW (in)	Max crack width (in)
0 ^k	9:20	0	0	.033	.015	.027	.038	.038
20 ^k	9:23	20.3	19.9	.033	.015	.027	.038	.038
40 ^k	9:28	40.2	40.1	.033	.015	.028	.038	.038
60 ^k	9:32	59.8	60.1	.033	.015	.030	.040	.040
80 ^k	9:43	79.6	80.2	.035	.019	.033	.045	.045
100 ^k	9:49	99.5	100.1	.040	.024	.036	.049	.049
110 ^k	9:54	109.6	109.9	.045	.028	.037	.052	.052
120 ^k								
130 ^k								

Notes:
 Test started 25 hrs from anchor install

Recorded by:
 Kinsley Skiller

Signature:


D12


3/22/17

20^k

SOUTH

NORTH

no cracks



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

D12 3/22/17

40^k
SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D12 3/22/17

60k

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

D12 3/22/17

80k
SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		


D12

3/22/17

100^k

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

D12


3/22/17

110^K

SOUTH

NORTH

no cracks down,
see photos



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

D12 3/22/17

Unloaded crack map OK

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

D12 Reload w/ Anchor


3/23/17

20^k

SOUTH

no new cracks
from unload

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D12 Reload


3/23/17

40K

SOUTH

NORTH

no new cracks
from 20K



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D12 Reload 3/23/17

60k

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D12 Reload

80K

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D12 Rebind 3/23/17

100^K

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		


D12 Reload 3/23/17

110k

SOUTH

no cracks marked / measured
see photos

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

Project: Tests to Determine the Behavior of Spliced #11 Bars

Specimen: D13

Safety and Test Procedure Briefing Documentation

By signing your name below you acknowledge that you were briefed on the safety concerns and testing procedure for beam tests to determine the behavior of spliced No. 11 bars at Bowen Laboratory on:

6/14/17 prior to participation in the test:

Print Name	Sign Name	Date
Kinsy Skillen	KCSkillen	6/14/17
Will Pollalis	Will Pollalis	6/14/17
Prateek Shah	P Shah	6/14/17
Jonathan Morrison	J Morrison	07/03/17

Recorded by:

KCS

Checked by:

Checked by:

D13


06/14/17

20 K

SOUTH

NORTH

NO CRACKS



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D13 06/14/17

40K

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D13 06/14/17

60k

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

D13 06/14/17

80K
SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		


D13

06/14/17

100K

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		


D13

06/14/17

105^k

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

Test: D13 Reload w/ Anchors						Date: 6/15/17		
load step	time	LC E (kips)	LC W (kips)	LVDT NE (in)	LVDT NW (in)	LVDT SE (in)	LVDT SW (in)	Max crack width (in)
0 ^K	4:52	0	0	.028	.026	.007	.028	.028
70 ^K	4:58	20.2	20	.028	.026	.007	.028	.028
40 ^K	5:00	39.9	39.9	.028	.028	.007	.029	.029
60 ^K	5:05	60.1	60.1	.033	.035	.008	.035	.035
80 ^K	5:10	80.1	80	.040	.042	.010	.041	.042
100 ^K	5:17	99.6	99.9	.047	.051	.012	.050	.051
110 ^K	5:20							
113 ^K	5:27	112	112	.080	.091	.017	.068	.091
120 ^K	5:33	118	118	.126	.145	.03	.102	.145

Notes:

Recorded by:
Kiasey Skiller
 Signature:
K.P. Skiller

D13


06/15/17

R20

SOUTH

NORTH

NO NEW
↑ CRACKS



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D13 06/15/17

R40
SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

D13


06/15/17

R60K

SOUTH

NORTH

No New Cracks



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		


D13

06/15/17

R80

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

06/15/17

D13
R100
SOUTH


NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

Project: Tests to Determine the Behavior of Spliced #11 Bars

Specimen: D14

Safety and Test Procedure Briefing Documentation

By signing your name below you acknowledge that you were briefed on the safety concerns and testing procedure for beam tests to determine the behavior of spliced No. 11 bars at Bowen Laboratory on:

6/19/17 prior to participation in the test:

Print Name	Sign Name	Date
Kinsy Skiller	Keskiller	6/19/17
Will Polzalis	Will Polzalis	6/19/17
Prateek Shal	PShal	6/19/17
JONATHAN WILLIAMS	JW	07/03/17

Recorded by:

KCS

Checked by:

Checked by:

D14


06/19/17

20k


SOUTH

NORTH

NO CRACKS



Series D



Drawing: Series D crack map

Sheet: 1 of 1

Project: EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS

Drawn by: KCS Checked by: SP

Date: 11/16/2016

D14


06/19/17

40K

SOUTH

NORTH

25



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D14 06/19/17

60 K

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D14 06/19/17

80 K

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D14 06/19/17

100K

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D14


06/20/17

R20 K

SOUTH

NORTH

No New Cracks



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

D14 06/20/17

R40K

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D14 06/20/17

R60 K

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

DI4 06/20/17

R30 K

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

DI4 06/20/17

R100 K

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		


D14

06/20/17

R110 K

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

Project: Tests to Determine the
Behavior of Spliced #11 Bars

Specimen: 015

Safety and Test Procedure Briefing Documentation

By signing your name below you acknowledge that you were briefed on the safety concerns and testing procedure for beam tests to determine the behavior of spliced No. 11 bars at Bowen Laboratory on:

6/22/17 prior to participation in the test:

Print Name	Sign Name	Date
Kinsy Skillen	KE Skillen	6/22/17
Will Pozzallo	Will Pozzallo	6/22/17
Pradeek Shal	P Shal	6/22/17
JONATHAN MONICAL	Jonathan Monical	07/03/17

Recorded by:

KCS

Checked by:

Checked by:

D15


06/22/17

20 K

SOUTH

NORTH

No Cracks



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		


D15

06/22/17

40 K

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

D15 06/22/17

60 K

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		


D15

06/22/17

BO K

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		


D15

06/22/17

100 K

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D15 6/22/17

112^K

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

Test: DIS w/ Anchor						Date: 6/23/17		
load step	time	LC E (kips)	LC W (kips)	LVDT NE (in)	LVDT NW (in)	LVDT SE (in)	LVDT SW (in)	Max crack width (in)
0 ^K	5:50	0 ^K	0 ^K	0.028	0.033	0.017	0.042	0.042
20 ^K	5:55	19.2	19.7	0.028	0.033	0.017	0.042	0.042
40 ^K	5:59	39.8	39.8	0.028	0.033	0.017	0.042	0.042
60 ^K	6:03	60.1	59.9	0.031	0.041	0.017	0.042	0.042
80 ^K	6:08	79.8	79.8	0.037	0.048	0.019	0.045	0.048
100 ^K	6:12	99.9	99.8	0.043	0.056	0.021	0.052	0.056
110 ^K	6:18	109.4	109.3	0.047	0.060	0.023	0.056	0.060
120 ^K	6:26	118.5	117	0.069	0.090	0.038	0.090	0.090
123 ^K	6:33	122	121	0.096	0.125	0.083	0.198	0.198
Notes:					Recorded by: Kinsay Skiller Signature: K.C. Skiller			

D15


06/23/17

R20 K

SOUTH

NORTH

New
No Cracks



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		


DIS

06/23/17

R40 K

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		


D15

06/23/17

R60 K

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		


D15

06/23/17

R80 K

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		


D15

06/23/17

R100 K

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		


D15

06/23/17

R110 K

SOUTH

NORTH



Series D



Drawing: Series D crack map

Sheet: 1 of 1

Project: EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS

Drawn by: KCS Checked by: SP


Date: 11/16/2016

D15
R120 K

06/23/17

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

Project: Tests to Determine the
Behavior of Spliced #11 Bars

Specimen: DI 6

Safety and Test Procedure Briefing Documentation

By signing your name below you acknowledge that you were briefed on the safety concerns and testing procedure for beam tests to determine the behavior of spliced No. 11 bars at Bowen Laboratory on: 6/29/17 prior to participation in the test:

Print Name	Sign Name	Date
Kinsy Skillen	K.C. Skillen	6/29/17
WILL POLLALIS	W.P. Pollalis	6/29/17
Prateek Shah	P. Shah	6/29/17
JONATHAN MORICAL	J.M. Morical	07/03/17

Recorded by:

KCS

Checked by:

Checked by:

D16


06/29/17

20 K

SOUTH

NORTH

NO CRACKS



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		


D16

06/29/17

40K

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		


D16

06/29/17

60k

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

D16
30K

06/29/17

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

DIG 06/29/17
 100 K

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		


D16

06/29/17

110K

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		


D16

06/30/17

R20 K

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D16


06/29/17

R40 K

SOUTH

NORTH

NO NEW CRACKS



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		


D16

06/29/17

R60 K

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		


D16

06/30/17

RBO 

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		


D16

06/30/17

R100 K

SOUTH

NORTH



20

75

Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		


D16

06/30/17

R110K

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

Project: Tests to Determine the Behavior of Spliced #11 Bars

Specimen: D17

Safety and Test Procedure Briefing Documentation

By signing your name below you acknowledge that you were briefed on the safety concerns and testing procedure for beam tests to determine the behavior of spliced No. 11 bars at Bowen Laboratory on:

7/5/17 prior to participation in the test:

Print Name

Sign Name

Date

Kinsy Skiller

KCSkiller

7/5/17

Aishwarya Puranam

Aishwarya

07/05/17

Lucas Laughery

Lucas Laughery

5/July/2017

Recorded by:

KCS

Checked by:

Checked by:

D17


07/05/17

20k

SOUTH

NORTH

NO CRACKS



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		


D17

07/05/17

40 K

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		


D17

07/05/17

60 k

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		


D17

07/05/17

80 k

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		


D17

07/05/17

100 k

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

Project: Tests to Determine the
Behavior of Spliced #11 Bars

Specimen: D18

Safety and Test Procedure Briefing Documentation

By signing your name below you acknowledge that you were briefed on the safety concerns and testing procedure for beam tests to determine the behavior of spliced No. 11 bars at Bowen Laboratory on: 7/6/17 prior to participation in the test:

Print Name	Sign Name	Date
Kinsy Skiller	KE Skiller	7/6/17
Prateek Shah	PShah	7/6/17
EMRE KAHRAMAN	EKA	7/6/17
Will Pallalis	W Pallalis	7/6/17
JASPAL SAINI	J Saini	7/6/17

Recorded by:

KES

Checked by:

Checked by:

D18


07/06/17

20 K

SOUTH

NORTH

No Cracks



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D18
40K

07/06/18

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D18
60K

07/06/17

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

DIB
30K

07/06/17

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D18
100K

07/06/17

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		


D16

07/06/17

106 K

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D18


07/07/17

R20

SOUTH

NORTH

No New Cracks



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D18


7/7/17

R40

SOUTH

NORTH

No New Cracks



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D18
R60

7/7/17

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

DB
R80

7/7/17

SOUTH

NORTH



Series D




Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

D18
R100

7/7/17

SOUTH

NORTH



Series D



Drawing:	Series D crack map	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/16/2016		

D18

7/7/17

R110

SOUTH

NORTH



Series D





Drawing:	Series D crack map	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/16/2016		

FENOC: SERIES D

Repair As-Built Documentation

Specimen	As-Built Distance, in.								
	(a) from South face to CL			(b) from East face to CL			(c) Embedment Depth		
	Rod 1	Rod 2	Rod 3	Rod 1	Rod 2	Rod 3	Rod 1	Rod 2	Rod 3
D1	NOT APPLICABLE, NO REPAIR								
D2	NOT APPLICABLE, NO REPAIR								
D3	NOT APPLICABLE, NO REPAIR								
D4	20 in	60 in	N/A	8 3/4	8 3/4	N/A	10 in	10 in	N/A
D5	13 1/3	40 in	66 2/3	8 3/4	8 3/4	8 3/4	12 1/8 in	12 1/8 in	12 in
D6	13 1/2	66 1/2	N/A	8 5/8	8 3/4	N/A	12 1/4	12 3/8	N/A
D7	13 1/2	40	66 5/8	8 3/4	8 5/8	8 3/4	12 1/4	12	12 1/4
D8	13 1/2	39 3/4	66 1/2	8 3/4	9	8 5/8	19	19 1/4	19
D9	N/A								→ Broke
D10	13 1/2	40	66 1/2	8 3/4	8 3/4	8 3/4	18 3/4	18 3/4	18 3/4
D11	N/A								→ Broke
D12	13 1/2	40	66 1/2	8 3/4	8 3/4	8 5/8	18 3/4	18 3/4	18 3/4



Notes:

↔ D8 - D12 → plate, nut, washers



↔ D9 + D11 broke before anchors could be installed

KCS ↔ nuts torqued to 100 lbf-ft

FENOC: SERIES D

Repair As-Built Documentation

Specimen	As-Built Distance, in.								
	(a) from South face to CL			(b) from East face to CL			(c) Embedment Depth		
	Rod 1	Rod 2	Rod 3	Rod 1	Rod 2	Rod 3	Rod 1	Rod 2	Rod 3
D13	13 $\frac{1}{2}$ "	40"	66 $\frac{1}{2}$ "	8 $\frac{3}{4}$ "	8 $\frac{3}{4}$ "	8 $\frac{3}{4}$ "	19"	19"	18 $\frac{3}{4}$ "
D14	13 $\frac{3}{4}$ "	40"	66 $\frac{1}{2}$ "	8 $\frac{3}{4}$ "	9"	9"	18 $\frac{3}{4}$ "	19"	18 $\frac{1}{2}$ "
D15	13 $\frac{1}{2}$ "	39 $\frac{3}{4}$ "	66 $\frac{1}{2}$ "	9"	9"	9"	18 $\frac{3}{4}$ "	18 $\frac{1}{2}$ "	18 $\frac{3}{4}$ "
D16	13 $\frac{1}{2}$ "	40"	66 $\frac{1}{2}$ "	9"	8 $\frac{3}{4}$ "	9"	18 $\frac{3}{4}$ "	18 $\frac{3}{4}$ "	18 $\frac{3}{4}$ "
D17	N/A								Broken
D18	13 $\frac{1}{2}$ "	39 $\frac{3}{4}$ "	66 $\frac{1}{2}$ "	9"	9"	8 $\frac{3}{8}$ "	19"	19 $\frac{1}{8}$ "	18 $\frac{3}{8}$ "



Notes:

- D17 broke before anchor install
- D13-D16, D18 → plate, nut washers
- 100 lb-ft torque

KCS

Adhesive Anchors Inspection Checklist for Concrete and Masonry

Periodic special must be performed where required in accordance with Section 1705.1.1 and Table 1705.3 of the 2012 IBC, or Section 1704.15 of the 2009 IBC and Table 1704.4 or Section 1704.13 of the 2006 or 2003 IBC, whereby periodic special inspection is defined in Section 1702.1 of the IBC and this report. (See Structural Drawings for Inspection requirements)

Project Name: D1-D3 N/A

Project Location: _____

Weather: _____ Air Temperature: _____ (°F / °C)

CODES <input type="checkbox"/> IBC 2003 <input type="checkbox"/> IBC 2006 <input type="checkbox"/> IBC 2009 <input type="checkbox"/> IBC 2012	Seismic Zone/ Seismic Design Category
--	---

Adhesive	Product Name/Manufacturer: _____
	Lot No.: _____
	ICC-ES Report No.: _____
	Adhesive expiration Date: ___/___/___ <input type="checkbox"/> Specified Dispenser <input type="checkbox"/> Specified Mixer
	Discard Initial Adhesive: _____ (# trigger pulls)
Adhesive Temperature: _____ (°F / °C) Gel Time: _____ Cure Time: _____ <small>(per manufacturers installation instructions)</small>	

Adhesive Element	Type: <input type="checkbox"/> All-Thread <input type="checkbox"/> Internally Threaded <input type="checkbox"/> Torque-Controlled <input type="checkbox"/> Rebar <input type="checkbox"/> Other _____ <small>(Safeset™ only to be used with Hilti HIT-HY 200)</small>
	Material: <input type="checkbox"/> Standard <input type="checkbox"/> Stainless Steel <input type="checkbox"/> High Strength
	Steel Grade/Coating: _____ Length: _____ (in/mm)
	Rod Diameter: <input type="checkbox"/> 3/8" <input type="checkbox"/> 1/2" <input type="checkbox"/> 5/8" <input type="checkbox"/> 3/4" <input type="checkbox"/> 7/8" <input type="checkbox"/> 1" <input type="checkbox"/> 1-1/4" <input type="checkbox"/> Other _____
	Rebar: <input type="checkbox"/> #3 <input type="checkbox"/> #4 <input type="checkbox"/> #5 <input type="checkbox"/> #6 <input type="checkbox"/> #7 <input type="checkbox"/> #8 <input type="checkbox"/> #9 <input type="checkbox"/> Other _____

Base Material	Base Material Type: <input type="checkbox"/> NW Concrete <input type="checkbox"/> LW Concrete <input type="checkbox"/> Brick <input type="checkbox"/> CMU <input type="checkbox"/> Other _____
	Base Material Strength: <input type="checkbox"/> 2000 psi <input type="checkbox"/> 3000 psi <input type="checkbox"/> 4000 psi <input type="checkbox"/> Other _____
	Base Material Thickness: _____ (in/mm)
	Base Material Temperature: _____ (°F / °C)

Drilling & Hole Cleaning	Drill Bit Diameter: _____ (in/mm) Hole Depth: _____ (in/mm) <small>(core bit diameter, if approved)</small>
	Drill Bit Type: <input type="checkbox"/> Carbide-Tip Drill Bit <input type="checkbox"/> Diamond Core Bit <input type="checkbox"/> Hollow Drill Bit <input type="checkbox"/> Other _____ <small>(ANSI B212.15-1994) (if appropriate and allowed) (Safeset™ only to be used with Hilti HIT-HY 200)</small>
	Hole Condition: <input type="checkbox"/> Dry <input type="checkbox"/> Water Saturated <input type="checkbox"/> Water Filled <input type="checkbox"/> Under Water
	Hole Cleaning: <input type="checkbox"/> Compressed Air <input type="checkbox"/> Hand Pump <input type="checkbox"/> Wire Brush <input type="checkbox"/> Other _____
	Hole cleaning in accordance with manufacturers' printed installation instructions: <input type="checkbox"/> Yes <input type="checkbox"/> No

Application	Anchor Application: <small>(please check all that apply)</small> <input type="checkbox"/> Tension <input type="checkbox"/> Shear <input type="checkbox"/> Overhead <input type="checkbox"/> Other _____
	Anchor insertion: <input type="checkbox"/> Twisting motion <input type="checkbox"/> Annular gap filled with adhesive <input type="checkbox"/> Air Void Free Injection
	Anchor Spacing: _____ (in/mm) Edge Distance: _____ (in/mm)
	Embedment (h _{ef}): _____ (in/mm) Installation Torque <small>(if required)</small> : _____ (ft-lb/Nm)

Completed by: _____ (Signature) Date: ___/___/___
 _____ (Print) Company: _____
 _____ (Title)



Adhesive Anchors Inspection Checklist for Concrete and Masonry

Periodic special must be performed where required in accordance with Section 1705.1.1 and Table 1705.3 of the 2012 IBC, or Section 1704.15 of the 2009 IBC and Table 1704.4 or Section 1704.13 of the 2006 or 2003 IBC, whereby periodic special inspection is defined in Section 1702.1 of the IBC and this report. (See Structural Drawings for Inspection requirements)

Project Name: FENOC 04
 Project Location: Bowen Lab Purdue
 Weather: inside Air Temperature: 60 (°F/°C)

CODES
<input type="checkbox"/> IBC 2003
<input type="checkbox"/> IBC 2006
<input type="checkbox"/> IBC 2009
<input type="checkbox"/> IBC 2012

Seismic Zone/ Seismic Design Category

Adhesive	Product Name/Manufacturer: <u>Hilti HIT-RE 500 V3</u>
	Lot No.: _____
	ICC-ES Report No.: _____
	Adhesive expiration Date: ___/___/___ <input type="checkbox"/> Specified Dispenser <input type="checkbox"/> Specified Mixer
	Discard Initial Adhesive: <u>8</u> (# trigger pulls)
Adhesive Temperature: <u>60°</u> (°F/°C) Gel Time: _____ Cure Time: <u>24 hrs.</u> <small>(per manufacturers installation instructions)</small>	

Adhesive Element	Type: <input checked="" type="checkbox"/> All-Thread <input type="checkbox"/> Internally Threaded <input type="checkbox"/> Torque-Controlled <input type="checkbox"/> Rebar <input type="checkbox"/> Other _____ <small>(Safeset™ only to be used with Hilti HIT-HY 200)</small>
	Material: <input checked="" type="checkbox"/> Standard <input type="checkbox"/> Stainless Steel <input type="checkbox"/> High Strength
	Steel Grade/Coating: <u>ASTM A193 B7</u> Length: <u>15 in</u> (in/mm)
	Rod Diameter: <input type="checkbox"/> 3/8" <input type="checkbox"/> 1/2" <input type="checkbox"/> 5/8" <input checked="" type="checkbox"/> 3/4" <input type="checkbox"/> 7/8" <input type="checkbox"/> 1" <input type="checkbox"/> 1-1/4" <input type="checkbox"/> Other _____
	Rebar: <input type="checkbox"/> #3 <input type="checkbox"/> #4 <input type="checkbox"/> #5 <input type="checkbox"/> #6 <input type="checkbox"/> #7 <input type="checkbox"/> #8 <input type="checkbox"/> #9 <input type="checkbox"/> Other _____

Base Material	Base Material Type: <input checked="" type="checkbox"/> NW Concrete <input type="checkbox"/> LW Concrete <input type="checkbox"/> Brick <input type="checkbox"/> CMU <input type="checkbox"/> Other _____
	Base Material Strength: <input type="checkbox"/> 2000 psi <input type="checkbox"/> 3000 psi <input checked="" type="checkbox"/> 4000 psi <input type="checkbox"/> Other _____
	Base Material Thickness: <u>30 in</u> (in/mm)
	Base Material Temperature: <u>60</u> (°F/°C)

Drilling & Hole Cleaning	Drill Bit Diameter: <u>7/8 in</u> (in/mm) Hole Depth: <u>10 in</u> (in/mm) <small>(core bit diameter, if approved)</small>
	Drill Bit Type: <input checked="" type="checkbox"/> Carbide-Tip Drill Bit <input type="checkbox"/> Diamond Core Bit <input type="checkbox"/> Hollow Drill Bit <input type="checkbox"/> Other _____ <small>(ANSI B212.15-1994) (if appropriate and allowed) (Safeset™ only to be used with Hilti HIT-HY 200)</small>
	Hole Condition: <input checked="" type="checkbox"/> Dry <input type="checkbox"/> Water Saturated <input type="checkbox"/> Water Filled <input type="checkbox"/> Under Water
	Hole Cleaning: <input checked="" type="checkbox"/> Compressed Air <input type="checkbox"/> Hand Pump <input checked="" type="checkbox"/> Wire Brush <input checked="" type="checkbox"/> Other <u>Vacuum</u>
	Hole cleaning in accordance with manufacturers' printed installation instructions: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No

Application	Anchor Application: <small>(please check all that apply)</small> <input checked="" type="checkbox"/> Tension <input type="checkbox"/> Shear <input type="checkbox"/> Overhead <input type="checkbox"/> Other _____
	Anchor insertion: <input checked="" type="checkbox"/> Twisting motion <input type="checkbox"/> Annular gap filled with adhesive <input type="checkbox"/> Air Void Free Injection
	Anchor Spacing: <u>40 in</u> (in/mm) Edge Distance: <u>8-3/4 in</u> (in/mm)
	Embedment (h _{ef}): <u>10 in</u> (in/mm) Installation Torque <small>(if required)</small> : _____ (ft-lb/Nm)

Completed by: Kinsey Skiller (Signature) Date: 2 / 20 / 17
 _____ (Print) Company: _____
 _____ (Title)

Adhesive Anchors Inspection Checklist for Concrete and Masonry

Periodic special must be performed where required in accordance with Section 1705.1.1 and Table 1705.3 of the 2012 IBC, or Section 1704.15 of the 2009 IBC and Table 1704.4 or Section 1704.13 of the 2006 or 2003 IBC, whereby periodic special inspection is defined in Section 1702.1 of the IBC and this report. (See Structural Drawings for inspection requirements)

Project Name: FENOC DS

Project Location: Bower Lab

Weather: inside Air Temperature: 60 (°F / °C)

CODES
<input type="checkbox"/> IBC 2003
<input type="checkbox"/> IBC 2006
<input type="checkbox"/> IBC 2009
<input type="checkbox"/> IBC 2012

Seismic Zone/ Seismic Design Category

Adhesive	Product Name/Manufacturer: <u>Hilti HIT-RE 500 V3</u>
	Lot No.: _____
	ICC-ES Report No.: _____
	Adhesive expiration Date: ___/___/___ <input type="checkbox"/> Specified Dispenser <input type="checkbox"/> Specified Mixer
	Discard Initial Adhesive: <u>8</u> (# trigger pulls)
Adhesive Temperature: <u>60°</u> (°F / °C) Gel Time: _____ Cure Time: <u>24 hrs</u> <small>(per manufacturers installation instructions)</small>	

Adhesive Element	Type: <input checked="" type="checkbox"/> All-Thread <input type="checkbox"/> Internally Threaded <input type="checkbox"/> Torque-Controlled <input type="checkbox"/> Rebar <input type="checkbox"/> Other _____ <small>(Safeset™ only to be used with Hilti HIT-HY 200)</small>
	Material: <input checked="" type="checkbox"/> Standard <input type="checkbox"/> Stainless Steel <input type="checkbox"/> High Strength
	Steel Grade/Coating: <u>ASTM A193 B7</u> Length: <u>15 in</u> (in/mm)
	Rod Diameter: <input type="checkbox"/> 3/8" <input type="checkbox"/> 1/2" <input type="checkbox"/> 5/8" <input checked="" type="checkbox"/> 3/4" <input type="checkbox"/> 7/8" <input type="checkbox"/> 1" <input type="checkbox"/> 1-1/4" <input type="checkbox"/> Other _____
	Rebar: <input type="checkbox"/> #3 <input type="checkbox"/> #4 <input type="checkbox"/> #5 <input type="checkbox"/> #6 <input type="checkbox"/> #7 <input type="checkbox"/> #8 <input type="checkbox"/> #9 <input type="checkbox"/> Other _____

Base Material	Base Material Type: <input checked="" type="checkbox"/> NW Concrete <input type="checkbox"/> LW Concrete <input type="checkbox"/> Brick <input type="checkbox"/> CMU <input type="checkbox"/> Other _____
	Base Material Strength: <input type="checkbox"/> 2000 psi <input type="checkbox"/> 3000 psi <input checked="" type="checkbox"/> 4000 psi <input type="checkbox"/> Other _____
	Base Material Thickness: <u>30 in</u> (in/mm)
	Base Material Temperature: <u>60° F</u> (°F / °C)

Drilling & Hole Cleaning	Drill Bit Diameter: <u>7/8"</u> (in/mm) Hole Depth: <u>12 in</u> (in/mm) <small>(core bit diameter, if approved)</small>
	Drill Bit Type: <input checked="" type="checkbox"/> Carbide-Tip Drill Bit <input type="checkbox"/> Diamond Core Bit <input type="checkbox"/> Hollow Drill Bit <input type="checkbox"/> Other _____ <small>(ANSI B212.15-1994) (if appropriate and allowed) (Safeset™ only to be used with Hilti HIT-HY 200)</small>
	Hole Condition: <input checked="" type="checkbox"/> Dry <input type="checkbox"/> Water Saturated <input type="checkbox"/> Water Filled <input type="checkbox"/> Under Water
	Hole Cleaning: <input checked="" type="checkbox"/> Compressed Air <input type="checkbox"/> Hand Pump <input checked="" type="checkbox"/> Wire Brush <input checked="" type="checkbox"/> Other <u>vacuum</u>
	Hole cleaning in accordance with manufacturers' printed installation instructions: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No

Application	Anchor Application: (please check all that apply) <input checked="" type="checkbox"/> Tension <input type="checkbox"/> Shear <input type="checkbox"/> Overhead <input type="checkbox"/> Other _____
	Anchor insertion: <input checked="" type="checkbox"/> Twisting motion <input type="checkbox"/> Annular gap filled with adhesive <input type="checkbox"/> Air Void Free Injection
	Anchor Spacing: <u>27 in</u> (in/mm) Edge Distance: <u>8-3/4"</u> (in/mm)
	Embedment (h _{ef}): <u>12 in</u> (in/mm) Installation Torque (if required): _____ (ft-lb/Nm)

Completed by: Kinsy Skiller (Signature) Date: 2/22/17
Kinsy Skiller (Print) Company: _____
 _____ (Title)

Adhesive Anchors Inspection Checklist for Concrete and Masonry

Periodic special must be performed where required in accordance with Section 1705.1.1 and Table 1705.3 of the 2012 IBC, or Section 1704.15 of the 2009 IBC and Table 1704.4 or Section 1704.13 of the 2006 or 2003 IBC, whereby periodic special inspection is defined in Section 1702.1 of the IBC and this report. (See Structural Drawings for inspection requirements)

Project Name: FENOG DG
 Project Location: Bower Lab
 Weather: inside Air Temperature: 60°F (°F/°C)

CODES <input type="checkbox"/> IBC 2003 <input type="checkbox"/> IBC 2006 <input type="checkbox"/> IBC 2009 <input type="checkbox"/> IBC 2012	Seismic Zone/ Seismic Design Category
--	--

Adhesive	Product Name/Manufacturer: <u>Hilti HIT RE 500 V3</u>
	Lot No.: _____
	ICC-ES Report No.: _____
	Adhesive expiration Date: ___/___/___ <input type="checkbox"/> Specified Dispenser <input type="checkbox"/> Specified Mixer
	Discard Initial Adhesive: <u>8</u> (# trigger pulls)
Adhesive Temperature: <u>60°F</u> (°F/°C) Gel Time: _____ Cure Time: <u>24 hrs</u> <small>(per manufacturers installation instructions)</small>	

Adhesive Element	Type: <input checked="" type="checkbox"/> All-Thread <input type="checkbox"/> Internally Threaded <input type="checkbox"/> Torque-Controlled <input type="checkbox"/> Rebar <input type="checkbox"/> Other _____ <small>(Safeset™ only to be used with Hilti HIT-HY 200)</small>
	Material: <input checked="" type="checkbox"/> Standard <input type="checkbox"/> Stainless Steel <input type="checkbox"/> High Strength
	Steel Grade/Coating: <u>ASTM A193 B7</u> Length: <u>15 in</u> (in/mm)
	Rod Diameter: <input type="checkbox"/> 3/8" <input type="checkbox"/> 1/2" <input type="checkbox"/> 5/8" <input checked="" type="checkbox"/> 3/4" <input type="checkbox"/> 7/8" <input type="checkbox"/> 1" <input type="checkbox"/> 1-1/4" <input type="checkbox"/> Other _____
	Rebar: <input type="checkbox"/> #3 <input type="checkbox"/> #4 <input type="checkbox"/> #5 <input type="checkbox"/> #6 <input type="checkbox"/> #7 <input type="checkbox"/> #8 <input type="checkbox"/> #9 <input type="checkbox"/> Other _____

Base Material	Base Material Type: <input checked="" type="checkbox"/> NW Concrete <input type="checkbox"/> LW Concrete <input type="checkbox"/> Brick <input type="checkbox"/> CMU <input type="checkbox"/> Other _____
	Base Material Strength: <input type="checkbox"/> 2000 psi <input type="checkbox"/> 3000 psi <input checked="" type="checkbox"/> 4000 psi <input type="checkbox"/> Other _____
	Base Material Thickness: <u>30 in</u> (in/mm)
	Base Material Temperature: <u>60°F</u> (°F/°C)

Drilling & Hole Cleaning	Drill Bit Diameter: <u>7/8"</u> (in/mm) Hole Depth: <u>12 in</u> (in/mm) <small>(core bit diameter, if approved)</small>
	Drill Bit Type: <input checked="" type="checkbox"/> Carbide-Tip Drill Bit <input type="checkbox"/> Diamond Core Bit <input type="checkbox"/> Hollow Drill Bit <input type="checkbox"/> Other _____ <small>(ANSI B212.15-1994) (if appropriate and allowed) (Safeset™ only to be used with Hilti HIT-HY 200)</small>
	Hole Condition: <input checked="" type="checkbox"/> Dry <input type="checkbox"/> Water Saturated <input type="checkbox"/> Water Filled <input type="checkbox"/> Under Water
	Hole Cleaning: <input checked="" type="checkbox"/> Compressed Air <input type="checkbox"/> Hand Pump <input checked="" type="checkbox"/> Wire Brush <input checked="" type="checkbox"/> Other <u>vacuum</u>
	Hole cleaning in accordance with manufacturers' printed installation instructions: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No

Application	Anchor Application: (please check all that apply) <input checked="" type="checkbox"/> Tension <input type="checkbox"/> Shear <input type="checkbox"/> Overhead <input type="checkbox"/> Other _____
	Anchor insertion: <input checked="" type="checkbox"/> Twisting motion <input type="checkbox"/> Annular gap filled with adhesive <input type="checkbox"/> Air Void Free Injection
	Anchor Spacing: <u>53 in</u> (in/mm) Edge Distance: _____ (in/mm)
	Embedment (h _{ef}): _____ (in/mm) Installation Torque (if required): _____ (ft-lb/Nm)

Completed by: KC Skiller (Signature) Date: 2/24/17
Kinsey Skiller (Print) Company: _____
 _____ (Title)

Adhesive Anchors Inspection Checklist for Concrete and Masonry

Periodic special must be performed where required in accordance with Section 1705.1.1 and Table 1705.3 of the 2012 IBC, or Section 1704.15 of the 2009 IBC and Table 1704.4 or Section 1704.13 of the 2006 or 2003 IBC, whereby periodic special inspection is defined in Section 1702.1 of the IBC and this report. (See Structural Drawings for inspection requirements)

Project Name: FENOC D7
 Project Location: Purdue Power Lab
 Weather: indoors Air Temperature: 60°F (°F/°C)

CODES
 IBC 2003
 IBC 2006
 IBC 2009
 IBC 2012

**Seismic Zone/
 Seismic Design Category**

Adhesive

Product Name/Manufacturer: Hilti HIT-RE 500 V3
 Lot No.: _____
 ICC-ES Report No.: _____
 Adhesive expiration Date: ___/___/___ Specified Dispenser Specified Mixer
 Discard Initial Adhesive: _____ (# trigger pulls)
 Adhesive Temperature: 60°F (°F/°C) Gel Time: _____ Cure Time: 48 hrs.
(per manufacturers installation instructions)

Adhesive Element

Type: All-Thread Internally Threaded Torque-Controlled Rebar Other _____
(Safeset™ only to be used with Hilti HIT-HY 200)
 Material: Standard Stainless Steel High Strength
 Steel Grade/Coating: ASTM A193 B7 Length: 15 in (in/mm)
 Rod Diameter: 3/8" 1/2" 5/8" 3/4" 7/8" 1" 1-1/4" Other _____
 Rebar: #3 #4 #5 #6 #7 #8 #9 Other _____

Base Material

Base Material Type: NW Concrete LW Concrete Brick CMU Other _____
 Base Material Strength: 2000 psi 3000 psi 4000 psi Other _____
 Base Material Thickness: 30 in (in/mm)
 Base Material Temperature: 60°F (°F/°C)

Drilling & Hole Cleaning

Drill Bit Diameter: 7/8 in (in/mm) Hole Depth: 12 in (in/mm)
(core bit diameter, if approved)
 Drill Bit Type: Carbide-Tip Drill Bit Diamond Core Bit Hollow Drill Bit Other _____
(ANSI B212.15-1994) (if appropriate and allowed) (Safeset™ only to be used with Hilti HIT-HY 200)
 Hole Condition: Dry Water Saturated Water Filled Under Water
 Hole Cleaning: Compressed Air Hand Pump Wire Brush Other vacuum
 Hole cleaning in accordance with manufacturers' printed installation instructions: Yes No

Application

Anchor Application: (please check all that apply) Tension Shear Overhead Other _____
 Anchor insertion: Twisting motion Annular gap filled with adhesive Air Void Free Injection
 Anchor Spacing: 26.5 in (in/mm) Edge Distance: 8-3/4 in (in/mm)
 Embedment (h_{ef}): 12 in (in/mm) Installation Torque (if required): _____ (ft-lb/Nm)

Completed by: [Signature] (Signature) Date: 2/26/17 6:10 pm
Kinsy Skiller (Print) Company: _____
 _____ (Title)

Adhesive Anchors Inspection Checklist for Concrete and Masonry

Periodic special must be performed where required in accordance with Section 1705.1.1 and Table 1705.3 of the 2012 IBC, or Section 1704.15 of the 2009 IBC and Table 1704.4 or Section 1704.13 of the 2006 or 2003 IBC, whereby periodic special inspection is defined in Section 1702.1 of the IBC and this report. (See Structural Drawings for Inspection requirements)

Project Name: D8

Project Location: _____

Weather: _____ Air Temperature: 60°F (°F/°C)

CODES <input type="checkbox"/> IBC 2003 <input type="checkbox"/> IBC 2006 <input type="checkbox"/> IBC 2009 <input type="checkbox"/> IBC 2012	Seismic Zone/ Seismic Design Category

Adhesive	Product Name/Manufacturer: <u>500 V3</u>
	Lot No.: _____
	ICC-ES Report No.: _____
	Adhesive expiration Date: ___/___/___ <input type="checkbox"/> Specified Dispenser <input type="checkbox"/> Specified Mixer
	Discard Initial Adhesive: _____ (# trigger pulls)
	Adhesive Temperature: <u>60°</u> (°F/°C) Gel Time: _____ Cure Time: <u>24 hrs</u> <small>(per manufacturers installation instructions)</small>

Adhesive Element	Type: <input checked="" type="checkbox"/> All-Thread <input type="checkbox"/> Internally Threaded <input type="checkbox"/> Torque-Controlled <input type="checkbox"/> Rebar <input type="checkbox"/> Other _____ <small>(Safeset™ only to be used with Hilti HIT-HY 200)</small>
	Material: <input checked="" type="checkbox"/> Standard <input type="checkbox"/> Stainless Steel <input type="checkbox"/> High Strength
	Steel Grade/Coating: <u>A193</u> Length: <u>24 in</u> (in/mm)
	Rod Diameter: <input type="checkbox"/> 3/8" <input type="checkbox"/> 1/2" <input type="checkbox"/> 5/8" <input checked="" type="checkbox"/> 3/4" <input type="checkbox"/> 7/8" <input type="checkbox"/> 1" <input type="checkbox"/> 1-1/4" <input type="checkbox"/> Other _____
	Rebar: <input type="checkbox"/> #3 <input type="checkbox"/> #4 <input type="checkbox"/> #5 <input type="checkbox"/> #6 <input type="checkbox"/> #7 <input type="checkbox"/> #8 <input type="checkbox"/> #9 <input type="checkbox"/> Other _____

Base Material	Base Material Type: <input checked="" type="checkbox"/> NW Concrete <input type="checkbox"/> LW Concrete <input type="checkbox"/> Brick <input type="checkbox"/> CMU <input type="checkbox"/> Other _____
	Base Material Strength: <input type="checkbox"/> 2000 psi <input type="checkbox"/> 3000 psi <input checked="" type="checkbox"/> 4000 psi <input type="checkbox"/> Other _____
	Base Material Thickness: <u>30 in</u> (in/mm)
	Base Material Temperature: <u>60</u> (°F/°C)

Drilling & Hole Cleaning	Drill Bit Diameter: <u>7/8 in</u> (in/mm) Hole Depth: <u>19 in</u> (in/mm) <small>(core bit diameter, if approved)</small>
	Drill Bit Type: <input checked="" type="checkbox"/> Carbide-Tip Drill Bit <input type="checkbox"/> Diamond Core Bit <input type="checkbox"/> Hollow Drill Bit <input type="checkbox"/> Other _____ <small>(ANSI B212.15-1994) (if appropriate and allowed) (Safeset™ only to be used with Hilti HIT-HY 200)</small>
	Hole Condition: <input checked="" type="checkbox"/> Dry <input type="checkbox"/> Water Saturated <input type="checkbox"/> Water Filled <input type="checkbox"/> Under Water
	Hole Cleaning: <input checked="" type="checkbox"/> Compressed Air <input type="checkbox"/> Hand Pump <input checked="" type="checkbox"/> Wire Brush <input checked="" type="checkbox"/> Other <u>vacuum</u>
	Hole cleaning in accordance with manufacturers' printed installation instructions: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No

Application	Anchor Application: (please check all that apply) <input checked="" type="checkbox"/> Tension <input type="checkbox"/> Shear <input type="checkbox"/> Overhead <input type="checkbox"/> Other _____
	Anchor insertion: <input checked="" type="checkbox"/> Twisting motion <input type="checkbox"/> Annular gap filled with adhesive <input type="checkbox"/> Air Void Free Injection
	Anchor Spacing: <u>27 in</u> (in/mm) Edge Distance: <u>9 in</u> (in/mm)
	Embedment (h _{ef}): <u>19 in</u> (in/mm) Installation Torque (if required): <u>0</u> (ft-lb/Nm)

Completed by: [Signature] (Signature) Date: 3/6/17

Kinsley Skillen (Print) Company: _____

_____ (Title)

Adhesive Anchors Inspection Checklist for Concrete and Masonry

Periodic special must be performed where required in accordance with Section 1705.1.1 and Table 1705.3 of the 2012 IBC, or Section 1704.15 of the 2009 IBC and Table 1704.4 or Section 1704.13 of the 2006 or 2003 IBC, whereby periodic special inspection is defined in Section 1702.1 of the IBC and this report. (See Structural Drawings for Inspection requirements)

Project Name: D9 N/A

Project Location: _____

Weather: _____ Air Temperature: _____ (°F / °C)

<p>CODES</p> <input type="checkbox"/> IBC 2003 <input type="checkbox"/> IBC 2006 <input type="checkbox"/> IBC 2009 <input type="checkbox"/> IBC 2012	<p>Seismic Zone/ Seismic Design Category</p>
--	---

Adhesive	Product Name/Manufacturer: _____
	Lot No.: _____
	ICC-ES Report No.: _____
	Adhesive expiration Date: ___/___/___ <input type="checkbox"/> Specified Dispenser <input type="checkbox"/> Specified Mixer
	Discard Initial Adhesive: _____ (# trigger pulls)
Adhesive Temperature: _____ (°F / °C) Gel Time: _____ Cure Time: _____ <small>(per manufacturers installation instructions)</small>	

Adhesive Element	Type: <input type="checkbox"/> All-Thread <input type="checkbox"/> Internally Threaded <input type="checkbox"/> Torque-Controlled <input type="checkbox"/> Rebar <input type="checkbox"/> Other _____ <small>(Safeset™ only to be used with Hilti HIT-HY 200)</small>
	Material: <input type="checkbox"/> Standard <input type="checkbox"/> Stainless Steel <input type="checkbox"/> High Strength
	Steel Grade/Coating: _____ Length: _____ (in/mm)
	Rod Diameter: <input type="checkbox"/> 3/8" <input type="checkbox"/> 1/2" <input type="checkbox"/> 5/8" <input type="checkbox"/> 3/4" <input type="checkbox"/> 7/8" <input type="checkbox"/> 1" <input type="checkbox"/> 1-1/4" <input type="checkbox"/> Other _____
	Rebar: <input type="checkbox"/> #3 <input type="checkbox"/> #4 <input type="checkbox"/> #5 <input type="checkbox"/> #6 <input type="checkbox"/> #7 <input type="checkbox"/> #8 <input type="checkbox"/> #9 <input type="checkbox"/> Other _____

Base Material	Base Material Type: <input type="checkbox"/> NW Concrete <input type="checkbox"/> LW Concrete <input type="checkbox"/> Brick <input type="checkbox"/> CMU <input type="checkbox"/> Other _____
	Base Material Strength: <input type="checkbox"/> 2000 psi <input type="checkbox"/> 3000 psi <input type="checkbox"/> 4000 psi <input type="checkbox"/> Other _____
	Base Material Thickness: _____ (in/mm)
	Base Material Temperature: _____ (°F / °C)

Drilling & Hole Cleaning	Drill Bit Diameter: _____ (in/mm) Hole Depth: _____ (in/mm) <small>(core bit diameter, if approved)</small>
	Drill Bit Type: <input type="checkbox"/> Carbide-Tip Drill Bit <input type="checkbox"/> Diamond Core Bit <input type="checkbox"/> Hollow Drill Bit <input type="checkbox"/> Other _____ <small>(ANSI B212.15-1994) (if appropriate and allowed) (Safeset™ only to be used with Hilti HIT-HY 200)</small>
	Hole Condition: <input type="checkbox"/> Dry <input type="checkbox"/> Water Saturated <input type="checkbox"/> Water Filled <input type="checkbox"/> Under Water
	Hole Cleaning: <input type="checkbox"/> Compressed Air <input type="checkbox"/> Hand Pump <input type="checkbox"/> Wire Brush <input type="checkbox"/> Other _____
	Hole cleaning in accordance with manufacturers' printed installation instructions: <input type="checkbox"/> Yes <input type="checkbox"/> No

Application	Anchor Application: <small>(please check all that apply)</small> <input type="checkbox"/> Tension <input type="checkbox"/> Shear <input type="checkbox"/> Overhead <input type="checkbox"/> Other _____
	Anchor insertion: <input type="checkbox"/> Twisting motion <input type="checkbox"/> Annular gap filled with adhesive <input type="checkbox"/> Air Void Free Injection
	Anchor Spacing: _____ (in/mm) Edge Distance: _____ (in/mm)
	Embedment (h _{ef}): _____ (in/mm) Installation Torque <small>(if required)</small> : _____ (ft-lb/Nm)

Completed by: _____ (Signature) Date: ___/___/___
 _____ (Print) Company: _____
 _____ (Title)

Adhesive Anchors Inspection Checklist for Concrete and Masonry

Periodic special must be performed where required in accordance with Section 1705.1.1 and Table 1705.3 of the 2012 IBC, or Section 1704.15 of the 2009 IBC and Table 1704.4 or Section 1704.13 of the 2006 or 2003 IBC, whereby periodic special inspection is defined in Section 1702.1 of the IBC and this report. (See Structural Drawings for Inspection requirements)

Project Name: D10

Project Location: Barr Lab

Weather: inside Air Temperature: 60 (°F / °C)

CODES
<input type="checkbox"/> IBC 2003
<input type="checkbox"/> IBC 2006
<input type="checkbox"/> IBC 2009
<input type="checkbox"/> IBC 2012

Seismic Zone/ Seismic Design Category

Adhesive	Product Name/Manufacturer: <u>500 V3</u>
	Lot No.: _____
	ICC-ES Report No.: _____
	Adhesive expiration Date: ___/___/___ <input type="checkbox"/> Specified Dispenser <input type="checkbox"/> Specified Mixer
	Discard Initial Adhesive: _____ (# trigger pulls)
Adhesive Temperature: _____ (°F / °C) Gel Time: _____ Cure Time: <u>24 hrs.</u>	
<small>(per manufacturers installation instructions)</small>	

Adhesive Element	Type: <input checked="" type="checkbox"/> All-Thread <input type="checkbox"/> Internally Threaded <input type="checkbox"/> Torque-Controlled <input type="checkbox"/> Rebar <input type="checkbox"/> Other _____ <small>(Safeset™ only to be used with Hilti HIT-HY 200)</small>
	Material: <input checked="" type="checkbox"/> Standard <input type="checkbox"/> Stainless Steel <input type="checkbox"/> High Strength
	Steel Grade/Coating: <u>A193 B7</u> Length: <u>24 in</u> (in/mm)
	Rod Diameter: <input type="checkbox"/> 3/8" <input type="checkbox"/> 1/2" <input type="checkbox"/> 5/8" <input checked="" type="checkbox"/> 3/4" <input type="checkbox"/> 7/8" <input type="checkbox"/> 1" <input type="checkbox"/> 1-1/4" <input type="checkbox"/> Other _____
	Rebar: <input type="checkbox"/> #3 <input type="checkbox"/> #4 <input type="checkbox"/> #5 <input type="checkbox"/> #6 <input type="checkbox"/> #7 <input type="checkbox"/> #8 <input type="checkbox"/> #9 <input type="checkbox"/> Other _____

Base Material	Base Material Type: <input checked="" type="checkbox"/> NW Concrete <input type="checkbox"/> LW Concrete <input type="checkbox"/> Brick <input type="checkbox"/> CMU <input type="checkbox"/> Other _____
	Base Material Strength: <input type="checkbox"/> 2000 psi <input type="checkbox"/> 3000 psi <input checked="" type="checkbox"/> 4000 psi <input type="checkbox"/> Other _____
	Base Material Thickness: <u>30 in</u> (in/mm)
	Base Material Temperature: <u>60</u> (°F / °C)

Drilling & Hole Cleaning	Drill Bit Diameter: <u>7/8 in</u> (in/mm) Hole Depth: <u>19 in</u> (in/mm) <small>(core bit diameter, if approved)</small>
	Drill Bit Type: <input checked="" type="checkbox"/> Carbide-Tip Drill Bit <input type="checkbox"/> Diamond Core Bit <input type="checkbox"/> Hollow Drill Bit <input type="checkbox"/> Other _____ <small>(ANSI B212.15-1994) (if appropriate and allowed) (Safeset™ only to be used with Hilti HIT-HY 200)</small>
	Hole Condition: <input checked="" type="checkbox"/> Dry <input type="checkbox"/> Water Saturated <input type="checkbox"/> Water Filled <input type="checkbox"/> Under Water
	Hole Cleaning: <input type="checkbox"/> Compressed Air <input type="checkbox"/> Hand Pump <input type="checkbox"/> Wire Brush <input checked="" type="checkbox"/> Other <u>vacuum</u>
	Hole cleaning in accordance with manufacturers' printed installation instructions: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No

Application	Anchor Application: (please check all that apply) <input checked="" type="checkbox"/> Tension <input type="checkbox"/> Shear <input type="checkbox"/> Overhead <input type="checkbox"/> Other _____
	Anchor insertion: <input checked="" type="checkbox"/> Twisting motion <input type="checkbox"/> Annular gap filled with adhesive <input type="checkbox"/> Air Void Free Injection
	Anchor Spacing: <u>27 in</u> (in/mm) Edge Distance: <u>9 in</u> (in/mm)
	Embedment (h _{ep}): <u>19 in</u> (in/mm) Installation Torque (if required): <u>100</u> (ft-lb/Nm)

Completed by: [Signature] (Signature) Date: 8/14/17
 _____ (Print) Company: _____
 _____ (Title)

Adhesive Anchors Inspection Checklist for Concrete and Masonry

Periodic special must be performed where required in accordance with Section 1705.1.1 and Table 1705.3 of the 2012 IBC, or Section 1704.15 of the 2009 IBC and Table 1704.4 or Section 1704.13 of the 2006 or 2003 IBC, whereby periodic special inspection is defined in Section 1702.1 of the IBC and this report. (See Structural Drawings for inspection requirements)

Project Name: D11 N/A

Project Location: _____

Weather: _____ Air Temperature: _____ (°F / °C)

CODES <input type="checkbox"/> IBC 2003 <input type="checkbox"/> IBC 2006 <input type="checkbox"/> IBC 2009 <input type="checkbox"/> IBC 2012	Seismic Zone/ Seismic Design Category

Adhesive	Product Name/Manufacturer: _____
	Lot No.: _____
	ICC-ES Report No.: _____
	Adhesive expiration Date: ___/___/___ <input type="checkbox"/> Specified Dispenser <input type="checkbox"/> Specified Mixer
	Discard Initial Adhesive: _____ (# trigger pulls)
Adhesive Temperature: _____ (°F / °C) <small>(per manufacturers installation instructions)</small> Gel Time: _____ Cure Time: _____	

Adhesive Element	Type: <input type="checkbox"/> All-Thread <input type="checkbox"/> Internally Threaded <input type="checkbox"/> Torque-Controlled <input type="checkbox"/> Rebar <input type="checkbox"/> Other _____ <small>(Safeset™ only to be used with Hilti HIT-HY 200)</small>
	Material: <input type="checkbox"/> Standard <input type="checkbox"/> Stainless Steel <input type="checkbox"/> High Strength
	Steel Grade/Coating: _____ Length: _____ (in/mm)
	Rod Diameter: <input type="checkbox"/> 3/8" <input type="checkbox"/> 1/2" <input type="checkbox"/> 5/8" <input type="checkbox"/> 3/4" <input type="checkbox"/> 7/8" <input type="checkbox"/> 1" <input type="checkbox"/> 1-1/4" <input type="checkbox"/> Other _____
	Rebar: <input type="checkbox"/> #3 <input type="checkbox"/> #4 <input type="checkbox"/> #5 <input type="checkbox"/> #6 <input type="checkbox"/> #7 <input type="checkbox"/> #8 <input type="checkbox"/> #9 <input type="checkbox"/> Other _____

Base Material	Base Material Type: <input type="checkbox"/> NW Concrete <input type="checkbox"/> LW Concrete <input type="checkbox"/> Brick <input type="checkbox"/> CMU <input type="checkbox"/> Other _____
	Base Material Strength: <input type="checkbox"/> 2000 psi <input type="checkbox"/> 3000 psi <input type="checkbox"/> 4000 psi <input type="checkbox"/> Other _____
	Base Material Thickness: _____ (in/mm)
	Base Material Temperature: _____ (°F / °C)

Drilling & Hole Cleaning	Drill Bit Diameter: _____ (in/mm) <small>(core bit diameter, if approved)</small> Hole Depth: _____ (in/mm)
	Drill Bit Type: <input type="checkbox"/> Carbide-Tip Drill Bit <input type="checkbox"/> Diamond Core Bit <input type="checkbox"/> Hollow Drill Bit <input type="checkbox"/> Other _____ <small>(ANSI B212.15-1994) (if appropriate and allowed) (Safeset™ only to be used with Hilti HIT-HY 200)</small>
	Hole Condition: <input type="checkbox"/> Dry <input type="checkbox"/> Water Saturated <input type="checkbox"/> Water Filled <input type="checkbox"/> Under Water
	Hole Cleaning: <input type="checkbox"/> Compressed Air <input type="checkbox"/> Hand Pump <input type="checkbox"/> Wire Brush <input type="checkbox"/> Other _____
	Hole cleaning in accordance with manufacturers' printed installation instructions: <input type="checkbox"/> Yes <input type="checkbox"/> No

Application	Anchor Application: <small>(please check all that apply)</small> <input type="checkbox"/> Tension <input type="checkbox"/> Shear <input type="checkbox"/> Overhead <input type="checkbox"/> Other _____
	Anchor insertion: <input type="checkbox"/> Twisting motion <input type="checkbox"/> Annular gap filled with adhesive <input type="checkbox"/> Air Void Free Injection
	Anchor Spacing: _____ (in/mm) Edge Distance: _____ (in/mm)
	Embedment (h_{ef}): _____ (in/mm) Installation Torque <small>(if required)</small> : _____ (ft-lb/Nm)

Completed by: _____ (Signature) Date: ___/___/___
 _____ (Print) Company: _____
 _____ (Title)

Adhesive Anchors Inspection Checklist for Concrete and Masonry

Periodic special must be performed where required in accordance with Section 1705.1.1 and Table 1705.3 of the 2012 IBC, or Section 1704.15 of the 2009 IBC and Table 1704.4 or Section 1704.13 of the 2006 or 2003 IBC, whereby periodic special inspection is defined in Section 1702.1 of the IBC and this report. (See Structural Drawings for Inspection requirements)

Project Name: D12
 Project Location: Power Feb
 Weather: inside Air Temperature: 60 (°F/°C)

CODES <input type="checkbox"/> IBC 2003 <input type="checkbox"/> IBC 2006 <input type="checkbox"/> IBC 2009 <input type="checkbox"/> IBC 2012	Seismic Zone/ Seismic Design Category

Adhesive	Product Name/Manufacturer: <u>500 V3</u>
	Lot No.: _____
	ICC-ES Report No.: _____
	Adhesive expiration Date: ___/___/___ <input type="checkbox"/> Specified Dispenser <input type="checkbox"/> Specified Mixer
	Discard Initial Adhesive: _____ (# trigger pulls)
Adhesive Temperature: <u>60</u> (°F/°C) Gel Time: _____ Cure Time: <u>24 hrs</u> <small>(per manufacturers installation instructions)</small>	

Adhesive Element	Type: <input checked="" type="checkbox"/> All-Thread <input type="checkbox"/> Internally Threaded <input type="checkbox"/> Torque-Controlled <input type="checkbox"/> Rebar <input type="checkbox"/> Other _____ <small>(Safeset™ only to be used with Hilti HIT-HY 200)</small>
	Material: <input checked="" type="checkbox"/> Standard <input type="checkbox"/> Stainless Steel <input type="checkbox"/> High Strength
	Steel Grade/Coating: <u>A193 B7</u> Length: <u>24 in</u> (in/mm)
	Rod Diameter: <input type="checkbox"/> 3/8" <input type="checkbox"/> 1/2" <input type="checkbox"/> 5/8" <input checked="" type="checkbox"/> 3/4" <input type="checkbox"/> 7/8" <input type="checkbox"/> 1" <input type="checkbox"/> 1-1/4" <input type="checkbox"/> Other _____
	Rebar: <input type="checkbox"/> #3 <input type="checkbox"/> #4 <input type="checkbox"/> #5 <input type="checkbox"/> #6 <input type="checkbox"/> #7 <input type="checkbox"/> #8 <input type="checkbox"/> #9 <input type="checkbox"/> Other _____

Base Material	Base Material Type: <input checked="" type="checkbox"/> NW Concrete <input type="checkbox"/> LW Concrete <input type="checkbox"/> Brick <input type="checkbox"/> CMU <input type="checkbox"/> Other _____
	Base Material Strength: <input type="checkbox"/> 2000 psi <input type="checkbox"/> 3000 psi <input checked="" type="checkbox"/> 4000 psi <input type="checkbox"/> Other _____
	Base Material Thickness: <u>30 in</u> (in/mm)
	Base Material Temperature: <u>60</u> (°F/°C)

Drilling & Hole Cleaning	Drill Bit Diameter: <u>7/8 in</u> (in/mm) Hole Depth: <u>19 in</u> (in/mm) <small>(core bit diameter, if approved)</small>
	Drill Bit Type: <input checked="" type="checkbox"/> Carbide-Tip Drill Bit <input type="checkbox"/> Diamond Core Bit <input type="checkbox"/> Hollow Drill Bit <input type="checkbox"/> Other _____ <small>(ANSI B212.15-1994) (if appropriate and allowed) (Safeset™ only to be used with Hilti HIT-HY 200)</small>
	Hole Condition: <input checked="" type="checkbox"/> Dry <input type="checkbox"/> Water Saturated <input type="checkbox"/> Water Filled <input type="checkbox"/> Under Water
	Hole Cleaning: <input checked="" type="checkbox"/> Compressed Air <input type="checkbox"/> Hand Pump <input type="checkbox"/> Wire Brush <input checked="" type="checkbox"/> Other <u>vacuum</u>
	Hole cleaning in accordance with manufacturers' printed installation instructions: <input type="checkbox"/> Yes <input type="checkbox"/> No

Application	Anchor Application: (please check all that apply) <input checked="" type="checkbox"/> Tension <input type="checkbox"/> Shear <input type="checkbox"/> Overhead <input type="checkbox"/> Other _____
	Anchor insertion: <input checked="" type="checkbox"/> Twisting motion <input type="checkbox"/> Annular gap filled with adhesive <input type="checkbox"/> Air Void Free Injection
	Anchor Spacing: <u>27 in</u> (in/mm) Edge Distance: <u>9 in</u> (in/mm)
	Embedment (h _{ep}): <u>19 in</u> (in/mm) Installation Torque (if required): <u>100</u> (ft-lb/Nm)

Completed by: [Signature] (Signature) Date: 3/22/17
Kinzy Skiller (Print) Company: _____
 _____ (Title)

Adhesive Anchors Inspection Checklist for Concrete and Masonry

Periodic special must be performed where required in accordance with Section 1705.1.1 and Table 1705.3 of the 2012 IBC, or Section 1704.15 of the 2009 IBC and Table 1704.4 or Section 1704.13 of the 2006 or 2003 IBC, whereby periodic special inspection is defined in Section 1702.1 of the IBC and this report. (See Structural Drawings for inspection requirements)

Project Name: FENOC D13
 Project Location: Purdue Bower Lab
 Weather: _____ Air Temperature: 80 (°F/°C)

CODES <input type="checkbox"/> IBC 2003 <input type="checkbox"/> IBC 2006 <input type="checkbox"/> IBC 2009 <input type="checkbox"/> IBC 2012	Seismic Zone/ Seismic Design Category
--	--

Adhesive	Product Name/Manufacturer: <u>500 V3</u>
	Lot No.: _____
	ICC-ES Report No.: _____
	Adhesive expiration Date: ___/___/___ <input type="checkbox"/> Specified Dispenser <input type="checkbox"/> Specified Mixer
	Discard Initial Adhesive: _____ (# trigger pulls)
Adhesive Temperature: <u>80</u> (°F/°C) Gel Time: _____ Cure Time: <u>24 hrs</u> <small>(per manufacturers installation instructions)</small>	

Adhesive Element	Type: <input checked="" type="checkbox"/> All-Thread <input type="checkbox"/> Internally Threaded <input type="checkbox"/> Torque-Controlled <input type="checkbox"/> Rebar <input type="checkbox"/> Other _____ <small>(Safeset™ only to be used with Hilti HIT-HY 200)</small>
	Material: <input checked="" type="checkbox"/> Standard <input type="checkbox"/> Stainless Steel <input type="checkbox"/> High Strength
	Steel Grade/Coating: <u>A193 B7</u> Length: <u>24 in</u> (in/mm)
	Rod Diameter: <input type="checkbox"/> 3/8" <input type="checkbox"/> 1/2" <input type="checkbox"/> 5/8" <input checked="" type="checkbox"/> 3/4" <input type="checkbox"/> 7/8" <input type="checkbox"/> 1" <input type="checkbox"/> 1-1/4" <input type="checkbox"/> Other _____
	Rebar: <input type="checkbox"/> #3 <input type="checkbox"/> #4 <input type="checkbox"/> #5 <input type="checkbox"/> #6 <input type="checkbox"/> #7 <input type="checkbox"/> #8 <input type="checkbox"/> #9 <input type="checkbox"/> Other _____

Base Material	Base Material Type: <input type="checkbox"/> NW Concrete <input type="checkbox"/> LW Concrete <input type="checkbox"/> Brick <input type="checkbox"/> CMU <input type="checkbox"/> Other _____
	Base Material Strength: <input type="checkbox"/> 2000 psi <input type="checkbox"/> 3000 psi <input type="checkbox"/> 4000 psi <input checked="" type="checkbox"/> Other <u>4500 psi</u>
	Base Material Thickness: <u>30 in</u> (in/mm)
	Base Material Temperature: <u>80</u> (°F/°C)

Drilling & Hole Cleaning	Drill Bit Diameter: <u>7/8</u> (in/mm) Hole Depth: <u>19</u> (in/mm) <small>(core bit diameter, if approved)</small>
	Drill Bit Type: <input checked="" type="checkbox"/> Carbide-Tip Drill Bit <input type="checkbox"/> Diamond Core Bit <input type="checkbox"/> Hollow Drill Bit <input type="checkbox"/> Other _____ <small>(ANSI B212.15-1994) (if appropriate and allowed) (Safeset™ only to be used with Hilti HIT-HY 200)</small>
	Hole Condition: <input checked="" type="checkbox"/> Dry <input type="checkbox"/> Water Saturated <input type="checkbox"/> Water Filled <input type="checkbox"/> Under Water
	Hole Cleaning: <input checked="" type="checkbox"/> Compressed Air <input type="checkbox"/> Hand Pump <input checked="" type="checkbox"/> Wire Brush <input checked="" type="checkbox"/> Other <u>vacuum</u>
	Hole cleaning in accordance with manufacturers' printed installation instructions: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No

Application	Anchor Application: (please check all that apply) <input checked="" type="checkbox"/> Tension <input type="checkbox"/> Shear <input type="checkbox"/> Overhead <input type="checkbox"/> Other _____
	Anchor insertion: <input checked="" type="checkbox"/> Twisting motion <input type="checkbox"/> Annular gap filled with adhesive <input type="checkbox"/> Air Void Free Injection
	Anchor Spacing: <u>27</u> (in/mm) Edge Distance: <u>9 in</u> (in/mm)
	Embedment (h _{ef}): <u>19</u> (in/mm) Installation Torque (if required): <u>100</u> (ft-lb/Nm)

Completed by: RCSkiler (Signature) Date: 6/14/17
Kinsy Skiler (Print) Company: _____
 _____ (Title)

Adhesive Anchors Inspection Checklist for Concrete and Masonry

Periodic special must be performed where required in accordance with Section 1705.1.1 and Table 1705.3 of the 2012 IBC, or Section 1704.15 of the 2009 IBC and Table 1704.4 or Section 1704.13 of the 2006 or 2003 IBC, whereby periodic special inspection is defined in Section 1702.1 of the IBC and this report. (See Structural Drawings for Inspection requirements)

Project Name: FENOC D14
 Project Location: Ridge Bower Lab
 Weather: _____ Air Temperature: 80 (°F)/°C

CODES <input type="checkbox"/> IBC 2003 <input type="checkbox"/> IBC 2006 <input type="checkbox"/> IBC 2009 <input type="checkbox"/> IBC 2012	Seismic Zone/ Seismic Design Category

Adhesive	Product Name/Manufacturer: <u>Soo V3</u>
	Lot No.: _____
	ICC-ES Report No.: _____
	Adhesive expiration Date: ___/___/___ <input type="checkbox"/> Specified Dispenser <input type="checkbox"/> Specified Mixer
	Discard Initial Adhesive: _____ (# trigger pulls)
Adhesive Temperature: <u>80</u> (°F)/°C <small>(per manufacturers installation instructions)</small> Gel Time: _____ Cure Time: <u>24 hrs</u>	

Adhesive Element	Type: <input checked="" type="checkbox"/> All-Thread <input type="checkbox"/> Internally Threaded <input type="checkbox"/> Torque-Controlled <input type="checkbox"/> Rebar <input type="checkbox"/> Other _____ <small>(Safeset™ only to be used with Hilti HIT-HY 200)</small>
	Material: <input checked="" type="checkbox"/> Standard <input type="checkbox"/> Stainless Steel <input type="checkbox"/> High Strength
	Steel Grade/Coating: <u>A193 B7</u> Length: <u>74 in</u> (in/mm)
	Rod Diameter: <input type="checkbox"/> 3/8" <input type="checkbox"/> 1/2" <input type="checkbox"/> 5/8" <input checked="" type="checkbox"/> 3/4" <input type="checkbox"/> 7/8" <input type="checkbox"/> 1" <input type="checkbox"/> 1-1/4" <input type="checkbox"/> Other _____
	Rebar: <input type="checkbox"/> #3 <input type="checkbox"/> #4 <input type="checkbox"/> #5 <input type="checkbox"/> #6 <input type="checkbox"/> #7 <input type="checkbox"/> #8 <input type="checkbox"/> #9 <input type="checkbox"/> Other _____

Base Material	Base Material Type: <input type="checkbox"/> NW Concrete <input type="checkbox"/> LW Concrete <input type="checkbox"/> Brick <input type="checkbox"/> CMU <input type="checkbox"/> Other _____
	Base Material Strength: <input type="checkbox"/> 2000 psi <input type="checkbox"/> 3000 psi <input type="checkbox"/> 4000 psi <input checked="" type="checkbox"/> Other <u>4500 psi</u>
	Base Material Thickness: <u>30 in</u> (in/mm)
	Base Material Temperature: <u>80</u> (°F)/°C

Drilling & Hole Cleaning	Drill Bit Diameter: <u>7/8</u> (in/mm) <small>(core bit diameter, if approved)</small> Hole Depth: <u>19</u> (in/mm)
	Drill Bit Type: <input checked="" type="checkbox"/> Carbide-Tip Drill Bit <input type="checkbox"/> Diamond Core Bit <input type="checkbox"/> Hollow Drill Bit <input type="checkbox"/> Other _____ <small>(ANSI B212.15-1994) (if appropriate and allowed) (Safeset™ only to be used with Hilti HIT-HY 200)</small>
	Hole Condition: <input checked="" type="checkbox"/> Dry <input type="checkbox"/> Water Saturated <input type="checkbox"/> Water Filled <input type="checkbox"/> Under Water
	Hole Cleaning: <input checked="" type="checkbox"/> Compressed Air <input type="checkbox"/> Hand Pump <input checked="" type="checkbox"/> Wire Brush <input type="checkbox"/> Other <u>vacuum</u>
	Hole cleaning in accordance with manufacturers' printed installation instructions: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No

Application	Anchor Application: <small>(please check all that apply)</small> <input checked="" type="checkbox"/> Tension <input type="checkbox"/> Shear <input type="checkbox"/> Overhead <input type="checkbox"/> Other _____
	Anchor insertion: <input checked="" type="checkbox"/> Twisting motion <input type="checkbox"/> Annular gap filled with adhesive <input type="checkbox"/> Air Void Free Injection
	Anchor Spacing: <u>27</u> (in/mm) Edge Distance: <u>9</u> (in/mm)
	Embedment (h _{ef}): <u>19</u> (in/mm) Installation Torque <small>(if required)</small> : <u>100</u> (ft-lb/Nm)

Completed by: KCSkiller (Signature) Date: 6/19/17
Kinsay Skiller (Print) Company: _____
 _____ (Title)



Adhesive Anchors Inspection Checklist for Concrete and Masonry

Periodic special must be performed where required in accordance with Section 1705.1.1 and Table 1705.3 of the 2012 IBC, or Section 1704.15 of the 2009 IBC and Table 1704.4 or Section 1704.13 of the 2006 or 2003 IBC, whereby periodic special inspection is defined in Section 1702.1 of the IBC and this report. (See Structural Drawings for inspection requirements)

Project Name: FENOC DIS
 Project Location: Purdue Bowen Lab
 Weather: _____ Air Temperature: 80 (°F/°C)

CODES <input type="checkbox"/> IBC 2003 <input type="checkbox"/> IBC 2006 <input type="checkbox"/> IBC 2009 <input type="checkbox"/> IBC 2012	Seismic Zone/ Seismic Design Category
--	--

Adhesive	Product Name/Manufacturer: <u>500 V3</u>
	Lot No.: _____
	ICC-ES Report No.: _____
	Adhesive expiration Date: ___/___/___ <input type="checkbox"/> Specified Dispenser <input type="checkbox"/> Specified Mixer
	Discard Initial Adhesive: _____ (# trigger pulls)
Adhesive Temperature: <u>80</u> (°F/°C) Gel Time: _____ Cure Time: <u>24 hrs</u> <small>(per manufacturers installation instructions)</small>	

Adhesive Element	Type: <input checked="" type="checkbox"/> All-Thread <input type="checkbox"/> Internally Threaded <input type="checkbox"/> Torque-Controlled <input type="checkbox"/> Rebar <input type="checkbox"/> Other _____ <small>(Safeset™ only to be used with Hilti HIT-HY 200)</small>
	Material: <input checked="" type="checkbox"/> Standard <input type="checkbox"/> Stainless Steel <input type="checkbox"/> High Strength
	Steel Grade/Coating: <u>A193 B7</u> Length: <u>24</u> (in/mm)
	Rod Diameter: <input type="checkbox"/> 3/8" <input type="checkbox"/> 1/2" <input type="checkbox"/> 5/8" <input checked="" type="checkbox"/> 3/4" <input type="checkbox"/> 7/8" <input type="checkbox"/> 1" <input type="checkbox"/> 1-1/4" <input type="checkbox"/> Other _____
	Rebar: <input type="checkbox"/> #3 <input type="checkbox"/> #4 <input type="checkbox"/> #5 <input type="checkbox"/> #6 <input type="checkbox"/> #7 <input type="checkbox"/> #8 <input type="checkbox"/> #9 <input type="checkbox"/> Other _____

Base Material	Base Material Type: <input checked="" type="checkbox"/> NW Concrete <input type="checkbox"/> LW Concrete <input type="checkbox"/> Brick <input type="checkbox"/> CMU <input type="checkbox"/> Other _____
	Base Material Strength: <input type="checkbox"/> 2000 psi <input type="checkbox"/> 3000 psi <input type="checkbox"/> 4000 psi <input checked="" type="checkbox"/> Other <u>4500 psi</u>
	Base Material Thickness: <u>30</u> (in/mm)
	Base Material Temperature: <u>80</u> (°F/°C)

Drilling & Hole Cleaning	Drill Bit Diameter: <u>7/8</u> (in/mm) Hole Depth: <u>19</u> (in/mm) <small>(core bit diameter, if approved)</small>
	Drill Bit Type: <input checked="" type="checkbox"/> Carbide-Tip Drill Bit <input type="checkbox"/> Diamond Core Bit <input type="checkbox"/> Hollow Drill Bit <input type="checkbox"/> Other _____ <small>(ANSI B212.15-1994) (if appropriate and allowed) (Safeset™ only to be used with Hilti HIT-HY 200)</small>
	Hole Condition: <input checked="" type="checkbox"/> Dry <input type="checkbox"/> Water Saturated <input type="checkbox"/> Water Filled <input type="checkbox"/> Under Water
	Hole Cleaning: <input checked="" type="checkbox"/> Compressed Air <input type="checkbox"/> Hand Pump <input checked="" type="checkbox"/> Wire Brush <input checked="" type="checkbox"/> Other <u>vacuum</u>
	Hole cleaning in accordance with manufacturers' printed installation instructions: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No

Application	Anchor Application: (please check all that apply) <input checked="" type="checkbox"/> Tension <input type="checkbox"/> Shear <input type="checkbox"/> Overhead <input type="checkbox"/> Other _____
	Anchor insertion: <input checked="" type="checkbox"/> Twisting motion <input type="checkbox"/> Annular gap filled with adhesive <input type="checkbox"/> Air Void Free Injection
	Anchor Spacing: <u>27</u> (in/mm) Edge Distance: <u>9</u> (in/mm)
	Embedment (h _{ef}): <u>19</u> (in/mm) Installation Torque (if required): <u>100</u> (ft-lb/Nm)

Completed by: Kinsy Skiller (Signature) Date: 6/22/17
Kinsy Skiller (Print) Company: _____
 _____ (Title)



Adhesive Anchors Inspection Checklist for Concrete and Masonry

Periodic special must be performed where required in accordance with Section 1705.1.1 and Table 1705.3 of the 2012 IBC, or Section 1704.15 of the 2009 IBC and Table 1704.4 or Section 1704.13 of the 2006 or 2003 IBC, whereby periodic special inspection is defined in Section 1702.1 of the IBC and this report. (See Structural Drawings for inspection requirements)

Project Name: FENOC D16
 Project Location: Purdue Power Lab
 Weather: _____ Air Temperature: 80 (°F/°C)

- CODES**
- IBC 2003
 - IBC 2006
 - IBC 2009
 - IBC 2012

**Seismic Zone/
Seismic Design Category**

Adhesive

Product Name/Manufacturer: 500 V3
 Lot No.: _____
 ICC-ES Report No.: _____
 Adhesive expiration Date: ___/___/___ Specified Dispenser Specified Mixer
 Discard Initial Adhesive: _____ (# trigger pulls)
 Adhesive Temperature: 80 (°F/°C) Gel Time: _____ Cure Time: 24 hrs
(per manufacturers installation instructions)

Adhesive Element

Type: All-Thread Internally Threaded Torque-Controlled Rebar Other _____
(Safeset™ only to be used with Hilti HIT-HY 200)
 Material: Standard Stainless Steel High Strength
 Steel Grade/Coating: A193 B7 Length: 24 (in/mm)
 Rod Diameter: 3/8" 1/2" 5/8" 3/4" 7/8" 1" 1-1/4" Other _____
 Rebar: #3 #4 #5 #6 #7 #8 #9 Other _____

Base Material

Base Material Type: NW Concrete LW Concrete Brick CMU Other _____
 Base Material Strength: 2000 psi 3000 psi 4000 psi Other 4500 psi
 Base Material Thickness: 30 (in/mm)
 Base Material Temperature: 80 (°F/°C)

Drilling & Hole Cleaning

Drill Bit Diameter: 7/8 (in/mm) Hole Depth: 19 (in/mm)
(core bit diameter, if approved)
 Drill Bit Type: Carbide-Tip Drill Bit Diamond Core Bit Hollow Drill Bit Other _____
(ANSI B212.15-1994) (if appropriate and allowed) (Safeset™ only to be used with Hilti HIT-HY 200)
 Hole Condition: Dry Water Saturated Water Filled Under Water
 Hole Cleaning: Compressed Air Hand Pump Wire Brush Other vacuum
 Hole cleaning in accordance with manufacturers' printed installation instructions: Yes No

Application

Anchor Application: (please check all that apply) Tension Shear Overhead Other _____
 Anchor insertion: Twisting motion Annular gap filled with adhesive Air Void Free Injection
 Anchor Spacing: 27 (in/mm) Edge Distance: 9 (in/mm)
 Embedment (h_{ef}): 17 (in/mm) Installation Torque (if required): 100 (ft-lb/Nm)

Completed by: KO. Skiller (Signature) Date: 6/29/17
Kinsay Skiller (Print) Company: _____
 _____ (Title)



Adhesive Anchors Inspection Checklist for Concrete and Masonry

Periodic special must be performed where required in accordance with Section 1705.1.1 and Table 1705.3 of the 2012 IBC, or Section 1704.15 of the 2009 IBC and Table 1704.4 or Section 1704.13 of the 2006 or 2003 IBC, whereby periodic special inspection is defined in Section 1702.1 of the IBC and this report. (See Structural Drawings for inspection requirements)

Project Name: D17 N/A

Project Location: _____

Weather: _____ Air Temperature: _____ (°F / °C)

CODES <input type="checkbox"/> IBC 2003 <input type="checkbox"/> IBC 2006 <input type="checkbox"/> IBC 2009 <input type="checkbox"/> IBC 2012	Seismic Zone/ Seismic Design Category

Adhesive	Product Name/Manufacturer: _____
	Lot No.: _____
	ICC-ES Report No.: _____
	Adhesive expiration Date: ___/___/___ <input type="checkbox"/> Specified Dispenser <input type="checkbox"/> Specified Mixer
	Discard Initial Adhesive: _____ (# trigger pulls)
Adhesive Temperature: _____ (°F / °C) Gel Time: _____ Cure Time: _____ <small>(per manufacturers installation instructions)</small>	

Adhesive Element	Type: <input type="checkbox"/> All-Thread <input type="checkbox"/> Internally Threaded <input type="checkbox"/> Torque-Controlled <input type="checkbox"/> Rebar <input type="checkbox"/> Other _____ <small>(Safeset™ only to be used with Hilti HIT-HY 200)</small>
	Material: <input type="checkbox"/> Standard <input type="checkbox"/> Stainless Steel <input type="checkbox"/> High Strength
	Steel Grade/Coating: _____ Length: _____ (in/mm)
	Rod Diameter: <input type="checkbox"/> 3/8" <input type="checkbox"/> 1/2" <input type="checkbox"/> 5/8" <input type="checkbox"/> 3/4" <input type="checkbox"/> 7/8" <input type="checkbox"/> 1" <input type="checkbox"/> 1-1/4" <input type="checkbox"/> Other _____
	Rebar: <input type="checkbox"/> #3 <input type="checkbox"/> #4 <input type="checkbox"/> #5 <input type="checkbox"/> #6 <input type="checkbox"/> #7 <input type="checkbox"/> #8 <input type="checkbox"/> #9 <input type="checkbox"/> Other _____

Base Material	Base Material Type: <input type="checkbox"/> NW Concrete <input type="checkbox"/> LW Concrete <input type="checkbox"/> Brick <input type="checkbox"/> CMU <input type="checkbox"/> Other _____
	Base Material Strength: <input type="checkbox"/> 2000 psi <input type="checkbox"/> 3000 psi <input type="checkbox"/> 4000 psi <input type="checkbox"/> Other _____
	Base Material Thickness: _____ (in/mm)
	Base Material Temperature: _____ (°F / °C)

Drilling & Hole Cleaning	Drill Bit Diameter: _____ (in/mm) Hole Depth: _____ (in/mm) <small>(core bit diameter, if approved)</small>
	Drill Bit Type: <input type="checkbox"/> Carbide-Tip Drill Bit <input type="checkbox"/> Diamond Core Bit <input type="checkbox"/> Hollow Drill Bit <input type="checkbox"/> Other _____ <small>(ANSI B212.15-1994) (if appropriate and allowed) (Safeset™ only to be used with Hilti HIT-HY 200)</small>
	Hole Condition: <input type="checkbox"/> Dry <input type="checkbox"/> Water Saturated <input type="checkbox"/> Water Filled <input type="checkbox"/> Under Water
	Hole Cleaning: <input type="checkbox"/> Compressed Air <input type="checkbox"/> Hand Pump <input type="checkbox"/> Wire Brush <input type="checkbox"/> Other _____
	Hole cleaning in accordance with manufacturers' printed installation instructions: <input type="checkbox"/> Yes <input type="checkbox"/> No

Application	Anchor Application: <small>(please check all that apply)</small> <input type="checkbox"/> Tension <input type="checkbox"/> Shear <input type="checkbox"/> Overhead <input type="checkbox"/> Other _____
	Anchor insertion: <input type="checkbox"/> Twisting motion <input type="checkbox"/> Annular gap filled with adhesive <input type="checkbox"/> Air Void Free Injection
	Anchor Spacing: _____ (in/mm) Edge Distance: _____ (in/mm)
	Embedment (h_{ef}): _____ (in/mm) Installation Torque <small>(if required)</small> : _____ (ft-lb/Nm)

Completed by: _____ (Signature) Date: ___/___/___
 _____ (Print) Company: _____
 _____ (Title)

Adhesive Anchors Inspection Checklist for Concrete and Masonry

Periodic special must be performed where required in accordance with Section 1705.1.1 and Table 1705.3 of the 2012 IBC, or Section 1704.15 of the 2009 IBC and Table 1704.4 or Section 1704.13 of the 2006 or 2003 IBC, whereby periodic special inspection is defined in Section 1702.1 of the IBC and this report. (See Structural Drawings for Inspection requirements)

Project Name: FENOC D18
 Project Location: Purdue Bowen Lab
 Weather: _____ Air Temperature: 80 (°F) (°C)

- CODES**
- IBC 2003
 - IBC 2006
 - IBC 2009
 - IBC 2012

**Seismic Zone/
Seismic Design Category**

Adhesive

Product Name/Manufacturer: 500 V3
 Lot No.: _____
 ICC-ES Report No.: _____
 Adhesive expiration Date: ___/___/___ Specified Dispenser Specified Mixer
 Discard Initial Adhesive: _____ (# trigger pulls)
 Adhesive Temperature: 80 (°F) (°C) Gel Time: _____ Cure Time: 24 hrs
(per manufacturers installation instructions)

Adhesive Element

Type: All-Thread Internally Threaded Torque-Controlled Rebar Other _____
(Safeset™ only to be used with Hilti HIT-HY 200)
 Material: Standard Stainless Steel High Strength
 Steel Grade/Coating: A193 B7 Length: 24 (in/mm)
 Rod Diameter: 3/8" 1/2" 5/8" 3/4" 7/8" 1" 1-1/4" Other _____
 Rebar: #3 #4 #5 #6 #7 #8 #9 Other _____

Base Material

Base Material Type: NW Concrete LW Concrete Brick CMU Other _____
 Base Material Strength: 2000 psi 3000 psi 4000 psi Other 4500 psi
 Base Material Thickness: 80 (in/mm)
 Base Material Temperature: 80 (°F) (°C)

Drilling & Hole Cleaning

Drill Bit Diameter: 7/8 (in/mm) Hole Depth: 19 (in/mm)
(core bit diameter, if approved)
 Drill Bit Type: Carbide-Tip Drill Bit Diamond Core Bit Hollow Drill Bit Other _____
(ANSI B212.15-1994) (if appropriate and allowed) (Safeset™ only to be used with Hilti HIT-HY 200)
 Hole Condition: Dry Water Saturated Water Filled Under Water
 Hole Cleaning: Compressed Air Hand Pump Wire Brush Other Vacuum
 Hole cleaning in accordance with manufacturers' printed installation instructions: Yes No

Application

Anchor Application: (please check all that apply) Tension Shear Overhead Other _____
 Anchor insertion: Twisting motion Annular gap filled with adhesive Air Void Free Injection
 Anchor Spacing: 27 (in/mm) Edge Distance: 9 (in/mm)
 Embedment (h_{ef}): 19 (in/mm) Installation Torque (if required): 100 (ft-lb/Nm)

Completed by: Keskin (Signature) Date: 7/7/17
Kinoy Skillin (Print) Company: _____
 _____ (Title)

Tests to Determine the Behavior of #11 Bars with Lap Splices – TEST SERIES D

Bowen Laboratory
Purdue University
November 18, 2016

Test Procedure

This procedure refers to the test described in the proposal titled Experimental Study of The Effect of Laminar Cracks on Strength and Ductility 79-in Splices of #11 Reinforcing Bars submitted to FirstEnergy Corporation (Sozen & Pujol, 2016). Test procedures are specified in this document.

1. Fabrication

1.1 Formwork

The formwork shall be made using non-absorbent plywood. Its interior shall be caulked to prevent water leakage and it shall be covered with a thin layer of oil before casting. The dimensions of the formwork shall be checked and recorded using Form 1.

1.2 Reinforcement Cages

The steel reinforcement cages shall be built following the attached drawings and forms. Reinforcing bars shall be supported by steel chairs placed as shown in the drawings, Form 2. To ensure alignment, the bars shall be tied to chairs and to one another using 16-gage steel wire. The location of the reinforcement shall be recorded using Form 1. The locations of wire ties and reinforcement markings, if any, shall be recorded using Form 2.

Tolerances (within the test region) are:

3/16" for horizontal cover and horizontal spacing measured to the surface of the bar (excluding ribs)

1/4" for vertical distances shown in Form 1

All other tolerance shall follow ACI 117.

1.3 Casting

Fresh concrete properties to be measured include:

Unit Weight

Slump Air Content

Each measurement will be performed by a third party using calibrated equipment. These measurements shall be made following ASTM C138, ASTM C143, ASTM C231 and recorded using Form 3.

Slump shall be measured before any other activity related to casting takes place to make sure that the delivered mix has satisfactory workability. The mixing truck shall deliver a ticket with the batched mix weights. These weights shall be examined to corroborate that the delivered mix has the specified proportions. Concrete shall not be accepted if it arrives more than 45 min. after leaving the batching plant. No water shall be added to the mix after the truck leaves the plant.

Specimens and cylinders shall be cast and vibrated in two lifts following ASTM C192. The vibrators to be used shall have the following cross-sectional dimensions:

For cylinders: 3/4" - 7/8"
For Larger Specimens: 1-3/4"

Their frequencies shall be between 50 and 200 Hz.

Excess concrete shall be removed off the formwork. The exposed surfaces of the specimens shall be finished using cast magnesium floats. Lifting inserts shall be inserted in the fresh concrete as soon as the finishing is completed.

Each test specimen shall be cast using concrete from a single mixing truck. A complete set of concrete samples (cylinders) shall be obtained from each truck. Test specimens and samples shall be marked with a number referring to the truck from which they were cast and the date of casting. In each casting day, trucks shall be numbered sequentially starting at 1. The number assigned to a truck shall be written clearly on the mix ticket describing the mix proportions for the batch. Test specimens shall be cast and tested oriented in the North-South axis of the laboratory. Specimen ends facing North during casting shall face North during testing. During finishing, the North end of each specimen shall be marked with the letter N.

These activities shall be documented using Form 3.

1.4 Curing

As soon as casting is completed all specimens shall be covered with impermeable sheets. When the concrete surface sets, wet burlap shall be inserted between these sheets and the exposed concrete. All formwork and molds shall be struck no later than three days after the cast.

All exposed concrete surfaces shall be covered by wet burlap and impermeable sheets for a total of at least seven days after casting.

Burlap shall be doused with water at least every other day during the curing period.

Curing activities shall be logged using Form 4.

Test cylinders shall be stored and cured next to the test specimens and under similar conditions of temperature and humidity.

The variation of concrete strength with time shall be monitored and recorded using Form 5 and 5B.

2. Calibration

Three types of measurements will be made: displacement, force, air content.

The apparatuses to be used to calibrate sensors to measure these quantities are:

Displacement Sensors: INSTRON Universal Testing Machine:

(S.N.:2630-115/590)

Load Sensors: INSTRON Universal Testing Machine

(S.N.: 120BTE502040)

Air Content: Calibrated Cylinder

(S.N.: To be provided by materials testing technician)

Load and displacement sensors will be calibrated following steps listed below:

- 1) Connect the sensor to the data-acquisition system that is going to be used in the test
- 2) Set and record the excitation voltage to the maximum possible value (not exceeding the maxima specified for the data-acquisition system and the sensor)
- 3) Set the data-acquisition equipment to record voltage
- 4) Set the gain of the data-acquisition system to the first available level lower than the ratio of the maximum range of the system to the maximum expected output from the sensor.
- 5) Mount the sensor on the universal testing machine
- 6) Apply a series of known displacement or force increments to the sensor ranging between 10% and 90% of the rated capacity of the sensor
- 7) Record the voltage read on the data-acquisition system at each known displacement or force increment
- 8) Create a plot of change in output voltage vs. change in force or displacement
- 9) Fit a line to the plot from 7) using "least squares"
- 10) Record the slope of the line from 8) (sensor sensitivity)

11) Label the cable used in the calibration with the serial number of the sensor

Sensors shall be calibrated before the first test and after the final test. Sensors will be calibrated using the same data acquisition system.

The apparatus used to measure air content of the fresh concrete shall be calibrated following the procedure described in ASTM C231 by a third party.

All calibrations shall be performed by at least two persons: one leading each step and the other checking the work of the first independently. A log of each calibration shall be made using Form 6 and it shall include an estimate of the accuracy of the sensor.

Sensors for which the sensitivity obtained in 9) above deviates by more than 10% from the nominal sensitivity (as reported by the manufacturer) shall not be used in any of the tests.

3. Setup

Each specimen shall be subjected to direct tension applied to the free ends of the bars protruding out of the test region.




Figure 1. Test Setup plan view (anchors not shown for clarity).

The maximum deviation from nominal setup dimensions shall be $\frac{1}{4}$ in.

As-built external dimensions of each test specimen shall be recorded using Form 7. The maximum deviation from nominal dimensions in the test region shall be $\frac{1}{4}$ in.

Forces will be applied using two hydraulic rams (one per bar on one side of the specimen). The rams shall be connected to a single manifold and pump using 10,000-psi hydraulic hoses. All hoses and other hydraulic hardware shall be inspected visually and replaced –if defective- before testing.

4. Instrumentation

Displacement sensors shall be installed across the plane of the lap splices to measure the widths of laminar cracks.

Bar forces will be measured using two force transducers (one per bar) opposite to the hydraulic jacks used to apply load.

All sensors (displacement and force) shall be connected to the data acquisition system using the same cables used during calibration. The excitation voltage and gain shall also be set to the value used in calibration. The data acquisition system shall be set to record voltage changes caused by loading. Before applying load with the hydraulic rams, all sensors shall be set to read a voltage value between 10% and 90% of the voltage output of the sensor at its rated capacity. These voltages shall be referred to as the “zero offsets” of the sensors.

Set the data acquisition system to scan all sensors and save at least one record per sensor every 1 sec.

Record a file of “zero offsets” capturing at least 10 min. of data before any load is applied with the hydraulic system.

Means of initial voltages for all sensors (mean “zero offsets”), sensor serial numbers, the most recent sensitivity constants, excitation voltages, and the channels of the data-acquisition system used for each sensor shall be recorded using Form 8. The pairing of channels and sensors shall be checked by a second person working independently from the person making the initial connections.

Infrared targets used to measure displacements shall be glued to one face of the test specimen, and glued to the protruding bars of one splice using adhesive. The numbering sequence of these targets shall be recorded using Form 9.

Video cameras (one for long-time lapse video and one for high-speed video) will be positioned to capture the response of each specimen. To the extent possible, the location of the cameras shall be the same in all tests.




Figure 2) Layout of infrared targets.

5. Testing

The following test schedule shall be followed:

Test Schedule

TEST	ANCHOR		INITIAL CRACK
	LENGTH	SPACING	
1-2	NA	NA	0.06"
3	NA	NA	0.10"
4-5	10"	20"	0.06"
6	10"	20"	0.10"
7-8	10"	40"	0.06"
9	10"	40"	0.10"
10-11	15"	20" or 40"	0.06"
12	15"	20" or 40"	0.10"
13	NA	NA	0.06"
14-15	NA	NA	0.10"
16	10"	20"	0.06"
17-18	10"	20"	0.10"
19	10"	40"	0.06"
20-21	10"	40"	0.10"
22	15"	20" or 40"	0.06"
23-24	15"	20" or 40"	0.10"

Note: ten spare specimens shall be cast (six initially and four later) in case failure takes place before the target crack-width is reached.

Anchor length, spacing, etc. are preliminary and may be adjusted based on the results of testing. Any adjustment to the test schedule shall be as directed by Bechtel Engineering.

The following actions shall take place during each test:

Incremental loadings shall be applied by tensioning the reinforcing bar. The load shall be applied in 10 kip to 20 kip increments until the target crack-width is reached.

At the end of each loading increment:

Record the load.

Mark Cracks: All visible cracks shall be marked using black permanent markers. Cracks shall be marked by drawing lines parallel to them and with an offset of approximately 0.25 in.

Measure Crack Widths: Crack widths shall be measured using crack comparators or graduated handheld microscopes.

Measure coordinates of infrared coordinates: A set of coordinates shall be obtained using an OptoTrak System 600 Pro.

In-Test Data Backup: At every loading increment the data being produced by the data-acquisition system shall be copied to an external hard drive or USB memory.

Photographs: A set of high-resolution photographs shall be obtained after cracks are marked at each loading increment. The photographs shall include views of both elevations of the test specimen and the top concrete surface above lap splices.

The following data shall be recorded throughout each test:

Sensor readings: To be recorded on a hard drive in volts. Conversion to engineering units shall be done after the test as follows:

-Subtract zero offsets

-Divide the result by the sensitivity obtained in the most recent calibration

Lapse video photographs: To be obtained every 5 min.

Actions to be taken at failure

Trigger high-speed camera to record breaking away of the concrete cover and relative movement of the bars.

Actions to be taken after test

Generate a record of sensors that may have malfunctioned or been accidentally moved during the test

Remove from all files recordings from sensors for which the results of the after-test calibration differ by more than 5% from the before-test calibration.

The referenced proposal describes the test procedure. Each specimen shall be loaded until laminar cracks widths of approximately 0.06" and 0.1" are observed. The load shall then be removed and, when applicable (Specimens 4-12 and 16-24), transverse reinforcement (anchor bolts) shall be installed as explained in Section 5.1. Then the load shall be reapplied until failure is obtained.

5.1 Anchor Bolt Installation

ASTM-A193 ¾-in. diameter threaded rods shall be used as anchors. Anchors are to be installed using product HIT-RE 500 V3 1400 Jumbo by Hilti. Installer is to be trained by a representative from Hilti. Installation is to comply with manufacturer's printed installation instructions (MPII), (Hilti, 2016). 15-in. long anchors are to include a nut and washer (to be torqued to 100 lbf-ft). 10-in. long anchors need not have a nut and a washer.

6. Reporting and Backup

Produce all the captured data in two ways:

By uploading data, photos, and video to datacenterhub.org or <ftp.ecn.purdue.edu>.

By recording all data, photos, and video on a magnetic hard drive

Reports shall be produced as described in the referenced proposal.

References

1. ASTM C192/C192M-16a Standard Practice for Making and Curing Concrete Test Specimens in the Laboratory, ASTM International, West Conshohocken, PA, 2016.
2. ASTM C138/C138M-16a Standard Test Method for Density (Unit Weight), Yield, and Air Content (Gravimetric) of Concrete, ASTM International, West Conshohocken, PA, 2016.
3. ASTM C143/C143M-15a Standard Test Method for Slump of Hydraulic-Cement Concrete, ASTM International, West Conshohocken, PA, 2015.
4. ASTM C231 / C231M-14, Standard Test Method for Air Content of Freshly Mixed Concrete by the Pressure Method, ASTM International, West Conshohocken, PA, 2014.
5. ACI-117, Specification for Tolerances for Concrete Construction and Materials (ACI117-10) and Commentary, American Concrete Institute, Farmington Hills, MI, 2010.
6. Hilti HIT-RE 500 V3 1400 Jumbo, Instructions for use, Doc-Nr: PUB / 5265274 / 000 / 00. Printed January 26, 2016.
7. Sozen M., Pujol S., "An Experimental Investigation of the Effect of Laminar Cracks on Strength of Unconfined 79-In. Lap Splices of #11 Reinforcing Bars." Proposal to FENOC, Oak Harbor, Ohio. 30 Sep. 2016.



Property Of: Purdue University
 Lafayette, IN
 P.O.#: N/A
 Tolerance: ±0.00025

Mfr: Fowler
 Mfr #: V1004+
 Range: 40
 Least Division: 0.00005
 Unit of Measure: Inches (1 in = 25.4mm)

Serial #: HG01 / 1045483
 Instrument: Height Gage
 Report #: 170432-L
 Page: 1 of 1

Calibration Report

Nominal (OD)	As Found	As Found Error	As Left	As Left Error
0.200	0.19995	-0.00005	0.19995	-0.00005
0.400	0.39990	-0.00010	0.39990	-0.00010
0.600	0.60000	0.00000	0.60000	0.00000
0.800	0.80000	0.00000	0.80000	0.00000
1.000	1.00000	0.00000	1.00000	0.00000
2.000	1.99995	-0.00005	1.99995	-0.00005
3.000	3.00000	0.00000	3.00000	0.00000
4.000	4.00000	0.00000	4.00000	0.00000
5.000	4.99990	-0.00010	4.99990	-0.00010
6.000	6.00000	0.00000	6.00000	0.00000
7.000	6.99990	-0.00010	6.99990	-0.00010
8.000	8.00000	0.00000	8.00000	0.00000
10.000	9.99990	-0.00010	9.99990	-0.00010
12.000	11.99995	-0.00005	11.99995	-0.00005
16.000	16.00000	0.00000	16.00000	0.00000
20.000	19.99995	-0.00005	19.99995	-0.00005
24.000	24.00000	0.00000	24.00000	0.00000
30.000	30.00000	0.00000	30.00000	0.00000
36.000	36.00000	0.00000	36.00000	0.00000
40.000	39.99985	-0.00015	39.99985	-0.00015

This uncertainty represents an expanded uncertainty expressed at approximately the 95% confidence level using a coverage factor of K=2. ±0.000460".

We certify that these gages were compared to masters traceable to the International System of Units (SI)

through the National Institute of Standards and Technology (NIST). Tolerances & Calibration in accordance with

ISO /IEC 17025, ISO 10012-1, ANSI /NCSL Z540-1, & G1 #14.0

Equipment Used: QC003 Dated 9/16, Due 9/18; QC1 Dated 9/16, Due 9/17.

Surface Plate 14997 Dated 12/16, Due 12/17.

As Found: Used.

Original Calibration: 4/22/2017

Your Suggested Recalibration: 4/22/2018

Factors may occur affecting the calibration before your suggested recalibration date.

Environment: Temperature: 67.6-68.6°F Humidity: 25-50%

Calibrated By:

David A. Kerr
 David A. Kerr, Calibration Technician

Inspected By:

[Signature]

CERTIFICATE OF CALIBRATION

ISSUED BY: INSTRON CALIBRATION LABORATORY

DATE OF ISSUE: 09-Dec-15

CERTIFICATE NUMBER: **340120915110036**

Page 1 of 4 pages

**Instron**

825 University Avenue
 Norwood, MA 02062-2643
 Telephone: (800) 473-7838
 Fax: (781) 575-5750
 Email: service_requests@instron.com

APPROVED SIGNATORY

Date of Calibration: **09-Dec-15**Customer Requested Due Date: **31-Dec-16***** * * CALIBRATION RESULTS * * *****Type of Calibration:** Strain **Relevant Standard:** ASTM E83-10a**System ID:** 120BTE502040 **Transducer ID:** 2630-115/590**Indicator 1. - Digital Readout (strain)****PASSED Class B-1 - 100% Range in Tension mode****Customer**

Name: PURDUE UNIVERSITY
 Address: US 231 BOWEN LABORATORY
 WEST LAFAYETTE, IN 47907
 KBROWER@PURDUE.EDU
 P.O./Contract No.:
 Contact: KEVIN BROWER

Machine

Manufacturer: SATEC
 Serial Number: 120BTE502040
 System ID: 120BTE502040
 Range Type: Single

Transducer

Manufacturer: INSTRON
 Transducer ID: 2630-115/590
 Extensometer Type: Type 1
 Travel (Tension): 1 in
 Travel (Compression): 0.1 in
 Gauge Length: 2 in
 Mode: Static (Tension/Compression)

Certification Statement

All indicators listed above were verified on-site at customer location by Instron in accordance with ASTM E83.

The verification and equipment used conform to a controlled Quality Assurance program which meets the specifications outlined in ANSI/NCSL Z540-1, ISO 10012, ISO 9001:2008 and ISO/IEC 17025:2005.

The testing machine was verified in the 'as found' condition.

Instron Calpro Version 3.30

The results indicated on this certificate and the following report relate only to the items verified. If there are methods or data included that are not covered by the NVLAP accreditation it will be identified in the comments. Any limitations of use as a result of this verification will be indicated in the comments. This report must not be used to claim product endorsement by NVLAP or the United States government. This report shall not be reproduced, except in full, without the approval of the issuing laboratory.

CERTIFICATE OF CALIBRATION

NVLAP ACCREDITED CALIBRATION LABORATORY No. 200301-0

CERTIFICATE NUMBER:

340120915110036

Page 2 of 4 pages

Summary of Results**Indicator 1. - Digital Readout (strain)**

Range	Tested Range	Mode	System Class*	Resolution	Resolution	ASTM E83 Lower Limit
(%)	(in)			(strain)	Class	(in)
100	0.1002 to 1.00369	Tension	B-1	0.00001	A	0.002

* System Class for a range is the worst of the following classes: gauge length class, resolution class, individual point error class, repeatability class and is also based on the measurement capability of the laboratory.

Gauge Length Measurement and Classification

Nominal Gauge Length (in)	Actual Gauge Length (in)	Measurement Type	Relative Error of Gauge Length for Each Measurement Made (%)			ASTM E83 Gauge Length Class	Uncertainty of Measurement* (in)
2	1.99865	Indirect	-0.229	-0.117	0.143	B-1	0.0032

* The reported expanded uncertainty is based on a standard uncertainty multiplied by a coverage factor $k = 2$, providing a level of confidence of approximately 95%.

Data Summary and Classification**Indicator 1. - Digital Readout (strain)**

% of Range	Run 1 Error		Run 2 Error		Repeat Error (strain)	Worst Class	Uncertainty of Measurement* (strain)
	Fixed (strain)	Relative (% of strain)	Fixed (strain)	Relative (% of strain)			
100% Range (Full Scale: 1.00369 in)							
10	-0.00018	-0.354	-0.00010	-0.199	0.00008	B-1	0.000093
20	-0.00043	-0.427	-0.00047	-0.466	0.00004	B-1	0.00017
40	-0.00082	-0.406	-0.00097	-0.482	0.00015	B-1	0.00033
70	-0.00059	-0.168	-0.00035	-0.101	0.00024	B-1	0.00058
100	-0.00184	-0.367	-0.00156	-0.311	0.00028	B-1	0.00082

* The reported expanded uncertainty is based on a standard uncertainty multiplied by a coverage factor $k = 2$, providing a level of confidence of approximately 95%.

Data**Indicator 1. - Digital Readout (strain)**

% of Range	Run 1		Run 2	
	Indicated (strain)	Applied (in)	Indicated (strain)	Applied (in)
100% Range (Full Scale: 1.00369 in)				
Run Temperature: 67.6 °F				
0	0	-0.000001	0	0.000000
10	0.050027	0.100410	0.05	0.100200
20	0.1	0.200858	0.1	0.200936
40	0.2	0.401631	0.2	0.401937
Run Temperature: 69.8 °F				

CERTIFICATE OF CALIBRATION

NVLAP ACCREDITED CALIBRATION LABORATORY No. 200301-0

CERTIFICATE NUMBER:

340120915110036

Page 3 of 4 pages

Data**Indicator 1. - Digital Readout (strain)**

% of Range	Run 1		Run 2	
	Indicated (strain)	Applied (in)	Indicated (strain)	Applied (in)
100% Range (Full Scale: 1.00369 in)				
Run Temperature: 67.6 °F			Run Temperature: 69.8 °F	
70	0.35	0.701182	0.35	0.700708
100	0.5	1.003686	0.5	1.003124

Verification Equipment

Make/Model	Serial Number	Description	Calibration Agency	Measurement Range	Cal Date	Cal Due
Extech 445580	1041758	temp. indicator	Masy Systems Inc.	NA	13-Feb-15	13-Feb-17
Epsilon 3590VHR	A5010 (ASTM)	disp. indicator	Epsilon Technology	2.00 in	29-Jan-15	29-Jan-16
Instron US Gauge Bar	I902 (ASTM)	gauge bar	A.A. Jansson	NA	29-May-14	29-May-16
Interface 9840	93112	force indicator	Instron	NA	24-Sep-14	24-Sep-16

Verification Equipment Usage

Measurement Type	Serial Number	Range (% of FS)	Mode	Percent(s) of Range	Accuracy (+/-)
Displacement	A5010 (ASTM)	100	T	10/ 20	0.00004 in
				40/ 70	0.000075 in
				100	0.00015 in
Gauge Length	93112	NA		NA*	0.015% of reading
	A5010 (ASTM)	NA		NA*	0.00004 in
	I902 (ASTM)	NA		NA*	0.00021 in
Temperature	1041758	All		All	1.8 °F

* Refer to Gauge Length Measurement and Classification section for usage.

Instron standards are traceable to the SI (The International System of Units) through standards maintained by the National Institute of Standards and Technology (NIST) or other internationally recognized National Metrology Institutes (NMIs).

The accuracy of the verification equipment used was equal to or better than the accuracy indicated in the table above.

Comments

Verified by: Rich Binford
Field Service Engineer

CERTIFICATE OF CALIBRATION

NVLAP ACCREDITED CALIBRATION LABORATORY No. 200301-0

CERTIFICATE NUMBER:

340120915110036

Page 4 of 4 pages

NOTE: Clause 9 of ASTM E-83 states; It is recommended that extensometer systems be verified annually or more frequently if required. In no case shall the time interval between verifications exceed 18 months (unless an extensometer is being used in a long-time test running beyond the 18 month period). An extensometer system shall not be used after an adjustment or repair that could affect its accuracy without first verifying its accuracy utilizing the procedure described in this practice.

CERTIFICATE OF CALIBRATION

ISSUED BY: INSTRON CALIBRATION LABORATORY

DATE OF ISSUE: 09-Dec-15

CERTIFICATE NUMBER: **340120915102905**

Page 1 of 4 pages

**Instron**

825 University Avenue
 Norwood, MA 02062-2643
 Telephone: (800) 473-7838
 Fax: (781) 575-5750
 Email: service_requests@instron.com

APPROVED SIGNATORY

Type of Calibration: Force
Relevant Standard: ASTM E4-14
Date of Calibration: 09-Dec-15

Customer Requested Due Date: 31-Dec-16**Customer**

Name: PURDUE UNIVERSITY
 Address: US 231 BOWEN LABORATORY
 WEST LAFAYETTE, IN 47907
 KBROWER@PURDUE.EDU
 P.O./Contract No.:
 Contact: KEVIN BROWER

Machine

Manufacturer: SATEC
 Serial Number: 120BTE502040
 System ID: 120BTE502040
 Range Type: Single

Transducer

Manufacturer: SATEC
 Transducer ID: 120BTE502040
 Capacity: 120000 lbf
 Type: Compression

Classification

1. Digital Readout - PASSED**

Certification Statement

This certifies that the forces verified with machine indicator(s) (listed above) that passed are WITHIN $\pm 1\%$ accuracy, 1% repeatability, and zero return tolerance.

All machine indicators were verified on-site at customer location by Instron in accordance with ASTM E4.

The certification is based on runs 1 and 2 only. A third run is taken to satisfy uncertainty requirements according to ISO 17025 specifications.

The verification and equipment used conform to a controlled Quality Assurance program which meets the specifications outlined in ANSI/NCSL Z540-1, ISO 10012, ISO 9001:2008 and ISO/IEC 17025:2005.

** within $\pm 0.5\%$ accuracy and 0.5% repeatability.

Method

The testing machine was verified in the 'as found' condition with no adjustments carried out.

Instron CalproCR Version 3.30

The results indicated on this certificate and the following report relate only to the items verified. If there are methods or data included that are not covered by the NVLAP accreditation it will be identified in the comments. Any limitations of use as a result of this verification will be indicated in the comments. This report must not be used to claim product endorsement by NVLAP or the United States government. This report shall not be reproduced, except in full, without the approval of the issuing laboratory.

CERTIFICATE OF CALIBRATION

NVLAP ACCREDITED CALIBRATION LABORATORY No. 200301-0

CERTIFICATE NUMBER:

340120915102905

Page 2 of 4 pages

Summary of Results

Temperature at start of verification: 71.20 °F.

Indicator 1. - Digital Readout (lbf)

Range	ASTM E4	ASTM E4	Zero	Resolution	ASTM E4
Full Scale	Max	Max Repeat	Return	(lbf)	Lower Limit
(%)	Error (%)	Error (%)			(lbf)
100	0.28	0.19	Pass	1	200

Temperature at end of verification: 71.20 °F.

Data Point Summary - Indicator 1. - Digital Readout (lbf)**COMPRESSION**

% of Range	Run 1 Error (%)	Run 2 Error (%)	Run 3 Error (%)	ASTM E4 Repeat Error (%)	Relative Uncertainty*	Uncertainty of Measurement* (± lbf)
100% Range (Full Scale: -119941.1 lbf)						
1	0.28	0.26	0.29	0.02	0.14	1.6
2	0.15	0.16	0.16	0.01	0.13	3.1
4	0.03	0.03	0.03	0.00	0.13	6.1
7	-0.02	-0.01	-0.01	0.01	0.13	11
10	0.11	0.11	0.12	0.00	0.13	15
20	0.14	0.14	0.15	0.00	0.13	31
40	0.10	0.10	0.10	0.00	0.13	61
70	0.21	0.05	0.07	0.16	0.16	137
100	0.24	0.05	0.07	0.19	0.18	211

* The reported expanded uncertainty is based on a standard uncertainty multiplied by a coverage factor $k = 2$, providing a level of confidence of approximately 95%.

Data - Indicator 1. - Digital Readout (lbf)**COMPRESSION**

% of Range	Run 1		Run 2		Run 3	
	Indicated (lbf)	Applied (lbf)	Indicated (lbf)	Applied (lbf)	Indicated (lbf)	Applied (lbf)
100% Range (Full Scale: -119941.1 lbf)						
0 Return	4		3		12	
1	-1200	-1196.65	-1200	-1196.85	-1200	-1196.55
2	-2400	-2396.45	-2400	-2396.25	-2400	-2396.05
4	-4800	-4798.6	-4800	-4798.4	-4800	-4798.35
7	-8400	-8401.4	-8400	-8400.85	-8400	-8400.8
10	-12000	-11986.44	-12000	-11987.03	-12000	-11985.26
20	-24000	-23967.57	-24000	-23965.8	-24000	-23964.03
40	-48000	-47953.43	-48000	-47950.48	-48000	-47949.89
70	-84000	-83820.71	-84000	-83957	-84000	-83944.02
100	-120000	-119711	-120000	-119941.1	-120000	-119918.68

CERTIFICATE OF CALIBRATION


NVLAP ACCREDITED CALIBRATION LABORATORY No. 200301-0

CERTIFICATE NUMBER:
340120915102905

Page 3 of 4 pages

The Return to Zero tolerance is \pm the indicator resolution, 0.1% of the maximum force verified in the range, or 1% of the lowest force verified in the range, whichever is greater.

Graphical Data - Indicator 1. - Digital Readout (lbf)



Verification Equipment

Make/Model	Serial Number	Description	Calibration Agency	Capacity	Cal Date	Cal Due
Extech 445580	1041758	temp. indicator	Masy Systems Inc.	NA	13-Feb-15	13-Feb-17
HBM 10KFRR	688077	load cell	Instron	12000 lbf	16-May-14	16-May-16
Interface 9840	93112	force indicator	Instron	NA	24-Sep-14	24-Sep-16
Strainsense 050530	050530	load cell	Instron	120000 lbf	16-Oct-14	16-Oct-16

Verification Equipment Usage

Range	Full Scale (%)	Mode	Standard Serial Number	Percent(s) of Range	Lower Limit for Standard (lbf)	Accuracy (+/-)
100	C	688077	1/ 2/ 4/ 7	Class A1: 256	0.1% of reading	
		050530	10/ 20/ 40/ 70/ 100	Class A1: 10552	0.1% of reading	
All	C	1041758	All	NA	1.8 °F	

CERTIFICATE OF CALIBRATION

NVLAP ACCREDITED CALIBRATION LABORATORY No. 200301-0

CERTIFICATE NUMBER:

340120915102905

Page 4 of 4 pages

Instron standards are traceable to the SI (The International System of Units) through standards maintained by the National Institute of Standards and Technology (NIST) or other internationally recognized National Metrology Institutes (NMIs).

The standard Class A lower limit is used for systems with an accuracy of +/-1.0% and the standard Class A1 lower limit is used for systems with an accuracy of +/-0.5%.

The accuracy of the force indicator used with elastic devices is incorporated into the devices stated accuracy.


Standard forces have been temperature compensated as necessary.


The accuracy of the verification equipment used was equal to or better than the accuracy indicated in the table above.

Comments

Verified by: Rich Binford
Field Service Engineer

NOTE: Clause 19 of ASTM E4 states; It is recommended that testing machines be verified annually or more frequently if required. In no case shall the time interval between verifications exceed 18 months (except for machines in which long term test runs beyond the 18 month period). Testing machines shall be verified immediately after repairs that may in any way affect the operation of the weighing system or values displayed. Verification is required immediately after a testing machine is relocated and where there is a reason to doubt the accuracy of the force indicating system, regardless of the time interval since the last verification.







Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: 01

Sheet 1 of 1

Formwork As-built Dimensions Series D

Section	Formwork As-built Dimensions Series D							
	1	2	3	4	5	6	7	8
A-A	78- $\frac{7}{8}$ "	79"	80- $\frac{1}{8}$ "	80"	N/A	N/A	N/A	N/A
B-B	4- $\frac{3}{8}$ "	6"	4- $\frac{3}{8}$ "	23- $\frac{3}{4}$ "	23- $\frac{5}{8}$ "	30"	30"	17- $\frac{5}{8}$ "
C-C	3"	6"	3"	23- $\frac{5}{8}$ "	23- $\frac{5}{8}$ "	30"	30"	17- $\frac{5}{8}$ "
D-D	3"	8- $\frac{3}{4}$ "	3"	23- $\frac{5}{8}$ "	23- $\frac{5}{8}$ "	30"	30"	17- $\frac{5}{8}$ "
Recorded by:			Signature				Date	Time
Kinsey Skillen							1/11/17	9:35m
Checked by:			Signature				Date	Time
Prateek Shah							1/11/17	9:35am
Checked by:			Signature				Date	Time
Comments:								


APPENDIX C Final Phase III Test Report
 25981-000-001-R-001-R-000002 Rev. 000 Sheet 174 of 575
 Appendix 9, Pg 1 of 39

DI


SOUTH

Wire Ties, Chairs

NORTH



Bar Marks



Specimen:	Series D Formwork As-builts	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/2/2016		

Appendix 9, Pg 2 of 39



Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: D2

Sheet 1 of 2


Formwork As-built Dimensions Series D

Section	Formwork As-built Dimensions Series D							
	1	2	3	4	5	6	7	8
A-A	78- $\frac{7}{8}$ "	78- $\frac{7}{8}$ "	80"	80"	NA	NA	NA	N/A
B-B	4- $\frac{3}{8}$ "	6"	4- $\frac{1}{2}$ "	23- $\frac{5}{8}$ "	23- $\frac{5}{8}$ "	30"	30"	17- $\frac{5}{8}$ "
C-C	3- $\frac{1}{3}$ "	6- $\frac{1}{8}$ "	3"	23- $\frac{3}{4}$ "	23- $\frac{3}{4}$ "	30"	30"	17- $\frac{5}{8}$ "
D-D	3"	8- $\frac{3}{4}$ "	3- $\frac{1}{8}$ "	23- $\frac{5}{8}$ "	23- $\frac{5}{8}$ "	30"	30"	17- $\frac{3}{4}$ "
Recorded by:			Signature				Date	Time
Kinsy Skiller							1/11/17	9:40 am
Checked by:			Signature				Date	Time
Prateek Shah							1/11/17	9:40 am
Checked by:			Signature				Date	Time
Comments:								


APPENDIX C: Final Phase III Test Report 2598-000-001 Rev. 000, Sheet 176 of 575 Appendix 9, Pg 3 of 39

02

SOUTH Wire Ties, Chairs NORTH



Bar Marks



Specimen:	Series D Formwork As-builts	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/2/2016		



Appendix 9, Pg 4 of 39

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: D3

Sheet 1 of 1

Section	Formwork As-built Dimensions Series D							
	1	2	3	4	5	6	7	8
A-A	78- $\frac{3}{4}$ "	79"	80"	80"	N/A	NA	NA	NA
B-B	4- $\frac{3}{8}$ "	6"	4- $\frac{1}{2}$ "	23- $\frac{5}{8}$ "	23- $\frac{5}{8}$ "	30- $\frac{1}{8}$ "	30"	17- $\frac{3}{4}$ "
C-C	3- $\frac{1}{8}$ "	6- $\frac{1}{8}$ "	3"	23- $\frac{5}{8}$ "	23- $\frac{5}{8}$ "	30"	30"	17- $\frac{5}{8}$ "
D-D	3"	8- $\frac{3}{4}$ "	3"	23- $\frac{5}{8}$ "	23- $\frac{5}{8}$ "	30"	30"	17- $\frac{5}{8}$ "
Recorded by:			Signature				Date	Time
Kinsy Skillen							11/11/17	9:50 am
Checked by:			Signature				Date	Time
Prateek Shah							11/11/17	9:50 am
Checked by:			Signature				Date	Time
Comments:								

D3


SOUTH

Wire Ties, Chairs

NORTH



Bar Marks



Specimen:	Series D Formwork As-builts	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/2/2016		



Appendix 9, Pg 6 of 39

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: D4

Sheet 1 of 1

Section	Formwork As-built Dimensions Series D							
	1	2	3	4	5	6	7	8
A-A	79"	79"	80"	80"	NA	NA	NA	NA
B-B	4- $\frac{3}{8}$ "	6"	4- $\frac{3}{8}$ "	23- $\frac{3}{4}$ "	23- $\frac{5}{8}$ "	30"	30"	17- $\frac{5}{8}$ "
C-C	3"	6"	3- $\frac{1}{8}$ "	23- $\frac{5}{8}$ "	23- $\frac{3}{4}$ "	30"	30"	17- $\frac{5}{8}$ "
D-D	3"	6"	3- $\frac{1}{8}$ "	23- $\frac{5}{8}$ "	23- $\frac{5}{8}$ "	30"	30"	17- $\frac{3}{4}$ "
Recorded by:			Signature				Date	Time
Kinscy Skiller							1/11/17	9:58 am
Checked by:			Signature				Date	Time
Prateek Shah							1/11/17	9:58 am
Checked by:			Signature				Date	Time
Comments:								


APPENDIX C: Purdue University Form Report 0599-000-00R-001R-001R-000002 Rev-000 Sheet 180 of 575 Appendix 9, Pg 7 of 39

D4

SOUTH Wire Ties, Chairs NORTH



Bar Marks





Specimen:	Series D Formwork As-builts	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/2/2016		

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: 05

Sheet 1 of 1

Section	Formwork As-built Dimensions Series D							
	1	2	3	4	5	6	7	8
A-A	79	78- $\frac{3}{4}$ "	80- $\frac{1}{8}$ "	80"	NA	NA	NA	NA
B-B	4- $\frac{1}{2}$ "	6"	4- $\frac{3}{8}$ "	23- $\frac{5}{8}$ "	23- $\frac{5}{8}$ "	30"	30"	17- $\frac{5}{8}$ "
C-C	3"	6"	3- $\frac{1}{8}$ "	23- $\frac{5}{8}$ "	23- $\frac{3}{4}$ "	30- $\frac{1}{8}$ "	30- $\frac{1}{8}$ "	17- $\frac{3}{4}$ "
D-D	3- $\frac{1}{8}$ "	8- $\frac{3}{4}$ "	3"	23- $\frac{5}{8}$ "	23- $\frac{5}{8}$ "	30"	30- $\frac{1}{8}$ "	17- $\frac{5}{8}$ "
Recorded by:			Signature				Date	Time
Kinsy Skiller							1/11/12	10:08 am
Checked by:			Signature				Date	Time
Prateek Shah							1/11/12	10:08 am
Checked by:			Signature				Date	Time

Comments:

ALL good


APPENDIX C: Bridge Phase III Test Report
6599-900-001R-001R-00002-Rev. 000- Sheet 1 of 5
Appendix 9, Pg 9 of 39

D5

SOUTH Wire Ties, Chairs NORTH



Bar Marks



Specimen:	Series D Formwork As-builts	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/2/2016		



Appendix 9, Pg 10 of 39

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: D6

Sheet 1 of 1

Section	Formwork As-built Dimensions Series D							
	1	2	3	4	5	6	7	8
A-A	79"	79"	80- $\frac{1}{8}$ "	80"	NA	NA	NA	NA
B-B	4- $\frac{3}{8}$ "	6"	4- $\frac{3}{8}$ "	23- $\frac{5}{8}$ "	23- $\frac{5}{8}$ "	30"	30- $\frac{1}{8}$ "	17- $\frac{3}{4}$ "
C-C	3"	4"	3- $\frac{1}{8}$ "	23- $\frac{5}{8}$ "	23- $\frac{5}{8}$ "	30"	30"	17- $\frac{5}{8}$ "
D-D	3- $\frac{1}{8}$ "	8- $\frac{3}{4}$ "	3"	23- $\frac{5}{8}$ "	23- $\frac{5}{8}$ "	30"	30"	17- $\frac{3}{4}$ "
Recorded by:			Signature				Date	Time
Kinsey Skiller							1/11/17	10:15 am
Checked by:			Signature				Date	Time
Prateek Shah							1/11/17	10:15 am
Checked by:			Signature				Date	Time
Comments:								

APPENDIX C


Appendix 9, Pg 11 of 39

D6

SOUTH Wire Ties, Chairs NORTH



Bar Marks



None





Specimen:	Series D Formwork As-builts	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/2/2016		

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: D7

Sheet 1 of 1


Section	Formwork As-built Dimensions Series D							
	1	2	3	4	5	6	7	8
A-A	79"	79"	80"	80"	NA	NA	NA	NA
B-B	4- $\frac{3}{8}$ "	6"	4- $\frac{3}{8}$ "	23- $\frac{3}{4}$ "	23- $\frac{3}{4}$ "	30"	30"	17- $\frac{5}{8}$ "
C-C	3"	6- $\frac{1}{8}$ "	3"	23- $\frac{5}{8}$ "	23- $\frac{3}{4}$ "	30"	30"	17- $\frac{5}{8}$ "
D-D	3- $\frac{1}{8}$ "	8- $\frac{3}{4}$ "	3"	23- $\frac{5}{8}$ "	23- $\frac{3}{4}$ "	30- $\frac{1}{8}$ "	30"	17- $\frac{5}{8}$ "
Recorded by:			Signature				Date	Time
Kinsy Skiller							1/11/17	10:20 am
Checked by:			Signature				Date	Time
Prateek Shah							1/11/17	10:20 am
Checked by:			Signature				Date	Time

Comments:


APPENDIX C: Produce Phase-III Test Report
 25984-000-30P-C01P-00002-Rev-000-Sheet 186 of 525
 Appendix 9, Pg 13 of 39

D7

SOUTH Wire Ties, Chairs NORTH



Bar Marks



Specimen:	Series D Formwork As-builts	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/2/2016		



Appendix 9, Pg 14 of 39

Project: Effects of laminar cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: D8

Sheet 1 of

Section	Formwork As-built Dimensions Series D							
	1	2	3	4	5	6	7	8
A-A	78- $\frac{3}{4}$ "	79"	80"	80"	NA	NA	NA	NA
B-B	4- $\frac{3}{8}$ "	6"	4- $\frac{1}{2}$ "	23- $\frac{5}{8}$ "	23- $\frac{5}{8}$ "	30"	30"	17- $\frac{3}{4}$ "
C-C	3"	6"	3- $\frac{1}{8}$ "	23- $\frac{5}{8}$ "	23- $\frac{3}{4}$ "	30"	30"	17- $\frac{5}{8}$ "
D-D	3- $\frac{1}{8}$ "	8- $\frac{3}{4}$ "	3"	23- $\frac{5}{8}$ "	23- $\frac{3}{4}$ "	30"	30"	17- $\frac{5}{8}$ "
Recorded by:			Signature				Date	Time
Kinsy Skillen							11/11/17	10:32 am
Checked by:			Signature				Date	Time
Prateek Shah							11/11/17	10:32 am
Checked by:			Signature				Date	Time
Comments:								

APPENDIX C: Purdue Phase III Test Report

2589-1-000-001-001-R-000021 Rev. 000, Sheet 488 of 575


Appendix 9, Pg 15 of 39

D8

SOUTH Wire Ties, Chairs NORTH



Bar Marks



none





Specimen:	Series D Formwork As-builts	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/2/2016		

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: D9


Sheet 1 of 1

Section	Formwork As-built Dimensions Series D							
	1	2	3	4	5	6	7	8
A-A	78 $\frac{7}{8}$ "	79"	80"	80"	N/A	N/A	N/A	N/A
B-B	4 - $\frac{1}{2}$ "	6"	4 - $\frac{3}{8}$ "	23 - $\frac{3}{4}$ "	23 - $\frac{5}{8}$ "	30"	30"	17 - $\frac{5}{8}$ "
C-C	3"	6"	3"	23 - $\frac{5}{8}$ "	23 - $\frac{5}{8}$ "	30 - $\frac{1}{8}$ "	30"	17 - $\frac{5}{8}$ "
D-D	3"	8 - $\frac{7}{8}$ "	3"	23 - $\frac{5}{8}$ "	23 - $\frac{5}{8}$ "	30"	30"	17 - $\frac{5}{8}$ "
Recorded by:			Signature				Date	Time
Kinsy Skiller							1/11/17	11:10 am
Checked by:			Signature				Date	Time
Prateek Shah							1/11/17	11:10am
Checked by:			Signature				Date	Time
Comments:								

APPENDIX C: Field Phase III Test Report 25884-000-30R-C01R-00002 Rev. 000 Sheet 490 of 525 Appendix 9, Pg 17 of 39

D9

SOUTH Wire Ties, Chairs NORTH



Bar Marks



none





Specimen:	Series D Formwork As-builts	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/2/2016		

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: D10

Sheet 1 of 1

Section	Formwork As-built Dimensions Series D								
	1	2	3	4	5	6	7	8	
A-A	79"	79"	80"	80- $\frac{1}{8}$ "	NA	NA	NA	NA	
B-B	4- $\frac{1}{2}$ "	6"	4- $\frac{1}{2}$ "	23- $\frac{5}{8}$ "	23- $\frac{5}{8}$ "	30"	30"	17- $\frac{3}{4}$ "	
C-C	3"	6"	3- $\frac{1}{8}$ "	23- $\frac{5}{8}$ "	23- $\frac{5}{8}$ "	30"	30"	17- $\frac{5}{8}$ "	
D-D	3- $\frac{1}{8}$ "	8- $\frac{5}{8}$ "	3- $\frac{1}{8}$ "	23- $\frac{5}{8}$ "	23- $\frac{5}{8}$ "	30"	30"	17- $\frac{5}{8}$ "	
Recorded by:			Signature			Date		Time	
Kinsey Skinner						1/11/17		11:15 am	
Checked by:			Signature			Date		Time	
Prateek Shah						1/11/17		11:15 am	
Checked by:			Signature			Date		Time	
Comments:									

APPENDIX C: Final Phase III Test Report

25884-000-30R-01B-00002-Rev.000-Sheet 192 of 525


Appendix 9, Pg 19 of 39

D10

SOUTH Wire Ties, Chairs NORTH



Bar Marks



Specimen:	Series D Formwork As-builts	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/2/2016		



Appendix 9, Pg 20 of 39

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: D11

Sheet 1 of 1

Section	Formwork As-built Dimensions Series D							
	1	2	3	4	5	6	7	8
A-A	78- $\frac{7}{8}$ "	79"	80"	80"	NA	NA	NA	NA
B-B	4- $\frac{1}{2}$ "	6"	7- $\frac{3}{8}$ "	23- $\frac{5}{8}$ "	23- $\frac{5}{8}$ "	30"	30"	17- $\frac{3}{4}$ "
C-C	5"	6"	3- $\frac{1}{8}$ "	23- $\frac{5}{8}$ "	23- $\frac{5}{8}$ "	30"	30"	17- $\frac{5}{8}$ "
D-D	5"	8- $\frac{3}{4}$ "	3- $\frac{1}{8}$ "	23- $\frac{3}{4}$ "	23- $\frac{3}{4}$ "	30"	30- $\frac{1}{8}$ "	17- $\frac{3}{4}$ "
Recorded by:			Signature				Date	Time
Kinsey Skillen							1/11/17	
Checked by:			Signature				Date	Time
Prateek Shah							1/11/17	
Checked by:			Signature				Date	Time
Comments:								

APPENDIX C: Field Photo, Test Report

26984-000-00R-001R-000002 Rev-000 Sheet 101 of 676

Appendix 9, Pg 21 of 39

LD


SOUTH

Wire Ties, Chairs

NORTH



Bar Marks



none





Specimen:	Series D Formwork As-builts	Sheet:	1	of	1
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/2/2016		

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: D12

Sheet 1 of 1

Section	Formwork As-built Dimensions Series D							
	1	2	3	4	5	6	7	8
A-A	79"	78- $\frac{7}{8}$ "	80"	80"	NA	NA	NA	NA
B-B	4- $\frac{1}{2}$ "	6"	4- $\frac{1}{2}$ "	23- $\frac{5}{8}$ "	23- $\frac{5}{8}$ "	30"	30- $\frac{1}{8}$ "	17- $\frac{5}{8}$ "
C-C	3- $\frac{1}{8}$ "	6"	3- $\frac{1}{8}$ "	23- $\frac{5}{8}$ "	23- $\frac{5}{8}$ "	30"	30"	17- $\frac{3}{4}$ "
D-D	3"	8- $\frac{7}{8}$ "	3"	23- $\frac{5}{8}$ "	23- $\frac{3}{4}$ "	30"	30- $\frac{1}{8}$ "	17- $\frac{3}{4}$ "
Recorded by:			Signature				Date	Time
Kinsy Skiller							1/11/17	
Checked by:			Signature				Date	Time
Prateek Shah							1/11/17	
Checked by:			Signature				Date	Time
Comments:								

APPENDIX C Due Photo Test Report

2698-000-00R-001R-00002-Rev-000-Sheet 106 of 676


Appendix 9, Pg 23 of 39

D12

SOUTH

Wire Ties, Chairs

NORTH



Bar Marks



None



Specimen:	Series D Formwork As-builts	Sheet:	1	of	1
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/2/2016		

Appendix 9, Pg 24 of 39

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: _____




Sheet 2 of 2

APPENDIX C: Purdue Phase III Test Report


*See formwork as-built drawings for dimension locations

Formwork As-built Dimensions Key - Series D								
Section	1	2	3	4	5	6	7	8
A-A	79"	79"	80"	80"	N/A	N/A	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
D-D	3"	8-3/4"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"


25991-000-001-001-00002, Rev 100, Sheet 498 of 575
Appendix 9, Pg 25 of 39



Drawing:	Series D Formwork As-builts	Sheet:	1	of	2
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/2/2016		



Section C-C
*Facing North



Section B-B, D-D
*Facing North



Drawing:	Series D Formwork As-builts	Sheet:	2	of	2
Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
		Date:	11/2/2016		

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: 013

Sheet 1 of 2

Section	Formwork As-built Dimensions Series D							
	1	2	3	4	5	6	7	8
A-A	78- $\frac{3}{4}$ "	79"	80"	80"	_____			
B-B	4- $\frac{3}{8}$ "	6"	4- $\frac{1}{2}$ "	23- $\frac{5}{8}$ "	23- $\frac{5}{8}$ "	30"	30"	17- $\frac{5}{8}$ "
C-C	3"	6"	3"	23- $\frac{5}{8}$ "	23- $\frac{5}{8}$ "	30"	30"	17- $\frac{5}{8}$ "
D-D	3"	8- $\frac{3}{4}$ "	3- $\frac{1}{8}$ "	23- $\frac{5}{8}$ "	23- $\frac{5}{8}$ "	30"	30"	17- $\frac{3}{4}$ "
Recorded by:			Signature				Date	Time
Kinsy Skillen			K.C. Skillen				7/26/17	8:00 am
Checked by:			Signature				Date	Time
Checked by:			Signature				Date	Time
Comments:								

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: D13

Sheet 2 of

*See formwork as-built drawings for dimension locations

Section	Formwork As-built Dimensions Key - Series D							
	1	2	3	4	5	6	7	8
A-A	79"	79"	80"	80"	N/A	N/A	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
D-D	3"	8-3/4"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"

25884-000-30R-C01R-00002, Rev. 000, Sheet 502 of 575
 Appendix 9, Pg 29 of 39

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: D14

Sheet 1 of 2

Section	Formwork As-built Dimensions Series D							
	1	2	3	4	5	6	7	8
A-A	79"	79"	80"	80"	<hr/>			
B-B	4- $\frac{3}{8}$ "	6"	4- $\frac{3}{8}$ "	23- $\frac{5}{8}$ "	23- $\frac{5}{8}$ "	30"	30"	17- $\frac{5}{8}$ "
C-C	3"	6"	3"	23- $\frac{5}{8}$ "	23- $\frac{5}{8}$ "	30"	30"	17- $\frac{5}{8}$ "
D-D	3"	8- $\frac{7}{8}$ "	3- $\frac{1}{8}$ "	23- $\frac{5}{8}$ "	23- $\frac{5}{8}$ "	30"	30"	17- $\frac{1}{2}$ "
Recorded by:			Signature				Date	Time
Kinscy Skiller			K.C. Skiller				4/26/17	8:12 am
Checked by:			Signature				Date	Time
Checked by:			Signature				Date	Time
Comments:								

Appendix 9, Pg 30 of 39

APPENDIX C: Pileup Phase III Test Report

25884-000-30R-C01R-00002, Rev. 000, Sheet 503 of 575

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: D14

Sheet 2 of 2

*See formwork as-built drawings for dimension locations

Section	Formwork As-built Dimensions Key - Series D							
	1	2	3	4	5	6	7	8
A-A	79"	79"	80"	80"	N/A	N/A	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
D-D	3"	8-3/4"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: DIS

Sheet 1 of

Section	Formwork As-built Dimensions Series D								
	1	2	3	4	5	6	7	8	
A-A	79"	79"	80"	80"	_____				
B-B	4- $\frac{1}{2}$ "	6"	4- $\frac{1}{2}$ "	23- $\frac{1}{2}$ "	23- $\frac{5}{8}$ "	30"	30"	17- $\frac{1}{2}$ "	
C-C	3"	6"	3- $\frac{1}{4}$ "	23- $\frac{1}{2}$ "	23- $\frac{5}{8}$ "	30- $\frac{1}{8}$ "	30"	17- $\frac{5}{8}$ "	
D-D	3"	8- $\frac{7}{8}$ "	7"	23- $\frac{1}{2}$ "	23- $\frac{5}{8}$ "	30"	30"	17- $\frac{1}{2}$ "	
Recorded by:			Signature				Date	Time	
Kinsy Skiller			K.C. Skiller				4/26/17	8:30 am	
Checked by:			Signature				Date	Time	
Checked by:			Signature				Date	Time	
Comments:									

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: DIS

Sheet 2 of 2

*See formwork as-built drawings for dimension locations

Section	Formwork As-built Dimensions Key - Series D							
	1	2	3	4	5	6	7	8
A-A	79"	79"	80"	80"	N/A	N/A	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
D-D	3"	8-3/4"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"

25884-000-30R-C01R-00002, Rev. 000, Sheet 506 of 575
Appendix 9, Pg 33 of 39

APPENDIX C: Purdue Phase III Test Report

Project: Effects of laminar cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: D16

Sheet 1 of 1

Section	Formwork As-built Dimensions Series D								
	1	2	3	4	5	6	7	8	
A-A	78- $\frac{7}{8}$ "	79"	80"	80"	<hr/>				
B-B	4- $\frac{1}{2}$ "	6"	4- $\frac{3}{8}$ "	23- $\frac{1}{2}$ "	23- $\frac{3}{4}$ "	30- $\frac{1}{8}$ "	30"	17- $\frac{1}{2}$ "	
C-C	3"	4"	3- $\frac{1}{8}$ "	23- $\frac{1}{2}$ "	23- $\frac{5}{8}$ "	30- $\frac{1}{8}$ "	30- $\frac{1}{8}$ "	17- $\frac{5}{8}$ "	
D-D	3"	8- $\frac{3}{4}$ "	3"	23- $\frac{5}{8}$ "	23- $\frac{5}{8}$ "	30"	30"	17- $\frac{5}{8}$ "	
Recorded by:			Signature				Date	Time	
Kinsy Skiller			K.C. Skiller				4/26/17	8:45 am	
Checked by:			Signature				Date	Time	
Checked by:			Signature				Date	Time	
Comments:									

APPENDIX C: Puddle Phase III Test Report

25884-000-30R-C01R-00002, Rev. 000, Sheet 507 of 575

Appendix 9, Pg 34 of 39

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: D16

Sheet 2 of 2

*See formwork as-built drawings for dimension locations

Section	Formwork As-built Dimensions Key - Series D							
	1	2	3	4	5	6	7	8
A-A	79"	79"	80"	80"	N/A	N/A	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
D-D	3"	8-3/4"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"

25884-000-30R-C01R-00002, Rev. 000, Sheet 508 of 575
Appendix 9, Pg 35 of 39

APPENDIX C: Purdue Phase III Test Report

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: D17

Sheet 1 of 1

Section	Formwork As-built Dimensions Series D							
	1	2	3	4	5	6	7	8
A-A	79"	78- $\frac{7}{8}$ "	80"	80"	_____			
B-B	4- $\frac{3}{8}$ "	6- $\frac{1}{8}$ "	4- $\frac{1}{2}$ "	23- $\frac{5}{8}$ "	23- $\frac{5}{8}$ "	30"	30"	17- $\frac{5}{8}$ "
C-C	3"	6"	3- $\frac{1}{8}$ "	23- $\frac{5}{8}$ "	23- $\frac{1}{2}$ "	30"	30"	17- $\frac{1}{2}$ "
D-D	3"	8- $\frac{3}{4}$ "	3"	23- $\frac{3}{4}$ "	23- $\frac{3}{4}$ "	30"	30"	17- $\frac{5}{8}$ "
Recorded by:			Signature				Date	Time
Kinsay Skiller			K.C. Skiller				4/26/17	7:15 am
Checked by:			Signature				Date	Time
Checked by:			Signature				Date	Time
Comments:								

APPENDIX C: Posture Phase III Test Report

25884-000-30R-C01R-00002, Rev. 000, Sheet 509 of 575

Appendix 9, Pg 36 of 39

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: D17

Sheet 2 of 2

*See formwork as-built drawings for dimension locations

Section	Formwork As-built Dimensions Key - Series D							
	1	2	3	4	5	6	7	8
A-A	79"	79"	80"	80"	N/A	N/A	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
D-D	3"	8-3/4"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: DIS

Sheet 1 of 2

Section	Formwork As-built Dimensions Series D							
	1	2	3	4	5	6	7	8
A-A	79"	79- $\frac{1}{8}$ "	80- $\frac{1}{8}$ "	80"	_____			
B-B	4- $\frac{1}{2}$ "	6"	4- $\frac{3}{8}$ "	23- $\frac{5}{8}$ "	23- $\frac{3}{4}$ "	30- $\frac{1}{8}$ "	30"	17- $\frac{5}{8}$ "
C-C	3"	6- $\frac{1}{8}$ "	3"	23- $\frac{1}{2}$ "	23- $\frac{1}{2}$ "	30"	30"	17- $\frac{1}{2}$ "
D-D	3"	8- $\frac{3}{4}$ "	3- $\frac{1}{8}$ "	23- $\frac{5}{8}$ "	23- $\frac{3}{4}$ "	30"	30"	17- $\frac{5}{8}$ "
Recorded by:			Signature				Date	Time
Kinsy Skiller			K.P. Skiller				4/26/17	9:30 am
Checked by:			Signature				Date	Time
Checked by:			Signature				Date	Time
Comments:								

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: DIS



Sheet 2 of 2

APPENDIX C: P-4 Due Phase III Test Report


*See formwork as-built drawings for dimension locations

Section	Formwork As-built Dimensions Key - Series D							
	1	2	3	4	5	6	7	8
A-A	79"	79"	80"	80"	N/A	N/A	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	3"	6"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"
D-D	3"	8-3/4"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"

25884-000-30R-C01R-00002, Rev. 000, Sheet 512 of 575
Appendix 9, Pg 39 of 39



Drawing:	Series D Concrete As-builts	Sheet:	1	of	2
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:
Date:			11/2/2016		



Section B-B, C-C
*Facing North



Drawing:	Series D Concrete As-builts	Sheet:	2	of	2	
	Project:	EXPERIMENTAL INVESTIGATION OF THE EFFECT OF LAMINAR CRACKS ON STRENGTH OF UNCONFINED 79-IN. LAP SPLICES OF #11 REINFORCING BARS	Drawn by:	KCS	Checked by:	SP
			Date:	11/2/2016		

Appendix 10, Pg 2 of 27

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: _____
Sheet 2 of 2

*See formwork as-built drawings for dimension locations


Section	Formwork As-built Dimensions Key - Series D							
	1	2	3	4	5	6	7	8
A-A	80"	80"	N/A	N/A	N/A	N/A	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	N/A	N/A	N/A	N/A	N/A	30"	30"	17-5/8"
D-D	3"	8-3/4"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: D1

Sheet 1 of 1

Section	Concrete As-built Dimensions Series D							
	1	2	3	4	5	6	7	8
A-A	80 - 1/4"	80 - 1/8"	—	—	—	—	—	—
B-B	4 - 1/2"	5 - 7/8"	4 - 3/8"	23 - 3/4"	23 - 5/8"	30"	30"	17 - 1/2"
C-C	—	—	—	—	—	30"	30"	17 - 5/8"
D-D	2 - 7/8"	8 - 3/4"	3"	23 - 5/8"	23 - 5/8"	30"	30"	17 - 1/2"
Recorded by:			Signature				Date	Time
Kinsay Skiller							1/18/17	6:45 pm
Checked by:			Signature				Date	Time
Checked by:			Signature				Date	Time

Comments:
 ↳ See back for nominal dimensions, taken prior to testing.
 ↳ depths see slight deviation from nominal value because of the screed + finishing process on the top face.


APPENDIX C: Final Report Phase III Test Report 25884-000-30R-C01R-00002 Rev. 000 Sheet 516 of 525 Appendix 10, Pg 4 of 27

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: 02

Sheet 1 of

Section	Concrete As-built Dimensions Series D							
	1	2	3	4	5	6	7	8
A-A	80"	79- $\frac{7}{8}$ "	—	—	—	—	—	—
B-B	4- $\frac{1}{2}$ "	6"	4- $\frac{3}{8}$ "	23- $\frac{5}{8}$ "	23- $\frac{1}{2}$ "	30"	30"	17- $\frac{1}{2}$ "
C-C	—	—	—	—	—	30"	30- $\frac{1}{8}$ "	17- $\frac{5}{8}$ "
D-D	3"	9"	2- $\frac{7}{8}$ "	23- $\frac{5}{8}$ "	23- $\frac{5}{8}$ "	30 $\frac{1}{8}$ "	30"	17- $\frac{5}{8}$ "
Recorded by:			Signature				Date	Time
Kinsey Skiller							1/18/17	7:00 pm
Checked by:			Signature				Date	Time
Checked by:			Signature				Date	Time


Comments:

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: **D3**

Sheet 1 of

Section	Concrete As-built Dimensions Series D								
	1	2	3	4	5	6	7	8	
A-A	80"	80"	<hr/>		<hr/>		<hr/>		
B-B	4- $\frac{3}{8}$ "	5- $\frac{3}{4}$ "	4- $\frac{1}{2}$ "	23- $\frac{5}{8}$ "	23- $\frac{1}{2}$ "	30- $\frac{1}{8}$ "	30"	17- $\frac{5}{8}$ "	
C-C	<hr/>		<hr/>		<hr/>		30- $\frac{1}{8}$ "	30"	17- $\frac{1}{2}$ "
D-D	3"	8- $\frac{3}{4}$ "	2- $\frac{7}{8}$ "	23- $\frac{1}{2}$ "	23- $\frac{1}{2}$ "	30"	30"	17- $\frac{1}{2}$ "	
Recorded by:			Signature				Date	Time	
Kinsey Skillen							1/18/17	7:08 pm	
Checked by:			Signature				Date	Time	
Checked by:			Signature				Date	Time	

Comments:

Appendix 10, Pg 6 of 27


APPENDIX C: Phase III Test Report
25884-000-30R-C01R-00002 Rev. 000 Sheet 518 of 525

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: D5

Sheet 1 of

Section	Concrete As-built Dimensions Series D								
	1	2	3	4	5	6	7	8	
A-A	80"	80"	<hr/>						
B-B	4- $\frac{7}{8}$ "	6"	4- $\frac{1}{2}$ "	23- $\frac{3}{4}$ "	23- $\frac{15}{16}$ "	30"	30- $\frac{1}{8}$ "	17- $\frac{5}{8}$ "	
C-C	<hr/>					30- $\frac{1}{4}$ "	30 $\frac{1}{4}$ "	17- $\frac{1}{2}$ "	
D-D	5"	8- $\frac{7}{8}$ "	3"	23- $\frac{3}{4}$ "	23- $\frac{3}{4}$ "	30- $\frac{1}{8}$ "	30"	17- $\frac{5}{8}$ "	
Recorded by:			Signature				Date	Time	
Kinsey Skillen							1/18/17	7:27 pm	
Checked by:			Signature				Date	Time	
Checked by:			Signature				Date	Time	


Comments:

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: D6

Sheet 1 of

Section	Concrete As-built Dimensions Series D								
	1	2	3	4	5	6	7	8	
A-A	80"	80"	<hr/>						
B-B	4- $\frac{1}{2}$ "	6"	4- $\frac{3}{8}$ "	23- $\frac{3}{4}$ "	23- $\frac{3}{4}$ "	30"	70- $\frac{1}{8}$ "	17- $\frac{1}{2}$ "	
C-C	<hr/>					30- $\frac{1}{4}$ "	30- $\frac{1}{8}$ "	17- $\frac{1}{2}$ "	
D-D	3"	8- $\frac{7}{8}$ "	3"	23- $\frac{3}{4}$ "	23- $\frac{3}{4}$ "	30- $\frac{1}{8}$ "	30"	17- $\frac{1}{8}$ "	
Recorded by:			Signature				Date	Time	
Kinsey Skillen							1/18/17	7:36 pm	
Checked by:			Signature				Date	Time	
Checked by:			Signature				Date	Time	

Comments:

Appendix 10, Pg 9 of 27

APPENDIX C: Puddle Phase III Test Report


25884-000-30R-C01R-00002, Rev. 000, Sheet 521 of 575

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: D7

Sheet 1 of

Section	Concrete As-built Dimensions Series D								
	1	2	3	4	5	6	7	8	
A-A	80"	80"	_____						
B-B	4- $\frac{3}{8}$ "	5- $\frac{3}{4}$ "	4- $\frac{3}{8}$ "	23- $\frac{5}{8}$ "	23- $\frac{3}{4}$ "	30"	30"	17- $\frac{5}{8}$ "	
C-C	_____					30- $\frac{1}{8}$ "	30- $\frac{1}{8}$ "	17- $\frac{3}{4}$ "	
D-D	2- $\frac{7}{8}$ "	9"	3"	23- $\frac{3}{4}$ "	23- $\frac{5}{8}$ "	30- $\frac{1}{8}$ "	30"	17- $\frac{1}{2}$ "	
Recorded by:			Signature				Date	Time	
Kinsay Skiller							1/18/17	8:00pm	
Checked by:			Signature				Date	Time	
Checked by:			Signature				Date	Time	

Comments:

Appendix 10, Pg 10 of 27


APPENDIX C: Practice Phase III Test Report 25884-000-30R-C01R-00002 Rev. 000 Sheet 522 of 575

Project: Effects of laminar cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: D9

Sheet 1 of 1

Section	Concrete As-built Dimensions Series D								
	1	2	3	4	5	6	7	8	
A-A	$80\frac{1}{4}"$	$77\frac{3}{4}"$	<hr/>					<hr/>	
B-B	$4\frac{1}{2}"$	6"	$4\frac{3}{8}"$	$23\frac{3}{4}"$	$23\frac{3}{4}"$	$30\frac{1}{4}"$	30"	$17\frac{1}{2}"$	
C-C	<hr/>					$30\frac{1}{8}"$	$30\frac{1}{8}"$	$17\frac{3}{4}"$	
D-D	3"	$8\frac{3}{4}"$	$2\frac{7}{8}"$	$23\frac{3}{4}"$	$23\frac{1}{2}"$	$30\frac{1}{4}"$	$30\frac{1}{8}"$	$17\frac{5}{8}"$	
Recorded by:			Signature				Date	Time	
Kinsy Skiller							1/18/17	9:00 pm	
Checked by:			Signature				Date	Time	
Checked by:			Signature				Date	Time	

Comments:

Appendix 10, Pg 12 of 27

APPENDIX C: Purdue Phase III Test Report


25884-000-30R-C01R-00002, Rev. 000, Sheet 524 of 575

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: D10

Sheet 1 of

Section	Concrete As-built Dimensions Series D								
	1	2	3	4	5	6	7	8	
A-A	80"	79- $\frac{7}{8}$ "	_____						
B-B	4- $\frac{1}{2}$ "	5- $\frac{7}{8}$ "	4- $\frac{1}{2}$ "	25- $\frac{3}{4}$ "	23- $\frac{11}{16}$ "	30- $\frac{1}{8}$ "	30- $\frac{1}{4}$ "	17- $\frac{5}{8}$ "	
C-C	_____					30- $\frac{1}{8}$ "	30"	17- $\frac{1}{2}$ "	
D-D	2- $\frac{7}{8}$ "	8- $\frac{3}{4}$ "	3- $\frac{1}{8}$ "	23- $\frac{3}{4}$ "	23- $\frac{3}{4}$ "	30"	30"	17- $\frac{1}{2}$ "	
Recorded by:			Signature				Date	Time	
Kinsey Skiller							1/18/17	9:00 pm	
Checked by:			Signature				Date	Time	
Checked by:			Signature				Date	Time	

Comments:

APPENDIX C: Purdue Phase III Test Report

25884-000-30R-C01R-00002, Rev. 000, Sheet 525 of 575


Appendix 10, Pg 13 of 27

Project: Effects of laminar cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: D11

Sheet 1 of

Section	Concrete As-built Dimensions Series D								
	1	2	3	4	5	6	7	8	
A-A	79 - $\frac{3}{4}$ "	80"	<hr/>						
B-B	4 - $\frac{1}{4}$ "	6 - $\frac{1}{8}$ "	4 - $\frac{1}{2}$ "	23 - $\frac{3}{4}$ "	23 - $\frac{3}{4}$ "	30"	30"	17 - $\frac{1}{2}$ "	
C-C	<hr/>					30 - $\frac{1}{8}$ "	30 - $\frac{1}{4}$ "	17 - $\frac{3}{8}$ "	
D-D	2 - $\frac{7}{8}$ "	8 - $\frac{3}{4}$ "	3 - $\frac{1}{8}$ "	23 - $\frac{3}{4}$ "	23 - $\frac{5}{8}$ "	30"	30 - $\frac{1}{4}$ "	17 - $\frac{1}{2}$ "	
Recorded by:			Signature				Date	Time	
Kinsey Skiller							1/18/17	9:00 pm	
Checked by:			Signature				Date	Time	
Checked by:			Signature				Date	Time	

Comments:

Appendix 10, Pg 14 of 27

APPENDIX C: Purdue Phase III Test Report


25884-000-30R-C01R-00002, Rev. 000, Sheet 526 of 575

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: D12

Sheet 1 of

Section	Concrete As-built Dimensions Series D								
	1	2	3	4	5	6	7	8	
A-A	80"	80"	<hr/>						
B-B	4- $\frac{3}{8}$ "	6"	4- $\frac{3}{8}$ "	23- $\frac{5}{8}$ "	23- $\frac{5}{8}$ "	30- $\frac{1}{8}$ "	30- $\frac{1}{8}$ "	17- $\frac{5}{8}$ "	
C-C	<hr/>					30- $\frac{1}{8}$ "	30"	17- $\frac{1}{2}$ "	
D-D	3"	8- $\frac{3}{4}$ "	2- $\frac{7}{8}$ "	23- $\frac{5}{8}$ "	23- $\frac{5}{8}$ "	30"	30- $\frac{1}{4}$ "	17- $\frac{1}{2}$ "	
Recorded by:			Signature				Date	Time	
Kinsey Skiller								9:00 pm	
Checked by:			Signature				Date	Time	
Checked by:			Signature				Date	Time	
Comments:									

Appendix 10, Pg 15 of 27

APPENDIX C: Phase III Test Report 25884-000-30R-C01R-00002 Rev. 000 Sheet 527 of 525

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: D13

Sheet 1 of 2

Section	Concrete As-built Dimensions Series D								
	1	2	3	4	5	6	7	8	
A-A	80"	80"							
B-B	4-1/2"	6"	4-3/8"	23-1/2"	23-1/2"	30"	30"	17-1/2"	
C-C						30-1/8"	30"	17-5/8"	
D-D	3"	8-3/4"	2-7/8"	23-1/2"	23-1/2"	30"	30"	17-1/2"	
Recorded by:			Signature				Date	Time	
Kinsey Skiller			K.C. Skiller				5/5/17	9:00 am	
Checked by:			Signature				Date	Time	
Checked by:			Signature				Date	Time	

Comments:

Appendix 10, Pg 16 of 27

APPENDIX C: Purdue Phase III Test Report

25884-000-30R-C01R-00002, Rev. 000, Sheet 528 of 575

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: D13

Sheet 2 of 2

*See formwork as-built drawings for dimension locations

Section	Formwork As-built Dimensions Key - Series D							
	1	2	3	4	5	6	7	8
A-A	80"	80"	N/A	N/A	N/A	N/A	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	N/A	N/A	N/A	N/A	N/A	30"	30"	17-5/8"
D-D	3"	8-3/4"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"

25884-000-30R-C01R-00002, Rev. 000, Sheet 529 of 575
 Appendix 10, Pg 17 of 27

APPENDIX C: Pujugue Phase III Test Report

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: D14

Sheet 1 of 2

Section	Concrete As-built Dimensions Series D								
	1	2	3	4	5	6	7	8	
A-A	79- $\frac{7}{8}$ "	80"							
B-B	4- $\frac{1}{2}$ "	6"	4- $\frac{1}{2}$ "	23- $\frac{1}{2}$ "	23- $\frac{1}{2}$ "	70"	29- $\frac{3}{8}$ "	17- $\frac{1}{2}$ "	
C-C						30- $\frac{1}{8}$ "	30- $\frac{1}{8}$ "	17- $\frac{5}{8}$ "	
D-D	3"	8- $\frac{3}{4}$ "	3"	23- $\frac{1}{2}$ "	23- $\frac{1}{2}$ "	30"	30"	17- $\frac{1}{2}$ "	
Recorded by:			Signature				Date	Time	
Kinsy Skiller			K. C. Skiller				5/5/17	9:20 am	
Checked by:			Signature				Date	Time	
Checked by:			Signature				Date	Time	

Comments:

Appendix 10, Pg 18 of 27

APPENDIX C: Purdue Phase III Test Report

25884-000-30R-C01R-00002, Rev. 000, Sheet 530 of 575

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: D14

Sheet 2 of 2

*See formwork as-built drawings for dimension locations

Section	Formwork As-built Dimensions Key - Series D							
	1	2	3	4	5	6	7	8
A-A	80"	80"	N/A	N/A	N/A	N/A	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	N/A	N/A	N/A	N/A	N/A	30"	30"	17-5/8"
D-D	3"	8-3/4"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"

25884-000-30R-C01R-00002, Rev. 000, Sheet 531 of 575
 Appendix 10, Pg 19 of 27

APPENDIX C: Puddle Phase III Test Report

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: DIS

Sheet 1 of

Section	Concrete As-built Dimensions Series D								
	1	2	3	4	5	6	7	8	
A-A	80"	79 - $\frac{7}{8}$ "	_____						
B-B	4 - $\frac{3}{8}$ "	6"	4 - $\frac{1}{2}$ "	23 - $\frac{5}{8}$ "	23 - $\frac{1}{2}$ "	30 - $\frac{1}{8}$ "	30"	17 - $\frac{1}{2}$ "	
C-C	_____					30"	30"	17 - $\frac{1}{2}$ "	
D-D	3"	8 - $\frac{3}{4}$ "	2 - $\frac{7}{8}$ "	23 - $\frac{1}{2}$ "	23 - $\frac{1}{2}$ "	30"	30"	17 - $\frac{5}{8}$ "	
Recorded by:			Signature				Date	Time	
Kinsy Skilbe			K. C. Skilbe				5/3/17	9:45 am	
Checked by:			Signature				Date	Time	
Checked by:			Signature				Date	Time	

Comments:

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: DIS

Sheet 2 of 2

*See formwork as-built drawings for dimension locations

Section	Formwork As-built Dimensions Key - Series D							
	1	2	3	4	5	6	7	8
A-A	80"	80"	N/A	N/A	N/A	N/A	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	N/A	N/A	N/A	N/A	N/A	30"	30"	17-5/8"
D-D	3"	8-3/4"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"

25884-000-30R-C01R-00002, Rev. 000, Sheet 533 of 575
 Appendix 10, Pg 21 of 27

APPENDIX C: Puque Phase III Test Report

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: DIG

Sheet 1 of 2

Section	Concrete As-built Dimensions Series D								
	1	2	3	4	5	6	7	8	
A-A	80"	80- $\frac{1}{8}$ "	_____						
B-B	4- $\frac{3}{8}$ "	6"	4- $\frac{1}{2}$ "	23- $\frac{1}{2}$ "	23- $\frac{1}{2}$ "	30"	30- $\frac{1}{8}$ "	17- $\frac{1}{2}$ "	
C-C	_____					30- $\frac{1}{8}$ "	30"	17- $\frac{5}{8}$ "	
D-D	3- $\frac{1}{8}$ "	8- $\frac{3}{4}$ "	3"	23- $\frac{5}{8}$ "	23- $\frac{1}{2}$ "	30"	30"	17- $\frac{5}{8}$ "	
Recorded by:			Signature				Date	Time	
Kinsy Skiller			K.C. Skiller				5/5/17	10:00 am	
Checked by:			Signature				Date	Time	
Checked by:			Signature				Date	Time	

Comments:

APPENDIX C: Puqque Phase III Test Report

25884-000-30R-C01R-00002, Rev. 000, Sheet 534 of 575

Appendix 10, Pg 22 of 27

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: D16

Sheet 2 of 2

*See formwork as-built drawings for dimension locations

Section	Formwork As-built Dimensions Key - Series D							
	1	2	3	4	5	6	7	8
A-A	80"	80"	N/A	N/A	N/A	N/A	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	N/A	N/A	N/A	N/A	N/A	30"	30"	17-5/8"
D-D	3"	8-3/4"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"

25884-000-30R-C01R-00002, Rev. 000, Sheet 535 of 575
 Appendix 10, Pg 23 of 27

APPENDIX C: Puddle Phase III Test Report

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: D17

Sheet 1 of

Section	Concrete As-built Dimensions Series D								
	1	2	3	4	5	6	7	8	
A-A	79 - $\frac{7}{8}$ "	80"	_____						
B-B	4 - $\frac{1}{2}$ "	6"	4 - $\frac{1}{2}$ "	23 - $\frac{5}{8}$ "	23 - $\frac{5}{8}$ "	30"	30"	17 - $\frac{5}{8}$ "	
C-C	_____					30"	30"	17 - $\frac{5}{8}$ "	
D-D	3"	8 - $\frac{7}{4}$ "	3"	23 - $\frac{3}{4}$ "	23 - $\frac{3}{4}$ "	30 - $\frac{1}{8}$ "	30 - $\frac{1}{8}$ "	17 - $\frac{1}{2}$ "	
Recorded by:			Signature				Date	Time	
Kinsy Skilbr			KC Skilbr				5/5/16	10:15	
Checked by:			Signature				Date	Time	
Checked by:			Signature				Date	Time	

Comments:

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

As-built Dimensions v.1
(Rev. 11/2/2016)

Specimen: D18

Sheet 2 of 2

*See formwork as-built drawings for dimension locations

Section	Formwork As-built Dimensions Key - Series D							
	1	2	3	4	5	6	7	8
A-A	80"	80"	N/A	N/A	N/A	N/A	N/A	N/A
B-B	4-3/8"	6"	4-3/8"	23-5/8"	23-5/8"	30"	30"	17-5/8"
C-C	N/A	N/A	N/A	N/A	N/A	30"	30"	17-5/8"
D-D	3"	8-3/4"	3"	23-5/8"	23-5/8"	30"	30"	17-5/8"

Appendix 10, Pg 27 of 27


25884-000-30R-C01R-00002, Rev. 000, Sheet 539 of 575

APPENDIX C: Puque Phase III Test Report

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Instrumentation Documentation v.1
(Rev. 11/1/2016)

Specimen: 01
Sheet 1 of 1

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity	Zero Offset	Location	Comments
1	1	10 V	LC	ALV03006	1.0767 $\frac{mV}{V}$	0 mV	E	full scale 112,400 LSF
2	1	10 V	LC	ALV03005	1.0779 $\frac{mV}{V}$	0 mV	W	"
3	1	30 V	LVDT	X0167	9902 $\frac{mV}{in}$	8878	W rotation	1" LVDT
4	1	30 V	LVDT	12838	40941 $\frac{mV}{in}$	6178 mV	NE	$\frac{1}{4}$ " "
5	1	30 V	LVDT	23618	20349 $\frac{mV}{in}$	3336 mV	SE	$\frac{1}{2}$ " "
6	1	30 V	LVDT	X00598	9911 $\frac{mV}{in}$	8623 mV	NW	1" "
7	1	30 V	LVDT	J4914	10053 $\frac{mV}{in}$	4400 mV	SW	1" "
8	1	30 V	LVDT	X0135	10097 $\frac{mV}{in}$	6410 mV	E rotation	1" "
Operator		Signature			Date		Time	
Kinsy Skiller					2/13/17		7:00 pm	
Checked by		Signature			Date		Time	
Checked by		Signature			Date		Time	

Notes:


APPENDIX C: Purdue Phase III Test Report
25884-000-30R-C01R-00002, Rev. 000, Sheet 540 of 575
Appendix 11, Pg 1 of 30

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Instrumentation Documentation v.1
(Rev. 11/1/2016)

Specimen: 02
Sheet 1 of 1

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity	Zero Offset	Location	Comments
1	1	10 V	LC	ALU03006	1.0767 $\frac{mV}{V}$	0 mV	E	full scale 112,400 $\mu\epsilon$
2	1	10 V	LC	ALU03005	1.0779 $\frac{mV}{V}$	0 mV	W	"
3	1	30 V	LVDT	X0167	9902 $\frac{mV}{in}$	-704 mV	W rotation	1" LVDT
4	1	30 V	LVDT	8702	10000 $\frac{mV}{in}$	7985 mV	NE	1" "
5	1	30 V	LVDT	23618	20349 $\frac{mV}{in}$	8237 mV	SE	$\frac{1}{2}$ " "
6	1	30 V	LVDT	X00598	9911 $\frac{mV}{in}$	7953 mV	NW	1" "
7	1	30 V	LVDT	J4914	10003 $\frac{mV}{in}$	7452 mV	SW	1" "
8	1	30 V	LVDT	X0185	10097 $\frac{mV}{in}$	9235 mV	E rotation	1" "

Operator	Signature	Date	Time
Kinsey Skille		2/15/17	8:00 am
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time

Notes:


APPENDIX C: Funding Phase III Test Report 2588-000-3DR-C01R-00002, Rev. 000, Sheet 541 of 575 Appendix 11, Pg 2 of 30

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Instrumentation Documentation v.1
(Rev. 11/1/2016)

Specimen: 03
Sheet 1 of 1

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity ($\frac{mV}{\sqrt{Hz}}$)	Zero Offset (mV)	Location	Comments
1	1	10 V	LC	ALU03006	1.0767 $\frac{mV}{\sqrt{Hz}}$	0 mV	E	full scale 112,400 $\mu\epsilon$
2	1	10 V	LC	ALU03005	1.0779 $\frac{mV}{\sqrt{Hz}}$	0 mV	W	"
3	1	30 V	LVDT	X0167	9902	7860	W rotation	1" LVDT
4	1	30 V	LVDT	8702	10318	7943	NE	1" "
5	1	30 V	LVDT	23618	20349	8051	SE	$\frac{1}{2}$ " "
6	1	30 V	LVDT	X00598	9911	9537	NW	1" "
7	1	30 V	LVDT	J4914	10003	7697	SW	1" "
8	1	30 V	LVDT	X0135	10097	8074	E rotation	1" "

Operator	Signature	Date	Time
Kinsay Skiller		2/15/17	6:30 pm
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time

Notes:


APPENDIX C: Furdie Phase III Test Report
25981-000-20R-G01R-000002 Rev 000 Sheet 5 of 57
Appendix 11, Pg 3 of 30

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Instrumentation Documentation v.1
(Rev. 11/1/2016)

Specimen: D4-1
Sheet 1 of 1

Data Acquisition System:									
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity (mV/V)	Zero Offset (mV)	Location	Comments	
1	1	10 V	LC	ALU03006	1.0767 $\frac{mV}{V}$	0 mV	E	full scale 112,400 lbf	
2	1	10 V	LC	ALU03005	1.0779 $\frac{mV}{V}$	0 mV	W	"	
3	1	30 V	LVDT	X0167	9902	7626	W rotation	1" LVDT	
4	1	30 V	LVDT	8702	10318	7823	NE	1" "	
5	1	30 V	LVDT	23618	20349	7460	SE	$\frac{1}{2}$ " "	
6	1	30 V	LVDT	X00598	9911	8068	NW	1" "	
7	1	30 V	LVDT	J4914	10003	7125	SW	1" "	
8	1	30 V	LVDT	X0135	10097	7195	E rotation	1" "	

Operator	Signature	Date	Time
Kinsy Skiller		2/20/17	3:30 pm
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time

Notes:


APPENDIX C: Funding Phase III Test Report 2588-000-30R-C01R-00002, Rev. 000, Sheet 543 of 575 Appendix 11, Pg 4 of 30

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Instrumentation Documentation v.1
(Rev. 11/1/2016)

Specimen: D4-2
Sheet 1 of 1

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity ($\frac{mV}{\mu V}$)	Zero Offset (mV)	Location	Comments
1	1	10 V	LC	ALU03006	1.0767 $\frac{mV}{\mu V}$	0 mV	E	full strain 112,400 lbf
2	1	10 V	LC	ALU03005	1.0779 $\frac{mV}{\mu V}$	0 mV	W	"
3	1	30 V	LVDT	X0167	9902	-793	W rotation	1" LVDT
4	1	30 V	LVDT	8702	10318	7381	NE	1" "
5	1	30 V	LVDT	23618	20349	7460	SE	$\frac{1}{2}$ " "
6	1	30 V	LVDT	X00598	9911	8059	NW	1" "
7	1	30 V	LVDT	J4914	10003	7150	SW	1" "
8	1	30 V	LVDT	X0185	10097	97	E rotation	1" "

Operator	Signature	Date	Time
Kinsay Skiller		2/21/17	6:30 pm
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time


Notes:
no true zero offset

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Instrumentation Documentation v.1
(Rev. 11/1/2016)

Specimen: 05-1
Sheet 1 of 1

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity ($\frac{mV}{V}$)	Zero Offset (mV)	Location	Comments
1	1	10 V	LC	ALV03006	1.0767 $\frac{mV}{V}$	0 mV	E	full scale 112,400 lbf
2	1	10 V	LC	ALV03005	1.0779 $\frac{mV}{V}$	0 mV	W	"
3	1	30 V	LVDT	X0167	9702	8084	W rotation	1" LVDT
4	1	30 V	LVDT	8702	10318	8358	NE	1" "
5	1	30 V	LVDT	23618	20349	7874	SE	1/2" "
6	1	30 V	LVDT	X00598	9911	8220	NW	1" "
7	1	30 V	LVDT	J4914	10003	7979	SW	1" "
8	1	30 V	LVDT	X0185	10097	8351	E rotation	1" "


Operator	Signature	Date	Time
Kinsay Skiller		2/22/17	7:00 am
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time

Notes:

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Instrumentation Documentation v.1
(Rev. 11/1/2016)

Specimen: D5-2
Sheet 1 of 1


Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity ($\frac{mV}{in}$)	Zero Offset(mV)	Location	Comments
1	1	10 V	LC	ALV03006	1.0767 $\frac{mV}{in}$	0 mV	E	full strain 112,400 lbf
2	1	10 V	LC	ALV03005	1.0779 $\frac{mV}{in}$	0 mV	W	"
3	1	30 V	LVDT	X0167	9902	-2117	W rotation	1" LVDT
4	1	30 V	LVDT	8702	10318	8390	NE	1" "
5	1	30 V	LVDT	23618	20349	7038	SE	$\frac{1}{2}$ " "
6	1	30 V	LVDT	X00598	9911	8218	NW	1" "
7	1	30 V	LVDT	J4914	10003	7606	SW	1" "
8	1	30 V	LVDT	X0185	10097	9061	E rotation	1" "
Operator		Signature			Date		Time	
Kinsley Skillen					2/23/17		10:30 am	
Checked by		Signature			Date		Time	
Checked by		Signature			Date		Time	

Notes:

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Instrumentation Documentation v.1
(Rev. 11/1/2016)

Specimen: DG-1
Sheet 1 of 1

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity ($\frac{mV}{in}$)	Zero Offset (mV)	Location	Comments
1	1	10 V	LC	ALV03006	1.0767 $\frac{mV}{in}$	0 mV	E	full scale 112,400 lbf
2	1	10 V	LC	ALV03005	1.0779 $\frac{mV}{in}$	0 mV	W	"
3	1	30 V	LVDT	X0167	9902	8755	W rotation	1" LVDT
4	1	30 V	LVDT	8702	10318	6942	NE	1" "
5	1	30 V	LVDT	23618	20349	6841	SE	$\frac{1}{2}$ " "
6	1	30 V	LVDT	X00598	9911	7067	NW	1" "
7	1	30 V	LVDT	J4914	10003	7037	SW	1" "
8	1	30 V	LVDT	X0185	10097	7348	E rotation	1" "
Operator		Signature			Date		Time	
Kinsy Skiller					2/23/16		6:00 pm	
Checked by		Signature			Date		Time	
Checked by		Signature			Date		Time	


Notes:

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Instrumentation Documentation v.1
(Rev. 11/1/2016)

Specimen: D6-2
Sheet 1 of 1

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity ($\frac{mV}{\sqrt{Hz}}$)	Zero Offset (mV)	Location	Comments
1	1	10 V	LC	ALU03006	1.0767 $\frac{mV}{\sqrt{Hz}}$	0 mV	E	full rate 112,400 Hz
2	1	10 V	LC	ALU03005	1.0779 $\frac{mV}{\sqrt{Hz}}$	0 mV	W	"
3	1	30 V	LVDT	X0167	9702	2579	W rotation	1" LVDT
4	1	30 V	LVDT	8702	10318	6678	NE	1" "
5	1	30 V	LVDT	23618	20349	6043	SE	$\frac{1}{2}$ " "
6	1	30 V	LVDT	X00598	9911	6960	NW	1" "
7	1	30 V	LVDT	J4914	10003	6924	SW	1" "
8	1	30 V	LVDT	X0135	10097	3339	E rotation	1" "


Operator	Signature	Date	Time
Kiaany Skiller		2/24/17	7:30 pm
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time

Notes:

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Instrumentation Documentation v.1
(Rev. 11/1/2016)

Specimen: D7-1
Sheet 1 of 1

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity ($\frac{mV}{in}$)	Zero Offset (mV)	Location	Comments
1	1	10 V	LC	ALU03006	1.0767 $\frac{mV}{in}$	0 mV	E	full state 112,400 lbf
2	1	10 V	LC	ALU03005	1.0779 $\frac{mV}{in}$	0 mV	W	"
3	1	30 V	LVDT	X0167	9902	5125	W rotation	1" LVDT
4	1	30 V	LVDT	8702	10318	7111	NE	1" "
5	1	30 V	LVDT	23618	20349	7155	SE	$\frac{1}{2}$ " "
6	1	30 V	LVDT	X00598	9911	6741	NW	1" "
7	1	30 V	LVDT	J4914	10003	6877	SW	1" "
8	1	30 V	LVDT	X0185	10097	5208	E rotation	1" "
Operator		Signature			Date		Time	
Kinsay Skiller					2/26/17		3:30 pm	
Checked by		Signature			Date		Time	
Checked by		Signature			Date		Time	


Notes:

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Instrumentation Documentation v.1
(Rev. 11/1/2016)

Specimen: 07-2
Sheet 1 of 1

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity ($\frac{mV}{in}$)	Zero Offset (mV)	Location	Comments
1	1	10 V	LC	ALV03006	1.0767 $\frac{mV}{in}$	0 mV	E	full strain 112,400 lbf
2	1	10 V	LC	ALV03005	1.0779 $\frac{mV}{in}$	0 mV	W	"
3	1	30 V	LVDT	X0167	9902	2321	W rotation	1" LVDT
4	1	30 V	LVDT	8702	10318	6975	NE	1" "
5	1	30 V	LVDT	23618	20349	6647	SE	$\frac{1}{2}$ " "
6	1	30 V	LVDT	X00598	9911	6504	NW	1" "
7	1	30 V	LVDT	J4914	10003	6451	SW	1" "
8	1	30 V	LVDT	X0185	10097	-2097	E rotation	1" "

Operator	Signature	Date	Time
Kinsley Skillen		2/28/17	6:45 pm
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time


Notes:

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Instrumentation Documentation v.1
(Rev. 11/1/2016)

Specimen: D8-1
Sheet 1 of 1

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity ($\frac{mV}{V}$)	Zero Offset (mV)	Location	Comments
1	1	10 V	LC	ALV03006	1.0767 $\frac{mV}{V}$	0 mV	E	full scale 112,400 μ bf
2	1	10 V	LC	ALV03005	1.0779 $\frac{mV}{V}$	0 mV	W	"
3	1	30 V	LVDT	X0167	9902	8620	W rotation	1" LVDT
4	1	30 V	LVDT	8702	10318	7384	NE	1" "
5	1	30 V	LVDT	23618	20349	5229	SE	$\frac{1}{2}$ " "
6	1	30 V	LVDT	X00598	9911	7429	NW	1" "
7	1	30 V	LVDT	J4914	10003	3936	SW	1" "
8	1	30 V	LVDT	X0185	10097	8933	E rotation	1" "

Operator	Signature	Date	Time
Kinscy Skiller		3/6/17	1:00 pm
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time


Notes:

Appendix 11, Fig 12 of 30

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Instrumentation Documentation v.1
(Rev. 11/1/2016)

Specimen: D8-2
Sheet 1 of 1

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity ($\frac{mV}{\mu V}$)	Zero Offset (mV)	Location	Comments
1	1	10 V	LC	ALU03006	1.0767 $\frac{mV}{\mu V}$	0 mV	E	full strain 112,400 $\mu\epsilon$
2	1	10 V	LC	ALU03005	1.0779 $\frac{mV}{\mu V}$	0 mV	W	"
3	1	30 V	LVDT	X0167	9902	-3665	W rotation	1" LVDT
4	1	30 V	LVDT	8702	10318	7052	NE	1" "
5	1	30 V	LVDT	23618	20349	4258	SE	$\frac{1}{2}$ " "
6	1	30 V	LVDT	X00598	9911	8075	NW	1" "
7	1	30 V	LVDT	J4914	10003	3447	SW	1" "
8	1	30 V	LVDT	X0185	10097	2868	E rotation	1" "
Operator		Signature			Date		Time	
Kinsy Skiller					3/7/17		4:30 pm	
Checked by		Signature			Date		Time	
Checked by		Signature			Date		Time	


Notes:

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Instrumentation Documentation v.1
(Rev. 11/1/2016)

Specimen: D9
Sheet 1 of 1

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity ($\frac{mV}{in}$)	Zero Offset (mV)	Location	Comments
1	1	10 V	LC	ALU03006	1.0767 $\frac{mV}{in}$	0 mV	E	full rate 112,400 Lbf
2	1	10 V	LC	ALU03005	1.0779 $\frac{mV}{in}$	0 mV	W	"
3	1	30 V	LVDT	X0167	9902	8704	W rotation	1" LVDT
4	1	30 V	LVDT	8702	10318	7046	NE	1" "
5	1	30 V	LVDT	23618	20349	6800	SE	$\frac{1}{2}$ " "
6	1	30 V	LVDT	X00598	9911	6677	NW	1" "
7	1	30 V	LVDT	J4914	10003	6248	SW	1" "
8	1	30 V	LVDT	X0185	10097	8870	E rotation	1" "


Operator	Signature	Date	Time
Kinsey Skiller		3/10/17	1:30 pm
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time

Notes:
failed before anchors could be installed

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Instrumentation Documentation v.1
(Rev. 11/1/2016)

Specimen: D10-1
Sheet 1 of 1

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity ($\frac{mV}{in}$)	Zero Offset(mV)	Location	Comments
1	1	10 V	LC	ALU03006	1.0767 $\frac{mV}{in}$	0 mV	E	full strain 112,400 $\mu\epsilon$
2	1	10 V	LC	ALU03005	1.0779 $\frac{mV}{in}$	0 mV	W	"
3	1	30 V	LVDT	X0167	9902	6953	W rotation	1" LVDT
4	1	30 V	LVDT	8702	10318	6528	NE	1" "
5	1	30 V	LVDT	23618	20349	5924	SE	$\frac{1}{2}$ " "
6	1	30 V	LVDT	X00598	9911	7678	NW	1" "
7	1	30 V	LVDT	J4914	10003	7321	SW	1" "
8	1	30 V	LVDT	X0185	10097	7873	E rotation	1" "
Operator		Signature			Date		Time	
Kelsey Skiller					3/14/17		11:00 am	
Checked by		Signature			Date		Time	
Checked by		Signature			Date		Time	

Notes:

Appendix 11, Pg 15 of 30

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Instrumentation Documentation v.1
(Rev. 11/1/2016)

Specimen: D10-2
Sheet 1 of 1

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity ($\frac{mV}{in}$)	Zero Offset (mV)	Location	Comments
1	1	10 V	LC	ALV03006	1.0767 $\frac{mV}{in}$	0 mV	E	full scale 112,400 lbf
2	1	10 V	LC	ALV03005	1.0779 $\frac{mV}{in}$	0 mV	W	"
3	1	30 V	LVDT	X0167	9702	-344 mV	W rotation	1" LVDT
4	1	30 V	LVDT	8702	10318	6489 mV	NE	1" "
5	1	30 V	LVDT	23618	20349	5205	SE	$\frac{1}{2}$ " "
6	1	30 V	LVDT	X00598	9911	7282	NW	1" "
7	1	30 V	LVDT	J4914	10003	6961	SW	1" "
8	1	30 V	LVDT	X0185	10097	448	E rotation	1" "
Operator		Signature			Date		Time	
Kinsley Skiller		K.C. Skiller			3/15/17		2:00 pm	
Checked by		Signature			Date		Time	
Checked by		Signature			Date		Time	

Notes:

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Instrumentation Documentation v.1
(Rev. 11/1/2016)

Specimen: D11
Sheet 1 of 1

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity ($\frac{mV}{\sqrt{Hz}}$)	Zero Offset (mV)	Location	Comments
1	1	10 V	LC	ALU03006	1.0767 $\frac{mV}{\sqrt{Hz}}$	0 mV	E	full scale 112,400 lbf
2	1	10 V	LC	ALU03005	1.0779 $\frac{mV}{\sqrt{Hz}}$	0 mV	W	"
3	1	30 V	LVDT	X0167	9902	7722	W rotation	1" LVDT
4	1	30 V	LVDT	8702	10318	7632	NE	1" "
5	1	30 V	LVDT	23618	20349	5097	SE	$\frac{1}{2}$ " "
6	1	30 V	LVDT	X00598	9911	6445	NW	1" "
7	1	30 V	LVDT	J4914	10003	7476	SW	1" "
8	1	30 V	LVDT	X0185	10097	5924	E rotation	1" "
Operator		Signature			Date		Time	
Kinsley Skiller		K.L. Skiller			3/17/17		1:00 pm	
Checked by		Signature			Date		Time	
Checked by		Signature			Date		Time	

Notes:

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Instrumentation Documentation v.1
(Rev. 11/1/2016)

Specimen: D12-1
Sheet 1 of 1

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity ($\frac{mV}{\sqrt{Hz}}$)	Zero Offset (mV)	Location	Comments
1	1	10 V	LC	ALV03006	1.0767 $\frac{mV}{\sqrt{Hz}}$	0 mV	E	full rate 112,400 lbf
2	1	10 V	LC	ALV03005	1.0779 $\frac{mV}{\sqrt{Hz}}$	0 mV	W	"
3	1	30 V	LVDT	X0167	9702	8925	W rotation	1" LVDT
4	1	30 V	LVDT	8702	10318	7016	NE	1" "
5	1	30 V	LVDT	23618	20349	6995	SE	$\frac{1}{2}$ " "
6	1	30 V	LVDT	X00598	9911	6936	NW	1" "
7	1	30 V	LVDT	J4914	10003	6621	SW	1" "
8	1	30 V	LVDT	X0185	10097	8985	E rotation	1" "
Operator		Signature			Date		Time	
Kinsley Skille		K.C. Skille			3/22/17		6:00 pm	
Checked by		Signature			Date		Time	
Checked by		Signature			Date		Time	

Notes:

Appendix 11, Pg 18 of 30

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Instrumentation Documentation v.1
(Rev. 11/1/2016)

Specimen: 072-2
Sheet 1 of 1

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity ($\frac{mV}{in}$)	Zero Offset (mV)	Location	Comments
1	1	10 V	LC	ALV03006	1.0767 $\frac{mV}{in}$	0 mV	E	full scale 112,400 lbf
2	1	10 V	LC	ALV03005	1.0779 $\frac{mV}{in}$	0 mV	W	"
3	1	30 V	LVDT	X0167	9902	-558	W rotation	1" LVDT
4	1	30 V	LVDT	8702	10316	6674	NE	1" "
5	1	30 V	LVDT	23618	20349	6436	SE	$\frac{1}{2}$ " "
6	1	30 V	LVDT	X00598	9911	6786	NW	1" "
7	1	30 V	LVDT	J4914	10003	6238	SW	1" "
8	1	30 V	LVDT	X0185	10097	2488	E rotation	1" "
Operator		Signature			Date		Time	
Kinsy Skiller		K.C. Skiller			3/23/17		9:00 pm	
Checked by		Signature			Date		Time	
Checked by		Signature			Date		Time	

Notes:

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Instrumentation Documentation v.1
(Rev. 11/1/2016)

Specimen: 13-1
Sheet 1 of 1

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity ($\frac{mV}{in}$)	Zero Offset (mV)	Location	Comments
1	1	10 V	LC	ALV03006	1.0767 $\frac{mV}{in}$	0 mV	E	full rate 112,400 LF
2	1	10 V	LC	ALV03005	1.0779 $\frac{mV}{in}$	0 mV	W	"
3	1	30 V	LVDT	X0167	9902	8278	W rotation	1" LVDT
4	1	30 V	LVDT	8702	10318	5155	NE	1" "
5	1	30 V	LVDT	23618	20349	5827	SE	$\frac{1}{2}$ " "
6	1	30 V	LVDT	X00598	9911	5145	NW	1" "
7	1	30 V	LVDT	J4914	10003	6490	SW	1" "
8	1	30 V	LVDT	X0185	10097	8897	E rotation	1" "
Operator		Signature			Date		Time	
Kinscy Skiller		KC Skiller			6/14/17		3:00 pm	
Checked by		Signature			Date		Time	
Checked by		Signature			Date		Time	

Notes:

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Instrumentation Documentation v.1
(Rev. 11/1/2016)

Specimen: 13-2
Sheet 1 of 1

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity ($\frac{mV}{in}$)	Zero Offset (mV)	Location	Comments
1	1	10 V	LC	ALU03006	1.0767 $\frac{mV}{in}$	0 mV	E	full scale 112,400 Δ bf
2	1	10 V	LC	ALU03005	1.0779 $\frac{mV}{in}$	0 mV	W	"
3	1	30 V	LVDT	X0167	9702	-662	W rotation	1" LVDT
4	1	30 V	LVDT	8702	10318	4864	NE	1" "
5	1	30 V	LVDT	23618	20349	5692	SE	$\frac{1}{2}$ " "
6	1	30 V	LVDT	X00598	9911	4888	NW	1" "
7	1	30 V	LVDT	J4914	10003	6211	SW	1" "
8	1	30 V	LVDT	X0185	10097	9842	E rotation	1" "

Operator	Signature	Date	Time
Kinsay Skillen	KCSkillen	6/15/17	5:00 pm
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time

Notes:

Appendix 11, Pg 21 of 30

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Instrumentation Documentation v.1
(Rev. 11/1/2016)

Specimen: 14-1
Sheet 1 of 1

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity ($\frac{mV}{\sqrt{Hz}}$)	Zero Offset (mV)	Location	Comments
1	1	10 V	LC	ALV03006	1.0767 $\frac{mV}{\sqrt{Hz}}$	0 mV	E	full rate 112,400 lbf
2	1	10 V	LC	ALV03005	1.0779 $\frac{mV}{\sqrt{Hz}}$	0 mV	W	"
3	1	30 V	LVDT	X0167	9902	8549	W rotation	1" LVDT
4	1	30 V	LVDT	8702	10318	4276	NE	1" "
5	1	30 V	LVDT	23618	20349	7741	SE	$\frac{1}{2}$ " "
6	1	30 V	LVDT	X00598	9911	6276	NW	1" "
7	1	30 V	LVDT	J4914	10003	3767	SW	1" "
8	1	30 V	LVDT	X0185	10097	1579	E rotation	1" "
Operator		Signature			Date		Time	
Kinsy Skeller		K.L. Skeller			6/19/17		3:15 pm	
Checked by		Signature			Date		Time	
Checked by		Signature			Date		Time	

Notes:

Appendix 11, Fig 22 of 30

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Instrumentation Documentation v.1
(Rev. 11/1/2016)

Specimen: 14-2
Sheet 1 of 1

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity ($\frac{mV}{\mu V}$)	Zero Offset (mV)	Location	Comments
1	1	10 V	LC	ALU03006	1.0767 $\frac{mV}{\mu V}$	0 mV	E	full scale 112,400 μV
2	1	10 V	LC	ALU03005	1.0779 $\frac{mV}{\mu V}$	0 mV	W	"
3	1	30 V	LVDT	X0167	9902	6716	W rotation	1" LVDT
4	1	30 V	LVDT	8702	10318	3782	NE	1" "
5	1	30 V	LVDT	23618	20349	7609	SE	$\frac{1}{2}$ " "
6	1	30 V	LVDT	X00598	9911	5996	NW	1" "
7	1	30 V	LVDT	J4914	10003	3614	SW	1" "
8	1	30 V	LVDT	X0185	10097	-4167	E rotation	1" "
Operator		Signature			Date		Time	
Kinsy Skiller		K.E. Skiller			6/20/17		4:30 pm	
Checked by		Signature			Date		Time	
Checked by		Signature			Date		Time	

Notes:

Appendix 11, Pg 23 of 30

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Instrumentation Documentation v.1
(Rev. 11/1/2016)

Specimen: DIS-1
Sheet 1 of 1

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity ($\frac{mV}{\sqrt{Hz}}$)	Zero Offset (mV)	Location	Comments
1	1	10 V	LC	ALV03006	1.0767 $\frac{mV}{\sqrt{Hz}}$	0 mV	E	full strain 112,400 lbf
2	1	10 V	LC	ALV03005	1.0779 $\frac{mV}{\sqrt{Hz}}$	0 mV	W	"
3	1	30 V	LVDT	X0167	9702	4093	W rotation	1" LVDT
4	1	30 V	LVDT	8702	10318	4598	NE	1" "
5	1	30 V	LVDT	23618	20349	7510	SE	$\frac{1}{2}$ " "
6	1	30 V	LVDT	X00598	9911	6812	NW	1" "
7	1	30 V	LVDT	J4914	10003	4684	SW	1" "
8	1	30 V	LVDT	X0185	10097	5233	E rotation	1" "
Operator		Signature			Date		Time	
Kinsy Skell		K.C. Skell			6/22/17		4:00 pm	
Checked by		Signature			Date		Time	
Checked by		Signature			Date		Time	

Notes:

Appendix 11, Fig 24 of 30

DIS-2

Specimen: DIS-2
 Sheet 1 of 1

Project: Effects of laminar cracks on 79-in lap splices of #11 reinforcing bars.

Instrumentation Documentation v.1
 (Rev. 11/1/2016)

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity ($\frac{mV}{in}$)	Zero Offset (mV)	Location	Comments
1	1	10 V	LC	ALV03006	1.0767 $\frac{mV}{in}$	0 mV	E	full strain 112,400 lbf
2	1	10 V	LC	ALV03005	1.0779 $\frac{mV}{in}$	0 mV	W	"
3	1	30 V	LVDT	X0167	9702	-608	W rotation	1" LVDT
4	1	30 V	LVDT	8702	10318	4611	NE	1" "
5	1	30 V	LVDT	23618	20349	7153	SE	$\frac{1}{2}$ " "
6	1	30 V	LVDT	X00598	9911	6487	NW	1" "
7	1	30 V	LVDT	J4914	10003	4261	SW	1" "
8	1	30 V	LVDT	X0185	10097	-2049	E rotation	1" "
Operator		Signature			Date		Time	
Kinsley Skiller		K.L. Skiller			6/23/17		5:45 pm	
Checked by		Signature			Date		Time	
Checked by		Signature			Date		Time	

Notes:

Appendix 11, Pg 25 of 30

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Instrumentation Documentation v.1
(Rev. 11/1/2016)

Specimen: 16-1
Sheet 1 of 1

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity $\left(\frac{mV}{in}\right)$	Zero Offset(mV)	Location	Comments
1	1	10 V	LC	ALV03006	1.0767 $\frac{mV}{in}$	0 mV	E	full rate 112,400 16F
2	1	10 V	LC	ALV03005	1.0779 $\frac{mV}{in}$	0 mV	W	"
3	1	30 V	LVDT	X0167	9902	5023	W rotation	1" LVDT
4	1	30 V	LVDT	8702	10316	4877	NE	1" "
5	1	30 V	LVDT	23618	20349	6603	SE	$\frac{1}{2}$ " "
6	1	30 V	LVDT	X00598	9911	7905	NW	1" "
7	1	30 V	LVDT	J4914	10003	6385	SW	1" "
8	1	30 V	LVDT	X0135	10097	3737	E rotation	1" "
Operator		Signature			Date		Time	
Kinsy Skiller		KSkiller			6/29/17		3:30 am	
Checked by		Signature			Date		Time	
Checked by		Signature			Date		Time	

Notes:

Appendix 11, Pg 26 of 30

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Instrumentation Documentation v.1
(Rev. 11/1/2016)

Specimen: 16-2
Sheet 1 of 1

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity ($\frac{mV}{in}$)	Zero Offset (mV)	Location	Comments
1	1	10 V	LC	ALV03006	1.0767 $\frac{mV}{in}$	0 mV	E	full scale 112,400 lbf
2	1	10 V	LC	ALV03005	1.0779 $\frac{mV}{in}$	0 mV	W	"
3	1	30 V	LVDT	X0167	9702	-1382	W rotation	1" LVDT
4	1	30 V	LVDT	8702	10318	4320	NE	1" "
5	1	30 V	LVDT	23618	20349	6386	SE	$\frac{1}{2}$ " "
6	1	30 V	LVDT	X00598	9911	7354	NW	1" "
7	1	30 V	LVDT	J4914	10003	6085	SW	1" "
8	1	30 V	LVDT	X0185	10097	-1727	E rotation	1" "

Operator	Signature	Date	Time
<i>Kinsey Skiller</i>	<i>K.C. Skiller</i>	6/30/17	4:30 pm
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time

Notes:

Appendix 11, Pg 27 of 30

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Instrumentation Documentation v.1
(Rev. 11/1/2016)

Specimen: 17
Sheet 1 of 1

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity ($\frac{mV}{\mu\epsilon}$)	Zero Offset (mV)	Location	Comments
1	1	10 V	LC	ALU03006	1.0767 $\frac{mV}{\mu\epsilon}$	0 mV	E	full strain 112,400 $\mu\epsilon$
2	1	10 V	LC	ALU03005	1.0779 $\frac{mV}{\mu\epsilon}$	0 mV	W	"
3	1	30 V	LVDT	X0167	9902	7945	W rotation	1" LVDT
4	1	30 V	LVDT	8702	10318	6365	NE	1" "
5	1	30 V	LVDT	23618	20349	6807	SE	$\frac{1}{2}$ " "
6	1	30 V	LVDT	X00598	9911	7284	NW	1" "
7	1	30 V	LVDT	J4914	10003	8175	SW	1" "
8	1	30 V	LVDT	X0135	10097	8526	E rotation	1" "

Operator	Signature	Date	Time
Kinsey Skillen	K.C Skillen	7/5/17	2:45 pm
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time

Notes:

Appendix 11, Pg 28 of 30

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.

Instrumentation Documentation v.1
(Rev. 11/1/2016)

Specimen: 18-1
Sheet 1 of 1

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity ($\frac{mV}{in}$)	Zero Offset(mV)	Location	Comments
1	1	10 V	LC	ALU03006	1.0767 $\frac{mV}{in}$	0 mV	E	full rate 112,400 16F
2	1	10 V	LC	ALU03005	1.0779 $\frac{mV}{in}$	0 mV	W	"
3	1	30 V	LVDT	X0167	9902	9800	W rotation	1" LVDT
4	1	30 V	LVDT	8702	10318	7938	NE	1" "
5	1	30 V	LVDT	23618	20349	7319	SE	$\frac{1}{2}$ " "
6	1	30 V	LVDT	X00598	9911	7073	NW	1" "
7	1	30 V	LVDT	J4914	10003	6746	SW	1" "
8	1	30 V	LVDT	X0135	10097	8789	E rotation	1" "

Operator	Signature	Date	Time
Kinsy Skiller	K.C. Skiller	7/6/17	2:15 pm
Checked by	Signature	Date	Time
Checked by	Signature	Date	Time

Notes:

Appendix 11, Fig 29 of 30

Project: Effects of laminars cracks on 79-in lap splices of #11 reinforcing bars.


Instrumentation Documentation v.1
(Rev. 11/1/2016)

Specimen: 18-2
Sheet 1 of 1

Data Acquisition System:								
Channel #	Gain	Excitation V.	Sensor	S.N.	Sensitivity ($\frac{mV}{in}$)	Zero Offset (mV)	Location	Comments
1	1	10 V	LC	ALU03006	1.0767 $\frac{mV}{in}$	0 mV	E	full trace 112,400 lbf
2	1	10 V	LC	ALU03005	1.0779 $\frac{mV}{in}$	0 mV	W	"
3	1	30 V	LVDT	X0167	9902	5422	W rotation	1" LVDT
4	1	30 V	LVDT	8702	10318	7661	NE	1" "
5	1	30 V	LVDT	23618	20349	7206	SE	$\frac{1}{2}$ " "
6	1	30 V	LVDT	X00598	9911	7016	NW	1" "
7	1	30 V	LVDT	J4914	10003	6676	SW	1" "
8	1	30 V	LVDT	X0185	10097	4795	E rotation	1" "
Operator		Signature			Date		Time	
Kinsay Skillman		KC Skillman			7/7/17		3:00 pm	
Checked by		Signature			Date		Time	
Checked by		Signature			Date		Time	

Notes:

Calibration Instrument Name and S.N.:		Inston 120BTE502040			
Data Acquisition System:		StrainSmart 8000			
Gain:		1			
Excitation Voltage:		10V			
Channel:		1			
Sensor:		Load Cell East			
Sensor S.N.:		ALU03006			
Measurand (lb _f)	Voltage (mV/V)	Measurand	Voltage (mV/V)	Measurand	Voltage
0	-.0525	109600	-1.063		
5100	-.1005	119700	-1.162		
19700	-.1925	124750	-1.211		
29700	-.2905				
40050	-.3915				
49900	-.4875				
60000	-.5857				
80000	-.7785				
90000	-.8765				
100200	-.975				
Operator		Signature		Date	Time
Kinsy Skiller		Klo Skiller		2/11/17	3:00 pm
Checked by		Signature		Date	Time
Checked by		Signature		Date	Time
Results	Sensitivity		Accuracy		
	103.2 $\frac{kip}{(mV/V)}$		± 400 lb _f		

Calibration Instrument Name and S.N.:		Instron 120RTE502040			
Data Acquisition System:		StrainSmart 8000			
Gain:		1			
Excitation Voltage:		10V			
Channel:		2			
Sensor:		Load Cell West			
Sensor S.N.:		AMU03005			
Measurand (lbf)	Voltage (mV)	Measurand	Voltage	Measurand	Voltage
0	0	90000	-0.857		
5200	-0.0535	100600	-0.9613		
9800	-0.0903	110000	-1.05		
19800	-0.1863	120000	-1.145		
30000	-0.282	125000	-1.196		
40000	-0.377				
50000	-0.4763				
59400	-0.568				
70000	-0.668				
80000	-0.7628				
Operator		Signature		Date	Time
Kinsley Skillen				2/11/17	3:00 pm
Checked by		Signature		Date	Time
Checked by		Signature		Date	Time
Results	Sensitivity			Accuracy	
	104.6 $\frac{\text{kip}}{\text{mV}}$ (✓)			± 500 lbf	

Calibration Instrument Name and S.N.:		Instron 120BTE502040			
Data Acquisition System:		Strainsmart 8000			
Gain:		1			
Excitation Voltage:		30V			
Channel:		4			
Sensor:		LVDT NE			
Sensor S.N.:		12838			
Measurand (in)	Voltage (mV)	Measurand (in)	Voltage (mV)	Measurand (in)	Voltage (mV)
-.25	-10105	-.25	-10105		
-.2	-8140	-.2	-8125		
-.15	-6111	-.15	-6078		
-.1	-4026	-.1	-4027		
-.05	-2030	-.05	-2003	0	20
0	-8	0	5	.05	2013
		.05	2044	.1	4077
		.1	4115	.15	6150
		.15	6172	.2	8207
		.2	8220	.25	10220
		.25	10220		
Operator		Signature		Date	Time
Kinsey Skiller		K.C. Skille		2/11/17	3:45pm
Checked by		Signature		Date	Time
Checked by		Signature		Date	Time
Results	Sensitivity			Accuracy	
	40748 $\frac{mV}{in}$			$\pm .002 in$	

Calibration Instrument Name and S.N.:		Inston 120BTE502040			
Data Acquisition System:		Strainnet 8000			
Gain:		1			
Excitation Voltage:		30V			
Channel:		5			
Sensor:		LVDT SE			
Sensor S.N.:		23618			
Measurand (in)	Voltage (mV)	Measurand	Voltage	Measurand	Voltage
-0.5	-10180	-0.5	-10180		
-0.375	-7620	-0.375	-7624		
-0.25	-5110	-0.25	-5109		
-0.125	-2560	-0.125	-2558		
0	-1	0	-9	0	-10
		0.125	2543	0.125	2550
		0.5	5110	0.5	5115
		0.375	7625	0.375	7625
		0.5	10154	0.5	10150
Operator		Signature		Date	Time
Kinsy Skillen		K.C Skillen		2/11/17	3:45pm
Checked by		Signature		Date	Time
Checked by		Signature		Date	Time
Results	Sensitivity			Accuracy	
	20350 $\frac{mV}{in}$			± .0014 in	


Calibration Instrument Name and S.N.:		Inston 120BTE502040			
Data Acquisition System:		Strainmat 8000			
Gain:		1			
Excitation Voltage:		30V			
Channel:		6			
Sensor:		LVDT NW			
Sensor S.N.:		X00598			
Measurand (in)	Voltage (mV)	Measurand	Voltage	Measurand	Voltage
-0.9	-8912	-0.9	-8912		
-0.75	-7420	-0.75	-7421		
-0.5	-4982	-0.5	-4983		
-0.25	-2512	-0.25	-2520		
0	0	0	-3	0	-8
		0.25	2500	0.25	2500
		0.5	4982	0.5	4980
		0.75	7437	0.75	7433
		0.9	8890	0.9	8890
Operator		Signature		Date	Time
Kinsy Skila		K.C. Skila		2/11/17	3:45pm
Checked by		Signature		Date	Time
Checked by		Signature		Date	Time
Results		Sensitivity		Accuracy	
		9911 $\frac{mV}{in}$		± .004 in	

Calibration Instrument Name and S.N.:		Inston 120BTE502040			
Data Acquisition System:		Strainnet 8000			
Gain:		1			
Excitation Voltage:		30V			
Channel:		7			
Sensor:		LVDT SW			
Sensor S.N.:					
Measurand (in)	Voltage (mV)	Measurand (in)	Voltage (mV)	Measurand (in)	Voltage (mV)
-0.9	-9014	-0.9	-9014		
-0.75	-7517	-0.75	-7520		
-0.5	-5043	-0.5	-5051		
-0.25	-2531	-0.25	-2531		
0	-3	0	-13	0	-9
		0.25	2520	0.25	2510
		0.5	5006	0.5	5003
		0.75	7474	0.75	7471
		0.9	8965	0.9	8965
Operator		Signature		Date	Time
Kinsy Skel		K.C. Skel		2/11/17	3:45 pm
Checked by		Signature		Date	Time
Checked by		Signature		Date	Time
Results	Sensitivity		Accuracy		
	10003 $\frac{mV}{in}$		± .005 in		

25884-000-30R-C01R-00002, Rev. 000

APPENDIX D

“Purdue Memo for Phase II Tests”

TO: Javeed Munshi and Jaspal Saini
FROM: M. A. Sozen and S. Pujol 
RE: Effect of Laminar-Crack Width on Strength of Unconfined Splices
of # 11 Reinforcing Bars
DATE: 3 June 2016

This memorandum has been prepared to summarize the information contained in our report to the First Energy Nuclear Operating Company of Ohio¹.

In 2012, two series of tests were made to determine the effect of existing laminar cracks on strength of unconfined lap splices of #11 bars having 79-in. and 120-in. laps with the conclusion that such cracks did not prevent the splices from developing the yield stress of the bars.²

The current study reported in 2016 focused on the width of the cracks that would not affect the splice strength. Because it had been observed in the 2012 tests that the 120-in. splices were, as would be expected, consistently stronger than 79-in. splices, the current tests included six full-scale specimens with 79-in splices (and no specimens with 120-in. splices). The result was that 79-in. splices with an existing laminar crack having a width of 0.05 in. did not prevent the splice from developing the yield stress of the bar.

Properties of Test Specimen

Profile and cross section of the test specimen are shown in Fig. 1. To simulate the conditions of the splices in the Davis-Besse shell structure, the side cover was 3 in. and the clear distance between the two splices was 6 in. To have the laminar crack to the plane of the splices, the top cover was 5 in., 2 in. more than the side cover. The depth of the specimen was chosen so that the yield stress of the bar could be developed if the splice served its requisite function.

¹ M.A. Sozen and S. Pujol, "An Experimental Investigation of Laminar Cracks on Strength of Unconfined 79-in. Lap Splices of #11 Reinforcing Bars," Bowen Laboratory, 8 June 2016.

² M. Sozen and S. Pujol, "An Investigation of The Effect of Laminar Cracks on Strength of Unconfined Lap Splices of #11 Reinforcing Bars," Bowen Laboratory, 12 July 2012.

Concrete compressive strength at time of test ranged from 5200 to 5900 psi as shown in Table 1. Measured yield stress of the bars was 65 ksi.

Tests

The tests were planned to have two loadings. The first loading was carried out to develop laminar cracking at the plane of the splice. The second loading was carried out from zero applied load to failure (Fig. 2 to 7).

The laminar-crack width is influenced by the tensile strength of the concrete and the bond between the bar and the surrounding concrete. Because both of these properties are subject to strong variations, the measured maximum crack widths at the end of Loading 1 varied from 0.021 to 0.054 in. (Table 2). At failure the maximum stress attained at the end of the splice varied from 73 to 74 ksi (Table 1). In effect, in each test the attained stress in the spliced bars exceeded the yield stress of the bar.

Conclusion

Based on the results of tests of Series C it is concluded that unconfined 79-in. splices of #11 bars with 0.05-in. laminar cracks, in their own plane, in concrete having a compressive strength of 5200 psi or more will develop more than the actual yield stress of the bars.

The test results indicate that the splice has the toughness required in the current design environment for structures to resist static and dynamic demands.

TABLE 1

Test Girder Designation	Concrete Compressive Strength (psi)	Concrete Splitting Strength (Tensile) (psi)	Maximum Applied Load (kip)	Maximum Midspan Deflection (in.)	Maximum Moment at Support (kip-ft)	Maximum Moment at Splice End (kip-ft)	Calc. Reinf. Stress at Support (ksi)	Calc. Reinf. Stress at Splice End (ksi)
C1	5300	500	39.7	0.70	427	419	74	73
C2	5200	450	40.0	0.85	430	422	75	74
C3	5900	500	40.4	0.79	434	426	76	74
C4	5700	500	40.9	0.83	439	431	76	75
C5	5600	500	40.2	0.82	432	424	75	74
C6	5300	400	40.7	0.92	437	429	76	75

TABLE 2

Test Girder Designation	From Optotrak			
	Max. Mid-span Deflection at Initial Loading (in.)	Max. Crack Width at Initial Loading (10 ⁻³ in)	Mid-span Deflection at last reading during reload (in.)	Max. Crack Width at last reading during reload (10 ⁻³ in)
C1	0.42	42	0.70	90
C2	0.40	21	0.41	25
C3	0.41	39	0.41	42
C4	0.52	52	0.50	53
C5	0.43	54	0.42	57
C6	0.52	30	0.52	33





Figure 1




Figure 2




Figure 3




Figure 3




Figure 4




Figure 5




Figure 6

25884-000-30R-C01R-00002, Rev. 000

APPENDIX E

“Memo from Dr. Santiago Pujol”

To: Energy Harbor Corporation

From: Santiago Pujol 

Santiago.pujol@canterbury.ac.nz

+1 765 231 5715

+64 3 369 1238



RE: Report 25884-000-30R-C01R-00002, Rev. 000 by Bechtel Co. on Effects of Laminar Cracks on Strength of Lap Splices of #11 Reinforcing Bars

Date: January 14, 2021

I confirm that the studies described in this report and its appendices indicate that laminar cracks with widths of up to 0.050" did not affect the strengths of test lap splices of #11 reinforcing bars representing lap splices in the Davis-Besse Shield Building. This conclusion is supported by tests conducted at Purdue University from 2012 to 2017. I was in charge of those tests together with the late Dr. Mete Sozen.

Repairs are recommended for areas affected by wider laminar cracks (with thicknesses exceeding 0.050") as well as areas affected by corrosion.

Attachment 2

Updated Final Safety Analysis Report Markup

(3 pages follow)

3.8.2.2 Shield Building

3.8.2.2.1 Description

The Shield Building is a reinforced concrete structure of right cylinder configuration with a shallow dome roof. An annular space is provided between the steel containment vessel and the interior face of the concrete shield building of approximately 4.5 feet to permit construction operations and periodic visual inspection of the steel containment vessel. The volume contained within this annulus is approximately 678,700 cu. ft. The Shield Building has a height of 279.5 ft. measured from the top of the foundation ring to the top of the dome. The thicknesses of the wall and the dome are approximately 2.5 ft. and 2 ft., respectively. The design bases for shielding requirements for operational radiation protection are discussed in Chapter 12.

(ADD PARAGRAPH SHOWN ON NEXT PAGE)

3.8.2.2.2 Design Bases

The Shield Building completely encloses the Containment Vessel, the personnel access openings, the equipment hatch, and that portion of all penetrations that are associated with primary containment. The design of the Shield Building provides for (1) biological shielding, (2) controlled release of the annulus atmosphere under accident condition, and (3) environmental protection of the Containment Vessel.

Adequate reinforcing is placed in the concrete walls, dome, and foundation to control cracking due to concrete shrinkage and temperature gradients. The loading combinations, as stated in Subsection 3.8.2.2.4, provide a design basis to ensure that the Shield Building suffers no loss of shielding or containment function due to seismic or tornado events.

The design of the Shield Building ensures an elastic behavior of steel reinforcement during a Maximum Possible Earthquake controlling cracking of concrete and impairment of leaktight integrity.

The personnel and equipment hatch openings and the major piping penetrations through the Shield Building are designed such that all the anticipated loads are carried by frame action around the openings in accordance with Welding Research Council Bulletin #102. This frame action is achieved by adding sufficient reinforcement around the perimeter of the openings. Diagonal bars at each corner of the opening are added to provide the horizontal and vertical shear resistance.

Normal Operating Conditions:

The normal ambient temperature in the annular space is set by heat loss through the steel containment vessel shell and concrete shield building. The steel containment vessel metal temperature can be maintained above 30°F during reactor operation.

Loss of Coolant Accident Conditions:

Following a loss of coolant accident, heat transferred to the air in the annular space could cause a pressure rise. Conservative assumptions for temperature transmission to the space, and pressure drop in the Emergency Ventilation System are used in sizing the ventilation system. Following this initial pressure transient, the Shield Building is maintained at a minimum negative pressure of 1/4-inch water gauge. The Shield Building structure is analyzed also to ensure

ADD TO THE END OF SECTION 3.8.2.2.1 (page 3.8-55):

Laminar cracking has been identified in the plane of the outer reinforcement layer of the structure. Reference 107 provides the root-cause analysis for the development of laminar cracking in the Shield Building shell. Propagation of the laminar cracking has subsequently been identified. Reference 108 provides the root-cause analysis for the propagation of the laminar cracking.

Reference 109 evaluates laminar cracking up to 0.050" in width for acceptability. This Technical Report concludes that laminar cracking up to this width has no effect on the structural behavior or capacity of the Shield Building considering reinforcement engagement, composite action of the shell, overall structural response, and serviceability/long term durability of the structure. Therefore, laminar cracking less than and equal to 0.050" is considered to be acceptable and included in the licensing and design basis of the Shield Building. The Shield Building is to be analyzed per licensing and design basis codes (ACI 318-63 and 307-69) and methodology without the need to explicitly consider laminar cracking up to 0.050" in the analysis. Laminar cracking greater than 0.050" is to be repaired. Refer to Section 18.1.43 for monitoring of laminar cracking.

Davis-Besse Unit 1 Updated Final Safety Analysis Report

- (97) NRC Letter from J. F. Stolz (NRC) to J. Williams (TED), Safety Evaluation of B&W Owners Group Reports Dealing with Elimination of Postulated Pipe Breaks in PWR Primary Main Loops, 2-18-86 (Log Number 1918).
- (98) TED Letter, Comparison of Davis-Besse Reactor Coolant System Leak Detection Systems to Regulatory Guide 1.45, dated 11-09-90 (Serial Number 1849).
- (99) AEC letter dated September 26, 1972, Docket No. 50-346, which requested a review of the Davis-Besse Station for potentially adverse affects to safety-related equipment from failures in non-Category I (seismic) equipment, such as flooding or the release of chemicals.
- (100) C-NSA-000.02-011, Turbine Building HELB Environments.
- (101) Safety Evaluation River Bend, Unit 1, License Amendment, Change the Method of Analysis for High Energy Line Break Analysis, U. S. Nuclear Regulatory Commission, dated May 20,2004, ADAMS ML041410566.
- (102) Bechtel Calculation 58.010, "Flow Rate due to a Crack in the Make-up Pump Discharge and Flood Water Heights in Associated Rooms" 3/16/1987, with the associated Bechtel Letter BT17624, March 18, 1987.
- (103) NUREG-0588, Revision 1, "Interim Staff Position on Environmental Qualification of Safety Related Electrical Equipment," Issued: July 1981.
- (104) NRC Letter from M. Mahoney (NRC) to B.S. Allen (FENOC), Approved License Amendment 281 and Safety Evaluation Report for Updated Davis-Besse Nuclear Power Station Leak-Before-Break (EBB) Evaluation, March 24, 2010. [ADAMS Accession No. ML100640506]
- (104a) NRC Letter from M. Mahoney (NRC) to B.S. Allen (FENOC), Corrections of Typographical Errors [revised pages], Approved License Amendment 281 and Safety Evaluation Report for Updated Davis-Besse Nuclear Power Station Leak-Before-Break (LBB) Evaluation, April 9, 2010. [ADAMS Accession No. ML100970549]
- (105) Structural Integrity Associates, Inc. (SIA), "Leak-Before-Break Evaluation of Reactor Coolant Pump Suction and Discharge Nozzle Weld Overlays for Davis-Besse Nuclear Power Station," Report 0800368.404, Revision 1, January 11, 2010.
- (106) Calculation C-CSS-099.20-044, Service Water Pump Room Tornado Depressurization Analysis.

ADD THE FOLLOWING:

- (107) Performance Improvement International, "Root Cause Assessment Davis-Besse Shield Building Laminar Cracking," Revision 2, 4/28/12 (Condition Report CR-2011-03346).
- (108) Performance Improvement International, "Root Cause Analysis: Laminar Crack Condition of the Davis-Besse Shield Building," Revision 0, 6/18/14 (Condition Report CR-2013-14097).
- (109) Bechtel Report 25884-000-30R-C01R-00002, Revision 0, "Incorporating Laminar Cracks of up to 0.050 inch in the Design Basis of the Davis Besse Shield Building," 2/3/21 (EER 601303393).