

# AI Qualification Protocol Development



**Leif Esp, EPRI**  
Program Manager, Plant Support / NDE Program

NRC Technical Information Exchange Meeting  
January 21, 2026

# AI Qualification Protocol Driver


- Objective
  - Develop a protocol under the ASME Section XI, Appendix VIII qualification program at EPRI to perform future qualifications of AI or AI assisted procedures / techniques for:
    - Detection of flaws
    - Characterization of flaws (e.g. orientation, surface connected / embedded, volumetric / planar)
    - Sizing of flaws (length sizing or thru-wall sizing)

**Current use cases focus on detection but progression to characterization and sizing seems possible**


# AI Qualification Use Cases Considered

- AI as Secondary Analysis
  - Primary analysis still carried out under the standard human based process
  - AI used as confirmatory or contradictory result in a qualified manner as part of the qualified examination
    - RVUHP Supplement 15 examinations
- AI as an Assisted Primary Analysis
  - Primary initial analysis (data screening) is performed by AI
  - Humans only review areas flagged by AI for further investigation
  - All non-flagged data “cleared” and no human analysis performed

**Not Considered – Fully Autonomous Analysis with AI – Code Changes Required**



## Simplified "standard" ASME Section XI, Appendix VIII qualification process




## AI/ML Affected Areas

# Key Take-Aways

- AI/ML will require qualification changes depending on the use case defined the applicable procedure
  - ASME Section XI, Appendix VIII rules will not change
  - How a procedure is required to demonstrate meeting those rules may change based on the selected use case
- The majority of the change will be up front with the examination procedure preparation
  - Ensuring the AI/ML process is well defined and includes all essential steps and processes
  - The development of the qualification plan by the qualification body will be vital to ensure the qualification can meet all of the requirements with the appropriate level of objective evidence
- Model validation and lock down at the completion of a successful qualification will be a key factor in issuing a qualification for a given procedure / technique (e.g. version control)
- One major change that requires additional investigation is the ability to create a benchmark set of flaws / specimens that future revisions of the model can be applied to for validation and qualification of model revisions that are efficient and effective for industry implementation

# Summary

- EPRI's current ASME Section XI, Appendix VIII process is suitable for qualification of AI/ML models that can be trained and locked down (non-continuous learning models).
- Additional guidance through an instruction (QPI) for the PDA will be completed to provide guidance on qualification planning to ensure all aspects are properly considered.
  - QPI planned for Q2 2026
- Re-qualification of updated models requires additional investigation to determine if a benchmark (re)qualification set is possible. The requirements for this are under consideration and will be included in the protocol / instruction.



# Questions / Discussion



**TOGETHER...SHAPING THE FUTURE OF ENERGY®**